

REPUBLIC OF TÜRKİYE MINISTRY OF ENVIRONMENT,
URBANIZATION, AND CLIMATE CHANGE

ELECTRICAL INSTALLATION UNIT PRICE ANALYSES FOR 2025

Higher Technical Board
Since 1934

REPUBLIC OF TÜRKİYE

MINISTRY OF ENVIRONMENT, URBANIZATION,

AND CLIMATE CHANGE

Higher Technical Board

1934

ELECTRICAL INSTALLATION UNIT PRICE ANALYSES

2025

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1101	**Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1101	Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	16.775,20	16.775,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1,75	165,00		288,75
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	16.775,20	2.155,23
				Material and Installation w/o Profit (TRY)	18.930,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.694,04**	
				Unit Price (TRY)	**23.663,04**	

Item No	Analysis Name					UoM
35.100.1103	**Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1103	Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	20.144,80	20.144,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	20.144,80	2.413,98
				Material and Installation w/o Profit (TRY)	22.558,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**28.198,47**	

Item No	Analysis Name					UoM
35.100.1104	**Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1104	Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	21.819,20	21.819,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	21.819,20	2.413,98
				Material and Installation w/o Profit (TRY)	24.233,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**30.291,47**	

Item No	Analysis Name					UoM
35.100.1105	**Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1105	Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	23.472,80	23.472,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician's helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	23.472,80	2.672,73
				Material and Installation w/o Profit (TRY)	26.145,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**32.681,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1106	**Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1106	Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	26.842,40	26.842,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician's helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	26.842,40	2.672,73
				Material and Installation w/o Profit (TRY)	29.515,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**36.893,91**	

Item No	Analysis Name					UoM
35.100.1107	**Galvanized steel floor-standing enclosure, minimum width 1,000 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1107	Galvanized steel floor-standing enclosure, minimum width 1000 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	30.160,00	30.160,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	30.160,00	2.931,48
				Material and Installation w/o Profit (TRY)	33.091,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**41.364,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1108	**Galvanized steel floor-standing enclosure, minimum width 1,200 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1108	Galvanized steel floor-standing enclosure, minimum width 1200 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	33.571,20	33.571,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,75	165,00		453,75
10.100.1081	Master electrician	h	5,5	250,00		1.375,00
10.100.1083	Master electrician's helper	h	5,5	185,00		1.017,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	33.571,20	3.190,23
				Material and Installation w/o Profit (TRY)	36.761,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.987,79**	
				Unit Price (TRY)	**45.951,79**	

Item No	Analysis Name					UoM
35.100.1151	**Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1151	Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	18.460,00	18.460,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,75	165,00		288,75
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	18.460,00	2.155,23
				Material and Installation w/o Profit (TRY)	20.615,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.694,04**	
				Unit Price (TRY)	**25.769,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1102	**Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1102	Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 400 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	18.460,00	18.460,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,75	165,00		288,75
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	18.460,00	2.155,23
				Material and Installation w/o Profit (TRY)	20.615,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.694,04**	
				Unit Price (TRY)	**25.769,04**	

Item No	Analysis Name					UoM
35.100.1152	**Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1152	Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	20.144,80	20.144,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,75	165,00		288,75
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	20.144,80	2.155,23
				Material and Installation w/o Profit (TRY)	22.300,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.694,04**	
				Unit Price (TRY)	**27.875,04**	

Item No	Analysis Name					UoM
35.100.1153	**Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1153	Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	21.819,20	21.819,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	21.819,20	2.413,98
				Material and Installation w/o Profit (TRY)	24.233,18	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**30.291,47**	

Item No	Analysis Name					UoM
35.100.1154	**Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1154	Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	23.472,80	23.472,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	23.472,80	2.413,98
				Material and Installation w/o Profit (TRY)	25.886,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**32.358,47**	

Item No	Analysis Name					UoM
35.100.1155	**Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1155	Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	26.842,40	26.842,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician’s helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	26.842,40	2.672,73
				Material and Installation w/o Profit (TRY)	29.515,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**36.893,91**	

Item No	Analysis Name					UoM
35.100.1156	**Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1156	Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	30.160,00	30.160,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician’s helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	30.160,00	2.672,73
				Material and Installation w/o Profit (TRY)	32.832,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**41.040,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1157	**Galvanized steel floor-standing enclosure, minimum width 1,000 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1157	Galvanized steel floor-standing enclosure, minimum width 1000 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	33.571,20	33.571,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	33.571,20	2.931,48
				Material and Installation w/o Profit (TRY)	36.502,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**45.628,35**	

Item No	Analysis Name					UoM
35.100.1158	**Galvanized steel floor-standing enclosure, minimum width 1,200 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1158	Galvanized steel floor-standing enclosure, minimum width 1200 mm / Minimum depth: 500 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	40.237,60	40.237,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2,75	165,00		453,75
10.100.1081	Master electrician	h	5,5	250,00		1.375,00
10.100.1083	Master electrician's helper	h	5,5	185,00		1.017,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	40.237,60	3.190,23
				Material and Installation w/o Profit (TRY)	43.427,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.987,79**	
				Unit Price (TRY)	**54.284,79**	

Item No	Analysis Name					UoM
35.100.1201	**Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1201	Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	20.144,80	20.144,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,75	165,00		288,75
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	20.144,80	2.155,23
				Material and Installation w/o Profit (TRY)	22.300,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.694,04**	
				Unit Price (TRY)	**27.875,04**	

Item No	Analysis Name					UoM
35.100.1202	**Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1202	Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	21.777,60	21.777,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	21.777,60	2.413,98
				Material and Installation w/o Profit (TRY)	24.191,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**30.239,47**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1203	**Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1203	Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	23.472,80	23.472,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	23.472,80	2.413,98
				Material and Installation w/o Profit (TRY)	25.886,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**32.358,47**	

Item No	Analysis Name					UoM
35.100.1204	**Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1204	Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	25.199,20	25.199,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician's helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	25.199,20	2.672,73
				Material and Installation w/o Profit (TRY)	27.871,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**34.839,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1205	**Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1205	Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	26.821,60	26.821,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician's helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	26.821,60	2.672,73
				Material and Installation w/o Profit (TRY)	29.494,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**36.867,91**	

Item No	Analysis Name					UoM
35.100.1206	**Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1206	Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	33.571,20	33.571,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	33.571,20	2.931,48
				Material and Installation w/o Profit (TRY)	36.502,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**45.628,35**	

Item No	Analysis Name					UoM
35.100.1207	**Galvanized steel floor-standing enclosure, minimum width 1,000 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1207	Galvanized steel floor-standing enclosure, minimum width 1000 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	40.237,60	40.237,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	40.237,60	2.931,48
				Material and Installation w/o Profit (TRY)	43.169,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**53.961,35**	

Item No	Analysis Name					UoM
35.100.1208	**Galvanized steel floor-standing enclosure, minimum width 1,200 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1208	Galvanized steel floor-standing enclosure, minimum width 1200 mm / Minimum depth: 600 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	46.956,00	46.956,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2,75	165,00		453,75
10.100.1081	Master electrician	h	5,5	250,00		1.375,00
10.100.1083	Master electrician's helper	h	5,5	185,00		1.017,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	46.956,00	3.190,23
				Material and Installation w/o Profit (TRY)	50.146,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.987,79**	
				Unit Price (TRY)	**62.682,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.1251	**Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1251	Galvanized steel floor-standing enclosure, minimum width 400 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	23.493,60	23.493,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	23.493,60	2.413,98
				Material and Installation w/o Profit (TRY)	25.907,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**32.384,47**	

Item No	Analysis Name					UoM
35.100.1252	**Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1252	Galvanized steel floor-standing enclosure, minimum width 500 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	25.168,00	25.168,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	25.168,00	2.413,98
				Material and Installation w/o Profit (TRY)	27.581,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**34.477,47**	

Item No	Analysis Name					UoM
35.100.1253	**Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1253	Galvanized steel floor-standing enclosure, minimum width 600 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	26.842,40	26.842,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician’s helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	26.842,40	2.672,73
				Material and Installation w/o Profit (TRY)	29.515,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**36.893,91**	

Item No	Analysis Name					UoM
35.100.1254	**Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1254	Galvanized steel floor-standing enclosure, minimum width 700 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	28.516,80	28.516,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician’s helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	28.516,80	2.672,73
				Material and Installation w/o Profit (TRY)	31.189,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**38.986,91**	

Item No	Analysis Name					UoM
35.100.1255	**Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1255	Galvanized steel floor-standing enclosure, minimum width 800 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	30.180,80	30.180,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	30.180,80	2.931,48
				Material and Installation w/o Profit (TRY)	33.112,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**41.390,35**	

Item No	Analysis Name					UoM
35.100.1256	**Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1256	Galvanized steel floor-standing enclosure, minimum width 900 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	40.237,60	40.237,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	40.237,60	2.931,48
				Material and Installation w/o Profit (TRY)	43.169,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**53.961,35**	

Item No	Analysis Name					UoM
35.100.1257	**Galvanized steel floor-standing enclosure, minimum width 1,000 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1257	Galvanized steel floor-standing enclosure, minimum width 1000 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	46.956,00	46.956,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2,75	165,00		453,75
10.100.1081	Master electrician	h	5,5	250,00		1.375,00
10.100.1083	Master electrician’s helper	h	5,5	185,00		1.017,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	46.956,00	3.190,23
				Material and Installation w/o Profit (TRY)	50.146,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.987,79**	
				Unit Price (TRY)	**62.682,79**	

Item No	Analysis Name					UoM
35.100.1258	**Galvanized steel floor-standing enclosure, minimum width 1,200 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1258	Galvanized steel floor-standing enclosure, minimum width 1200 mm / Minimum depth: 800 mm / Floor-standing galvanized steel enclosures (1st enclosure) (Market price)	Qty	1	53.643,20	53.643,20	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	53.643,20	3.613,98
				Material and Installation w/o Profit (TRY)	57.257,18	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.517,48**	
				Unit Price (TRY)	**71.571,48**	

Item No	Analysis Name					UoM
35.100.1301	**Additional galvanized steel floor-standing enclosure, minimum width 400 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1301	Additional galvanized steel floor-standing enclosure, minimum width 400 mm / Additional galvanized steel enclosures (Market price)	Qty	1	16.775,20	16.775,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	16.775,20	1.978,98
				Material and Installation w/o Profit (TRY)	18.754,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.473,72**	
				Unit Price (TRY)	**23.442,72**	

Item No	Analysis Name					UoM
35.100.1302	**Additional galvanized steel floor-standing enclosure, minimum width 500 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1302	Additional galvanized steel floor-standing enclosure, minimum width 500 mm / Additional galvanized steel enclosures (Market price)	Qty	1	18.460,00	18.460,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,75	165,00		288,75
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	18.460,00	2.155,23
				Material and Installation w/o Profit (TRY)	20.615,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.694,04**	
				Unit Price (TRY)	**25.769,04**	

Item No	Analysis Name					UoM
35.100.1303	**Additional galvanized steel floor-standing enclosure, minimum width 600 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1303	Additional galvanized steel floor-standing enclosure, minimum width 600 mm / Additional galvanized steel enclosures (Market price)	Qty	1	20.155,20	20.155,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1,75	165,00		288,75
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	20.155,20	2.155,23
				Material and Installation w/o Profit (TRY)	22.310,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.694,04**	
				Unit Price (TRY)	**27.888,04**	

Item No	Analysis Name					UoM
35.100.1304	**Additional galvanized steel floor-standing enclosure, minimum width 700 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1304	Additional galvanized steel floor-standing enclosure, minimum width 700 mm / Additional galvanized steel enclosures (Market price)	Qty	1	21.819,20	21.819,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	21.819,20	2.413,98
				Material and Installation w/o Profit (TRY)	24.233,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**30.291,47**	

Item No	Analysis Name					UoM
35.100.1305	**Additional galvanized steel floor-standing enclosure, minimum width 800 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1305	Additional galvanized steel floor-standing enclosure, minimum width 800 mm / Additional galvanized steel enclosures (Market price)	Qty	1	23.493,60	23.493,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	23.493,60	2.413,98
				Material and Installation w/o Profit (TRY)	25.907,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.017,47**	
				Unit Price (TRY)	**32.384,47**	

Item No	Analysis Name					UoM
35.100.1306	**Additional galvanized steel floor-standing enclosure, minimum width 900 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1306	Additional galvanized steel floor-standing enclosure, minimum width 900 mm / Additional galvanized steel enclosures (Market price)	Qty	1	26.821,60	26.821,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician's helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	26.821,60	2.672,73
				Material and Installation w/o Profit (TRY)	29.494,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**36.867,91**	

Item No	Analysis Name					UoM
35.100.1307	**Additional galvanized steel floor-standing enclosure, minimum width 1,000 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1307	Additional galvanized steel floor-standing enclosure, minimum width 1000 mm / Additional galvanized steel enclosures (Market price)	Qty	1	33.519,20	33.519,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,25	165,00		371,25
10.100.1081	Master electrician	h	4,5	250,00		1.125,00
10.100.1083	Master electrician's helper	h	4,5	185,00		832,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	33.519,20	2.672,73
				Material and Installation w/o Profit (TRY)	36.191,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.340,91**	
				Unit Price (TRY)	**45.239,91**	

Item No	Analysis Name					UoM
35.100.1308	**Additional galvanized steel floor-standing enclosure, minimum width 1,200 mm / Additional galvanized steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.1308	Additional galvanized steel floor-standing enclosure, minimum width 1200 mm / Additional galvanized steel enclosures (Market price)	Qty	1	40.216,80	40.216,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	40.216,80	2.931,48
				Material and Installation w/o Profit (TRY)	43.148,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**53.935,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.2101	**0.05 to 0.10 m² (including 0.10 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2101	0.05 to 0.10 m² (including 0.10 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	1.885,52	1.885,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	1.885,52	551,90
				Material and Installation w/o Profit (TRY)	2.437,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**689,88**	
				Unit Price (TRY)	**3.046,78**	

Item No	Analysis Name					UoM
35.100.2102	**0.10 to 0.20 m² (including 0.20 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2102	0.10 to 0.20 m² (including 0.20 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	2.634,32	2.634,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,06	687,95		41,28
				Total Excluding Profit (TRY)	2.634,32	558,78
				Material and Installation w/o Profit (TRY)	3.193,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**698,47**	
				Unit Price (TRY)	**3.991,38**	

Item No	Analysis Name					UoM
35.100.2103	**0.20 to 0.30 m² (including 0.30 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2103	0.20 to 0.30 m² (including 0.30 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	3.406,00	3.406,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,07	687,95		48,16
				Total Excluding Profit (TRY)	3.406,00	565,66
				Material and Installation w/o Profit (TRY)	3.971,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**707,07**	
				Unit Price (TRY)	**4.964,57**	

Item No	Analysis Name					UoM
35.100.2104	**0.30 to 0.40 m² (including 0.40 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2104	0.30 to 0.40 m² (including 0.40 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	4.154,80	4.154,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	4.154,80	579,42
				Material and Installation w/o Profit (TRY)	4.734,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**724,27**	
				Unit Price (TRY)	**5.917,78**	

Item No	Analysis Name					UoM
35.100.2105	**0.40 to 0.50 m² (including 0.50 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2105	0.40 to 0.50 m² (including 0.50 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	4.891,12	4.891,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	4.891,12	586,30
				Material and Installation w/o Profit (TRY)	5.477,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**6.846,77**	

Item No	Analysis Name					UoM
35.100.2106	**0.50 to 0.60 m² (including 0.60 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2106	0.50 to 0.60 m² (including 0.60 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	5.647,20	5.647,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,11	687,95		75,67
				Total Excluding Profit (TRY)	5.647,20	593,17
				Material and Installation w/o Profit (TRY)	6.240,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**741,46**	
				Unit Price (TRY)	**7.800,46**	

Item No	Analysis Name					UoM
35.100.2107	**0.60 to 0.70 m² (including 0.70 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2107	0.60 to 0.70 m² (including 0.70 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	6.385,60	6.385,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,12	687,95		82,55
				Total Excluding Profit (TRY)	6.385,60	600,05
				Material and Installation w/o Profit (TRY)	6.985,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**750,06**	
				Unit Price (TRY)	**8.732,06**	

Item No	Analysis Name					UoM
35.100.2108	**0.70 to 0.80 m² (including 0.80 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2108	0.70 to 0.80 m² (including 0.80 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	7.155,20	7.155,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,13	687,95		89,43
				Total Excluding Profit (TRY)	7.155,20	606,93
				Material and Installation w/o Profit (TRY)	7.762,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**758,66**	
				Unit Price (TRY)	**9.702,66**	

Item No	Analysis Name					UoM
35.100.2109	**0.80 to 0.90 m² (including 0.90 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2109	0.80 to 0.90 m² (including 0.90 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	7.904,00	7.904,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,14	687,95		96,31
				Total Excluding Profit (TRY)	7.904,00	613,81
				Material and Installation w/o Profit (TRY)	8.517,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**767,26**	
				Unit Price (TRY)	**10.647,26**	

Item No	Analysis Name					UoM
35.100.2110	**0.90 to 1.00 m² (including 0.10 m²) / Surface-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2110	0.90 to 1.00 m² (including 0.10 m²) / Surface-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	8.655,92	8.655,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,15	687,95		103,19
				Total Excluding Profit (TRY)	8.655,92	620,69
				Material and Installation w/o Profit (TRY)	9.276,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**775,86**	
				Unit Price (TRY)	**11.595,76**	

Item No	Analysis Name					UoM
35.100.2201	**0.05 to 0.10 m² (including 0.10 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2201	0.05 to 0.10 m² (including 0.10 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	1.979,12	1.979,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	1.979,12	545,02
				Material and Installation w/o Profit (TRY)	2.524,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**681,27**	
				Unit Price (TRY)	**3.155,17**	

Item No	Analysis Name					UoM
35.100.2202	**0.10 to 0.20 m² (including 0.20 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2202	0.10 to 0.20 m² (including 0.20 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	2.759,12	2.759,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	2.759,12	551,90
				Material and Installation w/o Profit (TRY)	3.311,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**689,88**	
				Unit Price (TRY)	**4.138,77**	

Item No	Analysis Name					UoM
35.100.2203	**0.20 to 0.30 m² (including 0.30 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2203	0.20 to 0.30 m² (including 0.30 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	3.572,40	3.572,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,07	687,95		48,16
				Total Excluding Profit (TRY)	3.572,40	565,66
				Material and Installation w/o Profit (TRY)	4.138,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**707,07**	
				Unit Price (TRY)	**5.172,58**	

Item No	Analysis Name					UoM
35.100.2204	**0.30 to 0.40 m² (including 0.40 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2204	0.30 to 0.40 m² (including 0.40 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	4.352,40	4.352,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,08	687,95		55,04
				Total Excluding Profit (TRY)	4.352,40	572,54
				Material and Installation w/o Profit (TRY)	4.924,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**715,67**	
				Unit Price (TRY)	**6.156,17**	

Item No	Analysis Name					UoM
35.100.2205	**0.40 to 0.50 m² (including 0.50 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2205	0.40 to 0.50 m² (including 0.50 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	5.130,32	5.130,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	5.130,32	579,42
				Material and Installation w/o Profit (TRY)	5.709,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**724,27**	
				Unit Price (TRY)	**7.137,17**	

Item No	Analysis Name					UoM
35.100.2206	**0.50 to 0.60 m² (including 0.60 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2206	0.50 to 0.60 m² (including 0.60 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	5.917,60	5.917,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	5.917,60	586,30
				Material and Installation w/o Profit (TRY)	6.503,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**8.129,88**	

Item No	Analysis Name					UoM
35.100.2207	**0.60 to 0.70 m² (including 0.70 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2207	0.60 to 0.70 m² (including 0.70 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	6.697,60	6.697,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,11	687,95		75,67
				Total Excluding Profit (TRY)	6.697,60	593,17
				Material and Installation w/o Profit (TRY)	7.290,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**741,46**	
				Unit Price (TRY)	**9.113,46**	

Item No	Analysis Name					UoM
35.100.2208	**0.70 to 0.80 m² (including 0.80 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2208	0.70 to 0.80 m² (including 0.80 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	7.498,40	7.498,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,12	687,95		82,55
				Total Excluding Profit (TRY)	7.498,40	600,05
				Material and Installation w/o Profit (TRY)	8.098,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**750,06**	
				Unit Price (TRY)	**10.123,06**	

Item No	Analysis Name					UoM
35.100.2209	**0.80 to 0.90 m² (including 0.90 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2209	0.80 to 0.90 m² (including 0.90 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	8.288,80	8.288,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,13	687,95		89,43
				Total Excluding Profit (TRY)	8.288,80	606,93
				Material and Installation w/o Profit (TRY)	8.895,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**758,66**	
				Unit Price (TRY)	**11.119,66**	

Item No	Analysis Name					UoM
35.100.2210	**0.90 to 1.00 m² (including 0.10 m²) / Flush-mounted galvanized steel electric panels / Galvanized Steel Electric Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.2210	0.90 to 1.00 m² (including 0.10 m²) / Flush-mounted galvanized steel electric panels / Enclosures (Market price)	Qty	1	9.071,92	9.071,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,14	687,95		96,31
				Total Excluding Profit (TRY)	9.071,92	613,81
				Material and Installation w/o Profit (TRY)	9.685,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**767,26**	
				Unit Price (TRY)	**12.107,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.6101	**800 mm width / Steel enclosures (1st enclosure) (TS 3367 EN 60439-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6101	With 800 mm width / Steel enclosures (1st enclosure) (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	26.416,00	26.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	26.416,00	2.931,48
				Material and Installation w/o Profit (TRY)	29.347,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**36.684,35**	

Item No	Analysis Name					UoM
35.100.6102	**900 mm width / Steel enclosures (1st enclosure) (TS 3367 EN 60439-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6102	900 mm width / Steel enclosures (1st enclosure) (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	28.579,20	28.579,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	28.579,20	2.931,48
				Material and Installation w/o Profit (TRY)	31.510,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**39.388,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.6201	**Enclosures with front cover / Special steel enclosures (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6201	Enclosures with front cover / Special steel enclosures (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	24.211,20	24.211,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	24.211,20	2.931,48
				Material and Installation w/o Profit (TRY)	27.142,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**33.928,35**	

Item No	Analysis Name					UoM
35.100.6202	**Enclosures with front and back cover / Special steel enclosures (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6202	Enclosures with front and back cover / Special steel enclosures (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	25.625,60	25.625,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	25.625,60	2.931,48
				Material and Installation w/o Profit (TRY)	28.557,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**35.696,35**	

Item No	Analysis Name					UoM
35.100.6301	**800 mm width / Additional steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6301	With 800 mm width / Additional steel enclosures / Enclosures (Market price)	Qty	1	17.752,80	17.752,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	17.752,80	2.931,48
				Material and Installation w/o Profit (TRY)	20.684,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**25.855,35**	

Item No	Analysis Name					UoM
35.100.6302	**900 mm width / Additional steel enclosures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6302	900 mm width / Additional steel enclosures / Enclosures (Market price)	Qty	1	20.384,00	20.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	20.384,00	2.931,48
				Material and Installation w/o Profit (TRY)	23.315,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,35**	
				Unit Price (TRY)	**29.144,35**	

Item No	Analysis Name					UoM
35.100.6350	**Steel cover with wire mesh**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6350	Wire-mesh steel sheet door / Panels (Market price)	Qty	1	937,04	937,04	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	937,04	1.035,00
				Material and Installation w/o Profit (TRY)	1.972,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**2.465,05**	

Item No	Analysis Name					UoM
35.100.6351	**Housing with wire mesh**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6351	Wire-mesh guard / Panels (Market price)	Qty	1	812,24	812,24	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	812,24	1.035,00
				Material and Installation w/o Profit (TRY)	1.847,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**2.309,05**	

Item No	Analysis Name					UoM
35.100.6401	**0.05 to 0.10 m² (including 0.10 m²) / Surface-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6401	0.05 to 0.10 m² (including 0.10 m²) / Surface-mounted steel electric panels (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	1.511,12	1.511,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	1.511,12	551,90
				Material and Installation w/o Profit (TRY)	2.063,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**689,88**	
				Unit Price (TRY)	**2.578,78**	

Item No	Analysis Name					UoM
35.100.6402	**0.10 to 0.20 m² (including 0.20 m²) / Surface-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6402	0.10 to 0.20 m² (including 0.20 m²) / Surface-mounted steel electric panels (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	2.135,12	2.135,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,06	687,95		41,28
				Total Excluding Profit (TRY)	2.135,12	558,78
				Material and Installation w/o Profit (TRY)	2.693,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**698,47**	
				Unit Price (TRY)	**3.367,37**	

Item No	Analysis Name					UoM
35.100.6403	**0.20 to 0.30 m² (including 0.30 m²) / Surface-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6403	0.20 to 0.30 m² (including 0.30 m²) / Surface-mounted steel electric panels (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	2.740,40	2.740,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,07	687,95		48,16
				Total Excluding Profit (TRY)	2.740,40	565,66
				Material and Installation w/o Profit (TRY)	3.306,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**707,07**	
				Unit Price (TRY)	**4.132,57**	

Item No	Analysis Name					UoM
35.100.6404	**0.30 to 0.40 m² (including 0.40 m²) / Surface-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6404	0.30 to 0.40 m² (including 0.40 m²) / Surface-mounted steel electric panels (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	3.936,40	3.936,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	3.936,40	579,42
				Material and Installation w/o Profit (TRY)	4.515,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**724,27**	
				Unit Price (TRY)	**5.644,77**	

Item No	Analysis Name					UoM
35.100.6405	**0.40 to 0.50 m² (including 0.50 m²) / Surface-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6405	0.40 to 0.50 m² (including 0.50 m²) / Surface-mounted steel electric panels (TS 3367 EN 60439-1) / Enclosures (Market price)	Qty	1	4.867,20	4.867,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	4.867,20	586,30
				Material and Installation w/o Profit (TRY)	5.453,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**6.816,88**	

Item No	Analysis Name					UoM
35.100.6501	**0.05 to 0.10 m² (including 0.10 m²) / Flush-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6501	0.05 to 0.10 m² (including 0.10 m²) / Flush-mounted steel electric panels (Market price)	Qty	1	1.563,12	1.563,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	1.563,12	545,02
				Material and Installation w/o Profit (TRY)	2.108,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**681,27**	
				Unit Price (TRY)	**2.635,17**	

Item No	Analysis Name					UoM
35.100.6502	**0.10 to 0.20 m² (including 0.20 m²) / Flush-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6502	0.10 to 0.20 m² (including 0.20 m²) / Flush-mounted steel electric panels (Market price)	Qty	1	2.228,72	2.228,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	2.228,72	551,90
				Material and Installation w/o Profit (TRY)	2.780,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**689,88**	
				Unit Price (TRY)	**3.475,77**	

Item No	Analysis Name					UoM
35.100.6503	**0.20 to 0.30 m² (including 0.30 m²) / Flush-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6503	0.20 to 0.30 m² (including 0.30 m²) / Flush-mounted steel electric panels (Market price)	Qty	1	3.083,60	3.083,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,07	687,95		48,16
				Total Excluding Profit (TRY)	3.083,60	565,66
				Material and Installation w/o Profit (TRY)	3.649,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**707,07**	
				Unit Price (TRY)	**4.561,57**	

Item No	Analysis Name					UoM
35.100.6504	**0.30 to 0.40 m² (including 0.40 m²) / Flush-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6504	0.30 to 0.40 m² (including 0.40 m²) / Flush-mounted steel electric panels (Market price)	Qty	1	4.466,80	4.466,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,08	687,95		55,04
				Total Excluding Profit (TRY)	4.466,80	572,54
				Material and Installation w/o Profit (TRY)	5.039,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**715,67**	
				Unit Price (TRY)	**6.299,18**	

Item No	Analysis Name					UoM
35.100.6505	**0.40 to 0.50 m² (including 0.50 m²) / Flush-mounted electric panels (TS 3367 EN 60439-1) Note: "Type tests" shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6505	0.40 to 0.50 m² (including 0.50 m²) / Flush-mounted steel electric panels (Market price)	Qty	1	5.501,60	5.501,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	5.501,60	579,42
				Material and Installation w/o Profit (TRY)	6.081,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**724,27**	
				Unit Price (TRY)	**7.601,28**	

Item No	Analysis Name					UoM
35.100.6560	**Government lodging-type steel electric panels up to 0.05 m² Note: ″Type tests″ shall be run, and the results of such tests shall be submitted to the Administration.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6560	Government lodging-type steel electric panels up to 0.05 m² / Enclosures (Market price)	Qty	1	1.357,20	1.357,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	1.357,20	538,14
				Material and Installation w/o Profit (TRY)	1.895,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**2.369,18**	

Item No	Analysis Name					UoM
35.100.6581	**4-fuse / Government lodging-type electric panel with automatic breaker**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6581	4-fuse / Government lodging-type electric panel with automatic breaker / Enclosures (Market price)	Qty	1	254,00	254,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,006	687,95		4,13
				Total Excluding Profit (TRY)	254,00	262,88
				Material and Installation w/o Profit (TRY)	516,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**328,60**	
				Unit Price (TRY)	**646,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.6582	**8-fuse / Government lodging-type electric panel with automatic breaker**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6582	8-fuse / Government lodging-type electric panel with automatic breaker / Enclosures (Market price)	Qty	1	320,00	320,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,007	687,95		4,82
				Total Excluding Profit (TRY)	320,00	263,57
				Material and Installation w/o Profit (TRY)	583,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**329,46**	
				Unit Price (TRY)	**729,46**	

Item No	Analysis Name					UoM
35.100.6583	**12-fuse / Government lodging-type electric panel with automatic breaker**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.6583	12-fuse / Government lodging-type electric panel with automatic breaker / Enclosures (Market price)	Qty	1	392,00	392,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,008	687,95		5,50
				Total Excluding Profit (TRY)	392,00	264,25
				Material and Installation w/o Profit (TRY)	656,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**330,31**	
				Unit Price (TRY)	**820,31**	

Item No	Analysis Name					UoM
35.100.7000	**Supply and installation, and coloring in compliance with TS EN 60445 of TSE-compliant copper busbars to be placed in cast metal boxes and enclosures**					**Kg**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7000	Supply and installation, and coloring in compliance with TS EN 60445 of TSE-compliant copper busbars to be placed in cast metal boxes and enclosures / Enclosures (Market price)	Kg	1	476,84	476,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			476,84	258,75
		Material and Installation w/o Profit (TRY)			735,59	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**919,49**	

Item No	Analysis Name					UoM
35.100.7101	**4 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7101	4 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	165,36	165,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,002	687,95		1,38
		Total Excluding Profit (TRY)			165,36	260,13
		Material and Installation w/o Profit (TRY)			425,49	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**325,16**	
		Unit Price (TRY)			**531,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.7102	**6 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7102	6 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	249,60	249,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,002	687,95		1,38
		Total Excluding Profit (TRY)			249,60	260,13
		Material and Installation w/o Profit (TRY)			509,73	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**325,16**	
		Unit Price (TRY)			**637,16**	

Item No	Analysis Name					UoM
35.100.7103	**8 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7103	8 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	336,96	336,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,003	687,95		2,06
		Total Excluding Profit (TRY)			336,96	260,81
		Material and Installation w/o Profit (TRY)			597,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**326,01**	
		Unit Price (TRY)			**747,21**	

Item No	Analysis Name					UoM
35.100.7104	**12 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7104	12 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	422,24	422,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,004	687,95		2,75
				Total Excluding Profit (TRY)	422,24	261,50
				Material and Installation w/o Profit (TRY)	683,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**326,88**	
				Unit Price (TRY)	**854,67**	

Item No	Analysis Name					UoM
35.100.7105	**16 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7105	16 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	567,84	567,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,004	687,95		2,75
				Total Excluding Profit (TRY)	567,84	261,50
				Material and Installation w/o Profit (TRY)	829,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**326,88**	
				Unit Price (TRY)	**1.036,67**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.7106	**18 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7106	18 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	718,64	718,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,005	687,95		3,44
				Total Excluding Profit (TRY)	718,64	262,19
				Material and Installation w/o Profit (TRY)	980,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**327,74**	
				Unit Price (TRY)	**1.226,04**	

Item No	Analysis Name					UoM
35.100.7107	**24 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7107	24 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	826,80	826,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,006	687,95		4,13
				Total Excluding Profit (TRY)	826,80	262,88
				Material and Installation w/o Profit (TRY)	1.089,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**328,60**	
				Unit Price (TRY)	**1.362,10**	

Item No	Analysis Name					UoM
35.100.7108	**36 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7108	36 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels / Enclosures (Market price)	Qty	1	1.118,00	1.118,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,007	687,95		4,82
				Total Excluding Profit (TRY)	1.118,00	263,57
				Material and Installation w/o Profit (TRY)	1.381,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**329,46**	
				Unit Price (TRY)	**1.726,96**	

Item No	Analysis Name					UoM
35.100.7201	**4 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7201	4 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	165,36	165,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,002	687,95		1,38
				Total Excluding Profit (TRY)	165,36	260,13
				Material and Installation w/o Profit (TRY)	425,49	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**325,16**	
				Unit Price (TRY)	**531,86**	

Item No	Analysis Name					UoM
35.100.7202	**6 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7202	6 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	249,60	249,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,002	687,95		1,38
		Total Excluding Profit (TRY)			249,60	260,13
		Material and Installation w/o Profit (TRY)			509,73	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**325,16**	
		Unit Price (TRY)			**637,16**	

Item No	Analysis Name					UoM
35.100.7203	**8 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7203	8 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	336,96	336,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,003	687,95		2,06
		Total Excluding Profit (TRY)			336,96	260,81
		Material and Installation w/o Profit (TRY)			597,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**326,01**	
		Unit Price (TRY)			**747,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.100.7204	**12 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7204	12 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	422,24	422,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,004	687,95		2,75
				Total Excluding Profit (TRY)	422,24	261,50
				Material and Installation w/o Profit (TRY)	683,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**326,88**	
				Unit Price (TRY)	**854,67**	

Item No	Analysis Name					UoM
35.100.7205	**16 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7205	16 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	567,84	567,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,004	687,95		2,75
				Total Excluding Profit (TRY)	567,84	261,50
				Material and Installation w/o Profit (TRY)	829,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**326,88**	
				Unit Price (TRY)	**1.036,67**	

Item No	Analysis Name					UoM
35.100.7206	**18 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7206	18 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	718,64	718,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,005	687,95		3,44
				Total Excluding Profit (TRY)	718,64	262,19
				Material and Installation w/o Profit (TRY)	980,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**327,74**	
				Unit Price (TRY)	**1.226,04**	

Item No	Analysis Name					UoM
35.100.7207	**24 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7207	24 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	826,80	826,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,006	687,95		4,13
				Total Excluding Profit (TRY)	826,80	262,88
				Material and Installation w/o Profit (TRY)	1.089,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**328,60**	
				Unit Price (TRY)	**1.362,10**	

Item No	Analysis Name					UoM
35.100.7208	**36 Automated fuse / Halogen-free, flame-retardant, surface-mounted panels.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.100.7208	36 Automated fuse / Halogen-free, flame-retardant, flush-mounted panels / Enclosures (Market price)	Qty	1	1.118,00	1.118,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,007	687,95		4,82
				Total Excluding Profit (TRY)	1.118,00	263,57
				Material and Installation w/o Profit (TRY)	1.381,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**329,46**	
				Unit Price (TRY)	**1.726,96**	

Item No	Analysis Name					UoM
35.105.1110	**Up to 16 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1110	Up to 16 A (at least 3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses (Market price)	Qty	1	69,14	69,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	69,14	103,50
				Material and Installation w/o Profit (TRY)	172,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**215,80**	

Item No	Analysis Name					UoM
35.105.1111	**Up to 25 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1111	Up to 25 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	69,14	69,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			69,14	103,50
		Material and Installation w/o Profit (TRY)			172,64	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**215,80**	

Item No	Analysis Name					UoM
35.105.1112	**Up to 40 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / (TS 5018-1 EN 60898-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1112	Up to 40 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	96,98	96,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			96,98	103,50
		Material and Installation w/o Profit (TRY)			200,48	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**250,60**	

Item No	Analysis Name					UoM
35.105.1113	**Up to 63 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1113	Up to 63 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	129,46	129,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			129,46	103,50
		Material and Installation w/o Profit (TRY)			232,96	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**291,20**	

Item No	Analysis Name					UoM
35.105.1120	**Single-phase, max. 16 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / (TS 5018-1 EN 60898-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1120	Single-phase, neutral-breaking, max. 16 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	171,38	171,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			171,38	103,50
		Material and Installation w/o Profit (TRY)			274,88	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**343,60**	

Item No	Analysis Name					UoM
35.105.1121	**Single-phase, max. 25 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / (TS 5018-1 EN 60898-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1121	Single-phase, neutral-breaking, max. 25 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	171,38	171,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	171,38	103,50
				Material and Installation w/o Profit (TRY)	274,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**343,60**	

Item No	Analysis Name					UoM
35.105.1122	**Single-phase, neutral-breaking, max. 40 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1122	Single-phase, neutral-breaking, max. 40 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	264,78	264,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	264,78	103,50
				Material and Installation w/o Profit (TRY)	368,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**460,35**	

Item No	Analysis Name					UoM
35.105.1123	**Single-phase, neutral-breaking, max. 63 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1123	Single-phase, neutral-breaking, max. 63 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	376,18	376,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	376,18	103,50
				Material and Installation w/o Profit (TRY)	479,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**599,60**	

Item No	Analysis Name					UoM
35.105.1130	**3-phase, max. 16 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1130	3-phase, max. 16 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	302,99	302,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	302,99	103,50
				Material and Installation w/o Profit (TRY)	406,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**508,11**	

Item No	Analysis Name					UoM
35.105.1131	**3-phase, max. 25 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / (TS 5018-1 EN 60898-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1131	3-phase, max. 25 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	302,99	302,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	302,99	103,50
				Material and Installation w/o Profit (TRY)	406,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**508,11**	

Item No	Analysis Name					UoM
35.105.1132	**3-phase, max. 40 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1132	3-phase, max. 40 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	363,31	363,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	363,31	103,50
				Material and Installation w/o Profit (TRY)	466,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**583,51**	

Item No	Analysis Name					UoM
35.105.1133	**3-phase, max. 63 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1133	3-phase, max. 63 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	473,74	473,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	473,74	103,50
				Material and Installation w/o Profit (TRY)	577,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**721,55**	

Item No	Analysis Name					UoM
35.105.1140	**3-phase, neutral-breaking, max. 16 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1140	3-phase, neutral-breaking, max. 16 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	390,28	390,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	390,28	103,50
				Material and Installation w/o Profit (TRY)	493,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**617,22**	

Item No	Analysis Name					UoM
35.105.1141	**3-phase, max. 25 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / (TS 5018-1 EN 60898-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1141	3-phase, neutral-breaking, max. 25 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	390,28	390,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	390,28	103,50
				Material and Installation w/o Profit (TRY)	493,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**617,22**	

Item No	Analysis Name					UoM
35.105.1142	**3-phase, neutral-breaking, max. 40 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1142	3-phase, neutral-breaking, max. 40 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	490,04	490,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	490,04	103,50
				Material and Installation w/o Profit (TRY)	593,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**741,92**	

Item No	Analysis Name					UoM
35.105.1143	**3-phase, neutral-breaking, max. 63 A (3 kA) / Switched Automatic Fuses (3 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1143	3-phase, neutral-breaking, max. 63 A (at least 3 kA) / Switched Automatic Fuses (at least 3 kA breaking capacity) / Fuses (Market price)	Qty	1	634,58	634,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	634,58	103,50
				Material and Installation w/o Profit (TRY)	738,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**922,60**	

Item No	Analysis Name					UoM
35.105.1210	**Up to 16 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1210	Up to 16 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	81,20	81,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	81,20	103,50
				Material and Installation w/o Profit (TRY)	184,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**230,88**	

Item No	Analysis Name					UoM
35.105.1211	**Up to 25 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1211	Up to 25 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	81,20	81,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			81,20	103,50
		Material and Installation w/o Profit (TRY)			184,70	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**230,88**	

Item No	Analysis Name					UoM
35.105.1212	**Up to 40 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1212	Up to 40 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	114,61	114,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			114,61	103,50
		Material and Installation w/o Profit (TRY)			218,11	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**272,64**	

Item No	Analysis Name					UoM
35.105.1213	**Up to 63 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1213	Up to 63 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	168,43	168,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	168,43	103,50
				Material and Installation w/o Profit (TRY)	271,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**339,91**	

Item No	Analysis Name					UoM
35.105.1220	**Single-phase, neutral-breaking, max. 16 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1220	Single-phase, neutral-breaking, max. 16 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	242,67	242,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	242,67	103,50
				Material and Installation w/o Profit (TRY)	346,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**432,71**	

Item No	Analysis Name					UoM
35.105.1221	**Single-phase, neutral-breaking, max. 25 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1221	Single-phase, neutral-breaking, max. 25 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	247,31	247,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	247,31	103,50
				Material and Installation w/o Profit (TRY)	350,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**438,51**	

Item No	Analysis Name					UoM
35.105.1222	**Single-phase, neutral-breaking, max. 40 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1222	Single-phase, neutral-breaking, max. 40 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	308,56	308,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	308,56	103,50
				Material and Installation w/o Profit (TRY)	412,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**515,08**	

Item No	Analysis Name					UoM
35.105.1223	**Single-phase, neutral-breaking, max. 63 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1223	Single-phase, neutral-breaking, max. 63 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	416,21	416,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	416,21	103,50
				Material and Installation w/o Profit (TRY)	519,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**649,64**	

Item No	Analysis Name					UoM
35.105.1230	**3-phase, max. 16 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1230	3-phase, max. 16 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	366,10	366,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	366,10	103,50
				Material and Installation w/o Profit (TRY)	469,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**587,00**	

Item No	Analysis Name					UoM
35.105.1231	**3-phase, max. 25 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1231	3-phase, max. 25 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	366,10	366,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	366,10	103,50
				Material and Installation w/o Profit (TRY)	469,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**587,00**	

Item No	Analysis Name					UoM
35.105.1232	**3-phase, max. 40 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1232	3-phase, max. 40 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	435,70	435,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	435,70	103,50
				Material and Installation w/o Profit (TRY)	539,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**674,00**	

Item No	Analysis Name					UoM
35.105.1233	**3-phase, max. 63 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1233	3-phase, max. 63 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	599,02	599,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	599,02	103,50
				Material and Installation w/o Profit (TRY)	702,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**878,15**	

Item No	Analysis Name					UoM
35.105.1240	**3-phase, neutral-breaking, max. 16 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1240	3-phase, neutral-breaking, max. 16 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	573,04	573,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	573,04	103,50
				Material and Installation w/o Profit (TRY)	676,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**845,67**	

Item No	Analysis Name					UoM
35.105.1241	**3-phase, neutral-breaking, max. 25 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1241	3-phase, neutral-breaking, max. 25 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	577,68	577,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	577,68	103,50
				Material and Installation w/o Profit (TRY)	681,18	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**851,47**	

Item No	Analysis Name					UoM
35.105.1242	**3-phase, neutral-breaking, max. 40 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1242	3-phase, neutral-breaking, max. 40 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	644,50	644,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	644,50	103,50
				Material and Installation w/o Profit (TRY)	748,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**935,00**	

Item No	Analysis Name					UoM
35.105.1243	**3-phase, neutral-breaking, max. 63 A (6 kA) / Switched Automatic Fuses (6 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1243	3-phase, neutral-breaking, max. 63 A (at least 6 kA) / Switched Automatic Fuses (at least 6 kA breaking capacity) / Fuses (Market price)	Qty	1	832,88	832,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	832,88	103,50
				Material and Installation w/o Profit (TRY)	936,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**1.170,47**	

Item No	Analysis Name					UoM
35.105.1310	**Up to 16 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1310	Up to 16 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	137,81	137,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	137,81	103,50
				Material and Installation w/o Profit (TRY)	241,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**301,64**	

Item No	Analysis Name					UoM
35.105.1311	**Up to 25 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1311	Up to 25 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	138,74	138,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	138,74	103,50
				Material and Installation w/o Profit (TRY)	242,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**302,80**	

Item No	Analysis Name					UoM
35.105.1312	**Up to 40 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1312	Up to 40 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	179,57	179,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	179,57	103,50
				Material and Installation w/o Profit (TRY)	283,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**353,84**	

Item No	Analysis Name					UoM
35.105.1313	**Up to 63 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1313	Up to 63 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	246,38	246,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	246,38	103,50
				Material and Installation w/o Profit (TRY)	349,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**437,35**	

Item No	Analysis Name					UoM
35.105.1320	**Single-phase, neutral-breaking, max. 16 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1320	Single-phase, neutral-breaking, max. 16 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	289,68	289,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	289,68	103,50
				Material and Installation w/o Profit (TRY)	393,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**491,48**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.105.1321	**Single-phase, neutral-breaking, max. 25 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1321	Single-phase, neutral-breaking, max. 25 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	291,66	291,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	291,66	103,50
				Material and Installation w/o Profit (TRY)	395,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**493,95**	

Item No	Analysis Name					UoM
35.105.1322	**Single-phase, neutral-breaking, max. 40 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1322	Single-phase, neutral-breaking, max. 40 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	347,56	347,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	347,56	103,50
				Material and Installation w/o Profit (TRY)	451,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**563,83**	

Item No	Analysis Name					UoM
35.105.1323	**Single-phase, neutral-breaking, max. 63 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1323	Single-phase, neutral-breaking, max. 63 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	524,41	524,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	524,41	103,50
				Material and Installation w/o Profit (TRY)	627,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**784,89**	

Item No	Analysis Name					UoM
35.105.1330	**3-phase, max. 16 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1330	3-phase, max. 16 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	544,27	544,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	544,27	103,50
				Material and Installation w/o Profit (TRY)	647,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**809,71**	

Item No	Analysis Name					UoM
35.105.1331	**3-phase, max. 25 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1331	3-phase, max. 25 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	545,20	545,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	545,20	103,50
				Material and Installation w/o Profit (TRY)	648,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**810,88**	

Item No	Analysis Name					UoM
35.105.1332	**3-phase, max. 40 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1332	3-phase, max. 40 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	650,06	650,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	650,06	103,50
				Material and Installation w/o Profit (TRY)	753,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**941,95**	

Item No	Analysis Name					UoM
35.105.1333	**3-phase, max. 63 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1333	3-phase, max. 63 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	934,96	934,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
			Total Excluding Profit (TRY)		934,96	103,50
			Material and Installation w/o Profit (TRY)		1.038,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**1.298,08**	

Item No	Analysis Name					UoM
35.105.1340	**3-phase, neutral-breaking, max. 16 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1340	3-phase, neutral-breaking, max. 16 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	624,48	624,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
			Total Excluding Profit (TRY)		624,48	103,50
			Material and Installation w/o Profit (TRY)		727,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**909,98**	

Item No	Analysis Name					UoM
35.105.1341	**3-phase, neutral-breaking, max. 25 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1341	3-phase, neutral-breaking, max. 25 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	625,84	625,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	625,84	103,50
				Material and Installation w/o Profit (TRY)	729,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**911,68**	

Item No	Analysis Name					UoM
35.105.1342	**3-phase, neutral-breaking, max. 40 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1342	3-phase, neutral-breaking, max. 40 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	751,73	751,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	751,73	103,50
				Material and Installation w/o Profit (TRY)	855,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**1.069,04**	

Item No	Analysis Name					UoM
35.105.1343	**3-phase, neutral-breaking, max. 63 A (10 kA) / Switched Automatic Fuses (10 kA breaking capacity) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1343	3-phase, neutral-breaking, max. 63 A (at least 10 kA) / Switched Automatic Fuses (at least 10 kA breaking capacity) / Fuses (Market price)	Qty	1	1.034,94	1.034,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	1.034,94	103,50
				Material and Installation w/o Profit (TRY)	1.138,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**1.423,05**	

Item No	Analysis Name					UoM
35.105.1501	**Up to 25 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1501	Up to 25 A / Knife Fuses / Fuses (Market price)	Qty	1	232,40	232,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	232,40	171,75
				Material and Installation w/o Profit (TRY)	404,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**505,19**	

Item No	Analysis Name					UoM
35.105.1502	**Up to 63 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1502	Up to 63 A / Knife Fuses / Fuses (Market price)	Qty	1	232,40	232,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	232,40	171,75
				Material and Installation w/o Profit (TRY)	404,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**505,19**	

Item No	Analysis Name					UoM
35.105.1503	**Up to 100 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1503	Up to 100 A / Knife Fuses / Fuses (Market price)	Qty	1	232,40	232,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	232,40	171,75
				Material and Installation w/o Profit (TRY)	404,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**505,19**	

Item No	Analysis Name					UoM
35.105.1504	**Up to 160 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1504	Up to 160 A / Knife Fuses / Fuses (Market price)	Qty	1	254,67	254,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	254,67	171,75
				Material and Installation w/o Profit (TRY)	426,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**533,02**	

Item No	Analysis Name					UoM
35.105.1505	**Up to 250 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1505	Up to 250 A / Knife Fuses / Fuses (Market price)	Qty	1	410,58	410,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	410,58	171,75
				Material and Installation w/o Profit (TRY)	582,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**727,91**	

Item No	Analysis Name					UoM
35.105.1506	**Up to 400 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1506	Up to 400 A / Knife Fuses / Fuses (Market price)	Qty	1	577,62	577,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	577,62	171,75
				Material and Installation w/o Profit (TRY)	749,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**936,71**	

Item No	Analysis Name					UoM
35.105.1507	**Up to 630 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1507	Up to 630 A / Knife Fuses / Fuses (Market price)	Qty	1	976,66	976,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	976,66	171,75
				Material and Installation w/o Profit (TRY)	1.148,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**1.435,51**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.105.1508	**Up to 1,000 A / Knife Fuses (TS 86 EN 60269-1) / Fuses**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1508	Up to 1000 A / Knife Fuses / Fuses (Market price)	Qty	1	7.900,62	7.900,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	7.900,62	171,75
				Material and Installation w/o Profit (TRY)	8.072,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**10.090,46**	

Item No	Analysis Name					UoM
35.105.1601	**Up to 3 x 25 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1601	Up to 3 x 25 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3) / Fuses (Market price)	Qty	1	812,00	812,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	812,00	258,75
				Material and Installation w/o Profit (TRY)	1.070,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.338,44**	

Item No	Analysis Name					UoM
35.105.1602	**Up to 3 x 63 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1602	Up to 3 x 63 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3) / Fuses (Market price)	Qty	1	812,00	812,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	812,00	258,75
				Material and Installation w/o Profit (TRY)	1.070,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.338,44**	

Item No	Analysis Name					UoM
35.105.1603	**Up to 3 x 100 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1603	Up to 3 x 100 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3) / Fuses (Market price)	Qty	1	812,00	812,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	812,00	258,75
				Material and Installation w/o Profit (TRY)	1.070,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.338,44**	

Item No	Analysis Name					UoM
35.105.1604	**Up to 3 x 160 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1604	Up to 3 x 160 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3) / Fuses (Market price)	Qty	1	932,00	932,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	932,00	258,75
				Material and Installation w/o Profit (TRY)	1.190,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.488,44**	

Item No	Analysis Name					UoM
35.105.1605	**Up to 3 x 250 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1605	Up to 3 x 250 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3) / Fuses (Market price)	Qty	1	2.500,00	2.500,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.500,00	258,75
				Material and Installation w/o Profit (TRY)	2.758,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.448,44**	

Item No	Analysis Name					UoM
35.105.1606	**Up to 3 x 400 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1606	Up to 3 x 400 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3) / Fuses (Market price)	Qty	1	3.792,00	3.792,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.792,00	258,75
				Material and Installation w/o Profit (TRY)	4.050,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.063,44**	

Item No	Analysis Name					UoM
35.105.1607	**Up to 3 x 630 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.105.1607	Up to 3 x 630 A (3-phase) / Fuse Switches (Fuse Knife Disconnector) (TS EN 60947-3) / Fuses (Market price)	Qty	1	5.264,00	5.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.264,00	258,75
				Material and Installation w/o Profit (TRY)	5.522,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.903,44**	

Item No	Analysis Name					UoM
35.110.1101	**3 x 10 A to 3 x 63 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1101	3 x 10 A to 3 x 63 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.255,44	2.255,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.255,44	300,00
				Material and Installation w/o Profit (TRY)	2.555,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**3.194,30**	

Item No	Analysis Name					UoM
35.110.1102	**Up to 3 x 100 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1102	Up to 3 x 100 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.255,44	2.255,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.255,44	343,50
				Material and Installation w/o Profit (TRY)	2.598,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.248,68**	

Item No	Analysis Name					UoM
35.110.1103	**Up to 3 x 125 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1103	Up to 3 x 125 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.941,84	2.941,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	2.941,84	387,00
				Material and Installation w/o Profit (TRY)	3.328,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.161,05**	

Item No	Analysis Name					UoM
35.110.1104	**Up to 3 x 160 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1104	Up to 3 x 160 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.038,64	3.038,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.038,64	387,00
				Material and Installation w/o Profit (TRY)	3.425,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.282,05**	

Item No	Analysis Name					UoM
35.110.1105	**Up to 3 x 200 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1105	Up to 3 x 200 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.777,84	3.777,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	3.777,84	430,50
				Material and Installation w/o Profit (TRY)	4.208,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**5.260,43**	

Item No	Analysis Name					UoM
35.110.1106	**Up to 3 x 250 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1106	Up to 3 x 250 A, Icu 35 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	4.253,04	4.253,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	4.253,04	430,50
				Material and Installation w/o Profit (TRY)	4.683,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**5.854,43**	

Item No	Analysis Name					UoM
35.110.1151	**Up to 3 x 400 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1151	Up to 3 x 400 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	11.222,64	11.222,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	11.222,64	430,50
				Material and Installation w/o Profit (TRY)	11.653,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**14.566,42**	

Item No	Analysis Name					UoM
35.110.1152	**Up to 3 x 500 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1152	Up to 3 x 500 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	12.938,64	12.938,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	12.938,64	474,00
				Material and Installation w/o Profit (TRY)	13.412,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**16.765,80**	

Item No	Analysis Name					UoM
35.110.1153	**Up to 3 x 630 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1153	Up to 3 x 630 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	15.103,44	15.103,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
			Total Excluding Profit (TRY)		15.103,44	474,00
			Material and Installation w/o Profit (TRY)		15.577,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**19.471,80**	

Item No	Analysis Name					UoM
35.110.1154	**Up to 3 x 800 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1154	Up to 3 x 800 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	24.352,24	24.352,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
			Total Excluding Profit (TRY)		24.352,24	517,50
			Material and Installation w/o Profit (TRY)		24.869,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**31.087,18**	

Item No	Analysis Name					UoM
35.110.1201	**3 x 10 A to 3 x 63 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1201	3 x 10 A to 3 x 63 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.317,04	2.317,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.317,04	300,00
				Material and Installation w/o Profit (TRY)	2.617,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**3.271,30**	

Item No	Analysis Name					UoM
35.110.1202	**Up to 3 x 100 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1202	Up to 3 x 100 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.317,04	2.317,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.317,04	343,50
				Material and Installation w/o Profit (TRY)	2.660,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.325,68**	

Item No	Analysis Name					UoM
35.110.1203	**Up to 3 x 125 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1203	Up to 3 x 125 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.017,28	3.017,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.017,28	387,00
				Material and Installation w/o Profit (TRY)	3.404,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.255,35**	

Item No	Analysis Name					UoM
35.110.1204	**Up to 3 x 160 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1204	Up to 3 x 160 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.113,28	3.113,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.113,28	387,00
				Material and Installation w/o Profit (TRY)	3.500,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.375,35**	

Item No	Analysis Name					UoM
35.110.1205	**Up to 3 x 200 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1205	Up to 3 x 200 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	4.112,24	4.112,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	4.112,24	430,50
				Material and Installation w/o Profit (TRY)	4.542,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**5.678,42**	

Item No	Analysis Name					UoM
35.110.1206	**Up to 3 x 250 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1206	Up to 3 x 250 A, Icu 50 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	4.490,64	4.490,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	4.490,64	430,50
				Material and Installation w/o Profit (TRY)	4.921,14	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**6.151,43**	

Item No	Analysis Name					UoM
35.110.1251	**Up to 3 x 400 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1251	Up to 3 x 400 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	12.947,44	12.947,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	12.947,44	430,50
				Material and Installation w/o Profit (TRY)	13.377,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**16.722,42**	

Item No	Analysis Name					UoM
35.110.1252	**Up to 3 x 500 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1252	Up to 3 x 500 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	15.041,84	15.041,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	15.041,84	474,00
				Material and Installation w/o Profit (TRY)	15.515,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**19.394,80**	

Item No	Analysis Name					UoM
35.110.1253	**Up to 3 x 630 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1253	Up to 3 x 630 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	16.951,44	16.951,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
			Total Excluding Profit (TRY)		16.951,44	474,00
			Material and Installation w/o Profit (TRY)		17.425,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**21.781,80**	

Item No	Analysis Name					UoM
35.110.1254	**Up to 3 x 800 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1254	Up to 3 x 800 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	23.331,44	23.331,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
			Total Excluding Profit (TRY)		23.331,44	517,50
			Material and Installation w/o Profit (TRY)		23.848,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**29.811,17**	

Item No	Analysis Name					UoM
35.110.1301	**Up to 3 x 1,000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1301	Up to 3 x 1,000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	32.777,36	32.777,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	32.777,36	517,50
				Material and Installation w/o Profit (TRY)	33.294,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**41.618,57**	

Item No	Analysis Name					UoM
35.110.1302	**Up to 3 x 1,250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1302	Up to 3 x 1,250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	35.153,36	35.153,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	35.153,36	517,50
				Material and Installation w/o Profit (TRY)	35.670,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**44.588,57**	

Item No	Analysis Name					UoM
35.110.1303	**Up to 3 x 1,600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1303	Up to 3 x 1,600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	48.265,36	48.265,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician's helper	h	1,25	185,00		231,25
				Total Excluding Profit (TRY)	48.265,36	626,25
				Material and Installation w/o Profit (TRY)	48.891,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**782,81**	
				Unit Price (TRY)	**61.114,51**	

Item No	Analysis Name					UoM
35.110.1351	**3 x 10 A to 3 x 63 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1351	3 x 10 A to 3 x 63 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.633,84	2.633,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.633,84	300,00
				Material and Installation w/o Profit (TRY)	2.933,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**3.667,30**	

Item No	Analysis Name					UoM
35.110.1352	**3 x 100 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1352	Up to 3 x 100 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.684,02	2.684,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.684,02	343,50
				Material and Installation w/o Profit (TRY)	3.027,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.784,40**	

Item No	Analysis Name					UoM
35.110.1353	**3 x 125 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1353	Up to 3 x 125 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.214,64	3.214,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.214,64	387,00
				Material and Installation w/o Profit (TRY)	3.601,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.502,05**	

Item No	Analysis Name					UoM
35.110.1354	**3 x 160 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1354	Up to 3 x 160 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.355,44	3.355,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.355,44	387,00
				Material and Installation w/o Profit (TRY)	3.742,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.678,05**	

Item No	Analysis Name					UoM
35.110.1355	**3 x 200 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1355	Up to 3 x 200 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	4.728,24	4.728,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	4.728,24	430,50
				Material and Installation w/o Profit (TRY)	5.158,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**6.448,42**	

Item No	Analysis Name					UoM
35.110.1356	**3 x 250 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1356	Up to 3 x 250 A, Icu 65 kA, I1 (0.8 - 1)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	5.229,84	5.229,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	5.229,84	430,50
				Material and Installation w/o Profit (TRY)	5.660,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**7.075,43**	

Item No	Analysis Name					UoM
35.110.1401	**Up to 3 x 400 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1401	Up to 3 x 400 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	15.525,84	15.525,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	15.525,84	430,50
				Material and Installation w/o Profit (TRY)	15.956,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**19.945,42**	

Item No	Analysis Name					UoM
35.110.1402	**Up to 3 x 500 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1402	Up to 3 x 500 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	17.919,44	17.919,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	17.919,44	474,00
				Material and Installation w/o Profit (TRY)	18.393,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**22.991,80**	

Item No	Analysis Name					UoM
35.110.1403	**Up to 3 x 630 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1403	Up to 3 x 630 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	19.952,24	19.952,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	19.952,24	474,00
				Material and Installation w/o Profit (TRY)	20.426,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**25.532,80**	

Item No	Analysis Name					UoM
35.110.1404	**Up to 3 x 800 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1404	Up to 3 x 800 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	28.153,84	28.153,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	28.153,84	517,50
				Material and Installation w/o Profit (TRY)	28.671,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**35.839,18**	

Item No	Analysis Name					UoM
35.110.1451	**Up to 3 x 1,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1451	Up to 3 x 1,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	40.274,96	40.274,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	40.274,96	517,50
				Material and Installation w/o Profit (TRY)	40.792,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**50.990,57**	

Item No	Analysis Name					UoM
35.110.1452	**Up to 3 x 1,250 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1452	Up to 3 x 1,250 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	41.630,16	41.630,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	41.630,16	517,50
				Material and Installation w/o Profit (TRY)	42.147,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**52.684,58**	

Item No	Analysis Name					UoM
35.110.1453	**Up to 3 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1453	Up to 3 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	50.130,96	50.130,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician's helper	h	1,25	185,00		231,25
				Total Excluding Profit (TRY)	50.130,96	626,25
				Material and Installation w/o Profit (TRY)	50.757,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**782,81**	
				Unit Price (TRY)	**63.446,51**	

Item No	Analysis Name					UoM
35.110.1501	**4 x 16 A to 4 x 63 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1501	4 x 16 A to 4 x 63 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.633,84	2.633,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.633,84	300,00
				Material and Installation w/o Profit (TRY)	2.933,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**3.667,30**	

Item No	Analysis Name					UoM
35.110.1502	**Up to 4 x 80, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1502	Up to 4 x 80, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.809,84	2.809,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.809,84	300,00
				Material and Installation w/o Profit (TRY)	3.109,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**3.887,30**	

Item No	Analysis Name					UoM
35.110.1503	**Up to 4 x 100, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1503	Up to 4 x 100 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	2.806,32	2.806,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.806,32	343,50
				Material and Installation w/o Profit (TRY)	3.149,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.937,28**	

Item No	Analysis Name					UoM
35.110.1504	**Up to 4 x 125, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1504	Up to 4 x 125 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.750,56	3.750,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.750,56	387,00
				Material and Installation w/o Profit (TRY)	4.137,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**5.171,95**	

Item No	Analysis Name					UoM
35.110.1505	**Up to 4 x 160, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1505	Up to 4 x 160 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.917,76	3.917,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.917,76	387,00
				Material and Installation w/o Profit (TRY)	4.304,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**5.380,95**	

Item No	Analysis Name					UoM
35.110.1506	**Up to 4 x 200 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1506	Up to 4 x 200 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	5.341,60	5.341,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	5.341,60	430,50
				Material and Installation w/o Profit (TRY)	5.772,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**7.215,13**	

Item No	Analysis Name					UoM
35.110.1507	**Up to 4 x 250 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1507	Up to 4 x 250 A, Icu 35 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	5.529,92	5.529,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	5.529,92	430,50
				Material and Installation w/o Profit (TRY)	5.960,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**7.450,52**	

Item No	Analysis Name					UoM
35.110.1551	**Up to 4 x 400 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1551	Up to 4 x 400 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	15.346,32	15.346,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	15.346,32	430,50
				Material and Installation w/o Profit (TRY)	15.776,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**19.721,03**	

Item No	Analysis Name					UoM
35.110.1552	**Up to 4 x 500 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1552	Up to 4 x 500 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	17.827,92	17.827,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	17.827,92	474,00
				Material and Installation w/o Profit (TRY)	18.301,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**22.877,40**	

Item No	Analysis Name					UoM
35.110.1553	**Up to 4 x 630 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1553	Up to 4 x 630 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	18.962,24	18.962,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	18.962,24	474,00
				Material and Installation w/o Profit (TRY)	19.436,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**24.295,30**	

Item No	Analysis Name					UoM
35.110.1554	**Up to 4 x 800 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1554	Up to 4 x 800 A, Icu 35 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 35 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	34.056,00	34.056,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	34.056,00	517,50
				Material and Installation w/o Profit (TRY)	34.573,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**43.216,88**	

Item No	Analysis Name					UoM
35.110.1601	**4 x 16 A to 4 x 63 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1601	4 x 16 A to 4 x 63 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.117,84	3.117,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.117,84	300,00
				Material and Installation w/o Profit (TRY)	3.417,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**4.272,30**	

Item No	Analysis Name					UoM
35.110.1602	**Up to 4 x 80 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1602	Up to 4 x 80 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.117,84	3.117,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.117,84	300,00
				Material and Installation w/o Profit (TRY)	3.417,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**4.272,30**	

Item No	Analysis Name					UoM
35.110.1603	**Up to 4 x 100 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1603	Up to 4 x 100 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.170,94	3.170,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	3.170,94	343,50
				Material and Installation w/o Profit (TRY)	3.514,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**4.393,05**	

Item No	Analysis Name					UoM
35.110.1604	**Up to 4 x 125 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1604	Up to 4 x 125 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.818,32	3.818,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.818,32	387,00
				Material and Installation w/o Profit (TRY)	4.205,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**5.256,65**	

Item No	Analysis Name					UoM
35.110.1605	**Up to 4 x 160 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1605	Up to 4 x 160 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	4.040,64	4.040,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	4.040,64	387,00
				Material and Installation w/o Profit (TRY)	4.427,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**5.534,55**	

Item No	Analysis Name					UoM
35.110.1606	**Up to 4 x 200 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1606	Up to 4 x 200 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	5.928,00	5.928,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	5.928,00	430,50
				Material and Installation w/o Profit (TRY)	6.358,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**7.948,13**	

Item No	Analysis Name					UoM
35.110.1607	**Up to 4 x 250 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1607	Up to 4 x 250 A, Icu 50 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	6.375,20	6.375,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	6.375,20	430,50
				Material and Installation w/o Profit (TRY)	6.805,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**8.507,13**	

Item No	Analysis Name					UoM
35.110.1651	**Up to 4 x 400 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1651	Up to 4 x 400 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	16.340,72	16.340,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	16.340,72	430,50
				Material and Installation w/o Profit (TRY)	16.771,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**20.964,03**	

Item No	Analysis Name					UoM
35.110.1652	**Up to 4 x 500 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1652	Up to 4 x 500 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	18.716,72	18.716,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	18.716,72	474,00
				Material and Installation w/o Profit (TRY)	19.190,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**23.988,40**	

Item No	Analysis Name					UoM
35.110.1653	**Up to 4 x 630 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1653	Up to 4 x 630 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	19.956,64	19.956,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	19.956,64	474,00
				Material and Installation w/o Profit (TRY)	20.430,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**25.538,30**	

Item No	Analysis Name					UoM
35.110.1654	**Up to 4 x 800 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1654	Up to 4 x 800 A, Icu 50 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	34.108,80	34.108,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	34.108,80	517,50
				Material and Installation w/o Profit (TRY)	34.626,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**43.282,88**	

Item No	Analysis Name					UoM
35.110.1701	**Up to 4 x 300 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1701	Up to 4 x 300 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	19.206,00	19.206,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	19.206,00	430,50
				Material and Installation w/o Profit (TRY)	19.636,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**24.545,63**	

Item No	Analysis Name					UoM
35.110.1702	**Up to 4 x 400 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1702	Up to 4 x 400 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	19.807,92	19.807,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	19.807,92	517,50
				Material and Installation w/o Profit (TRY)	20.325,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**25.406,77**	

Item No	Analysis Name					UoM
35.110.1703	**Up to 4 x 500 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1703	Up to 4 x 500 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	23.371,92	23.371,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	23.371,92	561,00
				Material and Installation w/o Profit (TRY)	23.932,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**701,25**	
				Unit Price (TRY)	**29.916,15**	

Item No	Analysis Name					UoM
35.110.1704	**Up to 4 x 630 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1704	Up to 4 x 630 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	25.298,24	25.298,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	25.298,24	561,00
				Material and Installation w/o Profit (TRY)	25.859,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**701,25**	
				Unit Price (TRY)	**32.324,05**	

Item No	Analysis Name					UoM
35.110.1705	**Up to 4 x 800 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1705	Up to 4 x 800 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	37.127,20	37.127,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	37.127,20	604,50
				Material and Installation w/o Profit (TRY)	37.731,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**755,63**	
				Unit Price (TRY)	**47.164,63**	

Item No	Analysis Name					UoM
35.110.1706	**Up to 4 x 1,000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1706	Up to 4 x 1,000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	43.659,44	43.659,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	43.659,44	648,00
				Material and Installation w/o Profit (TRY)	44.307,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**810,00**	
				Unit Price (TRY)	**55.384,30**	

Item No	Analysis Name					UoM
35.110.1707	**Up to 4 x 1,250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1707	Up to 4 x 1,250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	46.537,04	46.537,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	46.537,04	648,00
				Material and Installation w/o Profit (TRY)	47.185,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**810,00**	
				Unit Price (TRY)	**58.981,30**	

Item No	Analysis Name					UoM
35.110.1708	**Up to 4 x 1,600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1708	Up to 4 x 1,600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	64.251,44	64.251,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	64.251,44	735,00
				Material and Installation w/o Profit (TRY)	64.986,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**81.233,05**	

Item No	Analysis Name					UoM
35.110.1751	**4 x 16 A to 4 x 63 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1751	4 x 16 A to 4 x 63 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.786,64	3.786,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.786,64	300,00
				Material and Installation w/o Profit (TRY)	4.086,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**5.108,30**	

Item No	Analysis Name					UoM
35.110.1752	**Up to 4 x 80 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1752	Up to 4 x 80 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	3.953,84	3.953,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.953,84	300,00
				Material and Installation w/o Profit (TRY)	4.253,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**5.317,30**	

Item No	Analysis Name					UoM
35.110.1753	**Up to 4 x 100 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1753	Up to 4 x 100 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	4.152,72	4.152,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	4.152,72	343,50
				Material and Installation w/o Profit (TRY)	4.496,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**5.620,28**	

Item No	Analysis Name					UoM
35.110.1754	**Up to 4 x 125 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1754	Up to 4 x 125 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	6.009,52	6.009,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	6.009,52	387,00
				Material and Installation w/o Profit (TRY)	6.396,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**7.995,65**	

Item No	Analysis Name					UoM
35.110.1755	**Up to 4 x 160 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1755	Up to 4 x 160 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	6.478,56	6.478,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	6.478,56	387,00
				Material and Installation w/o Profit (TRY)	6.865,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**8.581,95**	

Item No	Analysis Name					UoM
35.110.1756	**Up to 4 x 200 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1756	Up to 4 x 200 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	9.257,60	9.257,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	9.257,60	430,50
				Material and Installation w/o Profit (TRY)	9.688,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**12.110,13**	

Item No	Analysis Name					UoM
35.110.1757	**Up to 4 x 250 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1757	Up to 4 x 250 A, Icu 65 kA, I1 (0.8 - 1)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	10.357,60	10.357,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	10.357,60	430,50
				Material and Installation w/o Profit (TRY)	10.788,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**13.485,13**	

Item No	Analysis Name					UoM
35.110.1801	**Up to 4 x 400 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1801	Up to 4 x 400 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	17.335,12	17.335,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	17.335,12	430,50
				Material and Installation w/o Profit (TRY)	17.765,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**22.207,02**	

Item No	Analysis Name					UoM
35.110.1802	**Up to 4 x 500 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1802	Up to 4 x 500 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	19.843,12	19.843,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	19.843,12	474,00
				Material and Installation w/o Profit (TRY)	20.317,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**25.396,40**	

Item No	Analysis Name					UoM
35.110.1803	**Up to 4 x 630 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1803	Up to 4 x 630 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	22.482,24	22.482,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	22.482,24	474,00
				Material and Installation w/o Profit (TRY)	22.956,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**28.695,30**	

Item No	Analysis Name					UoM
35.110.1804	**Up to 4 x 800 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1804	Up to 4 x 800 A, Icu 65 kA, I1 (0.8 - 1)In, I3 (6-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Adjustable Thermal Protection, Fixed Magnetic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	30.113,60	30.113,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	30.113,60	517,50
				Material and Installation w/o Profit (TRY)	30.631,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**38.288,88**	

Item No	Analysis Name					UoM
35.110.1851	**Up to 4 x 300 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1851	Up to 4 x 300 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	14.110,80	14.110,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	14.110,80	430,50
				Material and Installation w/o Profit (TRY)	14.541,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**18.176,63**	

Item No	Analysis Name					UoM
35.110.1852	**Up to 4 x 400 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1852	Up to 4 x 400 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	17.511,12	17.511,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	17.511,12	517,50
				Material and Installation w/o Profit (TRY)	18.028,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**22.535,77**	

Item No	Analysis Name					UoM
35.110.1853	**Up to 4 x 500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1853	Up to 4 x 500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	20.573,52	20.573,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	20.573,52	561,00
				Material and Installation w/o Profit (TRY)	21.134,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**701,25**	
				Unit Price (TRY)	**26.418,15**	

Item No	Analysis Name					UoM
35.110.1854	**Up to 4 x 630 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1854	Up to 4 x 630 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	22.693,44	22.693,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	22.693,44	561,00
				Material and Installation w/o Profit (TRY)	23.254,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**701,25**	
				Unit Price (TRY)	**29.068,05**	

Item No	Analysis Name					UoM
35.110.1855	**Up to 4 x 800 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1855	Up to 4 x 800 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	36.317,60	36.317,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	36.317,60	604,50
				Material and Installation w/o Profit (TRY)	36.922,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**755,63**	
				Unit Price (TRY)	**46.152,63**	

Item No	Analysis Name					UoM
35.110.1856	**Up to 4 x 1,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1856	Up to 4 x 1,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	45.269,84	45.269,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	45.269,84	648,00
				Material and Installation w/o Profit (TRY)	45.917,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**810,00**	
				Unit Price (TRY)	**57.397,30**	

Item No	Analysis Name					UoM
35.110.1857	**Up to 4 x 1,250 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1857	Up to 4 x 1,250 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	51.781,84	51.781,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	51.781,84	648,00
				Material and Installation w/o Profit (TRY)	52.429,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**810,00**	
				Unit Price (TRY)	**65.537,30**	

Item No	Analysis Name					UoM
35.110.1858	**Up to 4 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.1858	Up to 4 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Compact switches with thermal and magnetic protector (Market price)	Qty	1	65.527,44	65.527,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	65.527,44	735,00
				Material and Installation w/o Profit (TRY)	66.262,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**82.828,05**	

Item No	Analysis Name					UoM
35.110.2110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2110	Maximum 3 x 63 A / 3-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	1.450,50	1.450,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.450,50	300,00
				Material and Installation w/o Profit (TRY)	1.750,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.188,13**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.2120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2120	Maximum 3 x 100 A / 3-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	1.640,65	1.640,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.640,65	343,50
				Material and Installation w/o Profit (TRY)	1.984,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.480,19**	

Item No	Analysis Name					UoM
35.110.2130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2130	Maximum 3 x 125 A / 3-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.363,98	2.363,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	2.363,98	387,00
				Material and Installation w/o Profit (TRY)	2.750,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**3.438,72**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.2140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2140	Maximum 3 x 160 A / 3-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.455,25	2.455,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	2.455,25	387,00
				Material and Installation w/o Profit (TRY)	2.842,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**3.552,81**	

Item No	Analysis Name					UoM
35.110.2150						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2150	Maximum 3 x 250 A / 3-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	3.697,71	3.697,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	3.697,71	430,50
				Material and Installation w/o Profit (TRY)	4.128,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**5.160,26**	

Item No	Analysis Name					UoM
35.110.2210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2210	Maximum 3 x 63 A / 3-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	1.497,79	1.497,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.497,79	300,00
				Material and Installation w/o Profit (TRY)	1.797,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.247,24**	

Item No	Analysis Name					UoM
35.110.2220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2220	Maximum 3 x 100 A / 3-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	1.687,46	1.687,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.687,46	343,50
				Material and Installation w/o Profit (TRY)	2.030,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.538,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.2230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2230	Maximum 3 x 125 A / 3-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.286,95	2.286,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	2.286,95	387,00
				Material and Installation w/o Profit (TRY)	2.673,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**3.342,44**	

Item No	Analysis Name					UoM
35.110.2240						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2240	Maximum 3 x 160 A / 3-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.499,10	2.499,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	2.499,10	387,00
				Material and Installation w/o Profit (TRY)	2.886,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**3.607,63**	

Item No	Analysis Name					UoM
35.110.2250						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2250	Maximum 3 x 250 A / 3-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	3.723,13	3.723,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	3.723,13	430,50
				Material and Installation w/o Profit (TRY)	4.153,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**5.192,04**	

Item No	Analysis Name					UoM
35.110.2260						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2260	Maximum 3 x 400 A / 3-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	6.465,08	6.465,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	6.465,08	430,50
				Material and Installation w/o Profit (TRY)	6.895,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**8.619,48**	

Item No	Analysis Name					UoM
35.110.2270						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2270	Maximum 3 x 630 A / 3-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	6.966,89	6.966,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician’s helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	6.966,89	474,00
				Material and Installation w/o Profit (TRY)	7.440,89	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**9.301,11**	

Item No	Analysis Name					UoM
35.110.2310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2310	From 3 x 250 A to 3 x 320 A / 3-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	5.977,10	5.977,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	5.977,10	430,50
				Material and Installation w/o Profit (TRY)	6.407,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**8.009,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.2320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2320	Maximum 3 x 400 A / 3-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	6.711,40	6.711,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	6.711,40	430,50
				Material and Installation w/o Profit (TRY)	7.141,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**8.927,38**	

Item No	Analysis Name					UoM
35.110.2330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2330	Maximum 3 x 500 A / 3-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	7.084,07	7.084,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician’s helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	7.084,07	474,00
				Material and Installation w/o Profit (TRY)	7.558,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**9.447,59**	

Item No	Analysis Name					UoM
35.110.2340						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2340	Maximum 3 x 630 A / 3-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	7.232,33	7.232,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	7.232,33	474,00
				Material and Installation w/o Profit (TRY)	7.706,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**9.632,91**	

Item No	Analysis Name					UoM
35.110.2410						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2410	Maximum 4 x 63 A / 4-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	1.827,87	1.827,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.827,87	300,00
				Material and Installation w/o Profit (TRY)	2.127,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.659,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.2420						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2420	Maximum 4 x 100 A / 4-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.072,18	2.072,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.072,18	343,50
				Material and Installation w/o Profit (TRY)	2.415,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.019,60**	

Item No	Analysis Name					UoM
35.110.2430						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2430	Maximum 4 x 125 A / 4-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.619,17	2.619,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	2.619,17	387,00
				Material and Installation w/o Profit (TRY)	3.006,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**3.757,71**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.2440						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2440	Maximum 4 x 160 A / 4-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.771,32	2.771,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	2.771,32	387,00
				Material and Installation w/o Profit (TRY)	3.158,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**3.947,90**	

Item No	Analysis Name					UoM
35.110.2450						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2450	Maximum 4 x 250 A / 4-pole, minimum Icu at 400 V AC: 25 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	3.728,05	3.728,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	3.728,05	430,50
				Material and Installation w/o Profit (TRY)	4.158,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**5.198,19**	

Item No	Analysis Name					UoM
35.110.2510						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2510	Maximum 4 x 63 A / 4-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.077,62	2.077,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.077,62	300,00
				Material and Installation w/o Profit (TRY)	2.377,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.972,02**	

Item No	Analysis Name					UoM
35.110.2520						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2520	Maximum 4 x 100 A / 4-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	2.376,95	2.376,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.376,95	343,50
				Material and Installation w/o Profit (TRY)	2.720,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.400,56**	

Item No	Analysis Name					UoM
35.110.2530						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2530	Maximum 4 x 125 A / 4-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	3.087,31	3.087,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.087,31	387,00
				Material and Installation w/o Profit (TRY)	3.474,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.342,89**	

Item No	Analysis Name					UoM
35.110.2540						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2540	Maximum 4 x 160 A / 4-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	3.505,74	3.505,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.505,74	387,00
				Material and Installation w/o Profit (TRY)	3.892,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**4.865,92**	

Item No	Analysis Name					UoM
35.110.2550						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2550	Maximum 4 x 250 A / 4-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	4.997,77	4.997,77	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	4.997,77	430,50
				Material and Installation w/o Profit (TRY)	5.428,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**6.785,34**	

Item No	Analysis Name					UoM
35.110.2560						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2560	Maximum 4 x 400 A / 4-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	7.655,00	7.655,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	7.655,00	430,50
				Material and Installation w/o Profit (TRY)	8.085,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**10.106,88**	

Item No	Analysis Name					UoM
35.110.2570						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2570	Maximum 4 x 630 A / 4-pole, minimum Icu at 400 V AC: 35 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	9.182,56	9.182,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician’s helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	9.182,56	474,00
				Material and Installation w/o Profit (TRY)	9.656,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**12.070,70**	

Item No	Analysis Name					UoM
35.110.2610						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2610	From 4 x 250 A to 4 x 320 A / 4-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	8.522,36	8.522,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	8.522,36	430,50
				Material and Installation w/o Profit (TRY)	8.952,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**11.191,08**	

Item No	Analysis Name					UoM
35.110.2620						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2620	Maximum 4 x 400 A / 4-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	9.064,05	9.064,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	9.064,05	430,50
				Material and Installation w/o Profit (TRY)	9.494,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**538,13**	
				Unit Price (TRY)	**11.868,19**	

Item No	Analysis Name					UoM
35.110.2630						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2630	Maximum 4 x 500 A / 4-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	9.969,96	9.969,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician’s helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	9.969,96	474,00
				Material and Installation w/o Profit (TRY)	10.443,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**13.054,95**	

Item No	Analysis Name					UoM
35.110.2640						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.2640	Maximum 4 x 630 A / 4-pole, minimum Icu at 400 V AC: 50 kA / Compact fixed switches with thermal and magnetic protector (Market price)	Qty	1	10.872,79	10.872,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	10.872,79	474,00
				Material and Installation w/o Profit (TRY)	11.346,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**14.183,49**	

Item No	Analysis Name					UoM
35.110.5052						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5052	From 3 x 400 A to 3 x 630 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	39.353,97	39.353,97	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	39.353,97	1.200,00
				Material and Installation w/o Profit (TRY)	40.553,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.500,00**	
				Unit Price (TRY)	**50.692,46**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5053						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5053	Up to 3 x 800 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	40.858,46	40.858,46	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,7	250,00		675,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	40.858,46	1.560,00
				Material and Installation w/o Profit (TRY)	42.418,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.950,00**	
				Unit Price (TRY)	**53.023,07**	

Item No	Analysis Name					UoM
35.110.5054						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5054	Up to 3 x 1000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	42.573,09	42.573,09	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,9	250,00		725,00
10.100.1083	Master electrician's helper	h	3,4	185,00		629,00
				Total Excluding Profit (TRY)	42.573,09	1.684,00
				Material and Installation w/o Profit (TRY)	44.257,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.105,00**	
				Unit Price (TRY)	**55.321,36**	

Item No	Analysis Name					UoM
35.110.5055						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5055	Up to 3 x 1250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	46.558,42	46.558,42	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,9	250,00		725,00
10.100.1083	Master electrician’s helper	h	3,4	185,00		629,00
				Total Excluding Profit (TRY)	46.558,42	1.684,00
				Material and Installation w/o Profit (TRY)	48.242,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.105,00**	
				Unit Price (TRY)	**60.303,02**	

Item No	Analysis Name					UoM
35.110.5056						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5056	Up to 3 x 1600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	56.955,58	56.955,58	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,3	250,00		825,00
10.100.1083	Master electrician’s helper	h	3,9	185,00		721,50
				Total Excluding Profit (TRY)	56.955,58	1.876,50
				Material and Installation w/o Profit (TRY)	58.832,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.345,63**	
				Unit Price (TRY)	**73.540,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5057						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5057	Up to 3 x 2000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	59.137,69	59.137,69	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,6	250,00		900,00
10.100.1083	Master electrician’s helper	h	4,4	185,00		814,00
				Total Excluding Profit (TRY)	59.137,69	2.044,00
				Material and Installation w/o Profit (TRY)	61.181,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.555,00**	
				Unit Price (TRY)	**76.477,11**	

Item No	Analysis Name					UoM
35.110.5058						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5058	Up to 3 x 2500 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	69.015,52	69.015,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	69.015,52	2.070,00
				Material and Installation w/o Profit (TRY)	71.085,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.587,50**	
				Unit Price (TRY)	**88.856,90**	

Item No	Analysis Name					UoM
35.110.5101	**Up to 3 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5101	Up to 3 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	63.131,20	63.131,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,3	250,00		825,00
10.100.1083	Master electrician’s helper	h	3,3	185,00		610,50
				Total Excluding Profit (TRY)	63.131,20	1.765,50
				Material and Installation w/o Profit (TRY)	64.896,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.206,88**	
				Unit Price (TRY)	**81.120,88**	

Item No	Analysis Name					UoM
35.110.5102	**Up to 3 x 2,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5102	Up to 3 x 2000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	73.453,60	73.453,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,6	250,00		900,00
10.100.1083	Master electrician’s helper	h	3,6	185,00		666,00
				Total Excluding Profit (TRY)	73.453,60	1.896,00
				Material and Installation w/o Profit (TRY)	75.349,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.370,00**	
				Unit Price (TRY)	**94.187,00**	

Item No	Analysis Name					UoM
35.110.5103	**Up to 3 x 2,500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5103	Up to 3 x 2500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	87.938,40	87.938,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	87.938,40	2.070,00
				Material and Installation w/o Profit (TRY)	90.008,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.587,50**	
				Unit Price (TRY)	**112.510,50**	

Item No	Analysis Name					UoM
35.110.5104	**Up to 3 x 3,200 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5104	Up to 3 x 3200 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	104.403,20	104.403,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	6,5	250,00		1.625,00
10.100.1083	Master electrician’s helper	h	6,5	185,00		1.202,50
				Total Excluding Profit (TRY)	104.403,20	3.157,50
				Material and Installation w/o Profit (TRY)	107.560,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.946,88**	
				Unit Price (TRY)	**134.450,88**	

Item No	Analysis Name					UoM
35.110.5105	**Up to 3 x 4,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5105	Up to 3 x 4000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	143.616,00	143.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
				Total Excluding Profit (TRY)	143.616,00	3.375,00
				Material and Installation w/o Profit (TRY)	146.991,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.218,75**	
				Unit Price (TRY)	**183.738,75**	

Item No	Analysis Name					UoM
35.110.5151	**Up to 3 x 1,600 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5151	Up to 3 x 1,600 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	86.292,80	86.292,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,3	250,00		825,00
10.100.1083	Master electrician’s helper	h	3,3	185,00		610,50
				Total Excluding Profit (TRY)	86.292,80	1.765,50
				Material and Installation w/o Profit (TRY)	88.058,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.206,88**	
				Unit Price (TRY)	**110.072,88**	

Item No	Analysis Name					UoM
35.110.5152	**Up to 3 x 2,000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5152	Up to 3 x 2000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	95.427,20	95.427,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,6	250,00		900,00
10.100.1083	Master electrician’s helper	h	3,6	185,00		666,00
				Total Excluding Profit (TRY)	95.427,20	1.896,00
				Material and Installation w/o Profit (TRY)	97.323,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.370,00**	
				Unit Price (TRY)	**121.654,00**	

Item No	Analysis Name					UoM
35.110.5153	**Up to 3 x 2,500 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5153	Up to 3 x 2500 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	119.178,40	119.178,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	119.178,40	2.070,00
				Material and Installation w/o Profit (TRY)	121.248,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.587,50**	
				Unit Price (TRY)	**151.560,50**	

Item No	Analysis Name					UoM
35.110.5154	**Up to 3 x 3,200 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5154	Up to 3 x 3200 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	132.651,20	132.651,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	6,5	250,00		1.625,00
10.100.1083	Master electrician’s helper	h	6,5	185,00		1.202,50
				Total Excluding Profit (TRY)	132.651,20	3.157,50
				Material and Installation w/o Profit (TRY)	135.808,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.946,88**	
				Unit Price (TRY)	**169.760,88**	

Item No	Analysis Name					UoM
35.110.5155	**Up to 3 x 4,000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5155	Up to 3 x 4000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	169.488,00	169.488,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
				Total Excluding Profit (TRY)	169.488,00	3.375,00
				Material and Installation w/o Profit (TRY)	172.863,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.218,75**	
				Unit Price (TRY)	**216.078,75**	

Item No	Analysis Name					UoM
35.110.5156	**Up to 3 x 5,000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5156	Up to 3 x 5000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	254.443,20	254.443,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
				Total Excluding Profit (TRY)	254.443,20	3.810,00
				Material and Installation w/o Profit (TRY)	258.253,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.762,50**	
				Unit Price (TRY)	**322.816,50**	

Item No	Analysis Name					UoM
35.110.5182						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5182	From 4 x 400 A to 4 x 630 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	50.340,22	50.340,22	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	50.340,22	1.200,00
				Material and Installation w/o Profit (TRY)	51.540,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.500,00**	
				Unit Price (TRY)	**64.425,28**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5183						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5183	Up to 4 x 800 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	51.789,20	51.789,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,7	250,00		675,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	51.789,20	1.560,00
				Material and Installation w/o Profit (TRY)	53.349,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.950,00**	
				Unit Price (TRY)	**66.686,50**	

Item No	Analysis Name					UoM
35.110.5184						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5184	Up to 4 x 1000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	53.994,33	53.994,33	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,9	250,00		725,00
10.100.1083	Master electrician's helper	h	3,4	185,00		629,00
				Total Excluding Profit (TRY)	53.994,33	1.684,00
				Material and Installation w/o Profit (TRY)	55.678,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.105,00**	
				Unit Price (TRY)	**69.597,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5185						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5185	Up to 4 x 1250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	60.007,02	60.007,02	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,9	250,00		725,00
10.100.1083	Master electrician’s helper	h	3,4	185,00		629,00
				Total Excluding Profit (TRY)	60.007,02	1.684,00
				Material and Installation w/o Profit (TRY)	61.691,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.105,00**	
				Unit Price (TRY)	**77.113,77**	

Item No	Analysis Name					UoM
35.110.5186						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5186	Up to 4 x 1600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	78.220,83	78.220,83	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,3	250,00		825,00
10.100.1083	Master electrician’s helper	h	3,9	185,00		721,50
				Total Excluding Profit (TRY)	78.220,83	1.876,50
				Material and Installation w/o Profit (TRY)	80.097,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.345,63**	
				Unit Price (TRY)	**100.121,66**	

Item No	Analysis Name					UoM
35.110.5187						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5187	Up to 4 x 2000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	81.950,67	81.950,67	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,6	250,00		900,00
10.100.1083	Master electrician's helper	h	4,4	185,00		814,00
				Total Excluding Profit (TRY)	81.950,67	2.044,00
				Material and Installation w/o Profit (TRY)	83.994,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.555,00**	
				Unit Price (TRY)	**104.993,34**	

Item No	Analysis Name					UoM
35.110.5188						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5188	Up to 4 x 2500 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	93.017,31	93.017,31	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	93.017,31	2.070,00
				Material and Installation w/o Profit (TRY)	95.087,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.587,50**	
				Unit Price (TRY)	**118.859,14**	

Item No	Analysis Name					UoM
35.110.5201	**Up to 4 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5201	Up to 4 x 1,600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	93.772,80	93.772,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,3	250,00		825,00
10.100.1083	Master electrician’s helper	h	3,3	185,00		610,50
				Total Excluding Profit (TRY)	93.772,80	1.765,50
				Material and Installation w/o Profit (TRY)	95.538,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.206,88**	
				Unit Price (TRY)	**119.422,88**	

Item No	Analysis Name					UoM
35.110.5202	**Up to 4 x 2,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5202	Up to 4 x 2000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	105.547,20	105.547,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,6	250,00		900,00
10.100.1083	Master electrician’s helper	h	3,6	185,00		666,00
				Total Excluding Profit (TRY)	105.547,20	1.896,00
				Material and Installation w/o Profit (TRY)	107.443,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.370,00**	
				Unit Price (TRY)	**134.304,00**	

Item No	Analysis Name					UoM
35.110.5203	**Up to 4 x 2,500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5203	Up to 4 x 2500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	129.738,40	129.738,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	129.738,40	2.070,00
				Material and Installation w/o Profit (TRY)	131.808,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.587,50**	
				Unit Price (TRY)	**164.760,50**	

Item No	Analysis Name					UoM
35.110.5204	**Up to 4 x 3,200 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breaker**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5204	Up to 4 x 3200 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	148.227,20	148.227,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	6,5	250,00		1.625,00
10.100.1083	Master electrician’s helper	h	6,5	185,00		1.202,50
				Total Excluding Profit (TRY)	148.227,20	3.157,50
				Material and Installation w/o Profit (TRY)	151.384,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.946,88**	
				Unit Price (TRY)	**189.230,88**	

Item No	Analysis Name					UoM
35.110.5205	**Up to 4 x 4,000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5205	Up to 4 x 4000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	200.992,00	200.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
				Total Excluding Profit (TRY)	200.992,00	3.375,00
				Material and Installation w/o Profit (TRY)	204.367,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.218,75**	
				Unit Price (TRY)	**255.458,75**	

Item No	Analysis Name					UoM
35.110.5251	**Up to 4 x 1,600 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5251	Up to 4 x 1,600 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	101.164,80	101.164,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,3	250,00		825,00
10.100.1083	Master electrician’s helper	h	3,3	185,00		610,50
				Total Excluding Profit (TRY)	101.164,80	1.765,50
				Material and Installation w/o Profit (TRY)	102.930,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.206,88**	
				Unit Price (TRY)	**128.662,88**	

Item No	Analysis Name					UoM
35.110.5252	**Up to 4 x 2,000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5252	Up to 4 x 2000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	118.395,20	118.395,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,6	250,00		900,00
10.100.1083	Master electrician’s helper	h	3,6	185,00		666,00
				Total Excluding Profit (TRY)	118.395,20	1.896,00
				Material and Installation w/o Profit (TRY)	120.291,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.370,00**	
				Unit Price (TRY)	**150.364,00**	

Item No	Analysis Name					UoM
35.110.5253	**Up to 4 x 2,500 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5253	Up to 4 x 2500 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	146.986,40	146.986,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	146.986,40	2.070,00
				Material and Installation w/o Profit (TRY)	149.056,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.587,50**	
				Unit Price (TRY)	**186.320,50**	

Item No	Analysis Name					UoM
35.110.5254	**Up to 4 x 3,200 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5254	Up to 4 x 3200 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	168.731,20	168.731,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	6,5	250,00		1.625,00
10.100.1083	Master electrician’s helper	h	6,5	185,00		1.202,50
				Total Excluding Profit (TRY)	168.731,20	3.157,50
				Material and Installation w/o Profit (TRY)	171.888,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.946,88**	
				Unit Price (TRY)	**214.860,88**	

Item No	Analysis Name					UoM
35.110.5255	**Up to 4 x 4,000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5255	Up to 4 x 4000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	227.480,00	227.480,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
				Total Excluding Profit (TRY)	227.480,00	3.375,00
				Material and Installation w/o Profit (TRY)	230.855,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.218,75**	
				Unit Price (TRY)	**288.568,75**	

Item No	Analysis Name					UoM
35.110.5256	**Up to 4 x 5,000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5256	Up to 4 x 5000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Fixed) (Market price)	Qty	1	309.355,20	309.355,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
				Total Excluding Profit (TRY)	309.355,20	3.810,00
				Material and Installation w/o Profit (TRY)	313.165,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.762,50**	
				Unit Price (TRY)	**391.456,50**	

Item No	Analysis Name					UoM
35.110.5313						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5313	From 3 x 400 A to 3 x 630 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	47.615,26	47.615,26	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	47.615,26	2.235,00
				Material and Installation w/o Profit (TRY)	49.850,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.793,75**	
				Unit Price (TRY)	**62.312,83**	

Item No	Analysis Name					UoM
35.110.5314						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5314	Up to 3 x 800 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	49.728,69	49.728,69	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4,7	250,00		1.175,00
10.100.1083	Master electrician's helper	h	4,7	185,00		869,50
				Total Excluding Profit (TRY)	49.728,69	2.539,50
				Material and Installation w/o Profit (TRY)	52.268,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.174,38**	
				Unit Price (TRY)	**65.335,24**	

Item No	Analysis Name					UoM
35.110.5315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5315	Up to 3 x 1000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	50.916,67	50.916,67	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4,9	250,00		1.225,00
10.100.1083	Master electrician's helper	h	4,9	185,00		906,50
				Total Excluding Profit (TRY)	50.916,67	2.626,50
				Material and Installation w/o Profit (TRY)	53.543,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.283,13**	
				Unit Price (TRY)	**66.928,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5316						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5316	Up to 3 x 1250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	55.123,31	55.123,31	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4,9	250,00		1.225,00
10.100.1083	Master electrician's helper	h	4,9	185,00		906,50
				Total Excluding Profit (TRY)	55.123,31	2.626,50
				Material and Installation w/o Profit (TRY)	57.749,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.283,13**	
				Unit Price (TRY)	**72.187,26**	

Item No	Analysis Name					UoM
35.110.5317						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5317	Up to 3 x 1600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	66.459,40	66.459,40	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,3	250,00		1.325,00
10.100.1083	Master electrician's helper	h	5,3	185,00		980,50
				Total Excluding Profit (TRY)	66.459,40	2.800,50
				Material and Installation w/o Profit (TRY)	69.259,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.500,63**	
				Unit Price (TRY)	**86.574,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5318						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5318	Up to 3 x 2000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	70.317,76	70.317,76	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,6	250,00		1.400,00
10.100.1083	Master electrician’s helper	h	5,6	185,00		1.036,00
				Total Excluding Profit (TRY)	70.317,76	2.931,00
				Material and Installation w/o Profit (TRY)	73.248,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.663,75**	
				Unit Price (TRY)	**91.560,95**	

Item No	Analysis Name					UoM
35.110.5319						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5319	Up to 3 x 2500 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	73.251,74	73.251,74	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	73.251,74	3.105,00
				Material and Installation w/o Profit (TRY)	76.356,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**95.445,93**	

Item No	Analysis Name					UoM
35.110.5323						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5323	From 3 x 1500 A to 3 x 1600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	70.695,06	70.695,06	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	70.695,06	3.105,00
				Material and Installation w/o Profit (TRY)	73.800,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**92.250,07**	

Item No	Analysis Name					UoM
35.110.5324						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5324	Up to 3 x 2000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	79.834,46	79.834,46	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	79.834,46	3.105,00
				Material and Installation w/o Profit (TRY)	82.939,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**103.674,33**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5325						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5325	Up to 3 x 2500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	97.089,54	97.089,54	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	97.089,54	3.105,00
				Material and Installation w/o Profit (TRY)	100.194,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**125.243,17**	

Item No	Analysis Name					UoM
35.110.5326						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5326	Up to 3 x 3200 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	113.226,78	113.226,78	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7,5	250,00		1.875,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
				Total Excluding Profit (TRY)	113.226,78	3.850,00
				Material and Installation w/o Profit (TRY)	117.076,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.812,50**	
				Unit Price (TRY)	**146.345,98**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5327						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5327	Up to 3 x 4000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	152.428,95	152.428,95	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
				Total Excluding Profit (TRY)	152.428,95	3.975,00
				Material and Installation w/o Profit (TRY)	156.403,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.968,75**	
				Unit Price (TRY)	**195.504,94**	

Item No	Analysis Name					UoM
35.110.5333						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5333	From 3 x 1500 A to 3 x 1600 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	92.414,22	92.414,22	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,3	250,00		1.325,00
10.100.1083	Master electrician's helper	h	5,3	185,00		980,50
				Total Excluding Profit (TRY)	92.414,22	2.800,50
				Material and Installation w/o Profit (TRY)	95.214,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.500,63**	
				Unit Price (TRY)	**119.018,40**	

Item No	Analysis Name					UoM
35.110.5334						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5334	Up to 3 x 2000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	104.540,59	104.540,59	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,6	250,00		1.400,00
10.100.1083	Master electrician's helper	h	5,6	185,00		1.036,00
				Total Excluding Profit (TRY)	104.540,59	2.931,00
				Material and Installation w/o Profit (TRY)	107.471,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.663,75**	
				Unit Price (TRY)	**134.339,49**	

Item No	Analysis Name					UoM
35.110.5335						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5335	Up to 3 x 2500 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	125.227,74	125.227,74	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	125.227,74	3.105,00
				Material and Installation w/o Profit (TRY)	128.332,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**160.415,93**	

Item No	Analysis Name					UoM
35.110.5336						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5336	Up to 3 x 3200 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	145.985,80	145.985,80	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7,5	250,00		1.875,00
10.100.1083	Master electrician's helper	h	7,5	185,00		1.387,50
				Total Excluding Profit (TRY)	145.985,80	3.757,50
				Material and Installation w/o Profit (TRY)	149.743,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.696,88**	
				Unit Price (TRY)	**187.179,13**	

Item No	Analysis Name					UoM
35.110.5337						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5337	Up to 3 x 4000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	187.908,51	187.908,51	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
				Total Excluding Profit (TRY)	187.908,51	3.975,00
				Material and Installation w/o Profit (TRY)	191.883,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.968,75**	
				Unit Price (TRY)	**239.854,39**	

Item No	Analysis Name					UoM
35.110.5338						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5338	Up to 3 x 5000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 3-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	294.743,61	294.743,61	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician’s helper	h	10	185,00		1.850,00
				Total Excluding Profit (TRY)	294.743,61	4.845,00
				Material and Installation w/o Profit (TRY)	299.588,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**6.056,25**	
				Unit Price (TRY)	**374.485,76**	

Item No	Analysis Name					UoM
35.110.5343						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5343	From 4 x 400 A to 4 x 630 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	62.480,67	62.480,67	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	62.480,67	2.235,00
				Material and Installation w/o Profit (TRY)	64.715,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.793,75**	
				Unit Price (TRY)	**80.894,59**	

Item No	Analysis Name					UoM
35.110.5344						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5344	Up to 4 x 800 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	65.095,34	65.095,34	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4,7	250,00		1.175,00
10.100.1083	Master electrician's helper	h	4,7	185,00		869,50
				Total Excluding Profit (TRY)	65.095,34	2.539,50
				Material and Installation w/o Profit (TRY)	67.634,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.174,38**	
				Unit Price (TRY)	**84.543,55**	

Item No	Analysis Name					UoM
35.110.5345						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5345	Up to 4 x 1000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	67.099,77	67.099,77	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4,9	250,00		1.225,00
10.100.1083	Master electrician's helper	h	4,9	185,00		906,50
				Total Excluding Profit (TRY)	67.099,77	2.626,50
				Material and Installation w/o Profit (TRY)	69.726,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.283,13**	
				Unit Price (TRY)	**87.157,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5346						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5346	Up to 4 x 1250 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	72.060,48	72.060,48	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	4,9	250,00		1.225,00
10.100.1083	Master electrician's helper	h	4,9	185,00		906,50
				Total Excluding Profit (TRY)	72.060,48	2.626,50
				Material and Installation w/o Profit (TRY)	74.686,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.283,13**	
				Unit Price (TRY)	**93.358,72**	

Item No	Analysis Name					UoM
35.110.5347						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5347	Up to 4 x 1600 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	88.239,67	88.239,67	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,3	250,00		1.325,00
10.100.1083	Master electrician's helper	h	5,3	185,00		980,50
				Total Excluding Profit (TRY)	88.239,67	2.800,50
				Material and Installation w/o Profit (TRY)	91.040,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.500,63**	
				Unit Price (TRY)	**113.800,21**	

Item No	Analysis Name					UoM
35.110.5348						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5348	Up to 4 x 2000 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	91.995,67	91.995,67	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,6	250,00		1.400,00
10.100.1083	Master electrician's helper	h	5,6	185,00		1.036,00
				Total Excluding Profit (TRY)	91.995,67	2.931,00
				Material and Installation w/o Profit (TRY)	94.926,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.663,75**	
				Unit Price (TRY)	**118.658,34**	

Item No	Analysis Name					UoM
35.110.5349						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5349	Up to 4 x 2500 A, Icu 50 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 50 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	94.582,54	94.582,54	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	94.582,54	3.105,00
				Material and Installation w/o Profit (TRY)	97.687,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**122.109,42**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5353						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5353	From 4 x 1500 A to 4 x 1600 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	93.721,71	93.721,71	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,3	250,00		1.325,00
10.100.1083	Master electrician's helper	h	5,3	185,00		980,50
				Total Excluding Profit (TRY)	93.721,71	2.800,50
				Material and Installation w/o Profit (TRY)	96.522,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.500,63**	
				Unit Price (TRY)	**120.652,76**	

Item No	Analysis Name					UoM
35.110.5354						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5354	Up to 4 x 2000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	106.734,52	106.734,52	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,6	250,00		1.400,00
10.100.1083	Master electrician's helper	h	5,6	185,00		1.036,00
				Total Excluding Profit (TRY)	106.734,52	2.931,00
				Material and Installation w/o Profit (TRY)	109.665,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.663,75**	
				Unit Price (TRY)	**137.081,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5355						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5355	Up to 4 x 2500 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	129.606,31	129.606,31	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	129.606,31	3.105,00
				Material and Installation w/o Profit (TRY)	132.711,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**165.889,14**	

Item No	Analysis Name					UoM
35.110.5356						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5356	Up to 4 x 3200 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	149.088,69	149.088,69	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7,5	250,00		1.875,00
10.100.1083	Master electrician's helper	h	7,5	185,00		1.387,50
				Total Excluding Profit (TRY)	149.088,69	3.757,50
				Material and Installation w/o Profit (TRY)	152.846,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.696,88**	
				Unit Price (TRY)	**191.057,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5357						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5357	Up to 4 x 4000 A, Icu 65 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 65 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	201.608,51	201.608,51	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
				Total Excluding Profit (TRY)	201.608,51	3.975,00
				Material and Installation w/o Profit (TRY)	205.583,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.968,75**	
				Unit Price (TRY)	**256.979,39**	

Item No	Analysis Name					UoM
35.110.5363						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5363	From 4 x 1500 A to 4 x 1600 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	111.425,41	111.425,41	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,3	250,00		1.325,00
10.100.1083	Master electrician’s helper	h	5,3	185,00		980,50
				Total Excluding Profit (TRY)	111.425,41	2.800,50
				Material and Installation w/o Profit (TRY)	114.225,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.500,63**	
				Unit Price (TRY)	**142.782,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.110.5364						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5364	Up to 4 x 2000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	133.295,88	133.295,88	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5,6	250,00		1.400,00
10.100.1083	Master electrician’s helper	h	5,6	185,00		1.036,00
				Total Excluding Profit (TRY)	133.295,88	2.931,00
				Material and Installation w/o Profit (TRY)	136.226,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.663,75**	
				Unit Price (TRY)	**170.283,60**	

Item No	Analysis Name					UoM
35.110.5365						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5365	Up to 4 x 2500 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	161.104,70	161.104,70	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	161.104,70	3.105,00
				Material and Installation w/o Profit (TRY)	164.209,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**205.262,13**	

Item No	Analysis Name					UoM
35.110.5366						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5366	Up to 4 x 3200 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	192.638,33	192.638,33	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7,5	250,00		1.875,00
10.100.1083	Master electrician’s helper	h	7,5	185,00		1.387,50
				Total Excluding Profit (TRY)	192.638,33	3.757,50
				Material and Installation w/o Profit (TRY)	196.395,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.696,88**	
				Unit Price (TRY)	**245.494,79**	

Item No	Analysis Name					UoM
35.110.5367						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5367	Up to 4 x 4000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	250.656,31	250.656,31	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
				Total Excluding Profit (TRY)	250.656,31	3.975,00
				Material and Installation w/o Profit (TRY)	254.631,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.968,75**	
				Unit Price (TRY)	**318.289,14**	

Item No	Analysis Name					UoM
35.110.5368						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5368	Up to 4 x 5000 A, Icu 100 kA, I1 (0.5 - 1)In, I3 (2-10)In / 4-pole, min. Icu at 400 V AC: 100 kA, Electronic Protection / Air circuit breakers (Drawer Type) (Market price)	Qty	1	377.264,66	377.264,66	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician’s helper	h	10	185,00		1.850,00
				Total Excluding Profit (TRY)	377.264,66	4.845,00
				Material and Installation w/o Profit (TRY)	382.109,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**6.056,25**	
				Unit Price (TRY)	**477.637,07**	

Item No	Analysis Name					UoM
35.110.5501	**3- or 4-pole, max. 250 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5501	3- or 4-pole, max. 250 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2) (Market price)	Qty	1	10.502,80	10.502,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	10.502,80	300,00
				Material and Installation w/o Profit (TRY)	10.802,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**13.503,50**	

Item No	Analysis Name					UoM
35.110.5502	**3- or 4-pole, max. 630 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5502	3- or 4-pole, max. 630 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2) (Market price)	Qty	1	18.949,92	18.949,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	18.949,92	300,00
				Material and Installation w/o Profit (TRY)	19.249,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**24.062,40**	

Item No	Analysis Name					UoM
35.110.5503	**3- or 4-pole, max. 1,000 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5503	3- or 4-pole, max. 1,000 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers: (in compliance with TS EN 60947-2) (Market price)	Qty	1	27.519,36	27.519,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	27.519,36	300,00
				Material and Installation w/o Profit (TRY)	27.819,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**34.774,20**	

Item No	Analysis Name					UoM
35.110.5504	**3- or 4-pole, max. 1,600 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5504	3- or 4-pole, max. 1,600 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers: (in compliance with TS EN 60947-2) (Market price)	Qty	1	31.301,60	31.301,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	31.301,60	300,00
				Material and Installation w/o Profit (TRY)	31.601,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**39.502,00**	

Item No	Analysis Name					UoM
35.110.5505	**3- or 4-pole, max. 2,500 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5505	3- or 4-pole, max. 2,500 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2) (Market price)	Qty	1	32.436,80	32.436,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	32.436,80	300,00
				Material and Installation w/o Profit (TRY)	32.736,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**40.921,00**	

Item No	Analysis Name					UoM
35.110.5506	**3- or 4-pole, max. 5,000 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers (in compliance with TS EN 60947-2)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.110.5506	3- or 4-pole, max. 5,000 A / Additions for remote control, compact, thermally and magnetically protected air circuit breakers: (in compliance with TS EN 60947-2) (Market price)	Qty	1	33.369,60	33.369,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	33.369,60	300,00
				Material and Installation w/o Profit (TRY)	33.669,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**42.087,00**	

Item No	Analysis Name					UoM
35.115.1001	**Up to 2 x 25 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1001	Up to 2 x 25 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	554,95	554,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	554,95	300,00
				Material and Installation w/o Profit (TRY)	854,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.068,69**	

Item No	Analysis Name					UoM
35.115.1002	**Up to 2 x 40 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1002	Up to 2 x 40 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	571,73	571,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			571,73	300,00
		Material and Installation w/o Profit (TRY)			871,73	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**375,00**	
		Unit Price (TRY)			**1.089,66**	

Item No	Analysis Name					UoM
35.115.1003	**Up to 2 x 63 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1003	Up to 2 x 63 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	689,92	689,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			689,92	300,00
		Material and Installation w/o Profit (TRY)			989,92	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**375,00**	
		Unit Price (TRY)			**1.237,40**	

Item No	Analysis Name					UoM
35.115.1004	**Up to 2 x 80 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1004	Up to 2 x 80 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	1.095,57	1.095,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.095,57	300,00
				Material and Installation w/o Profit (TRY)	1.395,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.744,46**	

Item No	Analysis Name					UoM
35.115.1005	**Up to 2 x 100 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1005	Up to 2 x 100 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	1.643,18	1.643,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.643,18	300,00
				Material and Installation w/o Profit (TRY)	1.943,18	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.428,97**	

Item No	Analysis Name					UoM
35.115.1020	**Up to 4 x 25 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1020	Up to 4 x 25 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	780,31	780,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	780,31	343,50
				Material and Installation w/o Profit (TRY)	1.123,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.404,76**	

Item No	Analysis Name					UoM
35.115.1021	**Up to 4 x 40 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1021	Up to 4 x 40 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	805,34	805,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	805,34	343,50
				Material and Installation w/o Profit (TRY)	1.148,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.436,05**	

Item No	Analysis Name					UoM
35.115.1022	**Up to 4 x 63 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1022	Up to 4 x 63 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	919,61	919,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	919,61	343,50
				Material and Installation w/o Profit (TRY)	1.263,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.578,89**	

Item No	Analysis Name					UoM
35.115.1023	**Up to 4 x 80 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1023	Up to 4 x 80 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	1.545,41	1.545,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.545,41	343,50
				Material and Installation w/o Profit (TRY)	1.888,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.361,14**	

Item No	Analysis Name					UoM
35.115.1024	**Up to 4 x 100 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1024	Up to 4 x 100 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	2.461,43	2.461,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.461,43	343,50
				Material and Installation w/o Profit (TRY)	2.804,93	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.506,16**	

Item No	Analysis Name					UoM
35.115.1040	**Up to 4 x 125 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1040	Up to 4 x 125 A (30 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	4.863,17	4.863,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	4.863,17	343,50
				Material and Installation w/o Profit (TRY)	5.206,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**6.508,34**	

Item No	Analysis Name					UoM
35.115.1041	**Up to 2 x 25 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1041	Up to 2 x 25 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	527,92	527,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	527,92	300,00
				Material and Installation w/o Profit (TRY)	827,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.034,90**	

Item No	Analysis Name					UoM
35.115.1042	**Up to 2 x 40 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1042	Up to 2 x 40 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	547,35	547,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	547,35	300,00
				Material and Installation w/o Profit (TRY)	847,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.059,19**	

Item No	Analysis Name					UoM
35.115.1043	**Up to 2 x 63 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1043	Up to 2 x 63 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	664,51	664,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	664,51	300,00
				Material and Installation w/o Profit (TRY)	964,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.205,64**	

Item No	Analysis Name					UoM
35.115.1044	**Up to 2 x 80 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1044	Up to 2 x 80 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	1.045,19	1.045,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.045,19	300,00
				Material and Installation w/o Profit (TRY)	1.345,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.681,49**	

Item No	Analysis Name					UoM
35.115.1045	**Up to 2 x 100 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1045	Up to 2 x 100 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	1.611,08	1.611,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.611,08	300,00
				Material and Installation w/o Profit (TRY)	1.911,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.388,85**	

Item No	Analysis Name					UoM
35.115.1060	**Up to 4 x 25 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1060	Up to 4 x 25 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	723,14	723,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	723,14	343,50
				Material and Installation w/o Profit (TRY)	1.066,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.333,30**	

Item No	Analysis Name					UoM
35.115.1061	**Up to 4 x 40 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1061	Up to 4 x 40 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	756,19	756,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
		Total Excluding Profit (TRY)			756,19	343,50
		Material and Installation w/o Profit (TRY)			1.099,69	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**429,38**	
		Unit Price (TRY)			**1.374,61**	

Item No	Analysis Name					UoM
35.115.1062	**Up to 4 x 63 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1062	Up to 4 x 63 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	865,07	865,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
		Total Excluding Profit (TRY)			865,07	343,50
		Material and Installation w/o Profit (TRY)			1.208,57	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**429,38**	
		Unit Price (TRY)			**1.510,71**	

Item No	Analysis Name					UoM
35.115.1063	**Up to 4 x 80 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1063	Up to 4 x 80 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	1.416,84	1.416,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.416,84	343,50
				Material and Installation w/o Profit (TRY)	1.760,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.200,42**	

Item No	Analysis Name					UoM
35.115.1064	**Up to 4 x 100 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1064	Up to 4 x 100 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	2.061,33	2.061,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.061,33	343,50
				Material and Installation w/o Profit (TRY)	2.404,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.006,04**	

Item No	Analysis Name					UoM
35.115.1065	**Up to 4 x 125 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1065	Up to 4 x 125 A (300 mA) / Residual current circuit breakers (TS EN 61008-1 / TS EN 61008-2-1) (Market price)	Qty	1	4.303,78	4.303,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	4.303,78	343,50
				Material and Installation w/o Profit (TRY)	4.647,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**5.809,10**	

Item No	Analysis Name					UoM
35.115.1201	**3 x 80 A to 3 x 250 A (3-phase) 30-500 mA / Residual Current Protection Relay with Toroidal Current Transformer**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1201	3 x 80 A to 3 x 250 A (3-phase) 30-500 mA / Residual Current Protection Relay with Toroidal Current Transformer (Market price)	Qty	1	10.383,56	10.383,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	10.383,56	517,50
				Material and Installation w/o Profit (TRY)	10.901,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**13.626,32**	

Item No	Analysis Name					UoM
35.115.1202	**3 x 300 A to 3 x 1,250 A (3-phase) 30-500 mA / Residual Current Protection Relay with Toroidal Current Transformer**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1202	3 x 300 A to 3 x 1,250 A (3-phase) 30-500 mA / Residual Current Protection Relay with Toroidal Current Transformer (Market price)	Qty	1	18.303,56	18.303,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	18.303,56	517,50
				Material and Installation w/o Profit (TRY)	18.821,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**23.526,33**	

Item No	Analysis Name					UoM
35.115.1203	**3 x 1,600 A and above (3-phase) 30-500 mA / Residual Current Protection Relay with Toroidal Current Transformer**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1203	3 x 1,600 A and above (3-phase) 30-500 mA / Residual Current Protection Relay with Toroidal Current Transformer (Market price)	Qty	1	20.500,04	20.500,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	20.500,04	517,50
				Material and Installation w/o Profit (TRY)	21.017,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**26.271,93**	

Item No	Analysis Name					UoM
35.115.1501						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1501	In: up to 0.4 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	713,68	713,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	713,68	258,75
				Material and Installation w/o Profit (TRY)	972,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.215,54**	

Item No	Analysis Name					UoM
35.115.1502						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1502	In: up to 4 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	713,68	713,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	713,68	258,75
				Material and Installation w/o Profit (TRY)	972,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.215,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1503						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1503	In: up to 6.3 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	713,68	713,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	713,68	258,75
				Material and Installation w/o Profit (TRY)	972,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.215,54**	

Item No	Analysis Name					UoM
35.115.1504						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1504	In: up to 10 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	764,28	764,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	764,28	258,75
				Material and Installation w/o Profit (TRY)	1.023,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.278,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1505						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1505	In: up to 12 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	781,44	781,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	781,44	258,75
				Material and Installation w/o Profit (TRY)	1.040,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.300,24**	

Item No	Analysis Name					UoM
35.115.1506						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1506	In: up to 16 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	865,92	865,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	865,92	258,75
				Material and Installation w/o Profit (TRY)	1.124,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.405,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1507						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1507	In: up to 20 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	978,56	978,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	978,56	258,75
				Material and Installation w/o Profit (TRY)	1.237,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.546,64**	

Item No	Analysis Name					UoM
35.115.1508						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1508	In: up to 25 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.048,96	1.048,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.048,96	258,75
				Material and Installation w/o Profit (TRY)	1.307,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.634,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1509						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1509	In: up to 32 (Icu: 50 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.730,08	1.730,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.730,08	258,75
				Material and Installation w/o Profit (TRY)	1.988,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.486,04**	

Item No	Analysis Name					UoM
35.115.1550						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1550	In: up to 0.4 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	817,96	817,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	817,96	258,75
				Material and Installation w/o Profit (TRY)	1.076,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.345,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1551						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1551	In: up to 4 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	817,96	817,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	817,96	258,75
				Material and Installation w/o Profit (TRY)	1.076,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.345,89**	

Item No	Analysis Name					UoM
35.115.1552						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1552	In: up to 6.3 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	817,96	817,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	817,96	258,75
				Material and Installation w/o Profit (TRY)	1.076,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.345,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1553						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1553	In: up to 10 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	898,48	898,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	898,48	258,75
				Material and Installation w/o Profit (TRY)	1.157,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.446,54**	

Item No	Analysis Name					UoM
35.115.1554						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1554	In: up to 12 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	985,60	985,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	985,60	258,75
				Material and Installation w/o Profit (TRY)	1.244,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.555,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1555						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1555	In: up to 16 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	985,60	985,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	985,60	258,75
				Material and Installation w/o Profit (TRY)	1.244,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.555,44**	

Item No	Analysis Name					UoM
35.115.1556						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1556	In: up to 20 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.012,00	1.012,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.012,00	258,75
				Material and Installation w/o Profit (TRY)	1.270,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.588,44**	

Item No	Analysis Name					UoM
35.115.1557						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1557	In: up to 25 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.080,64	1.080,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.080,64	258,75
				Material and Installation w/o Profit (TRY)	1.339,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.674,24**	

Item No	Analysis Name					UoM
35.115.1558						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1558	In: up to 32 (Icu: 100 kA) / Motor protection circuit breaker / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.146,64	1.146,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.146,64	258,75
				Material and Installation w/o Profit (TRY)	1.405,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.756,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1602						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1602	Up to 2 x 25 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	705,33	705,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	705,33	300,00
				Material and Installation w/o Profit (TRY)	1.005,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.256,66**	

Item No	Analysis Name					UoM
35.115.1604						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1604	Up to 2 x 40 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	724,09	724,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	724,09	300,00
				Material and Installation w/o Profit (TRY)	1.024,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.280,11**	

Item No	Analysis Name					UoM
35.115.1606						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1606	Up to 2 x 63 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	895,06	895,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	895,06	300,00
				Material and Installation w/o Profit (TRY)	1.195,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.493,82**	

Item No	Analysis Name					UoM
35.115.1608						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1608	Up to 2 x 80 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.500,43	1.500,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.500,43	300,00
				Material and Installation w/o Profit (TRY)	1.800,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.250,54**	

Item No	Analysis Name					UoM
35.115.1610						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1610	Up to 2 x 100 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	2.091,57	2.091,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.091,57	300,00
				Material and Installation w/o Profit (TRY)	2.391,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.989,46**	

Item No	Analysis Name					UoM
35.115.1612						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1612	Up to 4 x 25 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	957,94	957,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	957,94	343,50
				Material and Installation w/o Profit (TRY)	1.301,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.626,80**	

Item No	Analysis Name					UoM
35.115.1614						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1614	Up to 4 x 40 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	979,90	979,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	979,90	343,50
				Material and Installation w/o Profit (TRY)	1.323,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.654,25**	

Item No	Analysis Name					UoM
35.115.1616						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1616	Up to 4 x 63 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.422,43	1.422,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.422,43	343,50
				Material and Installation w/o Profit (TRY)	1.765,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.207,41**	

Item No	Analysis Name					UoM
35.115.1618						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1618	Up to 4 x 80 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.799,37	1.799,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.799,37	343,50
				Material and Installation w/o Profit (TRY)	2.142,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.678,59**	

Item No	Analysis Name					UoM
35.115.1620						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1620	Up to 4 x 100 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	3.494,56	3.494,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	3.494,56	343,50
				Material and Installation w/o Profit (TRY)	3.838,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**4.797,57**	

Item No	Analysis Name					UoM
35.115.1622						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1622	Up to 4 x 125 A (30 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	6.048,15	6.048,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	6.048,15	343,50
				Material and Installation w/o Profit (TRY)	6.391,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**7.989,56**	

Item No	Analysis Name					UoM
35.115.1624						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1624	Up to 2 x 25 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	699,26	699,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	699,26	300,00
				Material and Installation w/o Profit (TRY)	999,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.249,08**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1626						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1626	Up to 2 x 40 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	715,15	715,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	715,15	300,00
				Material and Installation w/o Profit (TRY)	1.015,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.268,94**	

Item No	Analysis Name					UoM
35.115.1628						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1628	Up to 2 x 63 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	805,26	805,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	805,26	300,00
				Material and Installation w/o Profit (TRY)	1.105,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.381,58**	

Item No	Analysis Name					UoM
35.115.1630						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1630	Up to 2 x 80 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.150,15	1.150,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.150,15	300,00
				Material and Installation w/o Profit (TRY)	1.450,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.812,69**	

Item No	Analysis Name					UoM
35.115.1632						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1632	Up to 2 x 100 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.993,63	1.993,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.993,63	300,00
				Material and Installation w/o Profit (TRY)	2.293,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.867,04**	

Item No	Analysis Name					UoM
35.115.1634						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1634	Up to 4 x 25 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	935,02	935,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	935,02	343,50
				Material and Installation w/o Profit (TRY)	1.278,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.598,15**	

Item No	Analysis Name					UoM
35.115.1636						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1636	Up to 4 x 40 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	941,26	941,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	941,26	343,50
				Material and Installation w/o Profit (TRY)	1.284,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**1.605,95**	

Item No	Analysis Name					UoM
35.115.1638						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1638	Up to 4 x 63 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.399,23	1.399,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.399,23	343,50
				Material and Installation w/o Profit (TRY)	1.742,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.178,41**	

Item No	Analysis Name					UoM
35.115.1640						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1640	Up to 4 x 80 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.571,70	1.571,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.571,70	343,50
				Material and Installation w/o Profit (TRY)	1.915,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.394,00**	

Item No	Analysis Name					UoM
35.115.1642						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1642	Up to 4 x 100 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	3.071,98	3.071,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	3.071,98	343,50
				Material and Installation w/o Profit (TRY)	3.415,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**4.269,35**	

Item No	Analysis Name					UoM
35.115.1644						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1644	Up to 4 x 125 A (300 m A) / Residual current circuit breakers (Protection Class: A) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	5.477,17	5.477,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	5.477,17	343,50
				Material and Installation w/o Profit (TRY)	5.820,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**7.275,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1703						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1703	Up to 2 x 25 A (30 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.343,74	1.343,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.343,74	300,00
				Material and Installation w/o Profit (TRY)	1.643,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.054,68**	

Item No	Analysis Name					UoM
35.115.1706						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1706	Up to 2 x 40 A (30 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.539,96	1.539,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.539,96	300,00
				Material and Installation w/o Profit (TRY)	1.839,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.299,95**	

Item No	Analysis Name					UoM
35.115.1709						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1709	Up to 2 x 63 A (30 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.754,28	1.754,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.754,28	300,00
				Material and Installation w/o Profit (TRY)	2.054,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.567,85**	

Item No	Analysis Name					UoM
35.115.1712						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1712	Up to 4 x 25 A (30 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS Market price	Qty	1	1.843,85	1.843,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.843,85	343,50
				Material and Installation w/o Profit (TRY)	2.187,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.734,19**	

Item No	Analysis Name					UoM
35.115.1715						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1715	Up to 4 x 40 A (30 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	2.095,85	2.095,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.095,85	343,50
				Material and Installation w/o Profit (TRY)	2.439,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.049,19**	

Item No	Analysis Name					UoM
35.115.1718						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1718	Up to 4 x 63 A (30 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	2.373,95	2.373,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.373,95	343,50
				Material and Installation w/o Profit (TRY)	2.717,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.396,81**	

Item No	Analysis Name					UoM
35.115.1721						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1721	Up to 2 x 25 A (300 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.209,36	1.209,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.209,36	300,00
				Material and Installation w/o Profit (TRY)	1.509,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.886,70**	

Item No	Analysis Name					UoM
35.115.1724						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1724	Up to 2 x 40 A (300 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.385,96	1.385,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.385,96	300,00
				Material and Installation w/o Profit (TRY)	1.685,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.107,45**	

Item No	Analysis Name					UoM
35.115.1727						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1727	Up to 2 x 63 A (300 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.578,85	1.578,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.578,85	300,00
				Material and Installation w/o Profit (TRY)	1.878,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.348,56**	

Item No	Analysis Name					UoM
35.115.1730						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1730	Up to 4 x 25 A (300 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.659,47	1.659,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.659,47	343,50
				Material and Installation w/o Profit (TRY)	2.002,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.503,71**	

Item No	Analysis Name					UoM
35.115.1733						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1733	Up to 4 x 40 A (300 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	1.886,27	1.886,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.886,27	343,50
				Material and Installation w/o Profit (TRY)	2.229,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**2.787,21**	

Item No	Analysis Name					UoM
35.115.1736						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1736	Up to 4 x 63 A (300 m A) / Residual current circuit breakers (Protection Class: F) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	2.136,56	2.136,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	2.136,56	343,50
				Material and Installation w/o Profit (TRY)	2.480,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**3.100,07**	

Item No	Analysis Name					UoM
35.115.1803						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1803	Up to 2 x 25 A (30 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	4.806,12	4.806,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.806,12	300,00
				Material and Installation w/o Profit (TRY)	5.106,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**6.382,65**	

Item No	Analysis Name					UoM
35.115.1806						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1806	Up to 2 x 40 A (30 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	5.200,47	5.200,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.200,47	300,00
				Material and Installation w/o Profit (TRY)	5.500,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**6.875,59**	

Item No	Analysis Name					UoM
35.115.1809						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1809	Up to 2 x 63 A (30 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	6.163,54	6.163,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	6.163,54	300,00
				Material and Installation w/o Profit (TRY)	6.463,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**8.079,43**	

Item No	Analysis Name					UoM
35.115.1812						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1812	Up to 4 x 25 A (30 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	6.392,09	6.392,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	6.392,09	343,50
				Material and Installation w/o Profit (TRY)	6.735,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**8.419,49**	

Item No	Analysis Name					UoM
35.115.1815						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1815	Up to 4 x 40 A (30 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	6.966,65	6.966,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	6.966,65	343,50
				Material and Installation w/o Profit (TRY)	7.310,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**9.137,69**	

Item No	Analysis Name					UoM
35.115.1818						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1818	Up to 4 x 63 A (30 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	8.204,24	8.204,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	8.204,24	343,50
				Material and Installation w/o Profit (TRY)	8.547,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**10.684,67**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.115.1821						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1821	Up to 2 x 25 A (300 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	4.652,52	4.652,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.652,52	300,00
				Material and Installation w/o Profit (TRY)	4.952,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**6.190,65**	

Item No	Analysis Name					UoM
35.115.1824						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1824	Up to 2 x 40 A (300 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	5.011,62	5.011,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.011,62	300,00
				Material and Installation w/o Profit (TRY)	5.311,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**6.639,52**	

Item No	Analysis Name					UoM
35.115.1827						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1827	Up to 2 x 63 A (300 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	5.715,34	5.715,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.715,34	300,00
				Material and Installation w/o Profit (TRY)	6.015,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**7.519,18**	

Item No	Analysis Name					UoM
35.115.1830						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1830	Up to 4 x 25 A (300 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	6.096,59	6.096,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	6.096,59	343,50
				Material and Installation w/o Profit (TRY)	6.440,09	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**8.050,11**	

Item No	Analysis Name					UoM
35.115.1833						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1833	Up to 4 x 40 A (300 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	6.609,65	6.609,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	6.609,65	343,50
				Material and Installation w/o Profit (TRY)	6.953,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**8.691,44**	

Item No	Analysis Name					UoM
35.115.1836						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.1836	Up to 4 x 63 A (300 m A) / Residual current circuit breakers (Protection Class: B) / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	7.786,85	7.786,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	7.786,85	343,50
				Material and Installation w/o Profit (TRY)	8.130,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**429,38**	
				Unit Price (TRY)	**10.162,94**	

Item No	Analysis Name					UoM
35.115.2501	**110 - 220/15 V Up to 50 VA / Transformers (TS EN 61558-2-4, TS EN 61558-2-5, TS EN 61558-2-6, TS EN 61558-2-7, TS EN 61558-2-8, TS EN 61558-2-9, TS EN 61558-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.2501	110 - 220/15 V up to 50 VA / Transformers (Market price)	Qty	1	151,80	151,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	151,80	207,00
				Material and Installation w/o Profit (TRY)	358,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**448,50**	

Item No	Analysis Name					UoM
35.115.2502	**110 - 220/24 V Up to 500 VA / Transformers (TS EN 61558-2-4, TS EN 61558-2-5, TS EN 61558-2-6, TS EN 61558-2-7, TS EN 61558-2-8, TS EN 61558-2-9, TS EN 61558-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.2502	110 - 220/24 V up to 500 VA / Transformers (Market price)	Qty	1	693,00	693,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	693,00	207,00
				Material and Installation w/o Profit (TRY)	900,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.125,00**	

Item No	Analysis Name					UoM
35.115.2503	**110 - 220/24 V Up to 1,000 VA / Transformers (TS EN 61558-2-4, TS EN 61558-2-5, TS EN 61558-2-6, TS EN 61558-2-7, TS EN 61558-2-8, TS EN 61558-2-9, TS EN 61558-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.2503	110 - 220/24 V up to 1000 VA / Transformers (Market price)	Qty	1	968,44	968,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	968,44	207,00
				Material and Installation w/o Profit (TRY)	1.175,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.469,30**	

Item No	Analysis Name					UoM
35.115.2504	**110 - 220/48 V Up to 100 VA / Transformers (TS EN 61558-2-4, TS EN 61558-2-5, TS EN 61558-2-6, TS EN 61558-2-7, TS EN 61558-2-8, TS EN 61558-2-9, TS EN 61558-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.2504	110 - 220/48 V up to 100 VA / Transformers (Market price)	Qty	1	435,16	435,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	435,16	207,00
				Material and Installation w/o Profit (TRY)	642,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**802,70**	

Item No	Analysis Name					UoM
35.115.2505	**110 - 220/48 V Up to 500 VA / Transformers (TS EN 61558-2-4, TS EN 61558-2-5, TS EN 61558-2-6, TS EN 61558-2-7, TS EN 61558-2-8, TS EN 61558-2-9, TS EN 61558-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.115.2505	110 - 220/48 V up to 500 VA / Transformers (Market price)	Qty	1	836,44	836,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	836,44	207,00
				Material and Installation w/o Profit (TRY)	1.043,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.304,30**	

Item No	Analysis Name					UoM
35.116.1110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1110	4P 100 kA (I imp; 10/350µs) / Type 1 (Class B) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	10.522,96	10.522,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	10.522,96	207,00
				Material and Installation w/o Profit (TRY)	10.729,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**13.412,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.116.1205						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1205	1P 20 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	882,80	882,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
		Total Excluding Profit (TRY)			882,80	163,50
		Material and Installation w/o Profit (TRY)			1.046,30	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**204,38**	
		Unit Price (TRY)			**1.307,88**	

Item No	Analysis Name					UoM
35.116.1206						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1206	2P 20 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.283,49	1.283,49	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
		Total Excluding Profit (TRY)			1.283,49	163,50
		Material and Installation w/o Profit (TRY)			1.446,99	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**204,38**	
		Unit Price (TRY)			**1.808,74**	

Item No	Analysis Name					UoM
35.116.1207						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1207	3P 20 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.513,55	2.513,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.513,55	207,00
				Material and Installation w/o Profit (TRY)	2.720,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.400,69**	

Item No	Analysis Name					UoM
35.116.1208						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1208	4P 20 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.821,29	2.821,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.821,29	207,00
				Material and Installation w/o Profit (TRY)	3.028,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.785,36**	

Item No	Analysis Name					UoM
35.116.1209						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1209	1P 20 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	971,08	971,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	971,08	163,50
				Material and Installation w/o Profit (TRY)	1.134,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**1.418,22**	

Item No	Analysis Name					UoM
35.116.1210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1210	2P 20 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.411,84	1.411,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.411,84	163,50
				Material and Installation w/o Profit (TRY)	1.575,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**1.969,17**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.116.1211						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1211	3P 20 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.764,91	2.764,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.764,91	207,00
				Material and Installation w/o Profit (TRY)	2.971,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.714,89**	

Item No	Analysis Name					UoM
35.116.1212						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1212	4P 20 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	3.103,42	3.103,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.103,42	207,00
				Material and Installation w/o Profit (TRY)	3.310,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.138,02**	

Item No	Analysis Name					UoM
35.116.1213						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1213	1P 40 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.015,22	1.015,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.015,22	163,50
				Material and Installation w/o Profit (TRY)	1.178,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**1.473,40**	

Item No	Analysis Name					UoM
35.116.1214						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1214	2P 40 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.476,02	1.476,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.476,02	163,50
				Material and Installation w/o Profit (TRY)	1.639,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**2.049,40**	

Item No	Analysis Name					UoM
35.116.1215						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1215	3P 40 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.890,59	2.890,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.890,59	207,00
				Material and Installation w/o Profit (TRY)	3.097,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.871,99**	

Item No	Analysis Name					UoM
35.116.1216						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1216	4P 40 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	3.244,48	3.244,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.244,48	207,00
				Material and Installation w/o Profit (TRY)	3.451,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.314,35**	

Item No	Analysis Name					UoM
35.116.1217						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1217	1P 40 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.116,74	1.116,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.116,74	163,50
				Material and Installation w/o Profit (TRY)	1.280,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**1.600,30**	

Item No	Analysis Name					UoM
35.116.1218						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1218	2P 40 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.623,62	1.623,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.623,62	163,50
				Material and Installation w/o Profit (TRY)	1.787,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**2.233,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.116.1219						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1219	3P 40 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	3.179,65	3.179,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.179,65	207,00
				Material and Installation w/o Profit (TRY)	3.386,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.233,31**	

Item No	Analysis Name					UoM
35.116.1220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1220	4P 40 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	3.568,93	3.568,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.568,93	207,00
				Material and Installation w/o Profit (TRY)	3.775,93	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.719,91**	

Item No	Analysis Name					UoM
35.116.1221						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1221	1P 65 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.409,30	1.409,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.409,30	163,50
				Material and Installation w/o Profit (TRY)	1.572,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**1.966,00**	

Item No	Analysis Name					UoM
35.116.1222						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1222	2P 65 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.649,70	1.649,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.649,70	163,50
				Material and Installation w/o Profit (TRY)	1.813,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**2.266,50**	

Item No	Analysis Name					UoM
35.116.1223						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1223	3P 65 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	3.723,44	3.723,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.723,44	207,00
				Material and Installation w/o Profit (TRY)	3.930,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.913,05**	

Item No	Analysis Name					UoM
35.116.1224						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1224	4P 65 kA (I max; 8/20µs) / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	4.858,02	4.858,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	4.858,02	207,00
				Material and Installation w/o Profit (TRY)	5.065,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**6.331,28**	

Item No	Analysis Name					UoM
35.116.1225						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1225	1P 65 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.550,23	1.550,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.550,23	163,50
				Material and Installation w/o Profit (TRY)	1.713,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**2.142,16**	

Item No	Analysis Name					UoM
35.116.1226						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1226	2P 65 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.814,67	1.814,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.814,67	163,50
				Material and Installation w/o Profit (TRY)	1.978,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**2.472,71**	

Item No	Analysis Name					UoM
35.116.1227						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1227	3P 65 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	4.095,78	4.095,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	4.095,78	207,00
				Material and Installation w/o Profit (TRY)	4.302,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**5.378,48**	

Item No	Analysis Name					UoM
35.116.1228						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1228	4P 65 kA (I max; 8/20µs) IK / Type 2 (Class C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	5.343,82	5.343,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	5.343,82	207,00
				Material and Installation w/o Profit (TRY)	5.550,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**6.938,52**	

Item No	Analysis Name					UoM
35.116.1310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1310	1P 12,5 kA (I imp; 10/350µs) / Type 1+2 (Class B+C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	3.868,09	3.868,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	3.868,09	163,50
				Material and Installation w/o Profit (TRY)	4.031,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**5.039,49**	

Item No	Analysis Name					UoM
35.116.1320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1320	2P 25 kA (I imp; 10/350µs) / Type 1+2 (Class B+C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	3.928,05	3.928,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	3.928,05	163,50
				Material and Installation w/o Profit (TRY)	4.091,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**5.114,44**	

Item No	Analysis Name					UoM
35.116.1330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1330	3P 37,5 kA (I imp; 10/350µs) / Type 1+2 (Class B+C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	6.072,11	6.072,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	6.072,11	207,00
				Material and Installation w/o Profit (TRY)	6.279,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**7.848,89**	

Item No	Analysis Name					UoM
35.116.1340						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1340	4P 50 kA (I imp; 10/350µs) / Type 1+2 (Class B+C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	5.940,61	5.940,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	5.940,61	207,00
				Material and Installation w/o Profit (TRY)	6.147,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**7.684,51**	

Item No	Analysis Name					UoM
35.116.1350						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1350	4P 100 kA (I imp; 10/350µs) / Type 1+2 (Class B+C) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	15.396,40	15.396,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	15.396,40	207,00
				Material and Installation w/o Profit (TRY)	15.603,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**19.504,25**	

Item No	Analysis Name					UoM
35.116.1410						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1410	1P 8 kA (I max; 8/20µs) / Type 3 (Class D) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	671,49	671,49	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	671,49	163,50
				Material and Installation w/o Profit (TRY)	834,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**1.043,74**	

Item No	Analysis Name					UoM
35.116.1420						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1420	2P 8 kA (I max; 8/20µs) / Type 3 (Class D) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.710,65	1.710,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.710,65	163,50
				Material and Installation w/o Profit (TRY)	1.874,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**2.342,69**	

Item No	Analysis Name					UoM
35.116.1430						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1430	3P 8 kA (I max; 8/20µs) / Type 3 (Class D) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	1.546,27	1.546,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	1.546,27	207,00
				Material and Installation w/o Profit (TRY)	1.753,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**2.191,59**	

Item No	Analysis Name					UoM
35.116.1440						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1440	4P 8 kA (I max; 8/20µs) / Type 3 (Class D) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.166,84	2.166,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.166,84	207,00
				Material and Installation w/o Profit (TRY)	2.373,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**2.967,30**	

Item No	Analysis Name					UoM
35.116.1510						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1510	2P 12-20 kA (I max; 8/20µs) / Type 2+3 (Class C+D) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.124,60	2.124,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	2.124,60	163,50
				Material and Installation w/o Profit (TRY)	2.288,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**2.860,13**	

Item No	Analysis Name					UoM
35.116.1520						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1520	4P 12-20 kA (I max; 8/20µs) / Type 2+3 (Class C+D) surge arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	5.053,80	5.053,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	5.053,80	207,00
				Material and Installation w/o Profit (TRY)	5.260,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**6.576,00**	

Item No	Analysis Name					UoM
35.116.1610						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1610	10 kA (I imp; 10/350µs) / Data Protection Surge Arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.635,18	2.635,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	2.635,18	163,50
				Material and Installation w/o Profit (TRY)	2.798,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**204,38**	
				Unit Price (TRY)	**3.498,35**	

Item No	Analysis Name					UoM
35.116.1620						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.116.1620	20 kA (I imp; 10/350µs) / Data Protection Surge Arrester / Low-Voltage Surge Arresters (Market price)	Qty	1	2.900,00	2.900,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
		Total Excluding Profit (TRY)			2.900,00	163,50
		Material and Installation w/o Profit (TRY)			3.063,50	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**204,38**	
		Unit Price (TRY)			**3.829,38**	

Item No	Analysis Name					UoM
35.120.1101	**Up to 2 x 16 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1101	Up to 2 x 16 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	221,28	221,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			221,28	476,25
		Material and Installation w/o Profit (TRY)			697,53	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**595,31**	
		Unit Price (TRY)			**871,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1102	**Up to 2 x 25 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1102	Up to 2 x 25 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	278,88	278,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	278,88	476,25
				Material and Installation w/o Profit (TRY)	755,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**943,91**	

Item No	Analysis Name					UoM
35.120.1103	**Up to 2 x 40 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1103	Up to 2 x 40 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	308,64	308,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	308,64	476,25
				Material and Installation w/o Profit (TRY)	784,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**981,11**	

Item No	Analysis Name					UoM
35.120.1104	**Up to 3 x 25 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1104	Up to 3 x 25 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	260,16	260,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	260,16	476,25
				Material and Installation w/o Profit (TRY)	736,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**920,51**	

Item No	Analysis Name					UoM
35.120.1105	**Up to 3 x 40 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1105	Up to 3 x 40 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	500,16	500,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	500,16	476,25
				Material and Installation w/o Profit (TRY)	976,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**1.220,51**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1106	**Up to 3 x 63 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1106	Up to 3 x 63 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	758,40	758,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	758,40	476,25
				Material and Installation w/o Profit (TRY)	1.234,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**1.543,31**	

Item No	Analysis Name					UoM
35.120.1107	**Up to 3 x 100 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1107	Up to 3 x 100 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	1.489,92	1.489,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.489,92	476,25
				Material and Installation w/o Profit (TRY)	1.966,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.457,71**	

Item No	Analysis Name					UoM
35.120.1108	**Up to 3 x 125 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1108	Up to 3 x 125 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	1.883,52	1.883,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			1.883,52	476,25
		Material and Installation w/o Profit (TRY)			2.359,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**595,31**	
		Unit Price (TRY)			**2.949,71**	

Item No	Analysis Name					UoM
35.120.1109	**Up to 3 x 160 A / Step-type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1109	Up to 3 x 160 A / Step-type cam switches / Cam Switches (Market price)	Qty	1	2.142,72	2.142,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			2.142,72	476,25
		Material and Installation w/o Profit (TRY)			2.618,97	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**595,31**	
		Unit Price (TRY)			**3.273,71**	

Item No	Analysis Name					UoM
35.120.1151	**Up to 2 x 16 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1151	Up to 2 x 16 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	156,00	156,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	156,00	258,75
				Material and Installation w/o Profit (TRY)	414,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**518,44**	

Item No	Analysis Name					UoM
35.120.1152	**Up to 2 x 25 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1152	Up to 2 x 25 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	187,68	187,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	187,68	258,75
				Material and Installation w/o Profit (TRY)	446,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**558,04**	

Item No	Analysis Name					UoM
35.120.1153	**Up to 2 x 40 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1153	Up to 2 x 40 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	261,60	261,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	261,60	258,75
				Material and Installation w/o Profit (TRY)	520,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**650,44**	

Item No	Analysis Name					UoM
35.120.1154	**Up to 3 x 25 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1154	Up to 3 x 25 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	236,16	236,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	236,16	258,75
				Material and Installation w/o Profit (TRY)	494,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**618,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1155	**Up to 3 x 40 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1155	Up to 3 x 40 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	427,20	427,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	427,20	258,75
				Material and Installation w/o Profit (TRY)	685,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**857,44**	

Item No	Analysis Name					UoM
35.120.1156	**Up to 3 x 63 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1156	Up to 3 x 63 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	647,04	647,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	647,04	258,75
				Material and Installation w/o Profit (TRY)	905,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.132,24**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1157	**Up to 3 x 100 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1157	Up to 3 x 100 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	1.115,52	1.115,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.115,52	258,75
				Material and Installation w/o Profit (TRY)	1.374,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.717,84**	

Item No	Analysis Name					UoM
35.120.1158	**Up to 3 x 125 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1158	Up to 3 x 125 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	1.480,32	1.480,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.480,32	258,75
				Material and Installation w/o Profit (TRY)	1.739,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.173,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1159	**Up to 3 x 160 A / On-off type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1159	Up to 3 x 160 A / On-off type cam switches / Cam Switches (Market price)	Qty	1	1.758,72	1.758,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.758,72	258,75
		Material and Installation w/o Profit (TRY)			2.017,47	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**2.521,84**	

Item No	Analysis Name					UoM
35.120.1201	**Up to 3 x 25 A / Star-delta type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1201	Up to 3 x 25 A / Star-delta type cam switches / Cam Switches (Market price)	Qty	1	355,20	355,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
		Total Excluding Profit (TRY)			355,20	345,75
		Material and Installation w/o Profit (TRY)			700,95	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**432,19**	
		Unit Price (TRY)			**876,19**	

Item No	Analysis Name					UoM
35.120.1202	**Up to 3 x 40 A / Star-delta type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1202	Up to 3 x 40 A / Star-delta type cam switches / Cam Switches (Market price)	Qty	1	513,60	513,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	513,60	345,75
				Material and Installation w/o Profit (TRY)	859,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**432,19**	
				Unit Price (TRY)	**1.074,19**	

Item No	Analysis Name					UoM
35.120.1203	**Up to 3 x 63 A / Star-delta type cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1203	Up to 3 x 63 A / Star-delta type cam switches / Cam Switches (Market price)	Qty	1	1.023,36	1.023,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	1.023,36	345,75
				Material and Installation w/o Profit (TRY)	1.369,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**432,19**	
				Unit Price (TRY)	**1.711,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1251	**Up to 3 x 25 A / Reversing cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1251	Up to 3 x 25 A / Reversing cam switches / Cam Switches (Market price)	Qty	1	517,44	517,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	517,44	345,75
				Material and Installation w/o Profit (TRY)	863,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**432,19**	
				Unit Price (TRY)	**1.078,99**	

Item No	Analysis Name					UoM
35.120.1252	**Up to 3 x 40 A / Reversing cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1252	Up to 3 x 40 A / Reversing cam switches / Cam Switches (Market price)	Qty	1	623,04	623,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	623,04	345,75
				Material and Installation w/o Profit (TRY)	968,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**432,19**	
				Unit Price (TRY)	**1.210,99**	

Item No	Analysis Name					UoM
35.120.1253	**Up to 3 x 63 A / Reversing cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1253	Up to 3 x 63 A / Reversing cam switches / Cam Switches (Market price)	Qty	1	1.090,56	1.090,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
		Total Excluding Profit (TRY)			1.090,56	345,75
		Material and Installation w/o Profit (TRY)			1.436,31	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**432,19**	
		Unit Price (TRY)			**1.795,39**	

Item No	Analysis Name					UoM
35.120.1254	**Up to 3 x 100 A / Reversing cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1254	Up to 3 x 100 A / Reversing cam switches / Cam Switches (Market price)	Qty	1	2.545,92	2.545,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
		Total Excluding Profit (TRY)			2.545,92	345,75
		Material and Installation w/o Profit (TRY)			2.891,67	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**432,19**	
		Unit Price (TRY)			**3.614,59**	

Item No	Analysis Name					UoM
35.120.1255	**Up to 3 x 125 A / Reversing cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1255	Up to 3 x 125 A / Reversing cam switches / Cam Switches (Market price)	Qty	1	3.553,92	3.553,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
		Total Excluding Profit (TRY)			3.553,92	345,75
		Material and Installation w/o Profit (TRY)			3.899,67	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**432,19**	
		Unit Price (TRY)			**4.874,59**	

Item No	Analysis Name					UoM
35.120.1301	**Up to 2 x 16 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1301	Up to 2 x 16 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	293,28	293,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
		Total Excluding Profit (TRY)			293,28	563,25
		Material and Installation w/o Profit (TRY)			856,53	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**704,06**	
		Unit Price (TRY)			**1.070,66**	

Item No	Analysis Name					UoM
35.120.1302	**Up to 2 x 25 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1302	Up to 2 x 25 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	320,16	320,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
		Total Excluding Profit (TRY)			320,16	563,25
		Material and Installation w/o Profit (TRY)			883,41	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**704,06**	
		Unit Price (TRY)			**1.104,26**	

Item No	Analysis Name					UoM
35.120.1303	**Up to 2 x 40 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1303	Up to 2 x 40 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	401,76	401,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
		Total Excluding Profit (TRY)			401,76	563,25
		Material and Installation w/o Profit (TRY)			965,01	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**704,06**	
		Unit Price (TRY)			**1.206,26**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1304	**Up to 3 x 25 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1304	Up to 3 x 25 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	442,56	442,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	442,56	563,25
				Material and Installation w/o Profit (TRY)	1.005,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**704,06**	
				Unit Price (TRY)	**1.257,26**	

Item No	Analysis Name					UoM
35.120.1305	**Up to 3 x 40 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1305	Up to 3 x 40 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	741,12	741,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	741,12	563,25
				Material and Installation w/o Profit (TRY)	1.304,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**704,06**	
				Unit Price (TRY)	**1.630,46**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1306	**Up to 3 x 63 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1306	Up to 3 x 63 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	1.253,76	1.253,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	1.253,76	563,25
				Material and Installation w/o Profit (TRY)	1.817,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**704,06**	
				Unit Price (TRY)	**2.271,26**	

Item No	Analysis Name					UoM
35.120.1307	**Up to 3 x 100 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1307	Up to 3 x 100 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	1.797,12	1.797,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	1.797,12	563,25
				Material and Installation w/o Profit (TRY)	2.360,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**704,06**	
				Unit Price (TRY)	**2.950,46**	

Item No	Analysis Name					UoM
35.120.1308	**Up to 3 x 125 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1308	Up to 3 x 125 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	1.941,12	1.941,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician’s helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	1.941,12	563,25
				Material and Installation w/o Profit (TRY)	2.504,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**704,06**	
				Unit Price (TRY)	**3.130,46**	

Item No	Analysis Name					UoM
35.120.1309	**Up to 3 x 160 A / Step-type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1309	Up to 3 x 160 A / Step-type outdoor cam switches / Cam Switches (Market price)	Qty	1	2.229,12	2.229,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician’s helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	2.229,12	563,25
				Material and Installation w/o Profit (TRY)	2.792,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**704,06**	
				Unit Price (TRY)	**3.490,46**	

Item No	Analysis Name					UoM
35.120.1351	**Up to 2 x 16 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1351	Up to 2 x 16 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	212,64	212,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
		Total Excluding Profit (TRY)			212,64	302,25
		Material and Installation w/o Profit (TRY)			514,89	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**377,81**	
		Unit Price (TRY)			**643,61**	

Item No	Analysis Name					UoM
35.120.1352	**Up to 2 x 25 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1352	Up to 2 x 25 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	266,40	266,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
		Total Excluding Profit (TRY)			266,40	302,25
		Material and Installation w/o Profit (TRY)			568,65	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**377,81**	
		Unit Price (TRY)			**710,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1353	**Up to 2 x 40 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1353	Up to 2 x 40 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	292,32	292,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	292,32	302,25
				Material and Installation w/o Profit (TRY)	594,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**377,81**	
				Unit Price (TRY)	**743,21**	

Item No	Analysis Name					UoM
35.120.1354	**Up to 3 x 25 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1354	Up to 3 x 25 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	258,24	258,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	258,24	302,25
				Material and Installation w/o Profit (TRY)	560,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**377,81**	
				Unit Price (TRY)	**700,61**	

Item No	Analysis Name					UoM
35.120.1355	**Up to 3 x 40 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1355	Up to 3 x 40 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	561,60	561,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	561,60	302,25
				Material and Installation w/o Profit (TRY)	863,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**377,81**	
				Unit Price (TRY)	**1.079,81**	

Item No	Analysis Name					UoM
35.120.1356	**Up to 3 x 63 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1356	Up to 3 x 63 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	984,96	984,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	984,96	302,25
				Material and Installation w/o Profit (TRY)	1.287,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**377,81**	
				Unit Price (TRY)	**1.609,01**	

Item No	Analysis Name					UoM
35.120.1357	**Up to 3 x 100 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1357	Up to 3 x 100 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	1.499,52	1.499,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.499,52	302,25
				Material and Installation w/o Profit (TRY)	1.801,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**377,81**	
				Unit Price (TRY)	**2.252,21**	

Item No	Analysis Name					UoM
35.120.1358	**Up to 3 x 125 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1358	Up to 3 x 125 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	1.595,52	1.595,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.595,52	302,25
				Material and Installation w/o Profit (TRY)	1.897,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**377,81**	
				Unit Price (TRY)	**2.372,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1359	**Up to 3 x 160 A / On-off type outdoor cam switches / Cam Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1359	Up to 3 x 160 A / On-off type outdoor cam switches / Cam Switches (Market price)	Qty	1	1.950,72	1.950,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.950,72	302,25
				Material and Installation w/o Profit (TRY)	2.252,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**377,81**	
				Unit Price (TRY)	**2.816,21**	

Item No	Analysis Name					UoM
35.120.1401	**Up to 2 x 16 A / Latching Switch**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1401	Up to 2 x 16 A / Latching Switch (Market price)	Qty	1	60,58	60,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	60,58	171,75
				Material and Installation w/o Profit (TRY)	232,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**290,41**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1402	**Up to 3 x 25 A / Latching Switch**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1402	Up to 3 x 25 A / Latching Switch (Market price)	Qty	1	92,26	92,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	92,26	171,75
				Material and Installation w/o Profit (TRY)	264,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**330,01**	

Item No	Analysis Name					UoM
35.120.1403	**Up to 3 x 32 A / Latching Switch**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1403	Up to 3 x 32 A / Latching Switch (Market price)	Qty	1	154,66	154,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	154,66	171,75
				Material and Installation w/o Profit (TRY)	326,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**408,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1451	**Max. 24 V / Signal Lamps**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1451	Max. 24 V / Signal Lights (Market price)	Qty	1	53,57	53,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	53,57	60,00
				Material and Installation w/o Profit (TRY)	113,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**75,00**	
				Unit Price (TRY)	**141,96**	

Item No	Analysis Name					UoM
35.120.1452	**Max. 48 V / Signal Lamps**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1452	Max. 48 V / Signal Lights (Market price)	Qty	1	53,57	53,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	53,57	60,00
				Material and Installation w/o Profit (TRY)	113,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**75,00**	
				Unit Price (TRY)	**141,96**	

Item No	Analysis Name					UoM
35.120.1453	**Max. 65 V / Signal Lamps**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1453	Max. 65 V / Signal Lights (Market price)	Qty	1	53,57	53,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	53,57	60,00
				Material and Installation w/o Profit (TRY)	113,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**75,00**	
				Unit Price (TRY)	**141,96**	

Item No	Analysis Name					UoM
35.120.1454	**Max. 250 V / Signal Lamps**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1454	Max. 250 V / Signal Lights (Market price)	Qty	1	53,57	53,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	53,57	60,00
				Material and Installation w/o Profit (TRY)	113,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**75,00**	
				Unit Price (TRY)	**141,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.1455	**Max. 500 V / Signal Lamps**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.1455	Max. 500 V / Signal Lights (Market price)	Qty	1	53,57	53,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	53,57	60,00
				Material and Installation w/o Profit (TRY)	113,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**75,00**	
				Unit Price (TRY)	**141,96**	

Item No	Analysis Name					UoM
35.120.2001	**3 x 125 A / AUTOMATIC TRANSFER SWITCHES**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2001	3 x 125 A / AUTOMATIC TRANSFER SWITCHES / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	20.086,90	20.086,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	20.086,90	952,50
				Material and Installation w/o Profit (TRY)	21.039,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**26.299,25**	

Item No	Analysis Name					UoM
35.120.2002	**3 x 200 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2002	3 x 200 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	23.211,30	23.211,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	23.211,30	952,50
				Material and Installation w/o Profit (TRY)	24.163,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**30.204,75**	

Item No	Analysis Name					UoM
35.120.2003	**3 x 250 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2003	3 x 250 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	27.585,46	27.585,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	27.585,46	952,50
				Material and Installation w/o Profit (TRY)	28.537,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**35.672,45**	

Item No	Analysis Name					UoM
35.120.2004	**3 x 315 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2004	3 x 315 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	28.655,46	28.655,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	28.655,46	952,50
				Material and Installation w/o Profit (TRY)	29.607,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**37.009,95**	

Item No	Analysis Name					UoM
35.120.2005	**3 x 400 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2005	3 x 400 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	31.009,46	31.009,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	31.009,46	952,50
				Material and Installation w/o Profit (TRY)	31.961,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**39.952,45**	

Item No	Analysis Name					UoM
35.120.2006	**3 x 500 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2006	3 x 500 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	31.856,90	31.856,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	31.856,90	952,50
				Material and Installation w/o Profit (TRY)	32.809,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**41.011,75**	

Item No	Analysis Name					UoM
35.120.2007	**3 x 630 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2007	3 x 630 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	33.363,46	33.363,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	33.363,46	952,50
				Material and Installation w/o Profit (TRY)	34.315,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**42.894,95**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2008	**3 x 800 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2008	3 x 800 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	55.953,30	55.953,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
		Total Excluding Profit (TRY)			55.953,30	952,50
		Material and Installation w/o Profit (TRY)			56.905,80	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.190,63**	
		Unit Price (TRY)			**71.132,25**	

Item No	Analysis Name					UoM
35.120.2009	**3 x 1,000 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2009	3 x 1000 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	58.461,38	58.461,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
		Total Excluding Profit (TRY)			58.461,38	952,50
		Material and Installation w/o Profit (TRY)			59.413,88	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.190,63**	
		Unit Price (TRY)			**74.267,35**	

Item No	Analysis Name					UoM
35.120.2010	**3 x 1,250 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2010	3 x 1250 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	70.923,02	70.923,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	70.923,02	1.387,50
				Material and Installation w/o Profit (TRY)	72.310,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.734,38**	
				Unit Price (TRY)	**90.388,15**	

Item No	Analysis Name					UoM
35.120.2011	**3 x 1,600 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2011	3 x 1600 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	87.940,30	87.940,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	87.940,30	1.387,50
				Material and Installation w/o Profit (TRY)	89.327,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.734,38**	
				Unit Price (TRY)	**111.659,75**	

Item No	Analysis Name					UoM
35.120.2012	**3 x 2,000 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2012	3 x 2000 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	155.307,50	155.307,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	155.307,50	1.822,50
				Material and Installation w/o Profit (TRY)	157.130,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.278,13**	
				Unit Price (TRY)	**196.412,50**	

Item No	Analysis Name					UoM
35.120.2013	**3 x 2,500 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2013	3 x 2500 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	175.252,30	175.252,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	175.252,30	1.822,50
				Material and Installation w/o Profit (TRY)	177.074,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.278,13**	
				Unit Price (TRY)	**221.343,50**	

Item No	Analysis Name					UoM
35.120.2014	**3 x 3,200 A / AUTOMATIC TRANSFER SWITCHES**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2014	3 x 3200 A / AUTOMATIC TRANSFER SWITCHES / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	206.496,30	206.496,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	206.496,30	1.822,50
				Material and Installation w/o Profit (TRY)	208.318,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.278,13**	
				Unit Price (TRY)	**260.398,50**	

Item No	Analysis Name					UoM
35.120.2015	**4 x 100 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2015	4 x 100 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	16.483,14	16.483,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	16.483,14	1.170,00
				Material and Installation w/o Profit (TRY)	17.653,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**22.066,42**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2016	**4 x 200 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2016	4 x 200 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	24.640,82	24.640,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	24.640,82	1.170,00
				Material and Installation w/o Profit (TRY)	25.810,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**32.263,53**	

Item No	Analysis Name					UoM
35.120.2017	**4 x 315 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2017	4 x 315 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	30.453,06	30.453,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	30.453,06	1.170,00
				Material and Installation w/o Profit (TRY)	31.623,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**39.528,83**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2018	**4 x 400 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2018	4 x 400 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	32.952,58	32.952,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	32.952,58	1.170,00
				Material and Installation w/o Profit (TRY)	34.122,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**42.653,23**	

Item No	Analysis Name					UoM
35.120.2019	**4 x 500 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2019	4 x 500 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	33.877,06	33.877,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	33.877,06	1.170,00
				Material and Installation w/o Profit (TRY)	35.047,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**43.808,82**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2020	**4 x 630 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2020	4 x 630 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	35.460,66	35.460,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	35.460,66	1.170,00
				Material and Installation w/o Profit (TRY)	36.630,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**45.788,33**	

Item No	Analysis Name					UoM
35.120.2021	**4 x 800 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2021	4 x 800 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	59.668,34	59.668,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	59.668,34	1.170,00
				Material and Installation w/o Profit (TRY)	60.838,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**76.047,92**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2022	**4 x 1,000 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2022	4 x 1000 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	62.328,78	62.328,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	62.328,78	1.170,00
				Material and Installation w/o Profit (TRY)	63.498,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**79.373,48**	

Item No	Analysis Name					UoM
35.120.2023	**4 x 1,250 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2023	4 x 1250 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	75.682,38	75.682,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	75.682,38	1.822,50
				Material and Installation w/o Profit (TRY)	77.504,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.278,13**	
				Unit Price (TRY)	**96.881,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2024	**4 x 1,600 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2024	4 x 1600 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	93.932,30	93.932,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	93.932,30	1.822,50
				Material and Installation w/o Profit (TRY)	95.754,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.278,13**	
				Unit Price (TRY)	**119.693,50**	

Item No	Analysis Name					UoM
35.120.2025	**4 x 2,000 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2025	4 x 2000 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	165.921,90	165.921,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
				Total Excluding Profit (TRY)	165.921,90	2.257,50
				Material and Installation w/o Profit (TRY)	168.179,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.821,88**	
				Unit Price (TRY)	**210.224,25**	

Item No	Analysis Name					UoM
35.120.2026	**4 x 2,500 A / Automatic Transfer Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2026	4 x 2500 A / Automatic Transfer Switches / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	187.150,70	187.150,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
				Total Excluding Profit (TRY)	187.150,70	2.257,50
				Material and Installation w/o Profit (TRY)	189.408,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.821,88**	
				Unit Price (TRY)	**236.760,25**	

Item No	Analysis Name					UoM
35.120.2027	**4 x 3,200 A / AUTOMATIC TRANSFER SWITCHES**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2027	4 x 3200 A / AUTOMATIC TRANSFER SWITCHES / PROTECTION, CONTROL AND SWITCHING PRODUCTS (Market price)	Qty	1	220.705,90	220.705,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
				Total Excluding Profit (TRY)	220.705,90	2.257,50
				Material and Installation w/o Profit (TRY)	222.963,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.821,88**	
				Unit Price (TRY)	**278.704,25**	

Item No	Analysis Name					UoM
35.120.2101	**Up to 3 x 25 A / Automatic reversing switch with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2101	Up to 3 x 25 A / Automatic reversing switch with thermal and magnetic protector (Market price)	Qty	1	5.272,96	5.272,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	5.272,96	476,25
				Material and Installation w/o Profit (TRY)	5.749,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**7.186,51**	

Item No	Analysis Name					UoM
35.120.2102	**Up to 3 x 63 A / Automatic reversing switch with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2102	Up to 3 x 63 A / Automatic reversing switch with thermal and magnetic protector (Market price)	Qty	1	8.910,88	8.910,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	8.910,88	519,75
				Material and Installation w/o Profit (TRY)	9.430,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**11.788,29**	

Item No	Analysis Name					UoM
35.120.2103	**Up to 3 x 100 A / Automatic reversing switch with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2103	Up to 3 x 100 A / Automatic reversing switch with thermal and magnetic protector (Market price)	Qty	1	18.139,44	18.139,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,2	250,00		300,00
10.100.1083	Master electrician's helper	h	1,2	185,00		222,00
				Total Excluding Profit (TRY)	18.139,44	563,25
				Material and Installation w/o Profit (TRY)	18.702,69	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**704,06**	
				Unit Price (TRY)	**23.378,36**	

Item No	Analysis Name					UoM
35.120.2104	**Up to 3 x 200 A / Automatic reversing switch with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2104	Up to 3 x 200 A / Automatic reversing switch with thermal and magnetic protector (Market price)	Qty	1	23.836,56	23.836,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	23.836,56	693,75
				Material and Installation w/o Profit (TRY)	24.530,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**30.662,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2105	**Up to 3 x 400 A / Automatic reversing switch with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2105	Up to 3 x 400 A / Automatic reversing switch with thermal and magnetic protector (Market price)	Qty	1	29.307,52	29.307,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,7	250,00		425,00
10.100.1083	Master electrician's helper	h	1,7	185,00		314,50
				Total Excluding Profit (TRY)	29.307,52	780,75
				Material and Installation w/o Profit (TRY)	30.088,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**975,94**	
				Unit Price (TRY)	**37.610,34**	

Item No	Analysis Name					UoM
35.120.2106	**Up to 3 x 600 A / Automatic reversing switch with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2106	Up to 3 x 600 A / Automatic reversing switch with thermal and magnetic protector (Market price)	Qty	1	39.405,52	39.405,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	39.405,52	911,25
				Material and Installation w/o Profit (TRY)	40.316,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**50.395,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.120.2107	**Up to 3 x 1,000 A / Automatic reversing switch with thermal and magnetic protector**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.120.2107	Up to 3 x 1,000 A / Automatic reversing switch with thermal and magnetic protector (Market price)	Qty	1	64.280,48	64.280,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
		Total Excluding Profit (TRY)			64.280,48	1.346,25
		Material and Installation w/o Profit (TRY)			65.626,73	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.682,81**	
		Unit Price (TRY)			**82.033,41**	

Item No	Analysis Name					UoM
35.125.1101	**Up to 3 x 10 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1101	Up to 3 x 10 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	399,52	399,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			399,52	300,00
		Material and Installation w/o Profit (TRY)			699,52	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**375,00**	
		Unit Price (TRY)			**874,40**	

Item No	Analysis Name					UoM
35.125.1102	**Up to 3 x 16 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1102	Up to 3 x 16 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	495,44	495,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	495,44	300,00
				Material and Installation w/o Profit (TRY)	795,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**994,30**	

Item No	Analysis Name					UoM
35.125.1103	**Up to 3 x 25 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1103	Up to 3 x 25 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	652,96	652,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	652,96	300,00
				Material and Installation w/o Profit (TRY)	952,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.191,20**	

Item No	Analysis Name					UoM
35.125.1104	**Up to 3 x 40 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1104	Up to 3 x 40 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	1.507,44	1.507,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.507,44	300,00
				Material and Installation w/o Profit (TRY)	1.807,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.259,30**	

Item No	Analysis Name					UoM
35.125.1105	**Up to 3 x 63 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1105	Up to 3 x 63 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	2.440,24	2.440,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.440,24	300,00
				Material and Installation w/o Profit (TRY)	2.740,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**3.425,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.125.1106	**Up to 3 x 100 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1106	Up to 3 x 100 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	3.954,72	3.954,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician's helper	h	0,7	185,00		129,50
				Total Excluding Profit (TRY)	3.954,72	387,00
				Material and Installation w/o Profit (TRY)	4.341,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**483,75**	
				Unit Price (TRY)	**5.427,15**	

Item No	Analysis Name					UoM
35.125.1107	**Up to 3 x 160 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1107	Up to 3 x 160 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	6.392,32	6.392,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician's helper	h	0,9	185,00		166,50
				Total Excluding Profit (TRY)	6.392,32	474,00
				Material and Installation w/o Profit (TRY)	6.866,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**592,50**	
				Unit Price (TRY)	**8.582,90**	

Item No	Analysis Name					UoM
35.125.1108	**Up to 3 x 200 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1108	Up to 3 x 200 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	9.427,44	9.427,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	9.427,44	561,00
				Material and Installation w/o Profit (TRY)	9.988,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**701,25**	
				Unit Price (TRY)	**12.485,55**	

Item No	Analysis Name					UoM
35.125.1109	**Up to 3 x 300 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1109	Up to 3 x 300 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	16.793,92	16.793,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	16.793,92	561,00
				Material and Installation w/o Profit (TRY)	17.354,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**701,25**	
				Unit Price (TRY)	**21.693,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.125.1110	**Up to 3 x 400 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1110	Up to 3 x 400 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	20.947,52	20.947,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	20.947,52	735,00
				Material and Installation w/o Profit (TRY)	21.682,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**27.103,15**	

Item No	Analysis Name					UoM
35.125.1111	**Up to 3 x 630 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1111	Up to 3 x 630 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	39.436,32	39.436,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,9	250,00		475,00
10.100.1083	Master electrician's helper	h	1,9	185,00		351,50
				Total Excluding Profit (TRY)	39.436,32	909,00
				Material and Installation w/o Profit (TRY)	40.345,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.136,25**	
				Unit Price (TRY)	**50.431,65**	

Item No	Analysis Name					UoM
35.125.1112	**Up to 3 x 800 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1112	Up to 3 x 800 A / Dry-type contactors without protector / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	54.977,12	54.977,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	54.977,12	1.170,00
				Material and Installation w/o Profit (TRY)	56.147,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**70.183,90**	

Item No	Analysis Name					UoM
35.125.1201	**Capacitor duty contactor up to 15 kVAr / Contactors for capacitor switching / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1201	Capacitor duty contactor up to 15 kVAr / Contactors for capacitor switching / CONTACTORS (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	1.268,50	1.268,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.268,50	300,00
				Material and Installation w/o Profit (TRY)	1.568,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.960,63**	

Item No	Analysis Name					UoM
35.125.1202	**Capacitor duty contactor up to 20 kVAr / Contactors for capacitor switching / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1202	Capacitor duty contactor up to 20 kVAr / Contactors for capacitor switching / CONTACTORS (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	1.583,00	1.583,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.583,00	300,00
				Material and Installation w/o Profit (TRY)	1.883,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.353,75**	

Item No	Analysis Name					UoM
35.125.1203	**Capacitor duty contactor up to 30 kVAr / Contactors for capacitor switching / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1203	Capacitor duty contactor up to 30 kVAr / Contactors for capacitor switching / CONTACTORS (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	3.246,00	3.246,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.246,00	300,00
				Material and Installation w/o Profit (TRY)	3.546,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**4.432,50**	

Item No	Analysis Name					UoM
35.125.1204	**Capacitor duty contactor up to 50 kVAr / Contactors for capacitor switching / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1204	Capacitor duty contactor up to 50 kVAr / Contactors for capacitor switching / CONTACTORS (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	4.663,00	4.663,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.663,00	300,00
				Material and Installation w/o Profit (TRY)	4.963,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**6.203,75**	

Item No	Analysis Name					UoM
35.125.1205	**Capacitor duty contactor up to 60 kVAr / Contactors for capacitor switching / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1205	Capacitor duty contactor up to 60 kVAr / Contactors for capacitor switching / CONTACTORS (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	5.549,00	5.549,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.549,00	300,00
				Material and Installation w/o Profit (TRY)	5.849,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**7.311,25**	

Item No	Analysis Name					UoM
35.125.1210	**Capacitor duty contactor up to 60 kVAr / Contactors for capacitor switching / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1210	Capacitor duty contactor up to 80 kVAr / Contactors for capacitor switching / CONTACTORS (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	7.913,92	7.913,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	7.913,92	300,00
				Material and Installation w/o Profit (TRY)	8.213,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**10.267,40**	

Item No	Analysis Name					UoM
35.125.1301	**Up to 3 x 10 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1301	Up to 3 x 10 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	1.180,96	1.180,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.180,96	300,00
				Material and Installation w/o Profit (TRY)	1.480,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.851,20**	

Item No	Analysis Name					UoM
35.125.1302	**Up to 3 x 16 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1302	Up to 3 x 16 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	1.295,36	1.295,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.295,36	300,00
				Material and Installation w/o Profit (TRY)	1.595,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**1.994,20**	

Item No	Analysis Name					UoM
35.125.1303	**Up to 3 x 25 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1303	Up to 3 x 25 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	1.832,16	1.832,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.832,16	300,00
				Material and Installation w/o Profit (TRY)	2.132,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.665,20**	

Item No	Analysis Name					UoM
35.125.1304	**Up to 3 x 40 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1304	Up to 3 x 40 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	2.577,52	2.577,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.577,52	300,00
				Material and Installation w/o Profit (TRY)	2.877,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**3.596,90**	

Item No	Analysis Name					UoM
35.125.1305	**Up to 3 x 63 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1305	Up to 3 x 63 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	5.525,52	5.525,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.525,52	300,00
				Material and Installation w/o Profit (TRY)	5.825,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**7.281,90**	

Item No	Analysis Name					UoM
35.125.1306	**Up to 3 x 100 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1306	Up to 3 x 100 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	6.176,72	6.176,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	6.176,72	300,00
				Material and Installation w/o Profit (TRY)	6.476,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**8.095,90**	

Item No	Analysis Name					UoM
35.125.1307	**Up to 3 x 160 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1307	Up to 3 x 160 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	10.091,84	10.091,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	10.091,84	300,00
				Material and Installation w/o Profit (TRY)	10.391,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**12.989,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.125.1308	**Up to 3 x 200 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1308	Up to 3 x 200 A / Dry-type contactors with thermal protectors / Contactors (TS-3629) (TS EN 60947-4-1) (Market price)	Qty	1	16.785,12	16.785,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	16.785,12	300,00
				Material and Installation w/o Profit (TRY)	17.085,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**21.356,40**	

Item No	Analysis Name					UoM
35.125.1701	**Up to 3 x 12 A / Electronic motor protection device / Protected Remote Control Circuit Breakers**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1701	Up to 3 x 12 A / Electronic motor protection relay (Market price)	Qty	1	836,88	836,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	836,88	258,75
				Material and Installation w/o Profit (TRY)	1.095,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.369,54**	

Item No	Analysis Name					UoM
35.125.1751	**0 to 60 seconds / Time Delay Relay**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1751	0 to 60 seconds / Time Delay Relay / CONTACTORS (Market price)	Qty	1	651,20	651,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	651,20	258,75
				Material and Installation w/o Profit (TRY)	909,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.137,44**	

Item No	Analysis Name					UoM
35.125.1752	**1 to 10 minutes / Time Delay Relay**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1752	1 to 10 minutes / Time Delay Relay / CONTACTORS (Market price)	Qty	1	691,68	691,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	691,68	258,75
				Material and Installation w/o Profit (TRY)	950,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.188,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.125.1760	**Time relay that is used for lighting control.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1760	Time relay that is used for lighting control / CONTACTORS (Market price)	Qty	1	1.327,92	1.327,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.327,92	258,75
				Material and Installation w/o Profit (TRY)	1.586,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.983,34**	

Item No	Analysis Name					UoM
35.125.1770	**Photocell switch**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1770	Photocell switch / CONTACTORS (Market price)	Qty	1	503,36	503,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	503,36	258,75
				Material and Installation w/o Profit (TRY)	762,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**952,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.125.1782						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1782	Astronomical time relay / CONTACTORS (Market price)	Qty	1	1.448,02	1.448,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.448,02	258,75
		Material and Installation w/o Profit (TRY)			1.706,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**2.133,46**	

Item No	Analysis Name					UoM
35.125.1785						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.1785	Astronomical time relay (communication, RS-485) / CONTACTORS (Market price)	Qty	1	2.300,75	2.300,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			2.300,75	258,75
		Material and Installation w/o Profit (TRY)			2.559,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**3.199,38**	

Item No	Analysis Name					UoM
35.125.2101	**Up to 2 x 25 A (Single phase) / Mechanical contact type / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2101	Up to 2 x 25 A (Single phase) / Mechanical contact type / Float Switches (Market price)	Qty	1	494,12	494,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	494,12	150,00
				Material and Installation w/o Profit (TRY)	644,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**805,15**	

Item No	Analysis Name					UoM
35.125.2102	**Up to 3 x 25 A (Single phase) / Mechanical contact type / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2102	Up to 3 x 25 A (Single phase) / Mechanical contact type / Float Switches (Market price)	Qty	1	554,84	554,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	554,84	150,00
				Material and Installation w/o Profit (TRY)	704,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**881,05**	

Item No	Analysis Name					UoM
35.125.2201	**Up to 2 x 25 A (Single phase) / Mercury contact type / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2201	Up to 2 x 25 A (Single phase) / Mercury contact type / Float Switches (Market price)	Qty	1	575,08	575,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	575,08	150,00
				Material and Installation w/o Profit (TRY)	725,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**906,35**	

Item No	Analysis Name					UoM
35.125.2202	**Up to 3 x 25 A (Single phase) / Mercury contact type / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2202	Up to 3 x 25 A (Single phase) / Mercury contact type / Float Switches (Market price)	Qty	1	558,36	558,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	558,36	150,00
				Material and Installation w/o Profit (TRY)	708,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**885,45**	

Item No	Analysis Name					UoM
35.125.2301	**Up to 2 x 25 A (Single phase) / Regular contact type / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2301	Up to 2 x 25 A (Single phase) / Regular contact type / Float Switches (Market price)	Qty	1	287,32	287,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	287,32	150,00
				Material and Installation w/o Profit (TRY)	437,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**546,65**	

Item No	Analysis Name					UoM
35.125.2302	**Up to 3 x 25 A (Single phase) / Regular contact type / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2302	Up to 3 x 25 A (Single phase) / Regular contact type / Float Switches (Market price)	Qty	1	330,44	330,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	330,44	150,00
				Material and Installation w/o Profit (TRY)	480,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**600,55**	

Item No	Analysis Name					UoM
35.125.2401	**Up to 6 A, Same as the Item 719-100 except for having no contactor / Mechanical contact type without contactors / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2401	Up to 6 A, Same as the Item 719-100 except for having no contactor / Mechanical contact type without contactors / Float Switches (Market price)	Qty	1	173,80	173,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	173,80	150,00
				Material and Installation w/o Profit (TRY)	323,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**404,75**	

Item No	Analysis Name					UoM
35.125.2501	**Up to 6 A, Same as the Item 719-200 except for having no contactor / Mercury contact type without contactors / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2501	Up to 6 A, Same as the Item 719-200 except for having no contactor / Mercury contact type without contactors / Float Switches (Market price)	Qty	1	173,80	173,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	173,80	150,00
				Material and Installation w/o Profit (TRY)	323,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**404,75**	

Item No	Analysis Name					UoM
35.125.2601	**Up to 6 A, Same as the Item 719-300 except for having no contactor / Regular contact type without contactors / Float Switches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2601	Up to 6 A, Same as the Item 719-300 except for having no contactor / Regular contact type without contactors / Float Switches (Market price)	Qty	1	173,80	173,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	173,80	150,00
				Material and Installation w/o Profit (TRY)	323,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**404,75**	

Item No	Analysis Name					UoM
35.125.2701	**Up to 3 x 25 A / Star delta automatic switch with a contactor / Star Delta Switches (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2701	Up to 3 x 25 A / Star delta automatic switch with a contactor (Market price)	Qty	1	4.947,36	4.947,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	4.947,36	517,50
				Material and Installation w/o Profit (TRY)	5.464,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**6.831,07**	

Item No	Analysis Name					UoM
35.125.2702	**Up to 3 x 63 A / Star delta automatic switch with a contactor / Star Delta Switches (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2702	Up to 3 x 63 A / Star delta automatic switch with a contactor (Market price)	Qty	1	8.132,96	8.132,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	8.132,96	517,50
				Material and Installation w/o Profit (TRY)	8.650,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**10.813,07**	

Item No	Analysis Name					UoM
35.125.2703	**Up to 3 x 80 A / Star delta automatic switch with a contactor / Star Delta Switches (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2703	Up to 3 x 80 A / Star delta automatic switch with a contactor (Market price)	Qty	1	14.639,68	14.639,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	14.639,68	517,50
				Material and Installation w/o Profit (TRY)	15.157,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**18.946,47**	

Item No	Analysis Name					UoM
35.125.2704	**Up to 3 x 100 A / Star delta automatic switch with a contactor / Star Delta Switches (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2704	Up to 3 x 100 A / Star delta automatic switch with a contactor (Market price)	Qty	1	18.089,28	18.089,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	18.089,28	517,50
				Material and Installation w/o Profit (TRY)	18.606,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**23.258,47**	

Item No	Analysis Name					UoM
35.125.2705	**Up to 3 x 250 A / Star delta automatic switch with a contactor / Star Delta Switches (TS EN 60947-4-1)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.2705	Up to 3 x 250 A / Star delta automatic switch with a contactor (Market price)	Qty	1	28.631,68	28.631,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	28.631,68	517,50
				Material and Installation w/o Profit (TRY)	29.149,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**36.436,47**	

Item No	Analysis Name					UoM
35.125.3001	**1 NA 16 A with 1 contact - Controller voltage: 230 V / Remote controlled impulse current switch and its installation / Remote controlled impulse current switch and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.3001	1 NA 16 A with 1 contact - Controller voltage: 230 V / Remote controlled impulse current switch and its installation (Market price)	Qty	1	363,44	363,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	363,44	171,75
				Material and Installation w/o Profit (TRY)	535,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**214,69**	
				Unit Price (TRY)	**668,99**	

Item No	Analysis Name					UoM
35.125.3002	**2 NA 16 A with 2 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.3002	2 NA 16 A with 2 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation (Market price)	Qty	1	799,04	799,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	799,04	215,25
				Material and Installation w/o Profit (TRY)	1.014,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269,06**	
				Unit Price (TRY)	**1.267,86**	

Item No	Analysis Name					UoM
35.125.3003	**3 NA 16 A with 3 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.3003	3 NA 16 A with 3 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation (Market price)	Qty	1	1.564,64	1.564,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	1.564,64	215,25
				Material and Installation w/o Profit (TRY)	1.779,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**269,06**	
				Unit Price (TRY)	**2.224,86**	

Item No	Analysis Name					UoM
35.125.3004	**4 NA 16 A with 4 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.3004	4 NA 16 A with 4 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation (Market price)	Qty	1	1.608,64	1.608,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.608,64	258,75
				Material and Installation w/o Profit (TRY)	1.867,39	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.334,24**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.125.3005	**2 A/K 16 A with 2 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.3005	2 A/K 16 A with 2 contacts - Controller voltage: 230 V / Remote controlled impulse current switch and its installation (Market price)	Qty	1	807,84	807,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	807,84	215,25
				Material and Installation w/o Profit (TRY)	1.023,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**269,06**	
				Unit Price (TRY)	**1.278,86**	

Item No	Analysis Name					UoM
35.125.3050	**Side-switching auxiliary switch block for central control**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.125.3050	Side-switching auxiliary switch block for central control (Market price)	Qty	1	566,72	566,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	566,72	258,75
				Material and Installation w/o Profit (TRY)	825,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.031,84**	

Item No	Analysis Name					UoM
35.130.2101	**Reactive Power Control Relay / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2101	Min. 5 steps / SINGLE-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	5.131,52	5.131,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	5.131,52	1.217,50
				Material and Installation w/o Profit (TRY)	6.349,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.521,88**	
				Unit Price (TRY)	**7.936,28**	

Item No	Analysis Name					UoM
35.130.2102	**Reactive Power Control Relay / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2102	Min. 8 steps / SINGLE-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	5.733,12	5.733,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	5.733,12	1.785,00
				Material and Installation w/o Profit (TRY)	7.518,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.231,25**	
				Unit Price (TRY)	**9.397,65**	

Item No	Analysis Name					UoM
35.130.2103	**Reactive Power Control Relay / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2103	Min. 12 steps / SINGLE-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	6.453,76	6.453,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	6.453,76	2.352,50
				Material and Installation w/o Profit (TRY)	8.806,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.940,63**	
				Unit Price (TRY)	**11.007,83**	

Item No	Analysis Name					UoM
35.130.2201	**Reactive Power Control Relay / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2201	Min. 12 steps / 3-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	6.668,80	6.668,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	6.668,80	2.352,50
				Material and Installation w/o Profit (TRY)	9.021,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.940,63**	
				Unit Price (TRY)	**11.276,63**	

Item No	Analysis Name					UoM
35.130.2202	**Reactive Power Control Relay / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2202	Min. 18 steps / 3-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	8.665,60	8.665,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
				Total Excluding Profit (TRY)	8.665,60	3.487,50
				Material and Installation w/o Profit (TRY)	12.153,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.359,38**	
				Unit Price (TRY)	**15.191,38**	

Item No	Analysis Name					UoM
35.130.2203	**Reactive Power Control Relay / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2203	Min. 12 steps (MODBUS, RTU, Computer Communication) / 3-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	6.924,80	6.924,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
				Total Excluding Profit (TRY)	6.924,80	3.052,50
				Material and Installation w/o Profit (TRY)	9.977,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.815,63**	
				Unit Price (TRY)	**12.471,63**	

Item No	Analysis Name					UoM
35.130.2204	**Reactive Power Control Relay / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2204	Min. 18 steps (MODBUS, RTU, Computer Communication) / 3-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	8.883,20	8.883,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	8.883,20	4.187,50
				Material and Installation w/o Profit (TRY)	13.070,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**5.234,38**	
				Unit Price (TRY)	**16.338,38**	

Item No	Analysis Name					UoM
35.130.2301	**Reactive Power Control Relay (SVC) / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2301	Min. 12 steps / SVC 3-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	7.782,40	7.782,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	7.782,40	2.352,50
				Material and Installation w/o Profit (TRY)	10.134,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.940,63**	
				Unit Price (TRY)	**12.668,63**	

Item No	Analysis Name					UoM
35.130.2302	**Reactive Power Control Relay (SVC) / Relays**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2302	Min. 18 steps / SVC 3-PHASE REACTIVE POWER CONTROL RELAYS / RELAYS (Market price)	Qty	1	9.113,60	9.113,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
		Total Excluding Profit (TRY)			9.113,60	3.487,50
		Material and Installation w/o Profit (TRY)			12.601,10	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**4.359,38**	
		Unit Price (TRY)			**15.751,38**	

Item No	Analysis Name					UoM
35.130.2500	**Discharge Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2500	Discharge Unit / COMPENSATION SYSTEM (Market price)	Qty	1	1.127,68	1.127,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			1.127,68	141,75
		Material and Installation w/o Profit (TRY)			1.269,43	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**177,19**	
		Unit Price (TRY)			**1.586,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2601	**Max. 5 kVAR (3 x 8 A) / Inductive Load Driver**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2601	Max. 5 kVAR (3 x 8 A) / Inductive Load Driver (Market price)	Qty	1	4.980,48	4.980,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	4.980,48	517,50
				Material and Installation w/o Profit (TRY)	5.497,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**6.872,47**	

Item No	Analysis Name					UoM
35.130.2602	**Max. 10 kVAR (3 x 16 A) / Inductive Load Driver**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2602	Max. 10 kVAR (3 x 16 A) / Inductive Load Driver (Market price)	Qty	1	7.897,12	7.897,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	7.897,12	517,50
				Material and Installation w/o Profit (TRY)	8.414,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**10.518,27**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2603	**Max. 30 kVAR (3 x 50 A) / Inductive Load Driver**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2603	Max. 30 kVAR (3 x 50 A) / Inductive Load Driver (Market price)	Qty	1	11.764,48	11.764,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	11.764,48	517,50
				Material and Installation w/o Profit (TRY)	12.281,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**15.352,47**	

Item No	Analysis Name					UoM
35.130.2701	**Max. 230 V, 1 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2701	Max. 230 V, 1 kVAR / Shunt Reactor (Market price)	Qty	1	2.183,28	2.183,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.183,28	279,39
				Material and Installation w/o Profit (TRY)	2.462,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.078,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2702	**Max. 230 V, 1.5 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2702	Max. 230 V, 1.5 kVAR / Shunt Reactor (Market price)	Qty	1	2.804,56	2.804,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.804,56	279,39
				Material and Installation w/o Profit (TRY)	3.083,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.854,94**	

Item No	Analysis Name					UoM
35.130.2703	**Max. 230 V, 3 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2703	Max. 230 V, 3 kVAR / Shunt Reactor (Market price)	Qty	1	4.845,28	4.845,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	4.845,28	293,15
				Material and Installation w/o Profit (TRY)	5.138,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**366,44**	
				Unit Price (TRY)	**6.423,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2704	**Max. 230 V, 5 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2704	Max. 230 V, 5 kVAR / Shunt Reactor (Market price)	Qty	1	7.490,56	7.490,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,07	687,95		48,16
		Total Excluding Profit (TRY)			7.490,56	306,91
		Material and Installation w/o Profit (TRY)			7.797,47	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**383,64**	
		Unit Price (TRY)			**9.746,84**	

Item No	Analysis Name					UoM
35.130.2705	**Max. 230 V, 7.5 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2705	Max. 230 V, 7.5 kVAR / Shunt Reactor (Market price)	Qty	1	10.050,48	10.050,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,08	687,95		55,04
		Total Excluding Profit (TRY)			10.050,48	313,79
		Material and Installation w/o Profit (TRY)			10.364,27	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**392,24**	
		Unit Price (TRY)			**12.955,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2706	**Max. 230 V, 10 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2706	Max. 230 V, 10 kVAR / Shunt Reactor (Market price)	Qty	1	11.421,52	11.421,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			11.421,52	327,55
		Material and Installation w/o Profit (TRY)			11.749,07	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**409,44**	
		Unit Price (TRY)			**14.686,34**	

Item No	Analysis Name					UoM
35.130.2750	**Max. 400 V, 0.5 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2750	Max. 400V, 0.5 kVAr / Shunt Reactor (Market price)	Qty	1	2.764,08	2.764,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			2.764,08	272,51
		Material and Installation w/o Profit (TRY)			3.036,59	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**340,64**	
		Unit Price (TRY)			**3.795,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2751	**Max. 400 V, 1 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2751	Max. 400V, 1 kVAr / Shunt Reactor (Market price)	Qty	1	3.438,16	3.438,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.438,16	279,39
		Material and Installation w/o Profit (TRY)			3.717,55	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**4.646,94**	

Item No	Analysis Name					UoM
35.130.2752	**Max. 400 V, 1.5 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2752	Max. 400V, 1.5 kVAr / Shunt Reactor (Market price)	Qty	1	4.076,16	4.076,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,04	687,95		27,52
		Total Excluding Profit (TRY)			4.076,16	286,27
		Material and Installation w/o Profit (TRY)			4.362,43	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**357,84**	
		Unit Price (TRY)			**5.453,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2753	**Max. 400 V, 2.5 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2753	Max. 400V, 2.5 kVAr / Shunt Reactor (Market price)	Qty	1	6.504,08	6.504,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,06	687,95		41,28
				Total Excluding Profit (TRY)	6.504,08	300,03
				Material and Installation w/o Profit (TRY)	6.804,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,04**	
				Unit Price (TRY)	**8.505,14**	

Item No	Analysis Name					UoM
35.130.2754	**Max. 400 V, 5 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2754	Max. 400V, 5 kVAr / Shunt Reactor (Market price)	Qty	1	10.629,52	10.629,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,08	687,95		55,04
				Total Excluding Profit (TRY)	10.629,52	313,79
				Material and Installation w/o Profit (TRY)	10.943,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**392,24**	
				Unit Price (TRY)	**13.679,14**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2755	**Max. 400 V, 10 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2755	Max. 400V, 10 kVAr / Shunt Reactor (Market price)	Qty	1	17.130,96	17.130,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	17.130,96	436,30
				Material and Installation w/o Profit (TRY)	17.567,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**545,38**	
				Unit Price (TRY)	**21.959,07**	

Item No	Analysis Name					UoM
35.130.2756	**Max. 400 V, 15 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2756	Max. 400V, 15 kVAr / Shunt Reactor (Market price)	Qty	1	22.634,48	22.634,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,13	687,95		89,43
				Total Excluding Profit (TRY)	22.634,48	456,93
				Material and Installation w/o Profit (TRY)	23.091,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**571,16**	
				Unit Price (TRY)	**28.864,26**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2757	**Max. 400 V, 20 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2757	Max. 400V, 20 kVAr / Shunt Reactor (Market price)	Qty	1	28.527,84	28.527,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,17	687,95		116,95
				Total Excluding Profit (TRY)	28.527,84	634,45
				Material and Installation w/o Profit (TRY)	29.162,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**793,06**	
				Unit Price (TRY)	**36.452,86**	

Item No	Analysis Name					UoM
35.130.2758	**Max. 400 V, 25 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2758	Max. 400V, 25 kVAr / Shunt Reactor (Market price)	Qty	1	33.264,00	33.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,22	687,95		151,35
				Total Excluding Profit (TRY)	33.264,00	668,85
				Material and Installation w/o Profit (TRY)	33.932,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**836,06**	
				Unit Price (TRY)	**42.416,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.2759	**Max. 400 V, 50 kVAR / Shunt Reactor**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2759	Max. 400V, 50 kVAr / Shunt Reactor (Market price)	Qty	1	62.163,20	62.163,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,33	687,95		227,02
				Total Excluding Profit (TRY)	62.163,20	744,52
				Material and Installation w/o Profit (TRY)	62.907,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**930,65**	
				Unit Price (TRY)	**78.634,65**	

Item No	Analysis Name					UoM
35.130.2801	**Ethernet Communication Terminal / Communication Terminals**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2801	Ethernet Communication Terminal / Communication Terminals (Market price)	Qty	1	5.626,40	5.626,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	5.626,40	517,50
				Material and Installation w/o Profit (TRY)	6.143,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**7.679,88**	

Item No	Analysis Name					UoM
35.130.2802	**GPRS Communication Terminal / Communication Terminals**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.2802	GPRS Communication Terminal / Communication Terminals (Market price)	Qty	1	6.052,80	6.052,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	6.052,80	517,50
				Material and Installation w/o Profit (TRY)	6.570,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**8.212,88**	

Item No	Analysis Name					UoM
35.130.3105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3105	At least 400 VAC, at least 0.25 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.216,41	1.216,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.216,41	258,75
				Material and Installation w/o Profit (TRY)	1.475,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.843,95**	

Item No	Analysis Name					UoM
35.130.3110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3110	At least 400 VAC, at least 0.5 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.238,43	1.238,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.238,43	258,75
				Material and Installation w/o Profit (TRY)	1.497,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.871,48**	

Item No	Analysis Name					UoM
35.130.3115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3115	At least 400 VAC, at least 1 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.296,03	1.296,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.296,03	258,75
				Material and Installation w/o Profit (TRY)	1.554,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.943,47**	

Item No	Analysis Name					UoM
35.130.3120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3120	At least 400 VAC, at least 1.5 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.368,03	1.368,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.368,03	258,75
				Material and Installation w/o Profit (TRY)	1.626,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.033,47**	

Item No	Analysis Name					UoM
35.130.3125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3125	At least 400 VAC, at least 2.5 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.512,04	1.512,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.512,04	265,63
				Material and Installation w/o Profit (TRY)	1.777,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**332,04**	
				Unit Price (TRY)	**2.222,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3130	At least 400 VAC, at least 5 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.886,44	1.886,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.886,44	272,51
		Material and Installation w/o Profit (TRY)			2.158,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**340,64**	
		Unit Price (TRY)			**2.698,69**	

Item No	Analysis Name					UoM
35.130.3135						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3135	At least 400 VAC, at least 7.5 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.912,39	1.912,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.912,39	280,76
		Material and Installation w/o Profit (TRY)			2.193,15	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**350,95**	
		Unit Price (TRY)			**2.741,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3140	At least 400 VAC, at least 10 kVAr (at 230 VAC) / At least 400 VAC (operating voltage) 1-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.934,55	1.934,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	1.934,55	287,64
				Material and Installation w/o Profit (TRY)	2.222,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**359,55**	
				Unit Price (TRY)	**2.777,74**	

Item No	Analysis Name					UoM
35.130.3205						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3205	At least 440 VAC, at least 0.5 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	954,69	954,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	954,69	258,75
				Material and Installation w/o Profit (TRY)	1.213,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.516,80**	

Item No	Analysis Name					UoM
35.130.3210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3210	At least 440 VAC, at least 1 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	999,10	999,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	999,10	258,75
				Material and Installation w/o Profit (TRY)	1.257,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.572,31**	

Item No	Analysis Name					UoM
35.130.3215						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3215	At least 440 VAC, at least 1.5 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.054,61	1.054,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.054,61	265,63
				Material and Installation w/o Profit (TRY)	1.320,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**332,04**	
				Unit Price (TRY)	**1.650,30**	

Item No	Analysis Name					UoM
35.130.3220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3220	At least 440 VAC, at least 2.5 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.165,61	1.165,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,01	687,95		6,88
		Total Excluding Profit (TRY)			1.165,61	265,63
		Material and Installation w/o Profit (TRY)			1.431,24	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**332,04**	
		Unit Price (TRY)			**1.789,05**	

Item No	Analysis Name					UoM
35.130.3225						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3225	At least 440 VAC, at least 5 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.454,25	1.454,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.454,25	280,76
		Material and Installation w/o Profit (TRY)			1.735,01	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**350,95**	
		Unit Price (TRY)			**2.168,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3230	At least 440 VAC, at least 7.5 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.474,24	1.474,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.474,24	280,76
				Material and Installation w/o Profit (TRY)	1.755,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**350,95**	
				Unit Price (TRY)	**2.193,75**	

Item No	Analysis Name					UoM
35.130.3235						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3235	At least 440 VAC, at least 10 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.491,33	1.491,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	1.491,33	287,64
				Material and Installation w/o Profit (TRY)	1.778,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**359,55**	
				Unit Price (TRY)	**2.223,71**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3240						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3240	At least 440 VAC, at least 12.5 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.502,17	1.502,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	1.502,17	287,64
				Material and Installation w/o Profit (TRY)	1.789,81	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**359,55**	
				Unit Price (TRY)	**2.237,26**	

Item No	Analysis Name					UoM
35.130.3245						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3245	At least 440 VAC, at least 15 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.527,58	1.527,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	1.527,58	304,14
				Material and Installation w/o Profit (TRY)	1.831,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**380,17**	
				Unit Price (TRY)	**2.289,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3250						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3250	At least 440 VAC, at least 20 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.580,51	1.580,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,04	687,95		27,52
		Total Excluding Profit (TRY)			1.580,51	311,02
		Material and Installation w/o Profit (TRY)			1.891,53	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**388,77**	
		Unit Price (TRY)			**2.364,41**	

Item No	Analysis Name					UoM
35.130.3255						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3255	At least 440 VAC, at least 25 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.618,43	1.618,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,05	687,95		34,40
		Total Excluding Profit (TRY)			1.618,43	317,90
		Material and Installation w/o Profit (TRY)			1.936,33	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**397,38**	
		Unit Price (TRY)			**2.420,41**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3260						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3260	At least 440 VAC, at least 30 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.774,68	1.774,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,06	687,95		41,28
		Total Excluding Profit (TRY)			1.774,68	324,78
		Material and Installation w/o Profit (TRY)			2.099,46	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**405,97**	
		Unit Price (TRY)			**2.624,32**	

Item No	Analysis Name					UoM
35.130.3265						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3265	At least 440 VAC, at least 40 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.221,32	2.221,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,08	687,95		55,04
		Total Excluding Profit (TRY)			2.221,32	338,54
		Material and Installation w/o Profit (TRY)			2.559,86	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**423,18**	
		Unit Price (TRY)			**3.199,83**	

Item No	Analysis Name					UoM
35.130.3270						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3270	At least 440 VAC, at least 50 kVAr (at 400 VAC) / At least 440 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.780,35	2.780,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,09	687,95		61,92
		Total Excluding Profit (TRY)			2.780,35	345,42
		Material and Installation w/o Profit (TRY)			3.125,77	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**431,78**	
		Unit Price (TRY)			**3.907,21**	

Item No	Analysis Name					UoM
35.130.3305						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3305	At least 525 VAC, at least 0.5 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.111,59	1.111,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.111,59	258,75
		Material and Installation w/o Profit (TRY)			1.370,34	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.712,92**	

Item No	Analysis Name					UoM
35.130.3310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3310	At least 525 VAC, at least 1 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.163,30	1.163,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.163,30	258,75
				Material and Installation w/o Profit (TRY)	1.422,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.777,56**	

Item No	Analysis Name					UoM
35.130.3315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3315	At least 525 VAC, at least 1.5 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.227,93	1.227,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.227,93	265,63
				Material and Installation w/o Profit (TRY)	1.493,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**332,04**	
				Unit Price (TRY)	**1.866,95**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3320	At least 525 VAC, at least 2.5 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.357,18	1.357,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,01	687,95		6,88
		Total Excluding Profit (TRY)			1.357,18	265,63
		Material and Installation w/o Profit (TRY)			1.622,81	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**332,04**	
		Unit Price (TRY)			**2.028,51**	

Item No	Analysis Name					UoM
35.130.3325						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3325	At least 525 VAC, at least 5 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.693,25	1.693,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.693,25	280,76
		Material and Installation w/o Profit (TRY)			1.974,01	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**350,95**	
		Unit Price (TRY)			**2.467,51**	

Item No	Analysis Name					UoM
35.130.3330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3330	At least 525 VAC, at least 7.5 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.716,54	1.716,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.716,54	280,76
				Material and Installation w/o Profit (TRY)	1.997,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**350,95**	
				Unit Price (TRY)	**2.496,63**	

Item No	Analysis Name					UoM
35.130.3335						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3335	At least 525 VAC, at least 10 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.736,43	1.736,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	1.736,43	287,64
				Material and Installation w/o Profit (TRY)	2.024,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**359,55**	
				Unit Price (TRY)	**2.530,09**	

Item No	Analysis Name					UoM
35.130.3340						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3340	At least 525 VAC, at least 12.5 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.749,04	1.749,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	1.749,04	287,64
				Material and Installation w/o Profit (TRY)	2.036,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**359,55**	
				Unit Price (TRY)	**2.545,85**	

Item No	Analysis Name					UoM
35.130.3345						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3345	At least 525 VAC, at least 15 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.778,63	1.778,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	1.778,63	311,02
				Material and Installation w/o Profit (TRY)	2.089,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**388,77**	
				Unit Price (TRY)	**2.612,06**	

Item No	Analysis Name					UoM
35.130.3350						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3350	At least 525 VAC, at least 20 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.840,25	1.840,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,05	687,95		34,40
		Total Excluding Profit (TRY)			1.840,25	317,90
		Material and Installation w/o Profit (TRY)			2.158,15	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**397,38**	
		Unit Price (TRY)			**2.697,69**	

Item No	Analysis Name					UoM
35.130.3355						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3355	At least 525 VAC, at least 25 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.884,40	1.884,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,05	687,95		34,40
		Total Excluding Profit (TRY)			1.884,40	317,90
		Material and Installation w/o Profit (TRY)			2.202,30	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**397,38**	
		Unit Price (TRY)			**2.752,88**	

Item No	Analysis Name					UoM
35.130.3360						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3360	At least 525 VAC, at least 30 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.066,35	2.066,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,06	687,95		41,28
		Total Excluding Profit (TRY)			2.066,35	324,78
		Material and Installation w/o Profit (TRY)			2.391,13	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**405,97**	
		Unit Price (TRY)			**2.988,91**	

Item No	Analysis Name					UoM
35.130.3365						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3365	At least 525 VAC, at least 40 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.586,38	2.586,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,08	687,95		55,04
		Total Excluding Profit (TRY)			2.586,38	338,54
		Material and Installation w/o Profit (TRY)			2.924,92	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**423,18**	
		Unit Price (TRY)			**3.656,15**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3368						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3368	At least 525 VAC, at least 50 kVAr (at 480 VAC) / At least 525 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	3.237,29	3.237,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	3.237,29	345,42
				Material and Installation w/o Profit (TRY)	3.582,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**431,78**	
				Unit Price (TRY)	**4.478,39**	

Item No	Analysis Name					UoM
35.130.3405						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3405	At least 690 VAC, at least 0.5 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.687,60	1.687,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.687,60	258,75
				Material and Installation w/o Profit (TRY)	1.946,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.432,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3410						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3410	At least 690 VAC, at least 1 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.766,09	1.766,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,01	687,95		6,88
		Total Excluding Profit (TRY)			1.766,09	265,63
		Material and Installation w/o Profit (TRY)			2.031,72	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**332,04**	
		Unit Price (TRY)			**2.539,65**	

Item No	Analysis Name					UoM
35.130.3415						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3415	At least 690 VAC, at least 1.5 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	1.864,21	1.864,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,01	687,95		6,88
		Total Excluding Profit (TRY)			1.864,21	265,63
		Material and Installation w/o Profit (TRY)			2.129,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**332,04**	
		Unit Price (TRY)			**2.662,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3420						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3420	At least 690 VAC, at least 2.5 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.060,45	2.060,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			2.060,45	272,51
		Material and Installation w/o Profit (TRY)			2.332,96	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**340,64**	
		Unit Price (TRY)			**2.916,20**	

Item No	Analysis Name					UoM
35.130.3425						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3425	At least 690 VAC, at least 5 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.570,65	2.570,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			2.570,65	280,76
		Material and Installation w/o Profit (TRY)			2.851,41	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**350,95**	
		Unit Price (TRY)			**3.564,26**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3430						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3430	At least 690 VAC, at least 7.5 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.606,01	2.606,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.606,01	287,64
		Material and Installation w/o Profit (TRY)			2.893,65	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**359,55**	
		Unit Price (TRY)			**3.617,06**	

Item No	Analysis Name					UoM
35.130.3435						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3435	At least 690 VAC, at least 10 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.636,21	2.636,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.636,21	287,64
		Material and Installation w/o Profit (TRY)			2.923,85	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**359,55**	
		Unit Price (TRY)			**3.654,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3440						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3440	At least 690 VAC, at least 12.5 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.655,36	2.655,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	2.655,36	311,02
				Material and Installation w/o Profit (TRY)	2.966,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**388,77**	
				Unit Price (TRY)	**3.707,98**	

Item No	Analysis Name					UoM
35.130.3445						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3445	At least 690 VAC, at least 15 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.700,29	2.700,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	2.700,29	311,02
				Material and Installation w/o Profit (TRY)	3.011,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**388,77**	
				Unit Price (TRY)	**3.764,14**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.3450						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3450	At least 690 VAC, at least 20 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.793,83	2.793,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,05	687,95		34,40
		Total Excluding Profit (TRY)			2.793,83	317,90
		Material and Installation w/o Profit (TRY)			3.111,73	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**397,38**	
		Unit Price (TRY)			**3.889,66**	

Item No	Analysis Name					UoM
35.130.3455						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3455	At least 690 VAC, at least 25 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	2.860,86	2.860,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,06	687,95		41,28
		Total Excluding Profit (TRY)			2.860,86	324,78
		Material and Installation w/o Profit (TRY)			3.185,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**405,97**	
		Unit Price (TRY)			**3.982,05**	

Item No	Analysis Name					UoM
35.130.3460						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.3460	At least 690 VAC, at least 30 kVAr (at 600 VAC) / At least 690 VAC (operating voltage) 3-Phase Capacitors / COMPENSATION CAPACITORS (Market price)	Qty	1	3.137,09	3.137,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,06	687,95		41,28
		Total Excluding Profit (TRY)			3.137,09	324,78
		Material and Installation w/o Profit (TRY)			3.461,87	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**405,97**	
		Unit Price (TRY)			**4.327,34**	

Item No	Analysis Name					UoM
35.130.4105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4105	230 V at least 0.25 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	756,00	756,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			756,00	258,75
		Material and Installation w/o Profit (TRY)			1.014,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.268,44**	

Item No	Analysis Name					UoM
35.130.4110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4110	230 V at least 0.5 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	761,54	761,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	761,54	258,75
				Material and Installation w/o Profit (TRY)	1.020,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.275,36**	

Item No	Analysis Name					UoM
35.130.4115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4115	230 V at least 1 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	781,07	781,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	781,07	258,75
				Material and Installation w/o Profit (TRY)	1.039,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.299,78**	

Item No	Analysis Name					UoM
35.130.4120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4120	230 V at least 1.5 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	820,12	820,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	820,12	258,75
				Material and Installation w/o Profit (TRY)	1.078,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.348,59**	

Item No	Analysis Name					UoM
35.130.4125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4125	230 V at least 2.5 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	1.269,23	1.269,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.269,23	258,75
				Material and Installation w/o Profit (TRY)	1.527,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.909,97**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.4130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4130	230 V at least 4 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	2.103,12	2.103,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.103,12	258,75
				Material and Installation w/o Profit (TRY)	2.361,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.952,34**	

Item No	Analysis Name					UoM
35.130.4135						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4135	230 V at least 5 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	2.401,76	2.401,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.401,76	258,75
				Material and Installation w/o Profit (TRY)	2.660,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.325,64**	

Item No	Analysis Name					UoM
35.130.4140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4140	230 V at least 10 kVAr / Harmonic Filter Reactor (1 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	3.405,78	3.405,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.405,78	258,75
				Material and Installation w/o Profit (TRY)	3.664,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**4.580,66**	

Item No	Analysis Name					UoM
35.130.4305						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4305	400 V at least 1 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	1.386,38	1.386,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.386,38	258,75
				Material and Installation w/o Profit (TRY)	1.645,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.056,41**	

Item No	Analysis Name					UoM
35.130.4310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4310	400 V at least 2 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	1.800,00	1.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.800,00	258,75
				Material and Installation w/o Profit (TRY)	2.058,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.573,44**	

Item No	Analysis Name					UoM
35.130.4315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4315	400 V at least 3 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	2.032,25	2.032,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.032,25	258,75
				Material and Installation w/o Profit (TRY)	2.291,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.863,75**	

Item No	Analysis Name					UoM
35.130.4320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4320	400 V at least 4 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	2.322,58	2.322,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.322,58	258,75
				Material and Installation w/o Profit (TRY)	2.581,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.226,66**	

Item No	Analysis Name					UoM
35.130.4325						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4325	400 V at least 5 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	2.516,12	2.516,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.516,12	258,75
				Material and Installation w/o Profit (TRY)	2.774,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.468,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.4330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4330	400 V at least 6 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	2.709,67	2.709,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.709,67	258,75
				Material and Installation w/o Profit (TRY)	2.968,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.710,53**	

Item No	Analysis Name					UoM
35.130.4335						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4335	400 V at least 7 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	2.806,44	2.806,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.806,44	258,75
				Material and Installation w/o Profit (TRY)	3.065,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.831,49**	

Item No	Analysis Name					UoM
35.130.4340						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4340	400 V at least 10 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	3.016,55	3.016,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.016,55	258,75
				Material and Installation w/o Profit (TRY)	3.275,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**4.094,13**	

Item No	Analysis Name					UoM
35.130.4345						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4345	400 V at least 15 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	3.416,12	3.416,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.416,12	258,75
				Material and Installation w/o Profit (TRY)	3.674,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**4.593,59**	

Item No	Analysis Name					UoM
35.130.4350						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4350	400 V at least 20 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	4.277,40	4.277,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.277,40	258,75
				Material and Installation w/o Profit (TRY)	4.536,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.670,19**	

Item No	Analysis Name					UoM
35.130.4355						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4355	400 V at least 25 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	4.645,15	4.645,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.645,15	258,75
				Material and Installation w/o Profit (TRY)	4.903,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.129,88**	

Item No	Analysis Name					UoM
35.130.4360						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4360	400 V at least 30 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	5.158,05	5.158,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.158,05	258,75
				Material and Installation w/o Profit (TRY)	5.416,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.771,00**	

Item No	Analysis Name					UoM
35.130.4363						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4363	400 V at least 35 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	5.612,89	5.612,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.612,89	258,75
				Material and Installation w/o Profit (TRY)	5.871,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.339,55**	

Item No	Analysis Name					UoM
35.130.4368						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4368	400 V at least 40 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	5.717,64	5.717,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.717,64	258,75
				Material and Installation w/o Profit (TRY)	5.976,39	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.470,49**	

Item No	Analysis Name					UoM
35.130.4370						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4370	400 V at least 45 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	6.048,37	6.048,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	6.048,37	258,75
				Material and Installation w/o Profit (TRY)	6.307,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.883,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.130.4373						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.4373	400 V at least 50 kVAr / Harmonic Filter Reactor (3 Phase, 189 Hz, p=7%) / HARMONIC FILTER REACTORS (Market price)	Qty	1	6.348,55	6.348,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	6.348,55	258,75
				Material and Installation w/o Profit (TRY)	6.607,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**8.259,13**	

Item No	Analysis Name					UoM
35.130.5105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5105	400 V, at least 5 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	5.254,14	5.254,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	5.254,14	517,50
				Material and Installation w/o Profit (TRY)	5.771,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**7.214,55**	

Item No	Analysis Name					UoM
35.130.5110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5110	400 V, at least 10 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	7.325,76	7.325,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	7.325,76	517,50
				Material and Installation w/o Profit (TRY)	7.843,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**9.804,08**	

Item No	Analysis Name					UoM
35.130.5115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5115	400 V, at least 15 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	8.167,59	8.167,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	8.167,59	517,50
				Material and Installation w/o Profit (TRY)	8.685,09	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**10.856,36**	

Item No	Analysis Name					UoM
35.130.5120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5120	400 V, at least 25 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	9.009,43	9.009,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	9.009,43	517,50
				Material and Installation w/o Profit (TRY)	9.526,93	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**11.908,66**	

Item No	Analysis Name					UoM
35.130.5125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5125	400 V, at least 30 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	10.693,09	10.693,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	10.693,09	517,50
				Material and Installation w/o Profit (TRY)	11.210,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**14.013,24**	

Item No	Analysis Name					UoM
35.130.5130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5130	400 V, at least 50 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	12.831,71	12.831,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	12.831,71	517,50
				Material and Installation w/o Profit (TRY)	13.349,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**16.686,51**	

Item No	Analysis Name					UoM
35.130.5160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5160	230 V, at least 3 x 1.5 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	5.254,14	5.254,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	5.254,14	517,50
				Material and Installation w/o Profit (TRY)	5.771,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**7.214,55**	

Item No	Analysis Name					UoM
35.130.5165						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5165	230 V, at least 3 x 5 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	8.167,59	8.167,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	8.167,59	517,50
				Material and Installation w/o Profit (TRY)	8.685,09	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**10.856,36**	

Item No	Analysis Name					UoM
35.130.5170						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5170	230 V, at least 3 x 10 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	10.693,09	10.693,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	10.693,09	517,50
				Material and Installation w/o Profit (TRY)	11.210,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**14.013,24**	

Item No	Analysis Name					UoM
35.130.5175						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5175	230 V, at least 3 x 15 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	12.190,12	12.190,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	12.190,12	517,50
				Material and Installation w/o Profit (TRY)	12.707,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**15.884,53**	

Item No	Analysis Name					UoM
35.130.5180						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.130.5180	230 V, at least 3 x 20 kVAr / Thyristor Switching Module / COMPENSATION SYSTEM (Market price)	Qty	1	14.114,88	14.114,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	14.114,88	517,50
				Material and Installation w/o Profit (TRY)	14.632,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**18.290,47**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.135.1101	**0 to 60 V / Voltmeters (TS 5590 EN 60051-2) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1101	0 to 60 V / Voltmeters (TS 5590 EN 60051-2) / Metering Instruments (Market price)	Qty	1	568,40	568,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	568,40	207,00
				Material and Installation w/o Profit (TRY)	775,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**969,25**	

Item No	Analysis Name					UoM
35.135.1102	**0 to 500 V / Voltmeters (TS 5590 EN 60051-2) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1102	0 to 500 V / Voltmeters (TS 5590 EN 60051-2) / Metering Instruments (Market price)	Qty	1	592,76	592,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	592,76	207,00
				Material and Installation w/o Profit (TRY)	799,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**999,70**	

Item No	Analysis Name					UoM
35.135.1201						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1201	10 - 300 V AC (L-N), 10-500 V AC (L-L) / Digital Voltmeters / METERING INSTRUMENTS (Market price)	Qty	1	742,40	742,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	742,40	207,00
				Material and Installation w/o Profit (TRY)	949,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.186,75**	

Item No	Analysis Name					UoM
35.135.1301	**0 to 25 A / Ammeters (TS 5590 EN 60051-2) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1301	0 to 25 A / Ammeters (TS 5590 EN 60051-2) / Metering Instruments (Market price)	Qty	1	502,86	502,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	502,86	207,00
				Material and Installation w/o Profit (TRY)	709,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**887,33**	

Item No	Analysis Name					UoM
35.135.1302	**25 to 100 A / Ammeters (TS 5590 EN 60051-2) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1302	25 to 100 A / Ammeters (TS 5590 EN 60051-2) / Metering Instruments (Market price)	Qty	1	551,58	551,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	551,58	207,00
				Material and Installation w/o Profit (TRY)	758,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**948,23**	

Item No	Analysis Name					UoM
35.135.1303	**100 to 2,000 A / Ammeters (TS 5590 EN 60051-2) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1303	100 to 2,000 A / Ammeters (TS 5590 EN 60051-2) / Metering Instruments (Market price)	Qty	1	551,58	551,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	551,58	207,00
				Material and Installation w/o Profit (TRY)	758,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**948,23**	

Item No	Analysis Name					UoM
35.135.1401						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1401	1-10000/5A current transformer / Digital Ammeter / METERING INSTRUMENTS (Market price)	Qty	1	830,56	830,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	830,56	207,00
				Material and Installation w/o Profit (TRY)	1.037,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.296,95**	

Item No	Analysis Name					UoM
35.135.1501	**3 positions / Voltmeter Commutators (TS 4915 EN 60669-1) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1501	3 positions / Voltmeter Commutators (TS 4915 EN 60669-1) / Metering Instruments (Market price)	Qty	1	260,54	260,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	260,54	207,00
				Material and Installation w/o Profit (TRY)	467,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**584,43**	

Item No	Analysis Name					UoM
35.135.1502	**4 positions / Voltmeter Commutators (TS 4915 EN 60669-1) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1502	4 positions / Voltmeter Commutators (TS 4915 EN 60669-1) / Metering Instruments (Market price)	Qty	1	315,74	315,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	315,74	207,00
				Material and Installation w/o Profit (TRY)	522,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**653,42**	

Item No	Analysis Name					UoM
35.135.1503	**5 positions and above / Voltmeter Commutators (TS 4915 EN 60669-1) / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1503	5 positions and above / Voltmeter Commutators (TS 4915 EN 60669-1) / Metering Instruments (Market price)	Qty	1	327,60	327,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	327,60	207,00
				Material and Installation w/o Profit (TRY)	534,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**668,25**	

Item No	Analysis Name					UoM
35.135.1701	**Multimeter:(in compliance with TS IEC 61554)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1701	Multimeter: (In compliance with TS 61554) / Multimeters / Metering Instruments (Market price)	Qty	1	1.800,32	1.800,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	1.800,32	207,00
				Material and Installation w/o Profit (TRY)	2.007,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**2.509,15**	

Item No	Analysis Name					UoM
35.135.1702	**Multimeters in compliance with TS 4417 / Multimeters / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1702	Multimeter: (In compliance with TS 61554) / Multimeters / Metering Instruments (Market price)	Qty	1	1.800,32	1.800,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	1.800,32	207,00
				Material and Installation w/o Profit (TRY)	2.007,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**2.509,15**	

Item No	Analysis Name					UoM
35.135.1901	**100 - 500/5 A / Metering Current Transformer: (1kV 5-10 VA, Sn: 0.5 - 1) (Unit: Qty.) (TS- 620 EN 60044-1) Supply and installation of a class 0.5 - 1 metering current transformer with 5-10-VA power, of busbar or non-busbar type, and of the same quality as the metering instruments to be used. / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1901	100 - 500/5 A. / Metering Current Transformer: (1kV 5-10 VA, Cl: 0.5 -1) (TS- 620 EN 60044-1) / Metering Instruments (Market price)	Qty	1	542,30	542,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	542,30	207,00
				Material and Installation w/o Profit (TRY)	749,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**936,63**	

Item No	Analysis Name					UoM
35.135.1902	**501 - 2,000/5 A / Metering Current Transformer: (1kV 5-10 VA, Sn: 0.5 - 1) (Unit: Qty.) (TS- 620 EN 60044-1) Supply and installation of a class 0.5 - 1 metering current transformer with 5-10-VA power, of busbar or non-busbar type, and of the same quality as the metering instruments to be used. / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1902	501 - 2000/5 A. / Metering Current Transformer: (1kV 5-10 VA, Cl: 0.5 -1) (TS- 620 EN 60044-1) / Metering Instruments (Market price)	Qty	1	948,30	948,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	948,30	207,00
				Material and Installation w/o Profit (TRY)	1.155,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.444,13**	

Item No	Analysis Name					UoM
35.135.1903	**2,001 - 6,000/5 A Sn1, 10 VA / Metering Current Transformer: (1kV 5-10 VA, Sn: 0.5 - 1) (Unit: Qty.) (TS- 620 EN 60044-1) Supply and installation of a class 0.5 - 1 metering current transformer with 5-10-VA power, of busbar or non-busbar type, and of the same quality as the metering instruments to be used. / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.1903	2001 - 6000/5 A Sn1, 10 VA. / Metering Current Transformer: (1kV 5-10 VA, Cl: 0.5 -1) (TS- 620 EN 60044-1) / Metering Instruments (Market price)	Qty	1	1.579,92	1.579,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
		Total Excluding Profit (TRY)			1.579,92	207,00
		Material and Installation w/o Profit (TRY)			1.786,92	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**258,75**	
		Unit Price (TRY)			**2.233,65**	

Item No	Analysis Name					UoM
35.135.2001	**Gauge type / Frequency meter (TS 5592 EN 60051-4 / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2001	Gauge type / Frequency meter (TS 5592 EN 60051-4) / Metering Instruments (Market price)	Qty	1	620,02	620,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
		Total Excluding Profit (TRY)			620,02	207,00
		Material and Installation w/o Profit (TRY)			827,02	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**258,75**	
		Unit Price (TRY)			**1.033,78**	

Item No	Analysis Name					UoM
35.135.2002	**Vibration reed type / Frequency meter (TS 5592 EN 60051-4 / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2002	Vibration reed type / Frequency meter (TS 5592 EN 60051-4 / Metering Instruments (Market price)	Qty	1	819,54	819,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	819,54	207,00
				Material and Installation w/o Profit (TRY)	1.026,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.283,17**	

Item No	Analysis Name					UoM
35.135.2003	**Digital type / Frequency meter (TS 5592 EN 60051-4 / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2003	Digital type / Frequency meter (TS 5592 EN 60051-4 / Metering Instruments (Market price)	Qty	1	715,14	715,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	715,14	207,00
				Material and Installation w/o Profit (TRY)	922,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.152,67**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.135.2501 xxx	**Energy analyzer / Energy analyzers and circuit components / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2501 xxx	Energy analyzer	Qty	1	5.437,04	5.437,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			5.437,04	1.607,00
		Material and Installation w/o Profit (TRY)			7.044,04	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.008,75**	
		Unit Price (TRY)			**8.805,05**	

Item No	Analysis Name					UoM
35.135.2502 xxx	**Modbus module / Energy analyzers and circuit components / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2502	Modbus module	Qty	1	1.633,24	1.633,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
		Total Excluding Profit (TRY)			1.633,24	207,00
		Material and Installation w/o Profit (TRY)			1.840,24	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**258,75**	
		Unit Price (TRY)			**2.300,30**	

Item No	Analysis Name					UoM
35.135.2503 xxx	**Pulse module (digital output) / Energy analyzers and circuit components / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2503 xxx	Pulse module (digital output)	Qty	1	922,20	922,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	922,20	207,00
				Material and Installation w/o Profit (TRY)	1.129,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.411,50**	

Item No	Analysis Name					UoM
35.135.2504 xxx	**Alarm module / Energy analyzers and circuit components / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2504 xxx	Alarm module	Qty	1	1.016,16	1.016,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	1.016,16	207,00
				Material and Installation w/o Profit (TRY)	1.223,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.528,95**	

Item No	Analysis Name					UoM
35.135.2505 xxx	**2 analog output modules / Energy analyzers and circuit components / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2505 xxx	Two analog output modules	Qty	1	1.699,40	1.699,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	1.699,40	207,00
				Material and Installation w/o Profit (TRY)	1.906,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**2.383,00**	

Item No	Analysis Name					UoM
35.135.2506 xxx	**2 Digital output modules (digital output) / Energy analyzers and circuit components / Metering Instruments**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2506 xxx	Two digital output modules	Qty	1	860,72	860,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	860,72	207,00
				Material and Installation w/o Profit (TRY)	1.067,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.334,65**	

Item No	Analysis Name					UoM
35.135.2600	**COS Ø METER (TS 5594 EN 60051-5)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.2600	COS Ø METER (TS 5594 EN 60051-5) / METERING INSTRUMENTS (Market price)	Qty	1	934,96	934,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
		Total Excluding Profit (TRY)			934,96	207,00
		Material and Installation w/o Profit (TRY)			1.141,96	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**258,75**	
		Unit Price (TRY)			**1.427,45**	

Item No	Analysis Name					UoM
35.135.3101	**Up to 10 (60) A / Electronic electric meters with time tariffs**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3101	At least 5(80) A, 230 V / Single-Phase, Hour-Tariff Electronic Active Meters / METERS (Market price)	Qty	1	502,88	502,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
		Total Excluding Profit (TRY)			502,88	207,00
		Material and Installation w/o Profit (TRY)			709,88	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**258,75**	
		Unit Price (TRY)			**887,35**	

Item No	Analysis Name					UoM
35.135.3201	**3 x 230 / 400V, 3 x 10 (60) A / 3-Phase, Active, Electronic electric meters with time tariffs**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3201	At least 5(100) A, 3 x 230/400 V / 3-Phase, Hour-Tariff Electronic Active Meters / METERS (Market price)	Qty	1	1.071,84	1.071,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.071,84	250,50
		Material and Installation w/o Profit (TRY)			1.322,34	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**313,13**	
		Unit Price (TRY)			**1.652,92**	

Item No	Analysis Name					UoM
35.135.3301	**3 x 230 / 400V, 3 x 5 (7.5) A / 3-Phase, Active, Electronic electric meters with time tariffs**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3301	Transformer Meters, At least x../5(10) A, 3 x 58/100 V - 230/400 V / 3-Phase, Hour-Tariff Electronic (Active-Reactive) Meters / METERS (Market price)	Qty	1	2.633,04	2.633,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			2.633,04	250,50
		Material and Installation w/o Profit (TRY)			2.883,54	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**313,13**	
		Unit Price (TRY)			**3.604,43**	

Item No	Analysis Name					UoM
35.135.3302	**3 x 58 / 100V, 3 x 5 (7.5) A / 3-Phase, Reactive, Electronic electric meters with time tariffs**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3302	Directly Connected Meters, at least 5(100) A, 3 x 230/400 V / 3-Phase, Hour-Tariff Electronic (Active-Reactive) Meters / METERS (Market price)	Qty	1	2.734,24	2.734,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.734,24	250,50
				Material and Installation w/o Profit (TRY)	2.984,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**313,13**	
				Unit Price (TRY)	**3.730,92**	

Item No	Analysis Name					UoM
35.135.3510						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3510	At least 5(80) A, 230 V / Single-Phase, Hour-Tariff Electronic Double-Acting Active Meters / METERS (Market price)	Qty	1	1.643,61	1.643,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	1.643,61	207,00
				Material and Installation w/o Profit (TRY)	1.850,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**2.313,26**	

Item No	Analysis Name					UoM
35.135.3610						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3610	At least 5(100) A, 3 x 230/400 V / 3-Phase, Hour-Tariff Electronic Double-Acting Active Meters / METERS (Market price)	Qty	1	3.802,45	3.802,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.802,45	250,50
				Material and Installation w/o Profit (TRY)	4.052,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**313,13**	
				Unit Price (TRY)	**5.066,19**	

Item No	Analysis Name					UoM
35.135.3710						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3710	Transformer Meters, At least x../5(10) A, 3 x 58/100 V - 230/400 V / 3-Phase, Hour-Tariff Electronic Double-Acting (Active-Reactive) Meters / METERS (Market price)	Qty	1	4.166,16	4.166,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.166,16	250,50
				Material and Installation w/o Profit (TRY)	4.416,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**313,13**	
				Unit Price (TRY)	**5.520,82**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.135.3720						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.135.3720	Directly Connected Meters, at least 5(100) A, 3 x 230/400 V / 3-Phase, Hour-Tariff Electronic Double-Acting (Active-Reactive) Meters / METERS (Market price)	Qty	1	4.320,51	4.320,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.320,51	250,50
				Material and Installation w/o Profit (TRY)	4.571,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**313,13**	
				Unit Price (TRY)	**5.713,76**	

Item No	Analysis Name					UoM
35.140.1101	**4-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with peschel, bergman or PVC pipes / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1101	4-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with PVC pipes / Main and Subsidiary Panel Earth Lines (Market price)	m	1	14,23	14,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	14,23	28,00
				Material and Installation w/o Profit (TRY)	42,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**52,79**	

Item No	Analysis Name					UoM
35.140.1102	**6-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with peschel, bergman or PVC pipes / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1102	6-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with PVC pipes / Main and Subsidiary Panel Earth Lines (Market price)	m	1	21,81	21,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	21,81	28,00
				Material and Installation w/o Profit (TRY)	49,81	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**62,26**	

Item No	Analysis Name					UoM
35.140.1103	**10-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with peschel, bergman or PVC pipes / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1103	10-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with PVC pipes / Main and Subsidiary Panel Earth Lines (Market price)	m	1	35,38	35,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	35,38	34,00
				Material and Installation w/o Profit (TRY)	69,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**86,72**	

Item No	Analysis Name					UoM
35.140.1104	**16-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with peschel, bergman or PVC pipes / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1104	16-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with PVC pipes / Main and Subsidiary Panel Earth Lines (Market price)	m	1	56,91	56,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	56,91	36,50
				Material and Installation w/o Profit (TRY)	93,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**116,76**	

Item No	Analysis Name					UoM
35.140.1105	**25-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with peschel, bergman or PVC pipes / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1105	25-mm² Bare stranded or solid copper wire / Including any material and labor for installation in the same pipe as the principal feeder line in the installation with PVC pipes / Main and Subsidiary Panel Earth Lines (Market price)	m	1	90,60	90,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	90,60	42,50
				Material and Installation w/o Profit (TRY)	133,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**166,38**	

Item No	Analysis Name					UoM
35.140.1201	**8 mm, 4 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1201	8 mm. 4 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	14,23	14,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			14,23	28,00
		Material and Installation w/o Profit (TRY)			42,23	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**35,00**	
		Unit Price (TRY)			**52,79**	

Item No	Analysis Name					UoM
35.140.1202	**20 mm, 6 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1202	20 mm 6 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	21,81	21,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			21,81	28,00
		Material and Installation w/o Profit (TRY)			49,81	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**35,00**	
		Unit Price (TRY)			**62,26**	

Item No	Analysis Name					UoM
35.140.1203	**25 mm, 10 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1203	25 mm 10 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	35,38	35,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			35,38	34,00
		Material and Installation w/o Profit (TRY)			69,38	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**42,50**	
		Unit Price (TRY)			**86,72**	

Item No	Analysis Name					UoM
35.140.1204	**25 mm, 16 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1204	25 mm 16 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	56,91	56,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			56,91	36,50
		Material and Installation w/o Profit (TRY)			93,41	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**45,63**	
		Unit Price (TRY)			**116,76**	

Item No	Analysis Name					UoM
35.140.1205	**32 mm, 25 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1205	32 mm. 25 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	90,60	90,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	90,60	42,50
				Material and Installation w/o Profit (TRY)	133,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**166,38**	

Item No	Analysis Name					UoM
35.140.1206	**32 mm, 35 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1206	32 mm. 35 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	125,99	125,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	125,99	42,50
				Material and Installation w/o Profit (TRY)	168,49	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**210,61**	

Item No	Analysis Name					UoM
35.140.1207	**40 mm, 50 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1207	40 mm 50 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	168,11	168,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	168,11	48,50
				Material and Installation w/o Profit (TRY)	216,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**270,76**	

Item No	Analysis Name					UoM
35.140.1208	**40 mm, 70 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1208	40 mm 70 mm² Bare stranded or solid copper wire / Including supply of any material and labor for installation in the same pipe as the principal column lines through the steel pipe, gas pipe or galvanized pipe. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	244,86	244,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	244,86	51,00
				Material and Installation w/o Profit (TRY)	295,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**369,83**	

Item No	Analysis Name					UoM
35.140.1301	**4 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1301	4 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	14,13	14,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	14,13	28,00
				Material and Installation w/o Profit (TRY)	42,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**52,66**	

Item No	Analysis Name					UoM
35.140.1302	**6 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1302	6 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	22,09	22,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	22,09	28,00
				Material and Installation w/o Profit (TRY)	50,09	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**62,61**	

Item No	Analysis Name					UoM
35.140.1303	**10 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1303	10 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	35,66	35,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	35,66	34,00
				Material and Installation w/o Profit (TRY)	69,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**87,07**	

Item No	Analysis Name					UoM
35.140.1304	**16 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1304	16 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	56,72	56,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	56,72	36,50
				Material and Installation w/o Profit (TRY)	93,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**116,53**	

Item No	Analysis Name					UoM
35.140.1305	**25 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1305	25 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	90,89	90,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	90,89	42,50
				Material and Installation w/o Profit (TRY)	133,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**166,74**	

Item No	Analysis Name					UoM
35.140.1306	**35 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1306	35 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	126,45	126,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	126,45	42,50
				Material and Installation w/o Profit (TRY)	168,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**211,19**	

Item No	Analysis Name					UoM
35.140.1307	**50 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1307	50 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	168,57	168,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	168,57	48,50
				Material and Installation w/o Profit (TRY)	217,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**271,34**	

Item No	Analysis Name					UoM
35.140.1308	**70 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.1308	70 mm² Bare stranded or solid copper wire / A free console with earth lines installed on cable clips, including the supply of any material and labor. / Main and Subsidiary Panel Earth Lines (Market price)	m	1	243,45	243,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	243,45	51,00
				Material and Installation w/o Profit (TRY)	294,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**368,06**	

Item No	Analysis Name					UoM
35.140.2103	**2 x 1 mm² P.14 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2461	1x1 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	4,50	9,00	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	17,01	76,05
				Material and Installation w/o Profit (TRY)	93,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,06**	
				Unit Price (TRY)	**116,33**	

Item No	Analysis Name					UoM
35.140.2104	**2 x 1.5 mm² P.14 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	6,66	13,32	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	21,33	77,70
				Material and Installation w/o Profit (TRY)	99,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**97,13**	
				Unit Price (TRY)	**123,79**	

Item No	Analysis Name					UoM
35.140.2105	**2 x 2.5 mm² P.14 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	11,13	22,26	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
		Total Excluding Profit (TRY)			30,27	80,20
		Material and Installation w/o Profit (TRY)			110,47	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**100,25**	
		Unit Price (TRY)			**138,09**	

Item No	Analysis Name					UoM
35.140.2106	**2 x 4 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2403	1 x 4 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	17,16	34,32	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
		Total Excluding Profit (TRY)			42,33	82,05
		Material and Installation w/o Profit (TRY)			124,38	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**102,56**	
		Unit Price (TRY)			**155,47**	

Item No	Analysis Name					UoM
35.140.2107	**2 x 6 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2404	1 x 6 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	25,06	50,12	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
		Total Excluding Profit (TRY)			58,13	84,55
		Material and Installation w/o Profit (TRY)			142,68	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**105,69**	
		Unit Price (TRY)			**178,35**	

Item No	Analysis Name					UoM
35.140.2108	**2 x 10 mm² P.26 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2405	1 x 10 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	43,47	86,94	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
		Total Excluding Profit (TRY)			101,55	103,40
		Material and Installation w/o Profit (TRY)			204,95	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,25**	
		Unit Price (TRY)			**256,19**	

Item No	Analysis Name					UoM
35.140.2109	**2 x 16 mm² P.26 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	68,43	136,86	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician’s helper	h	0,16	185,00		29,60
		Total Excluding Profit (TRY)			151,47	109,40
		Material and Installation w/o Profit (TRY)			260,87	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**136,75**	
		Unit Price (TRY)			**326,09**	

Item No	Analysis Name					UoM
35.140.2110	**2 x 25 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	110,03	220,06	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,26	250,00		65,00
10.100.1083	Master electrician’s helper	h	0,17	185,00		31,45
		Total Excluding Profit (TRY)			234,67	117,90
		Material and Installation w/o Profit (TRY)			352,57	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**147,38**	
		Unit Price (TRY)			**440,71**	

Item No	Analysis Name					UoM
35.140.2111	**2 x 35 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2408	1 x 35 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	149,55	299,10	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician’s helper	h	0,17	185,00		31,45
		Total Excluding Profit (TRY)			313,71	122,05
		Material and Installation w/o Profit (TRY)			435,76	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**152,56**	
		Unit Price (TRY)			**544,70**	

Item No	Analysis Name					UoM
35.140.2112	**2 x 50 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2409	1 x 50 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	204,67	409,34	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,29	250,00		72,50
10.100.1083	Master electrician’s helper	h	0,18	185,00		33,30
		Total Excluding Profit (TRY)			423,95	130,55
		Material and Installation w/o Profit (TRY)			554,50	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**163,19**	
		Unit Price (TRY)			**693,13**	

Item No	Analysis Name					UoM
35.140.2130	**3 x 1.5 mm² P.14 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	6,66	19,98	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician’s helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	27,99	103,20
				Material and Installation w/o Profit (TRY)	131,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,00**	
				Unit Price (TRY)	**163,99**	

Item No	Analysis Name					UoM
35.140.2131	**3 x 2.5 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	11,13	33,39	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician’s helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	41,40	107,55
				Material and Installation w/o Profit (TRY)	148,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**134,44**	
				Unit Price (TRY)	**186,19**	

Item No	Analysis Name					UoM
35.140.2132	**3 x 4 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2403	1 x 4 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	17,16	51,48	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	59,49	110,05
				Material and Installation w/o Profit (TRY)	169,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**137,56**	
				Unit Price (TRY)	**211,92**	

Item No	Analysis Name					UoM
35.140.2133	**3 x 6 mm² P.26 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2404	1 x 6 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	25,06	75,18	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	89,79	124,55
				Material and Installation w/o Profit (TRY)	214,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**155,69**	
				Unit Price (TRY)	**267,93**	

Item No	Analysis Name					UoM
35.140.2134	**3 x 10 mm² P.26 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2405	1 x 10 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	43,47	130,41	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,19	185,00		35,15
		Total Excluding Profit (TRY)			145,02	134,90
		Material and Installation w/o Profit (TRY)			279,92	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**168,63**	
		Unit Price (TRY)			**349,90**	

Item No	Analysis Name					UoM
35.140.2135	**3 x 16 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	68,43	205,29	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,33	250,00		82,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			219,90	145,90
		Material and Installation w/o Profit (TRY)			365,80	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**182,38**	
		Unit Price (TRY)			**457,25**	

Item No	Analysis Name					UoM
35.140.2136	**3 x 25 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	110,03	330,09	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,36	250,00		90,00
10.100.1083	Master electrician’s helper	h	0,21	185,00		38,85
		Total Excluding Profit (TRY)			344,70	158,55
		Material and Installation w/o Profit (TRY)			503,25	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**198,19**	
		Unit Price (TRY)			**629,06**	

Item No	Analysis Name					UoM
35.140.2137	**3 x 35 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2408	1 x 35 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	149,55	448,65	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician’s helper	h	0,22	185,00		40,70
		Total Excluding Profit (TRY)			463,26	164,55
		Material and Installation w/o Profit (TRY)			627,81	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**205,69**	
		Unit Price (TRY)			**784,76**	

Item No	Analysis Name					UoM
35.140.2138	**3 x 25 + 16 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	110,03	330,09	
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	68,43	68,43	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,44	250,00		110,00
10.100.1083	Master electrician’s helper	h	0,26	185,00		48,10
		Total Excluding Profit (TRY)			413,13	194,40
		Material and Installation w/o Profit (TRY)			607,53	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**243,00**	
		Unit Price (TRY)			**759,41**	

Item No	Analysis Name					UoM
35.140.2160	**4 x 1.5 mm² P.26 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	6,66	26,64	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,29	250,00		72,50
10.100.1083	Master electrician’s helper	h	0,17	185,00		31,45
		Total Excluding Profit (TRY)			34,65	128,70
		Material and Installation w/o Profit (TRY)			163,35	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**160,88**	
		Unit Price (TRY)			**204,19**	

Item No	Analysis Name					UoM
35.140.2161	**4 x 2.5 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	11,13	44,52	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	52,53	133,05
				Material and Installation w/o Profit (TRY)	185,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**166,31**	
				Unit Price (TRY)	**231,98**	

Item No	Analysis Name					UoM
35.140.2162	**4 x 4 mm² P.26 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2403	1 x 4 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	17,16	68,64	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,34	250,00		85,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	83,25	150,05
				Material and Installation w/o Profit (TRY)	233,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,56**	
				Unit Price (TRY)	**291,63**	

Item No	Analysis Name					UoM
35.140.2163	**4 x 6 mm² P.26 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2404	1 x 6 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	25,06	100,24	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	114,85	154,40
				Material and Installation w/o Profit (TRY)	269,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**193,00**	
				Unit Price (TRY)	**336,56**	

Item No	Analysis Name					UoM
35.140.2164	**4 x 10 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2405	1 x 10 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	43,47	173,88	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,38	250,00		95,00
10.100.1083	Master electrician's helper	h	0,23	185,00		42,55
				Total Excluding Profit (TRY)	188,49	168,90
				Material and Installation w/o Profit (TRY)	357,39	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,13**	
				Unit Price (TRY)	**446,74**	

Item No	Analysis Name					UoM
35.140.2165	**4 x 16 mm² P.37 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	68,43	273,72	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,21	165,00		34,65
10.100.1081	Master electrician	h	0,41	250,00		102,50
10.100.1083	Master electrician's helper	h	0,24	185,00		44,40
		Total Excluding Profit (TRY)			288,33	181,55
		Material and Installation w/o Profit (TRY)			469,88	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**226,94**	
		Unit Price (TRY)			**587,35**	

Item No	Analysis Name					UoM
35.140.2190	**5 x 1.5 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	5	6,66	33,30	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			41,31	154,20
		Material and Installation w/o Profit (TRY)			195,51	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**192,75**	
		Unit Price (TRY)			**244,39**	

Item No	Analysis Name					UoM
35.140.2191	**5 x 2.5 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	5	11,13	55,65	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	63,66	161,05
				Material and Installation w/o Profit (TRY)	224,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**201,31**	
				Unit Price (TRY)	**280,89**	

Item No	Analysis Name					UoM
35.140.2200	**6 x 1.5 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	6	6,66	39,96	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,21	165,00		34,65
10.100.1081	Master electrician	h	0,41	250,00		102,50
10.100.1083	Master electrician's helper	h	0,23	185,00		42,55
				Total Excluding Profit (TRY)	47,97	179,70
				Material and Installation w/o Profit (TRY)	227,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**224,63**	
				Unit Price (TRY)	**284,59**	

Item No	Analysis Name					UoM
35.140.2201	**6 x 2.5 mm² P.18 / Installation of a NV (NYA) conductor as well as column and supply lines in Peschel, Bergman or PVC pipe as per TS 9756 HD 21.1 S2; TS 9757 HD 21.2 S2; TS 9758 HD 21.3.S3; TS 9759 HD 21.4 S2; TS 9760 HD 21.5 S3; TS IEC 227-6; TS HD 21.7 S2; TS HD 21.8 S1; TS HD 21.13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	6	11,13	66,78	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician’s helper	h	0,24	185,00		44,40
				Total Excluding Profit (TRY)	74,79	188,20
				Material and Installation w/o Profit (TRY)	262,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**235,25**	
				Unit Price (TRY)	**328,74**	

Item No	Analysis Name					UoM
35.140.2301	**2 x 2.5 mm² (1/2) Ø15 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	11,13	22,26	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	55,00	55,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician’s helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	77,26	135,25
				Material and Installation w/o Profit (TRY)	212,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**169,06**	
				Unit Price (TRY)	**265,64**	

Item No	Analysis Name					UoM
35.140.2302	**2 x 4 mm² (5/8) Ø18 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2403	1 x 4 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	17,16	34,32	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	102,32	151,80
				Material and Installation w/o Profit (TRY)	254,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189,75**	
				Unit Price (TRY)	**317,65**	

Item No	Analysis Name					UoM
35.140.2303	**2 x 6 mm² (3/4) Ø20 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2404	1 x 6 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	25,06	50,12	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,32	250,00		80,00
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	118,12	154,30
				Material and Installation w/o Profit (TRY)	272,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**192,88**	
				Unit Price (TRY)	**340,53**	

Item No	Analysis Name					UoM
35.140.2304	**2 x 10 mm² (3/4) Ø20 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2405	1 x 10 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	43,47	86,94	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,34	250,00		85,00
10.100.1083	Master electrician’s helper	h	0,26	185,00		48,10
				Total Excluding Profit (TRY)	154,94	162,80
				Material and Installation w/o Profit (TRY)	317,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203,50**	
				Unit Price (TRY)	**397,18**	

Item No	Analysis Name					UoM
35.140.2305	**2 x 16 mm² (1) Ø25 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	68,43	136,86	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,32	185,00		59,20
				Total Excluding Profit (TRY)	241,86	190,55
				Material and Installation w/o Profit (TRY)	432,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**238,19**	
				Unit Price (TRY)	**540,51**	

Item No	Analysis Name					UoM
35.140.2306	**2 x 25 mm² (1¼) Ø32 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	110,03	220,06	
20.300.1404	1¼″ ----- 32 ----- 42.4/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	135,00	135,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,51	250,00		127,50
10.100.1083	Master electrician’s helper	h	0,42	185,00		77,70
				Total Excluding Profit (TRY)	355,06	254,70
				Material and Installation w/o Profit (TRY)	609,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**318,38**	
				Unit Price (TRY)	**762,20**	

Item No	Analysis Name					UoM
35.140.2307	**2 x 35 mm² (1¼) Ø32 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2408	1 x 35 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	149,55	299,10	
20.300.1404	1¼″ ----- 32 ----- 42.4/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	135,00	135,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,52	250,00		130,00
10.100.1083	Master electrician’s helper	h	0,42	185,00		77,70
				Total Excluding Profit (TRY)	434,10	257,20
				Material and Installation w/o Profit (TRY)	691,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**321,50**	
				Unit Price (TRY)	**864,13**	

Item No	Analysis Name					UoM
35.140.2308	**2 x 50 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2409	1 x 50 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	204,67	409,34	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,31	165,00		51,15
10.100.1081	Master electrician	h	0,58	250,00		145,00
10.100.1083	Master electrician’s helper	h	0,47	185,00		86,95
				Total Excluding Profit (TRY)	564,34	283,10
				Material and Installation w/o Profit (TRY)	847,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**353,88**	
				Unit Price (TRY)	**1.059,30**	

Item No	Analysis Name					UoM
35.140.2309	**2 x 70 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2410	1 x 70 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	297,46	594,92	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,32	165,00		52,80
10.100.1081	Master electrician	h	0,66	250,00		165,00
10.100.1083	Master electrician’s helper	h	0,53	185,00		98,05
				Total Excluding Profit (TRY)	815,92	315,85
				Material and Installation w/o Profit (TRY)	1.131,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**394,81**	
				Unit Price (TRY)	**1.414,71**	

Item No	Analysis Name					UoM
35.140.2310	**3 x 2.5 mm² (5/8) Ø18 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	11,13	33,39	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician’s helper	h	0,28	185,00		51,80
				Total Excluding Profit (TRY)	101,39	177,30
				Material and Installation w/o Profit (TRY)	278,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**221,63**	
				Unit Price (TRY)	**348,36**	

Item No	Analysis Name					UoM
35.140.2311	**3 x 4 mm² (3/4) Ø20 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2403	1 x 4 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	17,16	51,48	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,38	250,00		95,00
10.100.1083	Master electrician’s helper	h	0,28	185,00		51,80
				Total Excluding Profit (TRY)	119,48	179,80
				Material and Installation w/o Profit (TRY)	299,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**224,75**	
				Unit Price (TRY)	**374,10**	

Item No	Analysis Name					UoM
35.140.2312	**3 x 6 mm² (1) Ø25 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2404	1 x 6 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	25,06	75,18	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,44	250,00		110,00
10.100.1083	Master electrician’s helper	h	0,33	185,00		61,05
				Total Excluding Profit (TRY)	180,18	204,05
				Material and Installation w/o Profit (TRY)	384,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255,06**	
				Unit Price (TRY)	**480,29**	

Item No	Analysis Name					UoM
35.140.2313	**3 x 10 mm² (1) Ø25 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2405	1 x 10 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	43,47	130,41	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,46	250,00		115,00
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	235,41	216,05
				Material and Installation w/o Profit (TRY)	451,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**270,06**	
				Unit Price (TRY)	**564,33**	

Item No	Analysis Name					UoM
35.140.2314	**3 x 16 mm² (1¼) Ø32 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	68,43	205,29	
20.300.1404	1¼″ ----- 32 ----- 42.4/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	135,00	135,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,33	165,00		54,45
10.100.1081	Master electrician	h	0,58	250,00		145,00
10.100.1083	Master electrician’s helper	h	0,45	185,00		83,25
				Total Excluding Profit (TRY)	340,29	282,70
				Material and Installation w/o Profit (TRY)	622,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**353,38**	
				Unit Price (TRY)	**778,74**	

Item No	Analysis Name					UoM
35.140.2315	**3 x 25 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	110,03	330,09	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,34	165,00		56,10
10.100.1081	Master electrician	h	0,65	250,00		162,50
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	485,09	311,10
				Material and Installation w/o Profit (TRY)	796,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**388,88**	
				Unit Price (TRY)	**995,24**	

Item No	Analysis Name					UoM
35.140.2316	**3 x 35 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2408	1 x 35 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	149,55	448,65	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,35	165,00		57,75
10.100.1081	Master electrician	h	0,66	250,00		165,00
10.100.1083	Master electrician’s helper	h	0,51	185,00		94,35
				Total Excluding Profit (TRY)	603,65	317,10
				Material and Installation w/o Profit (TRY)	920,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**396,38**	
				Unit Price (TRY)	**1.150,94**	

Item No	Analysis Name					UoM
35.140.2317	**3 x 50 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2409	1 x 50 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	204,67	614,01	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,37	165,00		61,05
10.100.1081	Master electrician	h	0,69	250,00		172,50
10.100.1083	Master electrician’s helper	h	0,53	185,00		98,05
				Total Excluding Profit (TRY)	769,01	331,60
				Material and Installation w/o Profit (TRY)	1.100,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**414,50**	
				Unit Price (TRY)	**1.375,76**	

Item No	Analysis Name					UoM
35.140.2318	**3 x 70 mm² (2) Ø50 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2410	1 x 70 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	297,46	892,38	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,38	165,00		62,70
10.100.1081	Master electrician	h	0,78	250,00		195,00
10.100.1083	Master electrician’s helper	h	0,59	185,00		109,15
				Total Excluding Profit (TRY)	1.113,38	366,85
				Material and Installation w/o Profit (TRY)	1.480,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**458,56**	
				Unit Price (TRY)	**1.850,29**	

Item No	Analysis Name					UoM
35.140.2319	**3 x 25 + 16 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	110,03	330,09	
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	68,43	68,43	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,39	165,00		64,35
10.100.1081	Master electrician	h	0,73	250,00		182,50
10.100.1083	Master electrician’s helper	h	0,55	185,00		101,75
		Total Excluding Profit (TRY)			553,52	348,60
		Material and Installation w/o Profit (TRY)			902,12	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**435,75**	
		Unit Price (TRY)			**1.127,65**	

Item No	Analysis Name					UoM
35.140.2320	**3 x 35 + 16 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2408	1 x 35 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	149,55	448,65	
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	68,43	68,43	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,56	185,00		103,60
		Total Excluding Profit (TRY)			672,08	357,10
		Material and Installation w/o Profit (TRY)			1.029,18	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**446,38**	
		Unit Price (TRY)			**1.286,48**	

Item No	Analysis Name					UoM
35.140.2321	**3 x 50 + 25 mm² (2) Ø50 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2409	1 x 50 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	204,67	614,01	
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	110,03	110,03	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,41	165,00		67,65
10.100.1081	Master electrician	h	0,84	250,00		210,00
10.100.1083	Master electrician’s helper	h	0,62	185,00		114,70
		Total Excluding Profit (TRY)			945,04	392,35
		Material and Installation w/o Profit (TRY)			1.337,39	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**490,44**	
		Unit Price (TRY)			**1.671,74**	

Item No	Analysis Name					UoM
35.140.2322	**3 x 70 + 35 mm² (2) Ø50 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2410	1 x 70 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	3	297,46	892,38	
30.140.2408	1 x 35 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	149,55	149,55	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,44	165,00		72,60
10.100.1081	Master electrician	h	0,88	250,00		220,00
10.100.1083	Master electrician’s helper	h	0,65	185,00		120,25
		Total Excluding Profit (TRY)			1.262,93	412,85
		Material and Installation w/o Profit (TRY)			1.675,78	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**516,06**	
		Unit Price (TRY)			**2.094,73**	

Item No	Analysis Name					UoM
35.140.2323	**4 x 2.5 mm² (3/4) Ø20 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	11,13	44,52	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,23	165,00		37,95
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician’s helper	h	0,31	185,00		57,35
				Total Excluding Profit (TRY)	112,52	202,80
				Material and Installation w/o Profit (TRY)	315,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**253,50**	
				Unit Price (TRY)	**394,15**	

Item No	Analysis Name					UoM
35.140.2324	**4 x 4 mm² (1) Ø25 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2403	1 x 4 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	17,16	68,64	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,23	165,00		37,95
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,36	185,00		66,60
				Total Excluding Profit (TRY)	173,64	229,55
				Material and Installation w/o Profit (TRY)	403,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**286,94**	
				Unit Price (TRY)	**503,99**	

Item No	Analysis Name					UoM
35.140.2325	**4 x 6 mm² (1) Ø25 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2404	1 x 6 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	25,06	100,24	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,24	165,00		39,60
10.100.1081	Master electrician	h	0,51	250,00		127,50
10.100.1083	Master electrician’s helper	h	0,37	185,00		68,45
				Total Excluding Profit (TRY)	205,24	235,55
				Material and Installation w/o Profit (TRY)	440,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**294,44**	
				Unit Price (TRY)	**550,99**	

Item No	Analysis Name					UoM
35.140.2326	**4 x 10 mm² (1) Ø25 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2405	1 x 10 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	43,47	173,88	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,26	165,00		42,90
10.100.1081	Master electrician	h	0,54	250,00		135,00
10.100.1083	Master electrician’s helper	h	0,39	185,00		72,15
				Total Excluding Profit (TRY)	278,88	250,05
				Material and Installation w/o Profit (TRY)	528,93	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**312,56**	
				Unit Price (TRY)	**661,16**	

Item No	Analysis Name					UoM
35.140.2327	**4 x 16 mm² (1½) Ø40 mm / Installation of a NV (NYA) conductor and supply lines in galvanized or internally and externally coated, threaded steel pipe (TS-9) as per TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, and TS HD 21,13 S1. / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	4	68,43	273,72	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,37	165,00		61,05
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,53	185,00		98,05
				Total Excluding Profit (TRY)	428,72	334,10
				Material and Installation w/o Profit (TRY)	762,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**417,63**	
				Unit Price (TRY)	**953,53**	

Item No	Analysis Name					UoM
35.140.2401						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	6,66	6,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	6,66	25,50
				Material and Installation w/o Profit (TRY)	32,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**40,20**	

Item No	Analysis Name					UoM
35.140.2402	**Similar to the item no. 780 - 118 except that the section shall be 1 x 2.5 mm² / 1 x 1.5 mm² / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	11,13	11,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			11,13	25,50
		Material and Installation w/o Profit (TRY)			36,63	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**31,88**	
		Unit Price (TRY)			**45,79**	

Item No	Analysis Name					UoM
35.140.2403	**Similar to the item no. 780 - 118 except that the section shall be 1 x 4 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2403	1 x 4 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	17,16	17,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			17,16	28,00
		Material and Installation w/o Profit (TRY)			45,16	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**35,00**	
		Unit Price (TRY)			**56,45**	

Item No	Analysis Name					UoM
35.140.2404	**Similar to the item no. 780 - 118 except that the section shall be 1 x 6 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2404	1 x 6 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	25,06	25,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			25,06	28,00
		Material and Installation w/o Profit (TRY)			53,06	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**35,00**	
		Unit Price (TRY)			**66,33**	

Item No	Analysis Name					UoM
35.140.2405	**Similar to the item no. 780 - 118 except that the section shall be 1 x 10 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2405	1 x 10 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	43,47	43,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			43,47	34,00
		Material and Installation w/o Profit (TRY)			77,47	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**42,50**	
		Unit Price (TRY)			**96,84**	

Item No	Analysis Name					UoM
35.140.2406	**Similar to the item no. 780 - 118 except that the section shall be 1 x 16 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2406	1 x 16 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	68,43	68,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			68,43	36,50
		Material and Installation w/o Profit (TRY)			104,93	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**45,63**	
		Unit Price (TRY)			**131,16**	

Item No	Analysis Name					UoM
35.140.2407	**Similar to the item no. 780 - 118 except that the section shall be 1 x 25 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2407	1 x 25 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	110,03	110,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			110,03	42,50
		Material and Installation w/o Profit (TRY)			152,53	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**53,13**	
		Unit Price (TRY)			**190,66**	

Item No	Analysis Name					UoM
35.140.2408	**Similar to the item no. 780 - 118 except that the section shall be 1 x 35 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2408	1 x 35 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	149,55	149,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	149,55	42,50
				Material and Installation w/o Profit (TRY)	192,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**240,06**	

Item No	Analysis Name					UoM
35.140.2409	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2409	1 x 50 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	204,67	204,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	204,67	48,50
				Material and Installation w/o Profit (TRY)	253,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**316,46**	

Item No	Analysis Name					UoM
35.140.2410	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2410	1 x 70 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	297,46	297,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	297,46	51,00
				Material and Installation w/o Profit (TRY)	348,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**435,57**	

Item No	Analysis Name					UoM
35.140.2415	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2415	1 x 95 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	406,76	406,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	406,76	59,50
				Material and Installation w/o Profit (TRY)	466,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**582,83**	

Item No	Analysis Name					UoM
35.140.2420	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2420	1 x 120 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	526,82	526,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			526,82	59,50
		Material and Installation w/o Profit (TRY)			586,32	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**74,38**	
		Unit Price (TRY)			**732,90**	

Item No	Analysis Name					UoM
35.140.2425	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2425	1 x 150 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	642,40	642,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			642,40	65,50
		Material and Installation w/o Profit (TRY)			707,90	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**81,88**	
		Unit Price (TRY)			**884,88**	

Item No	Analysis Name					UoM
35.140.2430	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2430	1 x 185 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	815,32	815,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			815,32	70,50
		Material and Installation w/o Profit (TRY)			885,82	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**88,13**	
		Unit Price (TRY)			**1.107,28**	

Item No	Analysis Name					UoM
35.140.2435	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2435	1 x 240 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	1.076,93	1.076,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			1.076,93	76,50
		Material and Installation w/o Profit (TRY)			1.153,43	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**95,63**	
		Unit Price (TRY)			**1.441,79**	

Item No	Analysis Name					UoM
35.140.2461	**Similar to the item no. 780 - 118 except that the section shall be 1 x 50 mm² / 1 x 1.5 mm² section / Separate Installation Parts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2461	1x1 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	4,50	4,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			4,50	25,50
		Material and Installation w/o Profit (TRY)			30,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**31,88**	
		Unit Price (TRY)			**37,50**	

Item No	Analysis Name					UoM
35.140.2501	**2 x 1.5 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2501	2 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	17,78	17,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			17,78	40,00
		Material and Installation w/o Profit (TRY)			57,78	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**50,00**	
		Unit Price (TRY)			**72,22**	

Item No	Analysis Name					UoM
35.140.2502	**2 x 2.5 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2502	2 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	26,52	26,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	26,52	42,50
				Material and Installation w/o Profit (TRY)	69,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**86,27**	

Item No	Analysis Name					UoM
35.140.2503	**2 x 4 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2503	2 x 4 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	40,04	40,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	40,04	45,00
				Material and Installation w/o Profit (TRY)	85,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**106,30**	

Item No	Analysis Name					UoM
35.140.2504	**2 x 6 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2504	2 x 6 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	57,20	57,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	57,20	48,50
				Material and Installation w/o Profit (TRY)	105,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**132,13**	

Item No	Analysis Name					UoM
35.140.2505	**2 x 10 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2505	2 x 10 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	100,36	100,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	100,36	59,50
				Material and Installation w/o Profit (TRY)	159,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**199,83**	

Item No	Analysis Name					UoM
35.140.2506	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2506	2 x 16 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	154,44	154,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	154,44	62,00
				Material and Installation w/o Profit (TRY)	216,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**270,55**	

Item No	Analysis Name					UoM
35.140.2507	**3 x 1.5 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	23,92	23,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	23,92	42,50
				Material and Installation w/o Profit (TRY)	66,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**83,03**	

Item No	Analysis Name					UoM
35.140.2508	**3 x 2.5 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2508	3 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	37,44	37,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	37,44	45,00
				Material and Installation w/o Profit (TRY)	82,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**103,05**	

Item No	Analysis Name					UoM
35.140.2509	**3 x 4 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2509	3 x 4 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	57,20	57,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	57,20	48,50
				Material and Installation w/o Profit (TRY)	105,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**132,13**	

Item No	Analysis Name					UoM
35.140.2510	**3 x 6 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2510	3 x 6 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	83,72	83,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	83,72	51,00
				Material and Installation w/o Profit (TRY)	134,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**168,40**	

Item No	Analysis Name					UoM
35.140.2511	**3 x 10 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2511	3 x 10 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	144,04	144,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	144,04	59,50
				Material and Installation w/o Profit (TRY)	203,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**254,42**	

Item No	Analysis Name					UoM
35.140.2512	**3 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2512	3 x 16 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	223,08	223,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	223,08	65,50
				Material and Installation w/o Profit (TRY)	288,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**360,73**	

Item No	Analysis Name					UoM
35.140.2513	**4 x 1.5 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2513	4 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	32,14	32,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	32,14	42,50
				Material and Installation w/o Profit (TRY)	74,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**93,30**	

Item No	Analysis Name					UoM
35.140.2514	**4 x 2.5 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2514	4 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	49,30	49,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	49,30	48,50
				Material and Installation w/o Profit (TRY)	97,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**122,25**	

Item No	Analysis Name					UoM
35.140.2515	**4 x 4 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2515	4 x 4 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	76,34	76,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,05	250,00		12,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	76,34	23,00
				Material and Installation w/o Profit (TRY)	99,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**28,75**	
				Unit Price (TRY)	**124,18**	

Item No	Analysis Name					UoM
35.140.2516	**4 x 6 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2516	4 x 6 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	110,66	110,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	110,66	53,50
				Material and Installation w/o Profit (TRY)	164,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**205,20**	

Item No	Analysis Name					UoM
35.140.2517	**4 x 10 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2517	4 x 10 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	189,70	189,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	189,70	65,50
				Material and Installation w/o Profit (TRY)	255,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**319,00**	

Item No	Analysis Name					UoM
35.140.2518	**4 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2518	4 x 16 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	291,62	291,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	291,62	68,00
				Material and Installation w/o Profit (TRY)	359,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**449,52**	

Item No	Analysis Name					UoM
35.140.2531	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2531	5 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	39,37	39,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,37	45,00
				Material and Installation w/o Profit (TRY)	84,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**105,46**	

Item No	Analysis Name					UoM
35.140.2532	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2532	5 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	61,30	61,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	61,30	51,00
				Material and Installation w/o Profit (TRY)	112,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**140,38**	

Item No	Analysis Name					UoM
35.140.2533	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2533	5 x 4 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	95,54	95,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	95,54	53,50
				Material and Installation w/o Profit (TRY)	149,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**186,30**	

Item No	Analysis Name					UoM
35.140.2534	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2534	5 x 6 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	137,68	137,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	137,68	57,00
				Material and Installation w/o Profit (TRY)	194,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**243,35**	

Item No	Analysis Name					UoM
35.140.2535	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2535	5 x 10 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	237,40	237,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	237,40	68,00
				Material and Installation w/o Profit (TRY)	305,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**381,75**	

Item No	Analysis Name					UoM
35.140.2536	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2536	5 x 16 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	367,82	367,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	367,82	76,50
				Material and Installation w/o Profit (TRY)	444,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**555,40**	

Item No	Analysis Name					UoM
35.140.2541	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2541	2 x 25 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	241,16	241,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	241,16	74,00
				Material and Installation w/o Profit (TRY)	315,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**393,95**	

Item No	Analysis Name					UoM
35.140.2543	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2543	2 x 35 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	328,17	328,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	328,17	76,50
				Material and Installation w/o Profit (TRY)	404,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**505,84**	

Item No	Analysis Name					UoM
35.140.2551	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2551	3 x 25 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	351,07	351,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	351,07	76,50
				Material and Installation w/o Profit (TRY)	427,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**534,46**	

Item No	Analysis Name					UoM
35.140.2553	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2553	3 x 35 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	477,51	477,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	477,51	85,00
				Material and Installation w/o Profit (TRY)	562,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**703,14**	

Item No	Analysis Name					UoM
35.140.2561	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2561	4 x 25 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	463,65	463,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	463,65	82,50
				Material and Installation w/o Profit (TRY)	546,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**682,69**	

Item No	Analysis Name					UoM
35.140.2563	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2563	4 x 35 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	629,88	629,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	629,88	91,00
				Material and Installation w/o Profit (TRY)	720,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**113,75**	
				Unit Price (TRY)	**901,10**	

Item No	Analysis Name					UoM
35.140.2571	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2571	5 x 25 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	577,39	577,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	577,39	91,00
				Material and Installation w/o Profit (TRY)	668,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**113,75**	
				Unit Price (TRY)	**835,49**	

Item No	Analysis Name					UoM
35.140.2573	**2 x 16 mm² / Installation of a supply line NVV (NYM) using lead-free, PVC-insulated cables in compliance with TS 9756 HD 21.1 S2, TS 9756 HD 21.1 S4, TS 9757 HD 21,2 S2, TS 9758 HD 21,3S3, TS 9759 HD 21,4 S2, TS 9760 HD 21,5 S3, TS IEC 227-6, TS HD 21,8 S1, TS HD 21,13 S1 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2573	5 x 35 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	785,89	785,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	785,89	99,50
				Material and Installation w/o Profit (TRY)	885,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**124,38**	
				Unit Price (TRY)	**1.106,74**	

Item No	Analysis Name					UoM
35.140.2601	**2 x 0.50 mm² FVV / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2601	2 x 0.50 mm² FVV / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	7,45	7,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	7,45	34,00
				Material and Installation w/o Profit (TRY)	41,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**51,81**	

Item No	Analysis Name					UoM
35.140.2602	**3 x 0.50 mm² FVV / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2602	3 x 0.50 mm² FVV / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	8,42	8,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	8,42	34,00
				Material and Installation w/o Profit (TRY)	42,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**53,03**	

Item No	Analysis Name					UoM
35.140.2603	**4 x 0.50 mm² FVV / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2603	4 x 0.50 mm² FVV / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	9,29	9,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	9,29	34,00
				Material and Installation w/o Profit (TRY)	43,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**54,11**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.140.2604	**2 x 0.75 mm² FVV / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2604	2 x 0.75 mm² FVV / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	11,12	11,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	11,12	34,00
				Material and Installation w/o Profit (TRY)	45,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**56,40**	

Item No	Analysis Name					UoM
35.140.2605	**3 x 0.75 mm² FVV / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2605	3 x 0.75 mm² FVV / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	13,82	13,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,82	34,00
				Material and Installation w/o Profit (TRY)	47,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**59,77**	

Item No	Analysis Name					UoM
35.140.2606	**4 x 0.75 mm² FVV / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2606	4 x 0.75 mm² FVV / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	19,87	19,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,87	36,50
				Material and Installation w/o Profit (TRY)	56,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**70,46**	

Item No	Analysis Name					UoM
35.140.2607	**2 x 0.75 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2607	2 x 0.75 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	10,91	10,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	10,91	34,00
				Material and Installation w/o Profit (TRY)	44,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**56,14**	

Item No	Analysis Name					UoM
35.140.2608	**3 x 0.75 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2608	3 x 0.75 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	14,47	14,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,47	34,00
				Material and Installation w/o Profit (TRY)	48,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**60,59**	

Item No	Analysis Name					UoM
35.140.2609	**4 x 0.75 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2609	4 x 0.75 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	18,90	18,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	18,90	36,50
				Material and Installation w/o Profit (TRY)	55,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**69,25**	

Item No	Analysis Name					UoM
35.140.2610	**5 x 0.75 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2610	5 x 0.75 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	21,60	21,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	21,60	40,00
				Material and Installation w/o Profit (TRY)	61,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**77,00**	

Item No	Analysis Name					UoM
35.140.2611	**6 x 0.75 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2611	6 x 0.75 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	22,36	22,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	22,36	42,50
				Material and Installation w/o Profit (TRY)	64,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**81,08**	

Item No	Analysis Name					UoM
35.140.2612	**7 x 0.75 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2612	7 x 0.75 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	24,15	24,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	24,15	42,50
				Material and Installation w/o Profit (TRY)	66,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**83,31**	

Item No	Analysis Name					UoM
35.140.2613	**2 x 1 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2613	2 x 1 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	13,19	13,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,19	34,00
				Material and Installation w/o Profit (TRY)	47,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**58,99**	

Item No	Analysis Name					UoM
35.140.2614	**3 x 1 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2614	3 x 1 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	18,09	18,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	18,09	36,50
				Material and Installation w/o Profit (TRY)	54,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**68,24**	

Item No	Analysis Name					UoM
35.140.2615	**4 x 1 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2615	4 x 1 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	23,73	23,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	23,73	40,00
				Material and Installation w/o Profit (TRY)	63,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**79,66**	

Item No	Analysis Name					UoM
35.140.2616	**5 x 1 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2616	5 x 1 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	29,58	29,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	29,58	42,50
				Material and Installation w/o Profit (TRY)	72,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**90,10**	

Item No	Analysis Name					UoM
35.140.2617	**6 x 1 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2617	6 x 1 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	40,22	40,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	40,22	42,50
				Material and Installation w/o Profit (TRY)	82,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**103,40**	

Item No	Analysis Name					UoM
35.140.2618	**7 x 1 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2618	7 x 1 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	42,35	42,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			42,35	42,50
		Material and Installation w/o Profit (TRY)			84,85	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**53,13**	
		Unit Price (TRY)			**106,06**	

Item No	Analysis Name					UoM
35.140.2619	**2 x 1.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2619	2 x 1.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	17,82	17,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			17,82	36,50
		Material and Installation w/o Profit (TRY)			54,32	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**45,63**	
		Unit Price (TRY)			**67,90**	

Item No	Analysis Name					UoM
35.140.2620	**3 x 1.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2620	3 x 1.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	24,94	24,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	24,94	42,50
				Material and Installation w/o Profit (TRY)	67,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**84,30**	

Item No	Analysis Name					UoM
35.140.2621	**4 x 1.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2621	4 x 1.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	31,75	31,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	31,75	42,50
				Material and Installation w/o Profit (TRY)	74,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**92,81**	

Item No	Analysis Name					UoM
35.140.2622	**5 x 1.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2622	5 x 1.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	41,71	41,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,71	45,00
				Material and Installation w/o Profit (TRY)	86,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**108,39**	

Item No	Analysis Name					UoM
35.140.2623	**6 x 1.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2623	6 x 1.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	54,29	54,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	54,29	48,50
				Material and Installation w/o Profit (TRY)	102,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**128,49**	

Item No	Analysis Name					UoM
35.140.2624	**7 x 1.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2624	7 x 1.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	59,53	59,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	59,53	51,00
				Material and Installation w/o Profit (TRY)	110,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**138,16**	

Item No	Analysis Name					UoM
35.140.2625	**2 x 2.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2625	2 x 2.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	27,56	27,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	27,56	42,50
				Material and Installation w/o Profit (TRY)	70,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**87,58**	

Item No	Analysis Name					UoM
35.140.2626	**3 x 2.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2626	3 x 2.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	37,52	37,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	37,52	42,50
				Material and Installation w/o Profit (TRY)	80,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**100,03**	

Item No	Analysis Name					UoM
35.140.2627	**4 x 2.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2627	4 x 2.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	51,14	51,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	51,14	48,50
				Material and Installation w/o Profit (TRY)	99,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**124,55**	

Item No	Analysis Name					UoM
35.140.2628	**5 x 2.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2628	5 x 2.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	66,34	66,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	66,34	51,00
				Material and Installation w/o Profit (TRY)	117,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**146,68**	

Item No	Analysis Name					UoM
35.140.2629	**6 x 2.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2629	6 x 2.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	81,53	81,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	81,53	53,50
				Material and Installation w/o Profit (TRY)	135,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**168,79**	

Item No	Analysis Name					UoM
35.140.2630	**7 x 2.5 mm² FVV-n / Fvv-Fvvn, Nymhy (Fd) Conductors in compliance with TS 936, (Cable Price)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2630	7 x 2.5 mm² FVV-n / FVV-FVVn, NYMHY (FD) type cable / MAIN LINE AND SUPPLY LINES (Market price)	m	1	90,97	90,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	90,97	57,00
				Material and Installation w/o Profit (TRY)	147,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**184,96**	

Item No	Analysis Name					UoM
35.140.3101	**1 x 6 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3101	1 x 6 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	29,24	29,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,24	36,50
				Material and Installation w/o Profit (TRY)	65,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**82,17**	

Item No	Analysis Name					UoM
35.140.3102	**1 x 10 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3102	1 x 10 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	47,58	47,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	47,58	42,50
				Material and Installation w/o Profit (TRY)	90,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**112,60**	

Item No	Analysis Name					UoM
35.140.3103	**1 x 16 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3103	1 x 16 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	73,78	73,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	73,78	42,50
				Material and Installation w/o Profit (TRY)	116,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**145,35**	

Item No	Analysis Name					UoM
35.140.3104	**1 x 25 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3104	1 x 25 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	114,13	114,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	114,13	48,50
				Material and Installation w/o Profit (TRY)	162,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**203,29**	

Item No	Analysis Name					UoM
35.140.3105	**1 x 35 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3105	1 x 35 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	158,14	158,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	158,14	51,00
				Material and Installation w/o Profit (TRY)	209,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**261,42**	

Item No	Analysis Name					UoM
35.140.3106	**1 x 50 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3106	1 x 50 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	208,97	208,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	208,97	53,50
				Material and Installation w/o Profit (TRY)	262,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**328,09**	

Item No	Analysis Name					UoM
35.140.3107	**1 x 70 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3107	1 x 70 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	294,91	294,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	294,91	59,50
				Material and Installation w/o Profit (TRY)	354,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**443,01**	

Item No	Analysis Name					UoM
35.140.3108	**1 x 95 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3108	1 x 95 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	408,09	408,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	408,09	65,50
				Material and Installation w/o Profit (TRY)	473,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**591,99**	

Item No	Analysis Name					UoM
35.140.3109	**1 x 120 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3109	1 x 120 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	516,04	516,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	516,04	68,00
				Material and Installation w/o Profit (TRY)	584,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**730,05**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.140.3110	**1 x 150 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3110	1 x 150 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	632,36	632,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	632,36	74,00
				Material and Installation w/o Profit (TRY)	706,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**882,95**	

Item No	Analysis Name					UoM
35.140.3111	**1 x 185 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3111	1 x 185 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	787,47	787,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	787,47	79,00
				Material and Installation w/o Profit (TRY)	866,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**1.083,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.140.3112	**1 x 240 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3112	1 x 240 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.052,61	1.052,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	1.052,61	87,50
				Material and Installation w/o Profit (TRY)	1.140,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**109,38**	
				Unit Price (TRY)	**1.425,14**	

Item No	Analysis Name					UoM
35.140.3130	**2 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3130	2 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	19,49	19,49	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	19,49	45,00
				Material and Installation w/o Profit (TRY)	64,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**80,61**	

Item No	Analysis Name					UoM
35.140.3131	**2 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3131	2 x 2.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	28,40	28,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	28,40	48,50
				Material and Installation w/o Profit (TRY)	76,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**96,13**	

Item No	Analysis Name					UoM
35.140.3132	**2 x 4 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3132	2 x 4 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	43,60	43,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	43,60	51,00
				Material and Installation w/o Profit (TRY)	94,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**118,25**	

Item No	Analysis Name					UoM
35.140.3133	**2 x 6 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3133	2 x 6 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	61,41	61,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	61,41	53,50
				Material and Installation w/o Profit (TRY)	114,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**143,64**	

Item No	Analysis Name					UoM
35.140.3134	**2 x 10 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3134	2 x 10 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	101,24	101,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	101,24	59,50
				Material and Installation w/o Profit (TRY)	160,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**200,93**	

Item No	Analysis Name					UoM
35.140.3135	**2 x 16 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3135	2 x 16 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	154,68	154,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	154,68	65,50
				Material and Installation w/o Profit (TRY)	220,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**275,23**	

Item No	Analysis Name					UoM
35.140.3136	**2 x 25 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3136	2 x 25 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	239,57	239,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	239,57	74,00
				Material and Installation w/o Profit (TRY)	313,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**391,96**	

Item No	Analysis Name					UoM
35.140.3160	**3 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3160	3 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	26,83	26,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	26,83	48,50
				Material and Installation w/o Profit (TRY)	75,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**94,16**	

Item No	Analysis Name					UoM
35.140.3161	**3 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3161	3 x 2.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	39,93	39,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	39,93	51,00
				Material and Installation w/o Profit (TRY)	90,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**113,66**	

Item No	Analysis Name					UoM
35.140.3162	**3 x 4 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3162	3 x 4 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	61,41	61,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	61,41	53,50
				Material and Installation w/o Profit (TRY)	114,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**143,64**	

Item No	Analysis Name					UoM
35.140.3163	**3 x 6 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3163	3 x 6 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	88,66	88,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	88,66	57,00
				Material and Installation w/o Profit (TRY)	145,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**182,07**	

Item No	Analysis Name					UoM
35.140.3164	**3 x 10 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3164	3 x 10 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	143,16	143,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	143,16	62,00
				Material and Installation w/o Profit (TRY)	205,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**256,45**	

Item No	Analysis Name					UoM
35.140.3165	**3 x 16 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3165	3 x 16 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	225,95	225,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	225,95	68,00
				Material and Installation w/o Profit (TRY)	293,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**367,44**	

Item No	Analysis Name					UoM
35.140.3166	**3 x 25 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3166	3 x 25 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	350,66	350,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	350,66	76,50
				Material and Installation w/o Profit (TRY)	427,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**533,95**	

Item No	Analysis Name					UoM
35.140.3190	**3 x 25 + 16 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3190	3 x 25 + 16 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	416,06	416,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	416,06	79,00
				Material and Installation w/o Profit (TRY)	495,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**618,83**	

Item No	Analysis Name					UoM
35.140.3191	**3 x 35 + 16 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3191	3 x 35 + 16 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	538,67	538,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	538,67	85,00
				Material and Installation w/o Profit (TRY)	623,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**779,59**	

Item No	Analysis Name					UoM
35.140.3192	**3 x 50 + 25 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3192	3 x 50 + 25 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	749,32	749,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	749,32	93,50
				Material and Installation w/o Profit (TRY)	842,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**1.053,53**	

Item No	Analysis Name					UoM
35.140.3193	**3 x 70 + 35 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3193	3 x 70 + 35 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.056,38	1.056,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	1.056,38	108,00
				Material and Installation w/o Profit (TRY)	1.164,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**135,00**	
				Unit Price (TRY)	**1.455,48**	

Item No	Analysis Name					UoM
35.140.3194	**3 x 95 + 50 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3194	3 x 95 + 50 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.464,06	1.464,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,29	250,00		72,50
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	1.464,06	121,50
				Material and Installation w/o Profit (TRY)	1.585,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**151,88**	
				Unit Price (TRY)	**1.981,95**	

Item No	Analysis Name					UoM
35.140.3195	**3 x 120 + 70 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3195	3 x 120 + 70 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.902,12	1.902,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,32	250,00		80,00
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
				Total Excluding Profit (TRY)	1.902,12	136,00
				Material and Installation w/o Profit (TRY)	2.038,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**170,00**	
				Unit Price (TRY)	**2.547,65**	

Item No	Analysis Name					UoM
35.140.3196	**3 x 150 + 70 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3196	3 x 150 + 70 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	2.258,44	2.258,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,34	250,00		85,00
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	2.258,44	144,50
				Material and Installation w/o Profit (TRY)	2.402,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**180,63**	
				Unit Price (TRY)	**3.003,68**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.140.3197	**3 x 185 + 95 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3197	3 x 185 + 95 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	2.832,74	2.832,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,38	250,00		95,00
10.100.1083	Master electrician's helper	h	0,19	185,00		35,15
				Total Excluding Profit (TRY)	2.832,74	161,50
				Material and Installation w/o Profit (TRY)	2.994,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**201,88**	
				Unit Price (TRY)	**3.742,80**	

Item No	Analysis Name					UoM
35.140.3198	**3 x 240 + 120 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3198	3 x 240 + 120 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	3.707,82	3.707,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,21	165,00		34,65
10.100.1081	Master electrician	h	0,42	250,00		105,00
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	3.707,82	178,50
				Material and Installation w/o Profit (TRY)	3.886,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**223,13**	
				Unit Price (TRY)	**4.857,90**	

Item No	Analysis Name					UoM
35.140.3220	**4 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3220	4 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	33,64	33,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	33,64	51,00
				Material and Installation w/o Profit (TRY)	84,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**105,80**	

Item No	Analysis Name					UoM
35.140.3221	**4 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3221	4 x 2.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	50,93	50,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	50,93	51,00
				Material and Installation w/o Profit (TRY)	101,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**127,41**	

Item No	Analysis Name					UoM
35.140.3222	**4 x 4 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3222	4 x 4 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	80,07	80,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	80,07	57,00
				Material and Installation w/o Profit (TRY)	137,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**171,34**	

Item No	Analysis Name					UoM
35.140.3223	**4 x 6 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS 1178 IEC 60502) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3223	4 x 6 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	114,65	114,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	114,65	59,50
				Material and Installation w/o Profit (TRY)	174,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**217,69**	

Item No	Analysis Name					UoM
35.140.3224	**4 x 10 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3224	4 x 10 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	190,11	190,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	190,11	68,00
				Material and Installation w/o Profit (TRY)	258,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**322,64**	

Item No	Analysis Name					UoM
35.140.3225	**4 x 16 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3225	4 x 16 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	294,59	294,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	294,59	70,50
				Material and Installation w/o Profit (TRY)	365,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**456,36**	

Item No	Analysis Name					UoM
35.140.3226	**4 x 25 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3226	4 x 25 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	468,46	468,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	468,46	85,00
				Material and Installation w/o Profit (TRY)	553,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**691,83**	

Item No	Analysis Name					UoM
35.140.3227	**4 x 35 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3227	4 x 35 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	635,09	635,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	635,09	91,00
				Material and Installation w/o Profit (TRY)	726,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**113,75**	
				Unit Price (TRY)	**907,61**	

Item No	Analysis Name					UoM
35.140.3228	**4 x 50 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3228	4 x 50 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	847,83	847,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	847,83	102,00
				Material and Installation w/o Profit (TRY)	949,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**1.187,29**	

Item No	Analysis Name					UoM
35.140.3229	**4 x 70 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3229	4 x 70 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.208,34	1.208,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	1.208,34	113,00
				Material and Installation w/o Profit (TRY)	1.321,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**141,25**	
				Unit Price (TRY)	**1.651,67**	

Item No	Analysis Name					UoM
35.140.3230	**4 x 95 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3230	4 x 95 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.687,28	1.687,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	1.687,28	130,00
				Material and Installation w/o Profit (TRY)	1.817,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**162,50**	
				Unit Price (TRY)	**2.271,60**	

Item No	Analysis Name					UoM
35.140.3231	**4 x 120 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3231	4 x 120 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	2.129,54	2.129,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,33	250,00		82,50
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	2.129,54	142,00
				Material and Installation w/o Profit (TRY)	2.271,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**177,50**	
				Unit Price (TRY)	**2.839,43**	

Item No	Analysis Name					UoM
35.140.3232	**4 x 150 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3232	4 x 150 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	2.607,42	2.607,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,36	250,00		90,00
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	2.607,42	153,00
				Material and Installation w/o Profit (TRY)	2.760,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**191,25**	
				Unit Price (TRY)	**3.450,53**	

Item No	Analysis Name					UoM
35.140.3233	**4 x 185 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3233	4 x 185 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	3.260,33	3.260,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	3.260,33	170,00
				Material and Installation w/o Profit (TRY)	3.430,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**212,50**	
				Unit Price (TRY)	**4.287,91**	

Item No	Analysis Name					UoM
35.140.3234	**4 x 240 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3234	4 x 240 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	4.289,46	4.289,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,44	250,00		110,00
10.100.1083	Master electrician's helper	h	0,22	185,00		40,70
				Total Excluding Profit (TRY)	4.289,46	187,00
				Material and Installation w/o Profit (TRY)	4.476,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**233,75**	
				Unit Price (TRY)	**5.595,57**	

Item No	Analysis Name					UoM
35.140.3250	**5 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3250	5 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	42,02	42,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	42,02	51,00
				Material and Installation w/o Profit (TRY)	93,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**116,28**	

Item No	Analysis Name					UoM
35.140.3251	**5 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3251	5 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	64,35	64,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	64,35	53,50
				Material and Installation w/o Profit (TRY)	117,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**147,31**	

Item No	Analysis Name					UoM
35.140.3260	**10 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3260	10 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	83,21	83,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	83,21	59,50
				Material and Installation w/o Profit (TRY)	142,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**178,39**	

Item No	Analysis Name					UoM
35.140.3261	**12 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3261	12 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	102,08	102,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	102,08	62,00
				Material and Installation w/o Profit (TRY)	164,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**205,10**	

Item No	Analysis Name					UoM
35.140.3262	**14 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3262	14 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	110,46	110,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	110,46	65,50
				Material and Installation w/o Profit (TRY)	175,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**219,95**	

Item No	Analysis Name					UoM
35.140.3263	**19 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3263	19 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	149,24	149,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	149,24	68,00
				Material and Installation w/o Profit (TRY)	217,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**271,55**	

Item No	Analysis Name					UoM
35.140.3264	**21 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3264	21 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	152,38	152,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	152,38	70,50
				Material and Installation w/o Profit (TRY)	222,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**278,60**	

Item No	Analysis Name					UoM
35.140.3265	**24 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3265	24 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	185,92	185,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	185,92	76,50
				Material and Installation w/o Profit (TRY)	262,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**328,02**	

Item No	Analysis Name					UoM
35.140.3266	**30 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables YVV (NYY) (TS IEC 60502-1+A1) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3266	30 x 1.5 mm² / Installation of column and supply lines with 1-KV YVV (NYY) underground cables / Main Line and Supply Lines (Market price)	m	1	232,03	232,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	232,03	79,00
				Material and Installation w/o Profit (TRY)	311,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**388,79**	

Item No	Analysis Name					UoM
35.140.3401	**3 x 6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3401	3 x 6 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	135,77	135,77	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			135,77	62,00
		Material and Installation w/o Profit (TRY)			197,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**77,50**	
		Unit Price (TRY)			**247,21**	

Item No	Analysis Name					UoM
35.140.3402	**3 x 10 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3402	3 x 10 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	217,69	217,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			217,69	68,00
		Material and Installation w/o Profit (TRY)			285,69	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**85,00**	
		Unit Price (TRY)			**357,11**	

Item No	Analysis Name					UoM
35.140.3403	**3 x 16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3403	3 x 16 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	332,61	332,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	332,61	76,50
				Material and Installation w/o Profit (TRY)	409,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**511,39**	

Item No	Analysis Name					UoM
35.140.3404	**3 x 25 + 16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3404	3 x 25 + 16 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	468,16	468,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	468,16	87,50
				Material and Installation w/o Profit (TRY)	555,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**109,38**	
				Unit Price (TRY)	**694,58**	

Item No	Analysis Name					UoM
35.140.3405	**3 x 35 + 16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3405	3 x 35 + 16 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	603,29	603,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	603,29	93,50
				Material and Installation w/o Profit (TRY)	696,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**870,99**	

Item No	Analysis Name					UoM
35.140.3406	**3 x 50 + 25 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3406	3 x 50 + 25 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	830,98	830,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	830,98	102,00
				Material and Installation w/o Profit (TRY)	932,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**1.166,22**	

Item No	Analysis Name					UoM
35.140.3407	**3 x 70 + 35 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3407	3 x 70 + 35 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	1.189,55	1.189,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	1.189,55	116,50
				Material and Installation w/o Profit (TRY)	1.306,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**145,63**	
				Unit Price (TRY)	**1.632,56**	

Item No	Analysis Name					UoM
35.140.3408	**3 x 95 + 50 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3408	3 x 95 + 50 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	1.666,22	1.666,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	1.666,22	130,00
				Material and Installation w/o Profit (TRY)	1.796,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**162,50**	
				Unit Price (TRY)	**2.245,28**	

Item No	Analysis Name					UoM
35.140.3409	**3 x 120 + 70 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3409	3 x 120 + 70 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	2.134,38	2.134,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,33	250,00		82,50
10.100.1083	Master electrician’s helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	2.134,38	142,00
				Material and Installation w/o Profit (TRY)	2.276,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**177,50**	
				Unit Price (TRY)	**2.845,48**	

Item No	Analysis Name					UoM
35.140.3410	**3 x 120 + 70 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3410	3 x 120 + 70 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	2.513,17	2.513,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	2.513,17	150,50
				Material and Installation w/o Profit (TRY)	2.663,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**188,13**	
				Unit Price (TRY)	**3.329,59**	

Item No	Analysis Name					UoM
35.140.3411	**3 x 185 + 95 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3411	3 x 185 + 95 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	3.176,04	3.176,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	3.176,04	170,00
				Material and Installation w/o Profit (TRY)	3.346,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212,50**	
				Unit Price (TRY)	**4.182,55**	

Item No	Analysis Name					UoM
35.140.3412	**3 x 240 + 120 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3412	3 x 240 + 120 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	4.135,77	4.135,77	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician’s helper	h	0,22	185,00		40,70
				Total Excluding Profit (TRY)	4.135,77	184,50
				Material and Installation w/o Profit (TRY)	4.320,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**230,63**	
				Unit Price (TRY)	**5.400,34**	

Item No	Analysis Name					UoM
35.140.3430	**4 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3430	4 x 1.5 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	53,31	53,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	53,31	53,50
				Material and Installation w/o Profit (TRY)	106,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**133,51**	

Item No	Analysis Name					UoM
35.140.3431	**4 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3431	4 x 2.5 mm² / Installation of column and supply lines with Y2-type 1-kV TYVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	76,18	76,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	76,18	59,50
				Material and Installation w/o Profit (TRY)	135,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**169,60**	

Item No	Analysis Name					UoM
35.140.3432	**4 x 4 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3432	4 x 4 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	118,74	118,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			118,74	62,00
		Material and Installation w/o Profit (TRY)			180,74	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**77,50**	
		Unit Price (TRY)			**225,93**	

Item No	Analysis Name					UoM
35.140.3433	**4 x 6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3433	4 x 6 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	164,28	164,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			164,28	65,50
		Material and Installation w/o Profit (TRY)			229,78	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**81,88**	
		Unit Price (TRY)			**287,23**	

Item No	Analysis Name					UoM
35.140.3434	**4 x 10 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3434	4 x 10 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	267,49	267,49	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	267,49	74,00
				Material and Installation w/o Profit (TRY)	341,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**426,86**	

Item No	Analysis Name					UoM
35.140.3435	**4 x 16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVMY (NYCY) Y 2 / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3435	4 x 16 mm² / Installation of column and supply lines with Y2-type 1-kV YVMY (NYCY) underground cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	410,70	410,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	410,70	76,50
				Material and Installation w/o Profit (TRY)	487,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**609,00**	

Item No	Analysis Name					UoM
35.140.3501	**3 x 2.5 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3501	3 x 2.5 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	68,73	68,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	68,73	57,00
				Material and Installation w/o Profit (TRY)	125,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**157,16**	

Item No	Analysis Name					UoM
35.140.3502	**3 x 4 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3502	3 x 4 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	104,91	104,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	104,91	62,00
				Material and Installation w/o Profit (TRY)	166,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**208,64**	

Item No	Analysis Name					UoM
35.140.3503	**3 x 6 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3503	3 x 6 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	134,70	134,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	134,70	68,00
				Material and Installation w/o Profit (TRY)	202,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**253,38**	

Item No	Analysis Name					UoM
35.140.3504	**3 x 10 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3504	3 x 10 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	204,93	204,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	204,93	74,00
				Material and Installation w/o Profit (TRY)	278,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**348,66**	

Item No	Analysis Name					UoM
35.140.3530	**4 x 1.5 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3530	4 x 1.5 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	61,82	61,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	61,82	57,00
				Material and Installation w/o Profit (TRY)	118,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**148,52**	

Item No	Analysis Name					UoM
35.140.3531	**4 x 2.5 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3531	4 x 2.5 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	83,63	83,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	83,63	59,50
				Material and Installation w/o Profit (TRY)	143,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**178,91**	

Item No	Analysis Name					UoM
35.140.3532	**4 x 4 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3532	4 x 4 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	128,32	128,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	128,32	68,00
				Material and Installation w/o Profit (TRY)	196,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**245,40**	

Item No	Analysis Name					UoM
35.140.3533	**4 x 6 /6 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3533	4 x 6 / 6 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	166,41	166,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	166,41	68,00
				Material and Installation w/o Profit (TRY)	234,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**293,01**	

Item No	Analysis Name					UoM
35.140.3534	**4 x 10 /10 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3534	4 x 10 / 10 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	247,27	247,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	247,27	76,50
				Material and Installation w/o Profit (TRY)	323,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**404,71**	

Item No	Analysis Name					UoM
35.140.3535	**4 x 16 /16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3535	4 x 16 / 16 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	385,59	385,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	385,59	85,00
				Material and Installation w/o Profit (TRY)	470,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**588,24**	

Item No	Analysis Name					UoM
35.140.3606	**3 x 25 + 16/16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3606	3 x 25 + 16/16 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	505,40	505,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	505,40	93,50
				Material and Installation w/o Profit (TRY)	598,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**748,63**	

Item No	Analysis Name					UoM
35.140.3607	**3 x 35 + 16/16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3607	3 x 35 + 16/16 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	640,53	640,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	640,53	96,00
				Material and Installation w/o Profit (TRY)	736,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**120,00**	
				Unit Price (TRY)	**920,66**	

Item No	Analysis Name					UoM
35.140.3608	**3 x 50 + 25/16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3608	3 x 50 + 25/16 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	870,35	870,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,26	250,00		65,00
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
		Total Excluding Profit (TRY)			870,35	110,50
		Material and Installation w/o Profit (TRY)			980,85	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**138,13**	
		Unit Price (TRY)			**1.226,06**	

Item No	Analysis Name					UoM
35.140.3609	**3 x 70 + 35/16 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3609	3 x 70 + 35/16 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.232,11	1.232,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,29	250,00		72,50
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
		Total Excluding Profit (TRY)			1.232,11	121,50
		Material and Installation w/o Profit (TRY)			1.353,61	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**151,88**	
		Unit Price (TRY)			**1.692,01**	

Item No	Analysis Name					UoM
35.140.3610	**3 x 95 + 50/25 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3610	3 x 95 + 50/25 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	1.698,14	1.698,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,32	250,00		80,00
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
				Total Excluding Profit (TRY)	1.698,14	136,00
				Material and Installation w/o Profit (TRY)	1.834,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**170,00**	
				Unit Price (TRY)	**2.292,68**	

Item No	Analysis Name					UoM
35.140.3611	**3 x 120 + 70/35 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY) YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3611	3 x 120 + 70/35 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	2.166,30	2.166,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	2.166,30	150,50
				Material and Installation w/o Profit (TRY)	2.316,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**188,13**	
				Unit Price (TRY)	**2.896,00**	

Item No	Analysis Name					UoM
35.140.3612	**3 x 150 + 70/35 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY) YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3612	3 x 150 + 70/35 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	2.566,37	2.566,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician's helper	h	0,19	185,00		35,15
		Total Excluding Profit (TRY)			2.566,37	159,00
		Material and Installation w/o Profit (TRY)			2.725,37	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**198,75**	
		Unit Price (TRY)			**3.406,71**	

Item No	Analysis Name					UoM
35.140.3613	**3 x 185 + 95/50 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY) YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3613	3 x 185 + 95/50 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	3.229,24	3.229,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,41	250,00		102,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			3.229,24	172,50
		Material and Installation w/o Profit (TRY)			3.401,74	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**215,63**	
		Unit Price (TRY)			**4.252,17**	

Item No	Analysis Name					UoM
35.140.3614	**3 x 240 + 120/60 mm² / Installation of column and supply lines with 1-KV underground cables in compliance with TS 1178 IEC 60502, YVOV (NYRY): YVŞÇV (NYFGBY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.3614	3 x 240 +120/60 mm² / Installation of column and supply lines with 1-kV YVOV (NYRY): YVŞÇV (NYFGBY) underground cables / Main Line and Supply Lines (Market price)	m	1	4.242,17	4.242,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,45	250,00		112,50
10.100.1083	Master electrician's helper	h	0,22	185,00		40,70
				Total Excluding Profit (TRY)	4.242,17	189,50
				Material and Installation w/o Profit (TRY)	4.431,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**236,88**	
				Unit Price (TRY)	**5.539,59**	

Item No	Analysis Name					UoM
35.140.5101	**3 x 25 rm / 16 mm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5101	3 x 25 rm / 16 mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	71,00	71,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	71,00	79,00
				Material and Installation w/o Profit (TRY)	150,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**187,50**	

Item No	Analysis Name					UoM
35.140.5102	**3 x 35 srm / 16 mm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5102	3 x 35 srm / 16 mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	86,59	86,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	86,59	85,00
				Material and Installation w/o Profit (TRY)	171,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**214,49**	

Item No	Analysis Name					UoM
35.140.5103	**3 x 50 srm / 25 rm mm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5103	3 x 50 srm / 25 rm mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	114,14	114,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	114,14	93,50
				Material and Installation w/o Profit (TRY)	207,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**259,55**	

Item No	Analysis Name					UoM
35.140.5104	**3 x 70 srm / 35 srmmm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5104	3 x 70 srm / 35 srm mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	157,44	157,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	157,44	108,00
				Material and Installation w/o Profit (TRY)	265,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**135,00**	
				Unit Price (TRY)	**331,80**	

Item No	Analysis Name					UoM
35.140.5105	**3 x 95 srm / 50 srmmm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5105	3 x 95 srm / 50 srm mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	210,58	210,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	210,58	119,00
				Material and Installation w/o Profit (TRY)	329,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**148,75**	
				Unit Price (TRY)	**411,98**	

Item No	Analysis Name					UoM
35.140.5106	**3 x 120 srm / 70 srmmm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5106	3 x 120 srm / 70 srm mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	266,66	266,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
		Total Excluding Profit (TRY)			266,66	133,50
		Material and Installation w/o Profit (TRY)			400,16	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**166,88**	
		Unit Price (TRY)			**500,20**	

Item No	Analysis Name					UoM
35.140.5107	**3 x 150 srm / 70 srmmm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5107	3 x 150 srm / 70 srm mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	315,86	315,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,33	250,00		82,50
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
		Total Excluding Profit (TRY)			315,86	142,00
		Material and Installation w/o Profit (TRY)			457,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**177,50**	
		Unit Price (TRY)			**572,33**	

Item No	Analysis Name					UoM
35.140.5108	**3 x 185 srm / 95 srmmm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5108	3 x 185 srm / 95 srm mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	399,50	399,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
			Total Excluding Profit (TRY)		399,50	155,50
			Material and Installation w/o Profit (TRY)		555,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,38**	
				Unit Price (TRY)	**693,75**	

Item No	Analysis Name					UoM
35.140.5109	**3 x 240 srmrm / 120 srmmm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5109	3 x 240 srm / 120 srm mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	517,58	517,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
			Total Excluding Profit (TRY)		517,58	170,00
			Material and Installation w/o Profit (TRY)		687,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**212,50**	
				Unit Price (TRY)	**859,48**	

Item No	Analysis Name					UoM
35.140.5110	**4 x 16 mm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502, YAVV (NAYY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5110	4 x 16 mm² / Installation of column and supply lines with 1-KV underground cables with YAVV (NAYY) conductors / Main Line and Supply Lines (Market price)	m	1	50,60	50,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	50,60	82,50
				Material and Installation w/o Profit (TRY)	133,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**166,38**	

Item No	Analysis Name					UoM
35.140.5201	**3 x 16 x 16 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5201	3 x 16 x 16 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	55,10	55,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	55,10	79,00
				Material and Installation w/o Profit (TRY)	134,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**167,63**	

Item No	Analysis Name					UoM
35.140.5202	**3 x 25 rm/ 16 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5202	3 x 25 rm / 16 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	79,70	79,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	79,70	85,00
				Material and Installation w/o Profit (TRY)	164,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**205,88**	

Item No	Analysis Name					UoM
35.140.5203	**3 x 35 srm/ 16 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5203	3 x 35 srm / 16 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	99,38	99,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	99,38	93,50
				Material and Installation w/o Profit (TRY)	192,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**241,10**	

Item No	Analysis Name					UoM
35.140.5204	**3 x 50 srm/ 25 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5204	3 x 50 srm / 25 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	131,86	131,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	131,86	102,00
				Material and Installation w/o Profit (TRY)	233,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**292,33**	

Item No	Analysis Name					UoM
35.140.5205	**3 x 70 srm/ 35 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5205	3 x 70 srm / 35 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	176,14	176,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	176,14	116,50
				Material and Installation w/o Profit (TRY)	292,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**145,63**	
				Unit Price (TRY)	**365,80**	

Item No	Analysis Name					UoM
35.140.5206	**3 x 95 srm/ 50 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5206	3 x 95 srm / 50 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	231,24	231,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	231,24	127,50
				Material and Installation w/o Profit (TRY)	358,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**159,38**	
				Unit Price (TRY)	**448,43**	

Item No	Analysis Name					UoM
35.140.5207	**3 x 120 srm/ 70 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5207	3 x 120 srm / 70 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	297,17	297,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,32	250,00		80,00
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
				Total Excluding Profit (TRY)	297,17	136,00
				Material and Installation w/o Profit (TRY)	433,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**170,00**	
				Unit Price (TRY)	**541,46**	

Item No	Analysis Name					UoM
35.140.5208	**3 x 150 srm/ 70 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5208	3 x 150 srm / 70 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	346,37	346,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	346,37	150,50
				Material and Installation w/o Profit (TRY)	496,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**188,13**	
				Unit Price (TRY)	**621,09**	

Item No	Analysis Name					UoM
35.140.5209	**3 x 185 srm/ 95 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5209	3 x 185 srm / 95 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	438,86	438,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,38	250,00		95,00
10.100.1083	Master electrician's helper	h	0,19	185,00		35,15
				Total Excluding Profit (TRY)	438,86	161,50
				Material and Installation w/o Profit (TRY)	600,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**201,88**	
				Unit Price (TRY)	**750,45**	

Item No	Analysis Name					UoM
35.140.5210	**3 x 240 srm/ 120 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVMV (NAYCY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5210	3 x 240 srm / 120 mm² / Installation of column and supply lines with 1-KV YAVMV (NAYCY) underground cables / Main Line and Supply Lines (Market price)	m	1	554,98	554,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician's helper	h	0,22	185,00		40,70
				Total Excluding Profit (TRY)	554,98	184,50
				Material and Installation w/o Profit (TRY)	739,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**230,63**	
				Unit Price (TRY)	**924,35**	

Item No	Analysis Name					UoM
35.140.5301	**4 x 16 mm² / Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5301	4 x 16 mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	58,55	58,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	58,55	79,00
				Material and Installation w/o Profit (TRY)	137,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**171,94**	

Item No	Analysis Name					UoM
35.140.5302	**3 x 25 rm/ 16 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5302	3 x 25 rm / 16 mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	79,21	79,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
			Total Excluding Profit (TRY)		79,21	87,50
			Material and Installation w/o Profit (TRY)		166,71	
% 25 Contractor's Profit and Overheads Included			**Instal. Cost (TRY)**		**109,38**	
			Unit Price (TRY)		**208,39**	

Item No	Analysis Name					UoM
35.140.5303	**3 x 35 srm/ 16 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5303	3 x 35 srm / 16 mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	99,88	99,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
			Total Excluding Profit (TRY)		99,88	93,50
			Material and Installation w/o Profit (TRY)		193,38	
% 25 Contractor's Profit and Overheads Included			**Instal. Cost (TRY)**		**116,88**	
			Unit Price (TRY)		**241,72**	

Item No	Analysis Name					UoM
35.140.5304	**3 x 50 srm/ 25 mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5304	3 x 50 srm / 25 rm mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	124,97	124,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	124,97	104,50
				Material and Installation w/o Profit (TRY)	229,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**130,63**	
				Unit Price (TRY)	**286,84**	

Item No	Analysis Name					UoM
35.140.5305	**3 x 70 srm/ 35 rm mm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5305	3 x 70 srm / 35 srm mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	175,15	175,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	175,15	116,50
				Material and Installation w/o Profit (TRY)	291,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**145,63**	
				Unit Price (TRY)	**364,56**	

Item No	Analysis Name					UoM
35.140.5306	**3 x 95 srm/ 50 srmmm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5306	3 x 95 srm / 50 srm mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	231,24	231,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	231,24	127,50
				Material and Installation w/o Profit (TRY)	358,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**159,38**	
				Unit Price (TRY)	**448,43**	

Item No	Analysis Name					UoM
35.140.5307	**3 x 120 srm/ 70 srmmm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5307	3 x 120 srm / 70 srm mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	299,14	299,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,33	250,00		82,50
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
				Total Excluding Profit (TRY)	299,14	138,50
				Material and Installation w/o Profit (TRY)	437,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**173,13**	
				Unit Price (TRY)	**547,05**	

Item No	Analysis Name					UoM
35.140.5308	**3 x 150 srm/ 70 srmmm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5308	3 x 150 srm / 70 srm mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	343,42	343,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,36	250,00		90,00
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	343,42	153,00
				Material and Installation w/o Profit (TRY)	496,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**191,25**	
				Unit Price (TRY)	**620,52**	

Item No	Analysis Name					UoM
35.140.5309	**3 x 185 srm/ 95 srmmm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5309	3 x 185 srm / 95 srm mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	437,88	437,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,39	250,00		97,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	437,88	167,50
				Material and Installation w/o Profit (TRY)	605,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**209,38**	
				Unit Price (TRY)	**756,73**	

Item No	Analysis Name					UoM
35.140.5310	**3 x 240 srm/ 120 srmmm² /Installation of column and supply lines with 1-KV underground cables with aluminum conductor in compliance with TS 1178 IEC 60502. YAVŞV (NAYFY) / Main Line and Supply Lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.5310	3 x 240 srm / 120 srm mm² / Installation of column and supply lines with 1-KV, underground YAVŞV (NAYFY) cables with aluminum conductor / Main Line and Supply Lines (Market price)	m	1	553,99	553,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,21	165,00		34,65
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	553,99	181,00
				Material and Installation w/o Profit (TRY)	734,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**226,25**	
				Unit Price (TRY)	**918,74**	

Item No	Analysis Name					UoM
35.150.1103	**2 x 1 mm² P.14 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z,O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1461	1 x 1 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	4,70	9,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	17,58	76,05
				Material and Installation w/o Profit (TRY)	93,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,06**	
				Unit Price (TRY)	**117,04**	

Item No	Analysis Name					UoM
35.150.1104	**2 x 1.5 mm² P.14 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	6,97	13,94	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
		Total Excluding Profit (TRY)			22,12	76,05
		Material and Installation w/o Profit (TRY)			98,17	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**95,06**	
		Unit Price (TRY)			**122,71**	

Item No	Analysis Name					UoM
35.150.1105	**2 x 2.5 mm² P.14 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z,O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	11,13	22,26	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
		Total Excluding Profit (TRY)			30,44	80,20
		Material and Installation w/o Profit (TRY)			110,64	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**100,25**	
		Unit Price (TRY)			**138,30**	

Item No	Analysis Name					UoM
35.150.1106	**2 x 4 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1403	1 x 4 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	17,47	34,94	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	43,12	82,05
				Material and Installation w/o Profit (TRY)	125,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**102,56**	
				Unit Price (TRY)	**156,46**	

Item No	Analysis Name					UoM
35.150.1107	**2 x 6 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1404	1 x 6 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	25,58	51,16	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	59,34	84,55
				Material and Installation w/o Profit (TRY)	143,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**105,69**	
				Unit Price (TRY)	**179,86**	

Item No	Analysis Name					UoM
35.150.1108	**2 x 10 mm² P.26 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1405	1 x 10 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	44,30	88,60	
30.160.6202	25-32 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	16,72	16,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
		Total Excluding Profit (TRY)			105,32	105,05
		Material and Installation w/o Profit (TRY)			210,37	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**131,31**	
		Unit Price (TRY)			**262,96**	

Item No	Analysis Name					UoM
35.150.1109	**2 x 16 mm² P.26 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	69,78	139,56	
30.160.6202	25-32 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	16,72	16,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
		Total Excluding Profit (TRY)			156,28	109,40
		Material and Installation w/o Profit (TRY)			265,68	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**136,75**	
		Unit Price (TRY)			**332,10**	

Item No	Analysis Name					UoM
35.150.1110	**2 x 25 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	112,42	224,84	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
		Total Excluding Profit (TRY)			258,90	126,40
		Material and Installation w/o Profit (TRY)			385,30	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**158,00**	
		Unit Price (TRY)			**481,62**	

Item No	Analysis Name					UoM
35.150.1111	**2 x 35 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1408	1 x 35 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	151,94	303,88	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
		Total Excluding Profit (TRY)			337,94	126,40
		Material and Installation w/o Profit (TRY)			464,34	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**158,00**	
		Unit Price (TRY)			**580,43**	

Item No	Analysis Name					UoM
35.150.1112	**2 x 50 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1409	1 x 50 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	208,10	416,20	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,19	185,00		35,15
		Total Excluding Profit (TRY)			450,26	134,90
		Material and Installation w/o Profit (TRY)			585,16	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**168,63**	
		Unit Price (TRY)			**731,45**	

Item No	Analysis Name					UoM
35.150.1130	**3 x 1.5 mm² P.14 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	6,97	20,91	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
		Total Excluding Profit (TRY)			29,09	101,55
		Material and Installation w/o Profit (TRY)			130,64	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**126,94**	
		Unit Price (TRY)			**163,30**	

Item No	Analysis Name					UoM
35.150.1131	**3 x 2.5 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	11,13	33,39	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
			Total Excluding Profit (TRY)		41,57	107,55
			Material and Installation w/o Profit (TRY)		149,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**134,44**	
				Unit Price (TRY)	**186,40**	

Item No	Analysis Name					UoM
35.150.1132	**3 x 4 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1403	1 x 4 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	17,47	52,41	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
			Total Excluding Profit (TRY)		60,59	110,05
			Material and Installation w/o Profit (TRY)		170,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**137,56**	
				Unit Price (TRY)	**213,30**	

Item No	Analysis Name					UoM
35.150.1133	**3 x 6 mm² P.26 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1404	1 x 6 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	25,58	76,74	
30.160.6202	25-32 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	16,72	16,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
			Total Excluding Profit (TRY)		93,46	124,55
			Material and Installation w/o Profit (TRY)		218,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**155,69**	
				Unit Price (TRY)	**272,51**	

Item No	Analysis Name					UoM
35.150.1134	**3 x 10 mm² P.26 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1405	1 x 10 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	44,30	132,90	
30.160.6202	25-32 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	16,72	16,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician's helper	h	0,19	185,00		35,15
			Total Excluding Profit (TRY)		149,62	139,05
			Material and Installation w/o Profit (TRY)		288,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**173,81**	
				Unit Price (TRY)	**360,84**	

Item No	Analysis Name					UoM
35.150.1135	**3 x 16 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	69,78	209,34	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,34	250,00		85,00
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
		Total Excluding Profit (TRY)			243,40	151,90
		Material and Installation w/o Profit (TRY)			395,30	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**189,88**	
		Unit Price (TRY)			**494,13**	

Item No	Analysis Name					UoM
35.150.1136	**3 x 25 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	112,42	337,26	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician's helper	h	0,23	185,00		42,55
		Total Excluding Profit (TRY)			371,32	166,40
		Material and Installation w/o Profit (TRY)			537,72	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**208,00**	
		Unit Price (TRY)			**672,15**	

Item No	Analysis Name					UoM
35.150.1137	**3 x 35 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1408	1 x 35 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	151,94	455,82	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,39	250,00		97,50
10.100.1083	Master electrician's helper	h	0,23	185,00		42,55
		Total Excluding Profit (TRY)			489,88	171,40
		Material and Installation w/o Profit (TRY)			661,28	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**214,25**	
		Unit Price (TRY)			**826,60**	

Item No	Analysis Name					UoM
35.150.1138	**3 x 25 + 16 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	112,42	337,26	
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	69,78	69,78	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,23	165,00		37,95
10.100.1081	Master electrician	h	0,46	250,00		115,00
10.100.1083	Master electrician's helper	h	0,27	185,00		49,95
		Total Excluding Profit (TRY)			441,10	202,90
		Material and Installation w/o Profit (TRY)			644,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**253,63**	
		Unit Price (TRY)			**805,00**	

Item No	Analysis Name					UoM
35.150.1160	**4 x 1.5 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	6,97	27,88	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,29	250,00		72,50
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
		Total Excluding Profit (TRY)			36,06	127,05
		Material and Installation w/o Profit (TRY)			163,11	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**158,81**	
		Unit Price (TRY)			**203,89**	

Item No	Analysis Name					UoM
35.150.1161	**4 x 2.5 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	11,13	44,52	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
		Total Excluding Profit (TRY)			52,70	133,05
		Material and Installation w/o Profit (TRY)			185,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**166,31**	
		Unit Price (TRY)			**232,19**	

Item No	Analysis Name					UoM
35.150.1162	**4 x 4 mm² P.26 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1403	1 x 4 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	17,47	69,88	
30.160.6202	25-32 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	16,72	16,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,33	250,00		82,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			86,60	147,55
		Material and Installation w/o Profit (TRY)			234,15	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**184,44**	
		Unit Price (TRY)			**292,69**	

Item No	Analysis Name					UoM
35.150.1163	**4 x 6 mm² P.26 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1404	1 x 6 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	25,58	102,32	
30.160.6202	25-32 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	16,72	16,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
		Total Excluding Profit (TRY)			119,04	154,40
		Material and Installation w/o Profit (TRY)			273,44	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**193,00**	
		Unit Price (TRY)			**341,80**	

Item No	Analysis Name					UoM
35.150.1164	**4 x 10 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1405	1 x 10 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	44,30	177,20	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,24	185,00		44,40
		Total Excluding Profit (TRY)			211,26	177,40
		Material and Installation w/o Profit (TRY)			388,66	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**221,75**	
		Unit Price (TRY)			**485,82**	

Item No	Analysis Name					UoM
35.150.1165	**4 x 16 mm² P.37 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	69,78	279,12	
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,21	165,00		34,65
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			313,18	188,40
		Material and Installation w/o Profit (TRY)			501,58	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**235,50**	
		Unit Price (TRY)			**626,98**	

Item No	Analysis Name					UoM
35.150.1190	**5 x 1.5 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	5	6,97	34,85	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			43,03	152,55
		Material and Installation w/o Profit (TRY)			195,58	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**190,69**	
		Unit Price (TRY)			**244,48**	

Item No	Analysis Name					UoM
35.150.1191	**5 x 2.5 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	5	11,13	55,65	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
		Total Excluding Profit (TRY)			63,83	161,05
		Material and Installation w/o Profit (TRY)			224,88	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**201,31**	
		Unit Price (TRY)			**281,10**	

Item No	Analysis Name					UoM
35.150.1200	**6 x 1.5 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	6	6,97	41,82	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,41	250,00		102,50
10.100.1083	Master electrician's helper	h	0,23	185,00		42,55
		Total Excluding Profit (TRY)			50,00	178,05
		Material and Installation w/o Profit (TRY)			228,05	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**222,56**	
		Unit Price (TRY)			**285,06**	

Item No	Analysis Name					UoM
35.150.1201	**6 x 2.5 mm² P.18 / Installation of column and supply lines within peschel, bergman or PVC pipes with (HO7Z, O7Z1) conductors / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	6	11,13	66,78	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician's helper	h	0,24	185,00		44,40
		Total Excluding Profit (TRY)			74,96	188,20
		Material and Installation w/o Profit (TRY)			263,16	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**235,25**	
		Unit Price (TRY)			**328,95**	

Item No	Analysis Name					UoM
35.150.1301	**2 x 2.5 mm² (1/2) Ø15 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	11,13	22,26	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	55,00	55,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician’s helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	77,26	132,75
				Material and Installation w/o Profit (TRY)	210,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**165,94**	
				Unit Price (TRY)	**262,51**	

Item No	Analysis Name					UoM
35.150.1302	**2 x 4 mm² (5/8) Ø18 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1403	1 x 4 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	17,47	34,94	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	102,94	151,80
				Material and Installation w/o Profit (TRY)	254,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189,75**	
				Unit Price (TRY)	**318,43**	

Item No	Analysis Name					UoM
35.150.1303	**2 x 6 mm² (3/4) Ø20 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1404	1 x 6 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	25,58	51,16	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,32	250,00		80,00
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	119,16	154,30
				Material and Installation w/o Profit (TRY)	273,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**192,88**	
				Unit Price (TRY)	**341,83**	

Item No	Analysis Name					UoM
35.150.1304	**2 x 10 mm² (3/4) Ø20 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1405	1 x 10 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	44,30	88,60	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,34	250,00		85,00
10.100.1083	Master electrician’s helper	h	0,26	185,00		48,10
				Total Excluding Profit (TRY)	156,60	162,80
				Material and Installation w/o Profit (TRY)	319,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203,50**	
				Unit Price (TRY)	**399,25**	

Item No	Analysis Name					UoM
35.150.1305	**2 x 16 mm² (1) Ø25 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	69,78	139,56	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,19	165,00		31,35
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,32	185,00		59,20
				Total Excluding Profit (TRY)	244,56	190,55
				Material and Installation w/o Profit (TRY)	435,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**238,19**	
				Unit Price (TRY)	**543,89**	

Item No	Analysis Name					UoM
35.150.1306	**2 x 25 mm² (1¼) Ø32 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	112,42	224,84	
20.300.1404	1¼″ ----- 32 ----- 42.4/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	135,00	135,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,51	250,00		127,50
10.100.1083	Master electrician’s helper	h	0,42	185,00		77,70
				Total Excluding Profit (TRY)	359,84	254,70
				Material and Installation w/o Profit (TRY)	614,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**318,38**	
				Unit Price (TRY)	**768,17**	

Item No	Analysis Name					UoM
35.150.1307	**2 x 35 mm² (1¼) Ø32 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1408	1 x 35 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	151,94	303,88	
20.300.1404	1¼″ ----- 32 ----- 42.4/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	135,00	135,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,52	250,00		130,00
10.100.1083	Master electrician's helper	h	0,42	185,00		77,70
				Total Excluding Profit (TRY)	438,88	257,20
				Material and Installation w/o Profit (TRY)	696,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**321,50**	
				Unit Price (TRY)	**870,10**	

Item No	Analysis Name					UoM
35.150.1308	**2 x 50 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1409	1 x 50 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	208,10	416,20	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,31	165,00		51,15
10.100.1081	Master electrician	h	0,58	250,00		145,00
10.100.1083	Master electrician's helper	h	0,47	185,00		86,95
				Total Excluding Profit (TRY)	571,20	283,10
				Material and Installation w/o Profit (TRY)	854,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**353,88**	
				Unit Price (TRY)	**1.067,88**	

Item No	Analysis Name					UoM
35.150.1309	**2 x 70 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1410	1 x 70 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	2	296,95	593,90	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,32	165,00		52,80
10.100.1081	Master electrician	h	0,66	250,00		165,00
10.100.1083	Master electrician’s helper	h	0,53	185,00		98,05
				Total Excluding Profit (TRY)	814,90	315,85
				Material and Installation w/o Profit (TRY)	1.130,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**394,81**	
				Unit Price (TRY)	**1.413,44**	

Item No	Analysis Name					UoM
35.150.1330	**3 x 2.5 mm² (3/4) Ø20 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	11,13	33,39	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician’s helper	h	0,28	185,00		51,80
				Total Excluding Profit (TRY)	101,39	177,30
				Material and Installation w/o Profit (TRY)	278,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**221,63**	
				Unit Price (TRY)	**348,36**	

Item No	Analysis Name					UoM
35.150.1331	**3 x 4 mm² (3/4) Ø20 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1403	1 x 4 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	17,47	52,41	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,38	250,00		95,00
10.100.1083	Master electrician's helper	h	0,28	185,00		51,80
				Total Excluding Profit (TRY)	120,41	179,80
				Material and Installation w/o Profit (TRY)	300,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**224,75**	
				Unit Price (TRY)	**375,26**	

Item No	Analysis Name					UoM
35.150.1332	**3 x 6 mm² (1) Ø25 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1404	1 x 6 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	25,58	76,74	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,44	250,00		110,00
10.100.1083	Master electrician's helper	h	0,33	185,00		61,05
				Total Excluding Profit (TRY)	181,74	204,05
				Material and Installation w/o Profit (TRY)	385,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**255,06**	
				Unit Price (TRY)	**482,24**	

Item No	Analysis Name					UoM
35.150.1333	**3 x 10 mm² (1) Ø25 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1405	1 x 10 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	44,30	132,90	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,22	165,00		36,30
10.100.1081	Master electrician	h	0,47	250,00		117,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	237,90	218,55
				Material and Installation w/o Profit (TRY)	456,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**273,19**	
				Unit Price (TRY)	**570,56**	

Item No	Analysis Name					UoM
35.150.1334	**3 x 16 mm² (1¼) Ø32 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	69,78	209,34	
20.300.1404	1¼″ ----- 32 ----- 42.4/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	135,00	135,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,33	165,00		54,45
10.100.1081	Master electrician	h	0,58	250,00		145,00
10.100.1083	Master electrician’s helper	h	0,45	185,00		83,25
				Total Excluding Profit (TRY)	344,34	282,70
				Material and Installation w/o Profit (TRY)	627,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**353,38**	
				Unit Price (TRY)	**783,80**	

Item No	Analysis Name					UoM
35.150.1335	**3 x 25 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	112,42	337,26	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,35	165,00		57,75
10.100.1081	Master electrician	h	0,65	250,00		162,50
10.100.1083	Master electrician’s helper	h	0,51	185,00		94,35
				Total Excluding Profit (TRY)	492,26	314,60
				Material and Installation w/o Profit (TRY)	806,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**393,25**	
				Unit Price (TRY)	**1.008,58**	

Item No	Analysis Name					UoM
35.150.1336	**3 x 35 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1408	1 x 35 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	151,94	455,82	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,35	165,00		57,75
10.100.1081	Master electrician	h	0,66	250,00		165,00
10.100.1083	Master electrician’s helper	h	0,51	185,00		94,35
				Total Excluding Profit (TRY)	610,82	317,10
				Material and Installation w/o Profit (TRY)	927,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**396,38**	
				Unit Price (TRY)	**1.159,90**	

Item No	Analysis Name					UoM
35.150.1337	**3 x 50 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1409	1 x 50 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	208,10	624,30	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,37	165,00		61,05
10.100.1081	Master electrician	h	0,69	250,00		172,50
10.100.1083	Master electrician’s helper	h	0,53	185,00		98,05
				Total Excluding Profit (TRY)	779,30	331,60
				Material and Installation w/o Profit (TRY)	1.110,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**414,50**	
				Unit Price (TRY)	**1.388,63**	

Item No	Analysis Name					UoM
35.150.1338	**3 x 70 mm² (2) Ø50 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1410	1 x 70 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	296,95	890,85	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,39	165,00		64,35
10.100.1081	Master electrician	h	0,78	250,00		195,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	1.111,85	370,35
				Material and Installation w/o Profit (TRY)	1.482,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**462,94**	
				Unit Price (TRY)	**1.852,75**	

Item No	Analysis Name					UoM
35.150.1360	**3 x 25 + 16 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	112,42	337,26	
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	69,78	69,78	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,39	165,00		64,35
10.100.1081	Master electrician	h	0,74	250,00		185,00
10.100.1083	Master electrician’s helper	h	0,55	185,00		101,75
		Total Excluding Profit (TRY)			562,04	351,10
		Material and Installation w/o Profit (TRY)			913,14	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**438,88**	
		Unit Price (TRY)			**1.141,42**	

Item No	Analysis Name					UoM
35.150.1361	**3 x 35 + 16 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1408	1 x 35 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	151,94	455,82	
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	69,78	69,78	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,56	185,00		103,60
		Total Excluding Profit (TRY)			680,60	357,10
		Material and Installation w/o Profit (TRY)			1.037,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**446,38**	
		Unit Price (TRY)			**1.297,13**	

Item No	Analysis Name					UoM
35.150.1362	**3 x 50 + 25 mm² (2) Ø50 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1409	1 x 50 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	208,10	624,30	
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	112,42	112,42	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,41	165,00		67,65
10.100.1081	Master electrician	h	0,84	250,00		210,00
10.100.1083	Master electrician’s helper	h	0,62	185,00		114,70
		Total Excluding Profit (TRY)			957,72	392,35
		Material and Installation w/o Profit (TRY)			1.350,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**490,44**	
				Unit Price (TRY)	**1.687,59**	

Item No	Analysis Name					UoM
35.150.1363	**3 x 70 + 35 mm² (2) Ø50 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1410	1 x 70 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	3	296,95	890,85	
30.150.1408	1 x 35 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	151,94	151,94	
20.300.1406	2″ ----- 50 ----- 60.3/3.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	221,00	221,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,44	165,00		72,60
10.100.1081	Master electrician	h	0,88	250,00		220,00
10.100.1083	Master electrician’s helper	h	0,65	185,00		120,25
				Total Excluding Profit (TRY)	1.263,79	412,85
				Material and Installation w/o Profit (TRY)	1.676,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**516,06**	
				Unit Price (TRY)	**2.095,80**	

Item No	Analysis Name					UoM
35.150.1370	**4 x 2.5 mm² (3/4) Ø20 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	11,13	44,52	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	68,00	68,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,23	165,00		37,95
10.100.1081	Master electrician	h	0,43	250,00		107,50
10.100.1083	Master electrician’s helper	h	0,31	185,00		57,35
				Total Excluding Profit (TRY)	112,52	202,80
				Material and Installation w/o Profit (TRY)	315,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**253,50**	
				Unit Price (TRY)	**394,15**	

Item No	Analysis Name					UoM
35.150.1371	**4 x 4 mm² (1) Ø25 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1403	1 x 4 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	17,47	69,88	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,23	165,00		37,95
10.100.1081	Master electrician	h	0,49	250,00		122,50
10.100.1083	Master electrician’s helper	h	0,36	185,00		66,60
				Total Excluding Profit (TRY)	174,88	227,05
				Material and Installation w/o Profit (TRY)	401,93	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**283,81**	
				Unit Price (TRY)	**502,41**	

Item No	Analysis Name					UoM
35.150.1372	**4 x 6 mm² (1) Ø25 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1404	1 x 6 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	25,58	102,32	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,24	165,00		39,60
10.100.1081	Master electrician	h	0,51	250,00		127,50
10.100.1083	Master electrician’s helper	h	0,37	185,00		68,45
				Total Excluding Profit (TRY)	207,32	235,55
				Material and Installation w/o Profit (TRY)	442,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**294,44**	
				Unit Price (TRY)	**553,59**	

Item No	Analysis Name					UoM
35.150.1373	**4 x 10 mm² (1) Ø25 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1405	1 x 10 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	44,30	177,20	
20.300.1403	1″ ----- 25 ----- 33.7/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	105,00	105,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,26	165,00		42,90
10.100.1081	Master electrician	h	0,55	250,00		137,50
10.100.1083	Master electrician’s helper	h	0,39	185,00		72,15
				Total Excluding Profit (TRY)	282,20	252,55
				Material and Installation w/o Profit (TRY)	534,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**315,69**	
				Unit Price (TRY)	**668,44**	

Item No	Analysis Name					UoM
35.150.1374	**4 x 16 mm² (1½) Ø40 mm / Installation of a supply line using (HO7Z, O7Z1, minimum 300/500 V) conductors within galvanized or internally and externally coated, threaded steel pipes (TS-9). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	4	69,78	279,12	
20.300.1405	1½″ ----- 40 ----- 48.3/3.25 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	1	155,00	155,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,37	165,00		61,05
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,53	185,00		98,05
				Total Excluding Profit (TRY)	434,12	334,10
				Material and Installation w/o Profit (TRY)	768,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**417,63**	
				Unit Price (TRY)	**960,28**	

Item No	Analysis Name					UoM
35.150.1401	**1 x 1.5 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	6,97	6,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	6,97	25,50
				Material and Installation w/o Profit (TRY)	32,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**40,59**	

Item No	Analysis Name					UoM
35.150.1402	**1 x 2.5 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	11,13	11,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	11,13	25,50
				Material and Installation w/o Profit (TRY)	36,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**45,79**	

Item No	Analysis Name					UoM
35.150.1403	**1 x 4 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1403	1 x 4 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	17,47	17,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	17,47	28,00
				Material and Installation w/o Profit (TRY)	45,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**56,84**	

Item No	Analysis Name					UoM
35.150.1404	**1 x 6 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1404	1 x 6 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	25,58	25,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	25,58	28,00
				Material and Installation w/o Profit (TRY)	53,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**66,97**	

Item No	Analysis Name					UoM
35.150.1405	**1 x 10 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1405	1 x 10 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	44,30	44,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	44,30	34,00
				Material and Installation w/o Profit (TRY)	78,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**97,88**	

Item No	Analysis Name					UoM
35.150.1406	**1 x 16 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1406	1 x 16 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	69,78	69,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	69,78	36,50
				Material and Installation w/o Profit (TRY)	106,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**132,85**	

Item No	Analysis Name					UoM
35.150.1407	**1 x 25 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1407	1 x 25 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	112,42	112,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	112,42	42,50
				Material and Installation w/o Profit (TRY)	154,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**193,65**	

Item No	Analysis Name					UoM
35.150.1408	**1 x 35 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1408	1 x 35 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	151,94	151,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	151,94	42,50
				Material and Installation w/o Profit (TRY)	194,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**243,05**	

Item No	Analysis Name					UoM
35.150.1409	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1409	1 x 50 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	208,10	208,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	208,10	48,50
				Material and Installation w/o Profit (TRY)	256,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**320,75**	

Item No	Analysis Name					UoM
35.150.1410	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1410	1 x 70 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	296,95	296,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	296,95	51,00
				Material and Installation w/o Profit (TRY)	347,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**434,94**	

Item No	Analysis Name					UoM
35.150.1415	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1415	1 x 95 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	407,07	407,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	407,07	59,50
				Material and Installation w/o Profit (TRY)	466,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**583,21**	

Item No	Analysis Name					UoM
35.150.1420	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1420	1 x 120 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	517,19	517,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	517,19	65,50
				Material and Installation w/o Profit (TRY)	582,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**728,36**	

Item No	Analysis Name					UoM
35.150.1425	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1425	1 x 150 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	634,73	634,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	634,73	68,00
				Material and Installation w/o Profit (TRY)	702,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**878,41**	

Item No	Analysis Name					UoM
35.150.1430	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1430	1 x 185 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	796,82	796,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	796,82	74,00
				Material and Installation w/o Profit (TRY)	870,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**1.088,53**	

Item No	Analysis Name					UoM
35.150.1435	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1435	1 x 240 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	1.047,99	1.047,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	1.047,99	82,50
				Material and Installation w/o Profit (TRY)	1.130,49	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**1.413,11**	

Item No	Analysis Name					UoM
35.150.1461	**1 x 50 mm² section / Plastic-insulated conductor, (HO7Z, O7Z1, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1461	1 x 1 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	1	4,70	4,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	4,70	25,50
				Material and Installation w/o Profit (TRY)	30,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**37,75**	

Item No	Analysis Name					UoM
35.150.1501	**2 x 1.5 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1501	2 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	20,02	20,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	20,02	40,00
				Material and Installation w/o Profit (TRY)	60,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**75,02**	

Item No	Analysis Name					UoM
35.150.1502	**2 x 2.5 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1502	2 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	29,81	29,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	29,81	42,50
				Material and Installation w/o Profit (TRY)	72,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**90,39**	

Item No	Analysis Name					UoM
35.150.1503	**2 x 4 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1503	2 x 4 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	44,30	44,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	44,30	45,00
				Material and Installation w/o Profit (TRY)	89,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**111,63**	

Item No	Analysis Name					UoM
35.150.1504	**2 x 6 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1504	2 x 6 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	63,54	63,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	63,54	48,50
				Material and Installation w/o Profit (TRY)	112,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**140,05**	

Item No	Analysis Name					UoM
35.150.1505	**2 x 10 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1505	2 x 10 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	107,74	107,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	107,74	59,50
				Material and Installation w/o Profit (TRY)	167,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**209,05**	

Item No	Analysis Name					UoM
35.150.1506	**2 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1506	2 x 16 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	162,86	162,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	162,86	65,50
				Material and Installation w/o Profit (TRY)	228,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**285,45**	

Item No	Analysis Name					UoM
35.150.1530	**3 x 1.5 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	26,62	26,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	26,62	42,50
				Material and Installation w/o Profit (TRY)	69,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**86,40**	

Item No	Analysis Name					UoM
35.150.1531	**3 x 2.5 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1531	3 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	39,62	39,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,62	42,50
				Material and Installation w/o Profit (TRY)	82,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**102,65**	

Item No	Analysis Name					UoM
35.150.1532	**3 x 4 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1532	3 x 4 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	63,02	63,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	63,02	48,50
				Material and Installation w/o Profit (TRY)	111,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**139,40**	

Item No	Analysis Name					UoM
35.150.1533	**3 x 6 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1533	3 x 6 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	91,10	91,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	91,10	51,00
				Material and Installation w/o Profit (TRY)	142,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**177,63**	

Item No	Analysis Name					UoM
35.150.1534	**3 x 10 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1534	3 x 10 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	153,50	153,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	153,50	59,50
				Material and Installation w/o Profit (TRY)	213,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**266,25**	

Item No	Analysis Name					UoM
35.150.1535	**3 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1535	3 x 16 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	234,62	234,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	234,62	65,50
				Material and Installation w/o Profit (TRY)	300,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**375,15**	

Item No	Analysis Name					UoM
35.150.1560	**4 x 1.5 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1560	4 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	33,90	33,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	33,90	42,50
				Material and Installation w/o Profit (TRY)	76,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**95,50**	

Item No	Analysis Name					UoM
35.150.1561	**4 x 2.5 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1561	4 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	51,58	51,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	51,58	45,00
				Material and Installation w/o Profit (TRY)	96,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**120,72**	

Item No	Analysis Name					UoM
35.150.1562	**4 x 4 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1562	4 x 4 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	83,82	83,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	83,82	51,00
				Material and Installation w/o Profit (TRY)	134,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**168,52**	

Item No	Analysis Name					UoM
35.150.1563	**4 x 6 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1563	4 x 6 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	119,18	119,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	119,18	53,50
				Material and Installation w/o Profit (TRY)	172,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**215,85**	

Item No	Analysis Name					UoM
35.150.1564	**4 x 10 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1564	4 x 10 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	200,30	200,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	200,30	65,50
				Material and Installation w/o Profit (TRY)	265,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**332,25**	

Item No	Analysis Name					UoM
35.150.1565	**4 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1565	4 x 16 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	308,46	308,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	308,46	70,50
				Material and Installation w/o Profit (TRY)	378,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**473,70**	

Item No	Analysis Name					UoM
35.150.1580	**4 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1580	5 x 1.5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	41,45	41,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,45	42,50
				Material and Installation w/o Profit (TRY)	83,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**104,94**	

Item No	Analysis Name					UoM
35.150.1581	**4 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1581	5 x 2.5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	63,47	63,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	63,47	48,50
				Material and Installation w/o Profit (TRY)	111,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**139,96**	

Item No	Analysis Name					UoM
35.150.1582	**4 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1582	5 x 4 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	103,57	103,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	103,57	53,50
				Material and Installation w/o Profit (TRY)	157,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**196,34**	

Item No	Analysis Name					UoM
35.150.1583	**4 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1583	5 x 6 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	147,87	147,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	147,87	59,50
				Material and Installation w/o Profit (TRY)	207,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**259,21**	

Item No	Analysis Name					UoM
35.150.1584	**4 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1584	5 x 10 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	247,50	247,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	247,50	65,50
				Material and Installation w/o Profit (TRY)	313,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**391,25**	

Item No	Analysis Name					UoM
35.150.1585	**4 x 16 mm² / Installation of supply lines using lead-free, PVC-insulated cables (NHXMH, min. 300/500 V) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1585	5 x 16 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	1	376,26	376,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	376,26	76,50
				Material and Installation w/o Profit (TRY)	452,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**565,95**	

Item No	Analysis Name					UoM
35.150.2101	**1 x 6 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2101	1 x 6 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	37,87	37,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			37,87	36,50
		Material and Installation w/o Profit (TRY)			74,37	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**45,63**	
		Unit Price (TRY)			**92,96**	

Item No	Analysis Name					UoM
35.150.2102	**1 x 10 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2102	1 x 10 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	61,53	61,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			61,53	42,50
		Material and Installation w/o Profit (TRY)			104,03	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**53,13**	
		Unit Price (TRY)			**130,04**	

Item No	Analysis Name					UoM
35.150.2103	**1 x 16 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2103	1 x 16 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	81,65	81,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	81,65	42,50
				Material and Installation w/o Profit (TRY)	124,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**155,19**	

Item No	Analysis Name					UoM
35.150.2104	**1 x 25 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2104	1 x 25 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	124,53	124,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	124,53	45,00
				Material and Installation w/o Profit (TRY)	169,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**211,91**	

Item No	Analysis Name					UoM
35.150.2105	**1 x 35 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2105	1 x 35 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	162,43	162,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	162,43	48,50
				Material and Installation w/o Profit (TRY)	210,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**263,66**	

Item No	Analysis Name					UoM
35.150.2106	**1 x 50 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2106	1 x 50 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	218,59	218,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	218,59	51,00
				Material and Installation w/o Profit (TRY)	269,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**336,99**	

Item No	Analysis Name					UoM
35.150.2107	**1 x 70 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2107	1 x 70 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	308,23	308,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	308,23	57,00
				Material and Installation w/o Profit (TRY)	365,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**456,54**	

Item No	Analysis Name					UoM
35.150.2108	**1 x 95 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2108	1 x 95 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	421,63	421,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	421,63	59,50
				Material and Installation w/o Profit (TRY)	481,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**601,41**	

Item No	Analysis Name					UoM
35.150.2109	**1 x 120 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2109	1 x 120 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	535,03	535,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	535,03	68,00
				Material and Installation w/o Profit (TRY)	603,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**753,79**	

Item No	Analysis Name					UoM
35.150.2110	**1 x 150 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2110	1 x 150 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	654,91	654,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	654,91	70,50
				Material and Installation w/o Profit (TRY)	725,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**906,76**	

Item No	Analysis Name					UoM
35.150.2111	**1 x 185 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2111	1 x 185 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	814,75	814,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	814,75	76,50
				Material and Installation w/o Profit (TRY)	891,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**1.114,06**	

Item No	Analysis Name					UoM
35.150.2112	**1 x 240 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2112	1 x 240 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.083,67	1.083,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	1.083,67	85,00
				Material and Installation w/o Profit (TRY)	1.168,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**1.460,84**	

Item No	Analysis Name					UoM
35.150.2113	**1 x 240 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2113	1 x 300 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.350,14	1.350,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	1.350,14	93,50
				Material and Installation w/o Profit (TRY)	1.443,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**1.804,55**	

Item No	Analysis Name					UoM
35.150.2114	**1 x 240 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2114	1 x 400 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.753,07	1.753,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	1.753,07	102,00
				Material and Installation w/o Profit (TRY)	1.855,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**2.318,84**	

Item No	Analysis Name					UoM
35.150.2120	**2 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2120	2 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	23,00	23,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	23,00	42,50
				Material and Installation w/o Profit (TRY)	65,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**81,88**	

Item No	Analysis Name					UoM
35.150.2121	**2 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2121	2 x 2,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	32,18	32,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	32,18	42,50
				Material and Installation w/o Profit (TRY)	74,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**93,35**	

Item No	Analysis Name					UoM
35.150.2122	**2 x 4 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2122	2 x 4 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	47,84	47,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	47,84	45,00
				Material and Installation w/o Profit (TRY)	92,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**116,05**	

Item No	Analysis Name					UoM
35.150.2123	**2 x 6 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2123	2 x 6 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	65,45	65,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	65,45	51,00
				Material and Installation w/o Profit (TRY)	116,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**145,56**	

Item No	Analysis Name					UoM
35.150.2124	**2 x 10 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2124	2 x 10 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	110,27	110,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
			Total Excluding Profit (TRY)		110,27	57,00
			Material and Installation w/o Profit (TRY)		167,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**209,09**	

Item No	Analysis Name					UoM
35.150.2125	**2 x 16 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2125	2 x 16 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	165,35	165,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
			Total Excluding Profit (TRY)		165,35	59,50
			Material and Installation w/o Profit (TRY)		224,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**281,06**	

Item No	Analysis Name					UoM
35.150.2126	**2 x 25 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2126	2 x 25 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	259,31	259,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	259,31	68,00
				Material and Installation w/o Profit (TRY)	327,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**409,14**	

Item No	Analysis Name					UoM
35.150.2150	**3 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2150	3 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	30,89	30,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	30,89	42,50
				Material and Installation w/o Profit (TRY)	73,39	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**91,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.150.2151	**3 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2151	3 x 2,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	44,60	44,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	44,60	45,00
				Material and Installation w/o Profit (TRY)	89,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**112,00**	

Item No	Analysis Name					UoM
35.150.2152	**3 x 4 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2152	3 x 4 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	67,61	67,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	67,61	48,50
				Material and Installation w/o Profit (TRY)	116,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**145,14**	

Item No	Analysis Name					UoM
35.150.2153	**3 x 6 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2153	3 x 6 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	94,07	94,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	94,07	51,00
				Material and Installation w/o Profit (TRY)	145,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**181,34**	

Item No	Analysis Name					UoM
35.150.2154	**3 x 10 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2154	3 x 10 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	156,71	156,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	156,71	59,50
				Material and Installation w/o Profit (TRY)	216,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**270,26**	

Item No	Analysis Name					UoM
35.150.2155	**3 x 16 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2155	3 x 16 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	220,43	220,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	220,43	62,00
				Material and Installation w/o Profit (TRY)	282,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**353,04**	

Item No	Analysis Name					UoM
35.150.2156	**3 x 25 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2156	3 x 25 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	371,63	371,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	371,63	70,50
				Material and Installation w/o Profit (TRY)	442,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**552,66**	

Item No	Analysis Name					UoM
35.150.2170	**3 x 25 + 16 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2170	3 x 25+16 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	434,70	434,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	434,70	76,50
				Material and Installation w/o Profit (TRY)	511,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**639,00**	

Item No	Analysis Name					UoM
35.150.2171	**3 x 35 + 16 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2171	3 x 35+16 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	564,30	564,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	564,30	85,00
				Material and Installation w/o Profit (TRY)	649,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**811,63**	

Item No	Analysis Name					UoM
35.150.2172	**3 x 50 + 25 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2172	3 x 50+25 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	784,08	784,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	784,08	93,50
				Material and Installation w/o Profit (TRY)	877,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**1.096,98**	

Item No	Analysis Name					UoM
35.150.2173	**3 x 70 + 35 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2173	3 x 70+35 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.103,76	1.103,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	1.103,76	102,00
				Material and Installation w/o Profit (TRY)	1.205,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**1.507,20**	

Item No	Analysis Name					UoM
35.150.2174	**3 x 90 + 50 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2174	3 x 95+50 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.531,44	1.531,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	1.531,44	113,00
				Material and Installation w/o Profit (TRY)	1.644,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**141,25**	
				Unit Price (TRY)	**2.055,55**	

Item No	Analysis Name					UoM
35.150.2175	**3 x 120 + 70 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2175	3 x 120+70 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.989,36	1.989,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	1.989,36	127,50
				Material and Installation w/o Profit (TRY)	2.116,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**159,38**	
				Unit Price (TRY)	**2.646,07**	

Item No	Analysis Name					UoM
35.150.2176	**3 x 150 + 70 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2176	3 x 150+70 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	2.345,76	2.345,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
				Total Excluding Profit (TRY)	2.345,76	133,50
				Material and Installation w/o Profit (TRY)	2.479,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**166,88**	
				Unit Price (TRY)	**3.099,08**	

Item No	Analysis Name					UoM
35.150.2177	**3 x 185 + 95 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2177	3 x 185+95 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	2.972,16	2.972,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,34	250,00		85,00
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	2.972,16	144,50
				Material and Installation w/o Profit (TRY)	3.116,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**180,63**	
				Unit Price (TRY)	**3.895,82**	

Item No	Analysis Name					UoM
35.150.2178	**3 x 240 + 120 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2178	3 x 240+120 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	3.891,24	3.891,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,39	250,00		97,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	3.891,24	167,50
				Material and Installation w/o Profit (TRY)	4.058,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**209,38**	
				Unit Price (TRY)	**5.073,42**	

Item No	Analysis Name					UoM
35.150.2190	**4 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2190	4 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	37,91	37,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	37,91	45,00
				Material and Installation w/o Profit (TRY)	82,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**103,64**	

Item No	Analysis Name					UoM
35.150.2191	**4 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2191	4 x 2,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	56,27	56,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	56,27	48,50
				Material and Installation w/o Profit (TRY)	104,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**130,96**	

Item No	Analysis Name					UoM
35.150.2192	**4 x 4 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2192	4 x 4 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	86,51	86,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	86,51	51,00
				Material and Installation w/o Profit (TRY)	137,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**171,89**	

Item No	Analysis Name					UoM
35.150.2193	**4 x 6 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2193	4 x 6 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	121,61	121,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	121,61	53,50
				Material and Installation w/o Profit (TRY)	175,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**218,89**	

Item No	Analysis Name					UoM
35.150.2194	**4 x 10 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2194	4 x 10 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	198,29	198,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	198,29	62,00
				Material and Installation w/o Profit (TRY)	260,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**325,36**	

Item No	Analysis Name					UoM
35.150.2195	**4 x 16 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2195	4 x 16 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	304,99	304,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	304,99	68,00
				Material and Installation w/o Profit (TRY)	372,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**466,24**	

Item No	Analysis Name					UoM
35.150.2196	**4 x 25 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2196	4 x 25 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	488,16	488,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	488,16	76,50
				Material and Installation w/o Profit (TRY)	564,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**705,83**	

Item No	Analysis Name					UoM
35.150.2197	**4 x 35 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2197	4 x 35 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	660,96	660,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	660,96	85,00
				Material and Installation w/o Profit (TRY)	745,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**932,45**	

Item No	Analysis Name					UoM
35.150.2198	**4 x 50 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2198	4 x 50 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	895,32	895,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	895,32	93,50
				Material and Installation w/o Profit (TRY)	988,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**1.236,03**	

Item No	Analysis Name					UoM
35.150.2199	**4 x 70 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2199	4 x 70 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.296,00	1.296,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	1.296,00	104,50
				Material and Installation w/o Profit (TRY)	1.400,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**130,63**	
				Unit Price (TRY)	**1.750,63**	

Item No	Analysis Name					UoM
35.150.2200	**4 x 95 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2200	4 x 95 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	1.789,56	1.789,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	1.789,56	119,00
				Material and Installation w/o Profit (TRY)	1.908,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**148,75**	
				Unit Price (TRY)	**2.385,70**	

Item No	Analysis Name					UoM
35.150.2201	**4 x 120 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2201	4 x 120 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	2.253,96	2.253,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,31	250,00		77,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	2.253,96	130,00
				Material and Installation w/o Profit (TRY)	2.383,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**162,50**	
				Unit Price (TRY)	**2.979,95**	

Item No	Analysis Name					UoM
35.150.2202	**4 x 150 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2202	4 x 150 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	2.739,96	2.739,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,33	250,00		82,50
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	2.739,96	142,00
				Material and Installation w/o Profit (TRY)	2.881,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**177,50**	
				Unit Price (TRY)	**3.602,45**	

Item No	Analysis Name					UoM
35.150.2203	**4 x 185 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2203	4 x 185 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	3.446,28	3.446,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,36	250,00		90,00
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	3.446,28	153,00
				Material and Installation w/o Profit (TRY)	3.599,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**191,25**	
				Unit Price (TRY)	**4.499,10**	

Item No	Analysis Name					UoM
35.150.2204	**4 x 240 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2204	4 x 240 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	4.506,84	4.506,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,21	165,00		34,65
10.100.1081	Master electrician	h	0,42	250,00		105,00
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	4.506,84	178,50
				Material and Installation w/o Profit (TRY)	4.685,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**223,13**	
				Unit Price (TRY)	**5.856,68**	

Item No	Analysis Name					UoM
35.150.2210	**5 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2210	5 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	47,09	47,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	47,09	48,50
				Material and Installation w/o Profit (TRY)	95,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**119,49**	

Item No	Analysis Name					UoM
35.150.2211	**5 x 2.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2211	5 x 2,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	70,85	70,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	70,85	51,00
				Material and Installation w/o Profit (TRY)	121,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**152,31**	

Item No	Analysis Name					UoM
35.150.2212	**5 x 4 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2212	5 x 4 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	108,65	108,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	108,65	53,50
				Material and Installation w/o Profit (TRY)	162,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**202,69**	

Item No	Analysis Name					UoM
35.150.2213	**5 x 6 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2213	5 x 6 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	151,85	151,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	151,85	57,00
				Material and Installation w/o Profit (TRY)	208,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**261,06**	

Item No	Analysis Name					UoM
35.150.2214	**5 x 10 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2214	5 x 10 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	251,21	251,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	251,21	68,00
				Material and Installation w/o Profit (TRY)	319,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**399,01**	

Item No	Analysis Name					UoM
35.150.2240	**10 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2240	10 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	94,61	94,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	94,61	59,50
				Material and Installation w/o Profit (TRY)	154,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**192,64**	

Item No	Analysis Name					UoM
35.150.2241	**12 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2241	12 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	124,85	124,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	124,85	62,00
				Material and Installation w/o Profit (TRY)	186,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**233,56**	

Item No	Analysis Name					UoM
35.150.2242	**14 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2242	14 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	171,29	171,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	171,29	65,50
				Material and Installation w/o Profit (TRY)	236,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**295,99**	

Item No	Analysis Name					UoM
35.150.2243	**19 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2243	19 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	220,97	220,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	220,97	68,00
				Material and Installation w/o Profit (TRY)	288,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**361,21**	

Item No	Analysis Name					UoM
35.150.2244	**21 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2244	21 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	244,73	244,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	244,73	70,50
				Material and Installation w/o Profit (TRY)	315,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**394,04**	

Item No	Analysis Name					UoM
35.150.2245	**24 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2245	24 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	279,29	279,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	279,29	76,50
				Material and Installation w/o Profit (TRY)	355,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**444,74**	

Item No	Analysis Name					UoM
35.150.2246	**30 x 1.5 mm² / Installation of column and supply lines with 1-KV underground cables (N2XH, 0.6/1kV). / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.2246	30 x 1,5 mm² / Installation of column and supply lines with 1-KV N2XH underground cables / Halogen-Free Cables (Market price)	m	1	350,35	350,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	350,35	79,00
				Material and Installation w/o Profit (TRY)	429,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**536,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.150.3101	**1x4re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3101	1x4 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	37,54	37,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	37,54	36,50
				Material and Installation w/o Profit (TRY)	74,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**92,55**	

Item No	Analysis Name					UoM
35.150.3102	**1x6re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3102	1x6 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	42,22	42,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	42,22	40,00
				Material and Installation w/o Profit (TRY)	82,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**102,78**	

Item No	Analysis Name					UoM
35.150.3103	**1x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3103	1x10 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	54,70	54,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	54,70	42,50
				Material and Installation w/o Profit (TRY)	97,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**121,50**	

Item No	Analysis Name					UoM
35.150.3104	**1x16rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3104	1x16 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	83,82	83,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	83,82	42,50
				Material and Installation w/o Profit (TRY)	126,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**157,90**	

Item No	Analysis Name					UoM
35.150.3105	**1x25rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3105	1x25 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	123,34	123,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	123,34	48,50
				Material and Installation w/o Profit (TRY)	171,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**214,80**	

Item No	Analysis Name					UoM
35.150.3106	**1x35rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3106	1x35 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	168,06	168,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	168,06	51,00
				Material and Installation w/o Profit (TRY)	219,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**273,82**	

Item No	Analysis Name					UoM
35.150.3107	**1x50rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3107	1x50 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	227,34	227,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	227,34	53,50
				Material and Installation w/o Profit (TRY)	280,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**351,05**	

Item No	Analysis Name					UoM
35.150.3108	**1x70rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3108	1x70 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	318,86	318,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	318,86	59,50
				Material and Installation w/o Profit (TRY)	378,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**472,95**	

Item No	Analysis Name					UoM
35.150.3109	**1x95rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3109	1x95 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	430,14	430,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	430,14	65,50
				Material and Installation w/o Profit (TRY)	495,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**619,55**	

Item No	Analysis Name					UoM
35.150.3110	**1x120rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3110	1x120 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	549,74	549,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	549,74	68,00
				Material and Installation w/o Profit (TRY)	617,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**772,17**	

Item No	Analysis Name					UoM
35.150.3111	**1x150rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3111	1x150 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	672,46	672,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	672,46	74,00
				Material and Installation w/o Profit (TRY)	746,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**933,08**	

Item No	Analysis Name					UoM
35.150.3112	**1x185rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3112	1x185 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	837,82	837,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	837,82	79,00
				Material and Installation w/o Profit (TRY)	916,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**1.146,03**	

Item No	Analysis Name					UoM
35.150.3113	**1x240rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3113	1x240rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	1.101,98	1.101,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	1.101,98	85,00
				Material and Installation w/o Profit (TRY)	1.186,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**1.483,72**	

Item No	Analysis Name					UoM
35.150.3114	**1x240rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3114	1x300rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	1.366,44	1.366,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	1.366,44	93,50
				Material and Installation w/o Profit (TRY)	1.459,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**1.824,93**	

Item No	Analysis Name					UoM
35.150.3115	**1x240rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3115	1x400rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	1.782,30	1.782,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	1.782,30	104,50
				Material and Installation w/o Profit (TRY)	1.886,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**130,63**	
				Unit Price (TRY)	**2.358,50**	

Item No	Analysis Name					UoM
35.150.3120	**2x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3120	2x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	25,06	25,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	25,06	45,00
				Material and Installation w/o Profit (TRY)	70,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**87,58**	

Item No	Analysis Name					UoM
35.150.3121	**2x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3121	2x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	38,06	38,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	38,06	48,50
				Material and Installation w/o Profit (TRY)	86,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**108,20**	

Item No	Analysis Name					UoM
35.150.3122	**2x4re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3122	2x4 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	53,66	53,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	53,66	51,00
				Material and Installation w/o Profit (TRY)	104,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**130,82**	

Item No	Analysis Name					UoM
35.150.3123	**2x6re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3123	2x6 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	72,38	72,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	72,38	57,00
				Material and Installation w/o Profit (TRY)	129,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**161,72**	

Item No	Analysis Name					UoM
35.150.3124	**2x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3124	2x10 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	117,10	117,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	117,10	62,00
				Material and Installation w/o Profit (TRY)	179,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**223,88**	

Item No	Analysis Name					UoM
35.150.3125	**2x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3125	2x16 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	173,83	173,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	173,83	68,00
				Material and Installation w/o Profit (TRY)	241,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**302,29**	

Item No	Analysis Name					UoM
35.150.3126	**2x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3126	2x25 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	265,63	265,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	265,63	76,50
				Material and Installation w/o Profit (TRY)	342,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**427,66**	

Item No	Analysis Name					UoM
35.150.3127	**2x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3127	2x35 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	354,17	354,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	354,17	82,50
				Material and Installation w/o Profit (TRY)	436,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**545,84**	

Item No	Analysis Name					UoM
35.150.3128	**2x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3128	2x50 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	475,33	475,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	475,33	87,50
				Material and Installation w/o Profit (TRY)	562,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**109,38**	
				Unit Price (TRY)	**703,54**	

Item No	Analysis Name					UoM
35.150.3140	**3x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3140	3x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	36,50	36,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	36,50	48,50
				Material and Installation w/o Profit (TRY)	85,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**106,25**	

Item No	Analysis Name					UoM
35.150.3141	**3x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3141	3x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	51,06	51,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	51,06	51,00
				Material and Installation w/o Profit (TRY)	102,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**127,58**	

Item No	Analysis Name					UoM
35.150.3142	**3x4re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3142	3x4 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	74,46	74,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	74,46	53,50
				Material and Installation w/o Profit (TRY)	127,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**159,95**	

Item No	Analysis Name					UoM
35.150.3143	**3x6re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3143	3x6 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	105,66	105,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	105,66	59,50
				Material and Installation w/o Profit (TRY)	165,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**206,45**	

Item No	Analysis Name					UoM
35.150.3144	**3x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3144	3x10 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	168,06	168,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	168,06	65,50
				Material and Installation w/o Profit (TRY)	233,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**291,95**	

Item No	Analysis Name					UoM
35.150.3145	**3x16rm/10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3145	3x16 rm/10 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	299,00	299,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	299,00	76,50
				Material and Installation w/o Profit (TRY)	375,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**469,38**	

Item No	Analysis Name					UoM
35.150.3146	**3x25rm/16rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3146	3x25 rm/16 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	457,08	457,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	457,08	82,50
				Material and Installation w/o Profit (TRY)	539,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**674,47**	

Item No	Analysis Name					UoM
35.150.3147	**3x35rm/16rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3147	3x35 rm/16 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	593,32	593,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	593,32	85,00
				Material and Installation w/o Profit (TRY)	678,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**847,90**	

Item No	Analysis Name					UoM
35.150.3148	**3x50rm/25rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3148	3x50 rm/25 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	816,40	816,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	816,40	93,50
				Material and Installation w/o Profit (TRY)	909,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**1.137,38**	

Item No	Analysis Name					UoM
35.150.3149	**3x70rm/35rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3149	3x70 rm/35 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	1.153,36	1.153,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	1.153,36	102,00
				Material and Installation w/o Profit (TRY)	1.255,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**1.569,20**	

Item No	Analysis Name					UoM
35.150.3150	**3x95rm/50rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3150	3x95 rm/50 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	1.586,00	1.586,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,27	250,00		67,50
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	1.586,00	116,50
				Material and Installation w/o Profit (TRY)	1.702,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**145,63**	
				Unit Price (TRY)	**2.128,13**	

Item No	Analysis Name					UoM
35.150.3151	**3x120rm/70rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3151	3x120 rm/70 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	2.055,04	2.055,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	2.055,04	127,50
				Material and Installation w/o Profit (TRY)	2.182,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**159,38**	
				Unit Price (TRY)	**2.728,18**	

Item No	Analysis Name					UoM
35.150.3152	**3x150rm/70rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3152	3x150 rm/70 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	2.439,84	2.439,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,32	250,00		80,00
10.100.1083	Master electrician's helper	h	0,16	185,00		29,60
				Total Excluding Profit (TRY)	2.439,84	136,00
				Material and Installation w/o Profit (TRY)	2.575,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**170,00**	
				Unit Price (TRY)	**3.219,80**	

Item No	Analysis Name					UoM
35.150.3153	**3x185rm/95rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3153	3x185 rm/95 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	3.057,60	3.057,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	3.057,60	147,00
				Material and Installation w/o Profit (TRY)	3.204,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**183,75**	
				Unit Price (TRY)	**4.005,75**	

Item No	Analysis Name					UoM
35.150.3154	**3x240rm/120rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3154	3x240rm/120 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	3.995,68	3.995,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,39	250,00		97,50
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	3.995,68	167,50
				Material and Installation w/o Profit (TRY)	4.163,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**209,38**	
				Unit Price (TRY)	**5.203,98**	

Item No	Analysis Name					UoM
35.150.3160	**4x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3160	4x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	45,34	45,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	45,34	51,00
				Material and Installation w/o Profit (TRY)	96,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**120,43**	

Item No	Analysis Name					UoM
35.150.3161	**4x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3161	4x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	65,10	65,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	65,10	51,00
				Material and Installation w/o Profit (TRY)	116,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**145,13**	

Item No	Analysis Name					UoM
35.150.3162	**4x4re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3162	4x4 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	95,26	95,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	95,26	59,50
				Material and Installation w/o Profit (TRY)	154,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**193,45**	

Item No	Analysis Name					UoM
35.150.3163	**4x6re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3163	4x6 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	132,18	132,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	132,18	59,50
				Material and Installation w/o Profit (TRY)	191,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**239,60**	

Item No	Analysis Name					UoM
35.150.3164	**4x10rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3164	4x10 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	215,38	215,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	215,38	68,00
				Material and Installation w/o Profit (TRY)	283,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**354,23**	

Item No	Analysis Name					UoM
35.150.3165	**4x16rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3165	4x16 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	323,54	323,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	323,54	76,50
				Material and Installation w/o Profit (TRY)	400,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**500,05**	

Item No	Analysis Name					UoM
35.150.3166	**4x25rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3166	4x25 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	515,84	515,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	515,84	85,00
				Material and Installation w/o Profit (TRY)	600,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**751,05**	

Item No	Analysis Name					UoM
35.150.3167	**4x35rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3167	4x35 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	689,00	689,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	689,00	91,00
				Material and Installation w/o Profit (TRY)	780,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**113,75**	
				Unit Price (TRY)	**975,00**	

Item No	Analysis Name					UoM
35.150.3168	**4x50rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3168	4x50 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	931,84	931,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	931,84	96,00
				Material and Installation w/o Profit (TRY)	1.027,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**120,00**	
				Unit Price (TRY)	**1.284,80**	

Item No	Analysis Name					UoM
35.150.3169	**4x70rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3169	4x70 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	1.330,16	1.330,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,26	250,00		65,00
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	1.330,16	110,50
				Material and Installation w/o Profit (TRY)	1.440,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**138,13**	
				Unit Price (TRY)	**1.800,83**	

Item No	Analysis Name					UoM
35.150.3170	**4x95rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3170	4x95 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	1.846,00	1.846,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,14	165,00		23,10
10.100.1081	Master electrician	h	0,28	250,00		70,00
10.100.1083	Master electrician's helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	1.846,00	119,00
				Material and Installation w/o Profit (TRY)	1.965,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**148,75**	
				Unit Price (TRY)	**2.456,25**	

Item No	Analysis Name					UoM
35.150.3171	**4x120rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3171	4x120 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	2.311,92	2.311,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,16	165,00		26,40
10.100.1081	Master electrician	h	0,32	250,00		80,00
10.100.1083	Master electrician’s helper	h	0,16	185,00		29,60
				Total Excluding Profit (TRY)	2.311,92	136,00
				Material and Installation w/o Profit (TRY)	2.447,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**170,00**	
				Unit Price (TRY)	**3.059,90**	

Item No	Analysis Name					UoM
35.150.3172	**4x150rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3172	4x150 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	2.831,92	2.831,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,17	165,00		28,05
10.100.1081	Master electrician	h	0,34	250,00		85,00
10.100.1083	Master electrician’s helper	h	0,17	185,00		31,45
				Total Excluding Profit (TRY)	2.831,92	144,50
				Material and Installation w/o Profit (TRY)	2.976,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**180,63**	
				Unit Price (TRY)	**3.720,53**	

Item No	Analysis Name					UoM
35.150.3173	**4x185rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3173	4x185 rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	3.533,92	3.533,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,18	165,00		29,70
10.100.1081	Master electrician	h	0,37	250,00		92,50
10.100.1083	Master electrician's helper	h	0,18	185,00		33,30
				Total Excluding Profit (TRY)	3.533,92	155,50
				Material and Installation w/o Profit (TRY)	3.689,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,38**	
				Unit Price (TRY)	**4.611,77**	

Item No	Analysis Name					UoM
35.150.3174	**4x240rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3174	4x240rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	4.636,32	4.636,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,21	165,00		34,65
10.100.1081	Master electrician	h	0,42	250,00		105,00
10.100.1083	Master electrician's helper	h	0,21	185,00		38,85
				Total Excluding Profit (TRY)	4.636,32	178,50
				Material and Installation w/o Profit (TRY)	4.814,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**223,13**	
				Unit Price (TRY)	**6.018,52**	

Item No	Analysis Name					UoM
35.150.3175	**4x240rm / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3175	4x300rm / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	5.761,62	5.761,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,23	165,00		37,95
10.100.1081	Master electrician	h	0,47	250,00		117,50
10.100.1083	Master electrician's helper	h	0,23	185,00		42,55
				Total Excluding Profit (TRY)	5.761,62	198,00
				Material and Installation w/o Profit (TRY)	5.959,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**247,50**	
				Unit Price (TRY)	**7.449,52**	

Item No	Analysis Name					UoM
35.150.3180	**5x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3180	5x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	59,38	59,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	59,38	51,00
				Material and Installation w/o Profit (TRY)	110,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**137,97**	

Item No	Analysis Name					UoM
35.150.3181	**5x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3181	5x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	83,30	83,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	83,30	57,00
				Material and Installation w/o Profit (TRY)	140,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**175,38**	

Item No	Analysis Name					UoM
35.150.3182	**7x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3182	7x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	79,14	79,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	79,14	57,00
				Material and Installation w/o Profit (TRY)	136,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**170,17**	

Item No	Analysis Name					UoM
35.150.3183	**7x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3183	7x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	112,42	112,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	112,42	59,50
				Material and Installation w/o Profit (TRY)	171,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**214,90**	

Item No	Analysis Name					UoM
35.150.3184	**10x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3184	10x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	115,54	115,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	115,54	68,00
				Material and Installation w/o Profit (TRY)	183,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**229,43**	

Item No	Analysis Name					UoM
35.150.3185	**10x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3185	10x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	163,38	163,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	163,38	70,50
				Material and Installation w/o Profit (TRY)	233,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**292,35**	

Item No	Analysis Name					UoM
35.150.3186	**12x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3186	12x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	123,86	123,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	123,86	68,00
				Material and Installation w/o Profit (TRY)	191,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**239,83**	

Item No	Analysis Name					UoM
35.150.3187	**12x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3187	12x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	191,46	191,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	191,46	70,50
				Material and Installation w/o Profit (TRY)	261,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**327,45**	

Item No	Analysis Name					UoM
35.150.3188	**19x1.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3188	19x1.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	199,16	199,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	199,16	76,50
				Material and Installation w/o Profit (TRY)	275,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**344,57**	

Item No	Analysis Name					UoM
35.150.3189	**19x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3189	19x2.5 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	295,88	295,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	295,88	82,50
				Material and Installation w/o Profit (TRY)	378,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**472,98**	

Item No	Analysis Name					UoM
35.150.3190	**19x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3190	5x4 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	121,74	121,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	121,74	62,00
				Material and Installation w/o Profit (TRY)	183,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**229,68**	

Item No	Analysis Name					UoM
35.150.3191	**19x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3191	5x6 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	168,54	168,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	168,54	68,00
				Material and Installation w/o Profit (TRY)	236,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**295,68**	

Item No	Analysis Name					UoM
35.150.3192	**19x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3192	5x10re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	266,77	266,77	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	266,77	76,50
				Material and Installation w/o Profit (TRY)	343,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**429,09**	

Item No	Analysis Name					UoM
35.150.3193	**19x2.5re / N2XHFE 180 0.6/1kV fireproof cables (Cable Price) / Flame-retardant, halogen-free cables for main line and supply lines**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3193	5x16 re / N2XH FE 180 type 0.6/1kV fire-resistant cable / Halogen-Free Cables (Market price)	m	1	405,65	405,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	405,65	82,50
				Material and Installation w/o Profit (TRY)	488,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**610,19**	

Item No	Analysis Name					UoM
35.150.3201	**1 x 1.5 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3201	1x1.5 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	11,42	11,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	11,42	25,50
				Material and Installation w/o Profit (TRY)	36,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**46,15**	

Item No	Analysis Name					UoM
35.150.3202	**1 x 2.5 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3202	1 x 2.5 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	17,70	17,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	17,70	25,50
				Material and Installation w/o Profit (TRY)	43,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**54,00**	

Item No	Analysis Name					UoM
35.150.3203	**1 x 4 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3203	1 x 4 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	26,99	26,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	26,99	28,00
				Material and Installation w/o Profit (TRY)	54,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**68,74**	

Item No	Analysis Name					UoM
35.150.3204	**1 x 6 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3204	1 x 6 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	37,41	37,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	37,41	31,50
				Material and Installation w/o Profit (TRY)	68,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**86,14**	

Item No	Analysis Name					UoM
35.150.3205	**1 x 10 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3205	1 x 10 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	73,81	73,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	73,81	34,00
				Material and Installation w/o Profit (TRY)	107,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**134,76**	

Item No	Analysis Name					UoM
35.150.3206	**1 x 16 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3206	1 x 16 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	115,25	115,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	115,25	40,00
				Material and Installation w/o Profit (TRY)	155,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**194,06**	

Item No	Analysis Name					UoM
35.150.3207	**1 x 25 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3207	1 x 25 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	176,85	176,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	176,85	42,50
				Material and Installation w/o Profit (TRY)	219,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**274,19**	

Item No	Analysis Name					UoM
35.150.3208	**1 x 35 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3208	1 x 35 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	231,73	231,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	231,73	45,00
				Material and Installation w/o Profit (TRY)	276,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**345,91**	

Item No	Analysis Name					UoM
35.150.3209	**1 x 50 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3209	1 x 50 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	351,57	351,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	351,57	51,00
				Material and Installation w/o Profit (TRY)	402,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**503,21**	

Item No	Analysis Name					UoM
35.150.3210	**1 x 70 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3210	1 x 70 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	497,17	497,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	497,17	57,00
				Material and Installation w/o Profit (TRY)	554,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**692,71**	

Item No	Analysis Name					UoM
35.150.3211	**1 x 95 mm² / Silicon Cables Resistant to Extreme Heat / Silicon Cables Resistant to Extreme Heat**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.3211	1 x 95 mm² / Silicon-insulated Cables Resistant to Extreme Heat (Market price)	m	1	706,61	706,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	706,61	62,00
				Material and Installation w/o Profit (TRY)	768,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**960,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1101	**Single-switch outlet branch / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	11,13	111,30	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	6,66	66,60	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,17	165,00		193,05
10.100.1081	Master electrician	h	2,29	250,00		572,50
10.100.1083	Master electrician’s helper	h	1,67	185,00		308,95
		Total Excluding Profit (TRY)			323,48	1.074,50
		Material and Installation w/o Profit (TRY)			1.397,98	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.343,13**	
		Unit Price (TRY)			**1.747,47**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1102	**Commutator outlet line / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	11,13	111,30	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	20	6,66	133,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	12,5	8,01	100,13	
30.185.1102	Flush-mounted commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	44,39	44,39	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,53	165,00		252,45
10.100.1081	Master electrician	h	3,12	250,00		780,00
10.100.1083	Master electrician’s helper	h	2,2	185,00		407,00
		Total Excluding Profit (TRY)			409,03	1.439,45
		Material and Installation w/o Profit (TRY)			1.848,48	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.799,31**	
		Unit Price (TRY)			**2.310,60**	

Item No	Analysis Name					UoM
35.160.1103	**Two-way outlet branch / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	11,13	111,30	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	20	6,66	133,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	12,5	8,01	100,13	
30.185.1103	Flush-mounted two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	43,85	87,70	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,68	165,00		277,20
10.100.1081	Master electrician	h	3,47	250,00		867,50
10.100.1083	Master electrician's helper	h	2,55	185,00		471,75
				Total Excluding Profit (TRY)	452,34	1.616,45
				Material and Installation w/o Profit (TRY)	2.068,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.020,56**	
				Unit Price (TRY)	**2.585,99**	

Item No	Analysis Name					UoM
35.160.1104	**Parallel outlet / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	6,66	66,60	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,58	165,00		95,70
10.100.1081	Master electrician	h	1,15	250,00		287,50
10.100.1083	Master electrician's helper	h	0,85	185,00		157,25
				Total Excluding Profit (TRY)	126,66	540,45
				Material and Installation w/o Profit (TRY)	667,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**675,56**	
				Unit Price (TRY)	**833,89**	

Item No	Analysis Name					UoM
35.160.1105	**Chandelier outlet. / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	11,13	111,30	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	6,66	99,90	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,32	165,00		217,80
10.100.1081	Master electrician	h	2,69	250,00		672,50
10.100.1083	Master electrician’s helper	h	1,92	185,00		355,20
		Total Excluding Profit (TRY)			356,78	1.245,50
		Material and Installation w/o Profit (TRY)			1.602,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.556,88**	
		Unit Price (TRY)			**2.002,85**	

Item No	Analysis Name					UoM
35.160.1106	**Parallel chandelier outlet / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	6,66	99,90	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,73	165,00		120,45
10.100.1081	Master electrician	h	1,45	250,00		362,50
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			159,96	667,95
		Material and Installation w/o Profit (TRY)			827,91	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**834,94**	
		Unit Price (TRY)			**1.034,89**	

Item No	Analysis Name					UoM
35.160.1107	**3-phase outlet. / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	20	11,13	222,60	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	20	6,66	133,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,48	165,00		244,20
10.100.1081	Master electrician	h	3,52	250,00		880,00
10.100.1083	Master electrician's helper	h	1,98	185,00		366,30
				Total Excluding Profit (TRY)	501,38	1.490,50
				Material and Installation w/o Profit (TRY)	1.991,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.863,13**	
				Unit Price (TRY)	**2.489,85**	

Item No	Analysis Name					UoM
35.160.1108	**3-phase parallel outlet. / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	20	6,66	133,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,73	165,00		120,45
10.100.1081	Master electrician	h	1,45	250,00		362,50
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	193,26	667,95
				Material and Installation w/o Profit (TRY)	861,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**834,94**	
				Unit Price (TRY)	**1.076,51**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1151	**Single switch outlet branch for the security line. / Security line light outlets (The security line shall be plastic-insulated) / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	6,66	99,90	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,48	165,00		244,20
10.100.1081	Master electrician	h	2,91	250,00		727,50
10.100.1083	Master electrician’s helper	h	1,98	185,00		366,30
		Total Excluding Profit (TRY)			412,43	1.338,00
		Material and Installation w/o Profit (TRY)			1.750,43	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.672,50**	
		Unit Price (TRY)			**2.188,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1152	**Dual switch outlet branch for the security line. / Security line light outlets: The security line shall be plastic-insulated / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	30	6,66	199,80	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	12,5	8,01	100,13	
30.185.1102	Flush-mounted commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	44,39	44,39	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,99	165,00		328,35
10.100.1081	Master electrician	h	4,04	250,00		1.010,00
10.100.1083	Master electrician’s helper	h	2,66	185,00		492,10
				Total Excluding Profit (TRY)	531,28	1.830,45
				Material and Installation w/o Profit (TRY)	2.361,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.288,06**	
				Unit Price (TRY)	**2.952,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1153	**Two-way switch outlet branch for the security line. / Security line light outlets: The security line shall be plastic-insulated / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	30	6,66	199,80	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	12,5	8,01	100,13	
30.185.1103	Flush-mounted two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	43,85	87,70	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,99	165,00		328,35
10.100.1081	Master electrician	h	4,39	250,00		1.097,50
10.100.1083	Master electrician’s helper	h	2,66	185,00		492,10
				Total Excluding Profit (TRY)	574,59	1.917,95
				Material and Installation w/o Profit (TRY)	2.492,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.397,44**	
				Unit Price (TRY)	**3.115,68**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1154	**Parallel outlet branch for the security line. / Security line light outlets: The security line shall be plastic-insulated / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	6,66	99,90	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,73	165,00		120,45
10.100.1081	Master electrician	h	1,45	250,00		362,50
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	159,96	667,95
				Material and Installation w/o Profit (TRY)	827,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**834,94**	
				Unit Price (TRY)	**1.034,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1155	**Chandelier outlet branch for the security line. / Security line light outlets: The security line shall be plastic-insulated / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	20	6,66	133,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,93	165,00		318,45
10.100.1081	Master electrician	h	3,91	250,00		977,50
10.100.1083	Master electrician’s helper	h	2,53	185,00		468,05
				Total Excluding Profit (TRY)	445,73	1.764,00
				Material and Installation w/o Profit (TRY)	2.209,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.205,00**	
				Unit Price (TRY)	**2.762,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1156	**Parallel chandelier outlet branch for the security line. / Security line light outlets: The security line shall be plastic-insulated / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	20	6,66	133,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,95	165,00		156,75
10.100.1081	Master electrician	h	1,91	250,00		477,50
10.100.1083	Master electrician’s helper	h	1,23	185,00		227,55
				Total Excluding Profit (TRY)	193,26	861,80
				Material and Installation w/o Profit (TRY)	1.055,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.077,25**	
				Unit Price (TRY)	**1.318,82**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1157	**3-phase outlet branch for the security line. / Security line light outlets: The security line shall be plastic-insulated / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	25	11,13	278,25	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	25	6,66	166,50	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,79	165,00		295,35
10.100.1081	Master electrician	h	3,52	250,00		880,00
10.100.1083	Master electrician’s helper	h	2,29	185,00		423,65
				Total Excluding Profit (TRY)	590,33	1.599,00
				Material and Installation w/o Profit (TRY)	2.189,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.998,75**	
				Unit Price (TRY)	**2.736,66**	

Item No	Analysis Name					UoM
35.160.1158	**3-phase parallel outlet branch for the security line. / Security line light outlets: The security line shall be plastic-insulated / Lighting Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	25	6,66	166,50	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,88	165,00		145,20
10.100.1081	Master electrician	h	1,76	250,00		440,00
10.100.1083	Master electrician’s helper	h	1,15	185,00		212,75
				Total Excluding Profit (TRY)	226,56	797,95
				Material and Installation w/o Profit (TRY)	1.024,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**997,44**	
				Unit Price (TRY)	**1.280,64**	

Item No	Analysis Name					UoM
35.160.1180	**Impulse current switch controlled outlet (with materials certified for compliance with TS and CE)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	11,13	111,30	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	10	6,66	66,60	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,02	165,00		168,30
10.100.1081	Master electrician	h	2,04	250,00		510,00
10.100.1083	Master electrician’s helper	h	1,42	185,00		262,70
				Total Excluding Profit (TRY)	278,01	941,00
				Material and Installation w/o Profit (TRY)	1.219,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.176,25**	
				Unit Price (TRY)	**1.523,76**	

Item No	Analysis Name					UoM
35.160.1211	**Single switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	6,66	99,90	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,85	165,00		305,25
10.100.1081	Master electrician	h	3,41	250,00		852,50
10.100.1083	Master electrician’s helper	h	2,48	185,00		458,80
		Total Excluding Profit (TRY)			709,69	1.616,55
		Material and Installation w/o Profit (TRY)			2.326,24	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.020,69**	
		Unit Price (TRY)			**2.907,80**	

Item No	Analysis Name					UoM
35.160.1212	**Dual switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	30	6,66	199,80	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,58	165,00		425,70
10.100.1081	Master electrician	h	4,71	250,00		1.177,50
10.100.1083	Master electrician’s helper	h	3,55	185,00		656,75
		Total Excluding Profit (TRY)			953,57	2.259,95
		Material and Installation w/o Profit (TRY)			3.213,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.824,94**	
		Unit Price (TRY)			**4.016,90**	

Item No	Analysis Name					UoM
35.160.1213	**Two-way outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	30	6,66	199,80	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,73	165,00		450,45
10.100.1081	Master electrician	h	5,06	250,00		1.265,00
10.100.1083	Master electrician’s helper	h	3,9	185,00		721,50
		Total Excluding Profit (TRY)			1.018,48	2.436,95
		Material and Installation w/o Profit (TRY)			3.455,43	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.046,19**	
		Unit Price (TRY)			**4.319,29**	

Item No	Analysis Name					UoM
35.160.1214	**Parallel outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,13	165,00		186,45
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	1,53	185,00		283,05
		Total Excluding Profit (TRY)			513,47	969,50
		Material and Installation w/o Profit (TRY)			1.482,97	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.211,88**	
		Unit Price (TRY)			**1.853,71**	

Item No	Analysis Name					UoM
35.160.1221	**Single-switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	23,92	119,60	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,15	165,00		189,75
10.100.1081	Master electrician	h	2,24	250,00		560,00
10.100.1083	Master electrician’s helper	h	1,52	185,00		281,20
				Total Excluding Profit (TRY)	454,39	1.030,95
				Material and Installation w/o Profit (TRY)	1.485,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.288,69**	
				Unit Price (TRY)	**1.856,68**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1222	**Dual switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	10	23,92	239,20	
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,39	165,00		229,35
10.100.1081	Master electrician	h	2,83	250,00		707,50
10.100.1083	Master electrician’s helper	h	1,86	185,00		344,10
				Total Excluding Profit (TRY)	580,47	1.280,95
				Material and Installation w/o Profit (TRY)	1.861,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.601,19**	
				Unit Price (TRY)	**2.326,78**	

Item No	Analysis Name					UoM
35.160.1223	**Two-way outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	10	23,92	239,20	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,54	165,00		254,10
10.100.1081	Master electrician	h	3,43	250,00		857,50
10.100.1083	Master electrician’s helper	h	2,21	185,00		408,85
				Total Excluding Profit (TRY)	645,38	1.520,45
				Material and Installation w/o Profit (TRY)	2.165,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.900,56**	
				Unit Price (TRY)	**2.707,29**	

Item No	Analysis Name					UoM
35.160.1224	**Parallel outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	23,92	119,60	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,39	165,00		64,35
10.100.1081	Master electrician	h	0,79	250,00		197,50
10.100.1083	Master electrician's helper	h	0,54	185,00		99,90
		Total Excluding Profit (TRY)			191,12	361,75
		Material and Installation w/o Profit (TRY)			552,87	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**452,19**	
		Unit Price (TRY)			**691,09**	

Item No	Analysis Name					UoM
35.160.1231	**Single-switch outlet branch / Branch and outlet lines made of lead-free antigron / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2508	3 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	37,44	187,20	
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	23,92	119,60	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,83	165,00		136,95
10.100.1081	Master electrician	h	1,57	250,00		392,50
10.100.1083	Master electrician's helper	h	1,08	185,00		199,80
		Total Excluding Profit (TRY)			434,59	729,25
		Material and Installation w/o Profit (TRY)			1.163,84	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**911,56**	
		Unit Price (TRY)			**1.454,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1232	**Dual switch outlet branch / Branch and outlet lines made of lead-free antigron / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2508	3 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	37,44	187,20	
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	10	23,92	239,20	
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,05	165,00		173,25
10.100.1081	Master electrician	h	2,16	250,00		540,00
10.100.1083	Master electrician’s helper	h	1,4	185,00		259,00
				Total Excluding Profit (TRY)	560,67	972,25
				Material and Installation w/o Profit (TRY)	1.532,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.215,31**	
				Unit Price (TRY)	**1.916,15**	

Item No	Analysis Name					UoM
35.160.1233	**Two-way outlet branch / Branch and outlet lines made of lead-free antigron / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2508	3 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	37,44	187,20	
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	10	23,92	239,20	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,2	165,00		198,00
10.100.1081	Master electrician	h	2,51	250,00		627,50
10.100.1083	Master electrician’s helper	h	1,75	185,00		323,75
				Total Excluding Profit (TRY)	625,58	1.149,25
				Material and Installation w/o Profit (TRY)	1.774,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.436,56**	
				Unit Price (TRY)	**2.218,54**	

Item No	Analysis Name					UoM
35.160.1234	**Parallel outlet branch / Branch and outlet lines made of lead-free antigron / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2507	3 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	23,92	119,60	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,39	165,00		64,35
10.100.1081	Master electrician	h	0,79	250,00		197,50
10.100.1083	Master electrician’s helper	h	0,54	185,00		99,90
				Total Excluding Profit (TRY)	191,12	361,75
				Material and Installation w/o Profit (TRY)	552,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**452,19**	
				Unit Price (TRY)	**691,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1241	**Single switch outlet branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	6,66	99,90	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,23	165,00		367,95
10.100.1081	Master electrician	h	4,06	250,00		1.015,00
10.100.1083	Master electrician’s helper	h	3,13	185,00		579,05
				Total Excluding Profit (TRY)	1.009,64	1.962,00
				Material and Installation w/o Profit (TRY)	2.971,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.452,50**	
				Unit Price (TRY)	**3.714,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1242	**Dual switch outlet branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	30	6,66	199,80	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	3,71	165,00		612,15
10.100.1081	Master electrician	h	5,44	250,00		1.360,00
10.100.1083	Master electrician’s helper	h	4,06	185,00		751,10
				Total Excluding Profit (TRY)	1.253,52	2.723,25
				Material and Installation w/o Profit (TRY)	3.976,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.404,06**	
				Unit Price (TRY)	**4.970,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1243	**Two-way outlet branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	11,13	166,95	
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	30	6,66	199,80	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	3,86	165,00		636,90
10.100.1081	Master electrician	h	5,79	250,00		1.447,50
10.100.1083	Master electrician’s helper	h	4,41	185,00		815,85
		Total Excluding Profit (TRY)			1.318,43	2.900,25
		Material and Installation w/o Profit (TRY)			4.218,68	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.625,31**	
		Unit Price (TRY)			**5.273,35**	

Item No	Analysis Name					UoM
35.160.1244	**Parallel outlet branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	15	6,66	99,90	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,1	165,00		181,50
10.100.1081	Master electrician	h	1,95	250,00		487,50
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
			Total Excluding Profit (TRY)		446,42	946,50
			Material and Installation w/o Profit (TRY)		1.392,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.183,13**	
				Unit Price (TRY)	**1.741,15**	

Item No	Analysis Name					UoM
35.160.1500	**Power socket outlet branch for the security line. / Power Socket Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	36	11,13	400,68	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	12	8,01	96,12	
30.185.1201	Flush-mounted earthed socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	47,09	47,09	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	1,74	165,00		287,10
10.100.1081	Master electrician	h	3,53	250,00		882,50
10.100.1083	Master electrician’s helper	h	2,39	185,00		442,15
			Total Excluding Profit (TRY)		563,90	1.611,75
			Material and Installation w/o Profit (TRY)		2.175,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.014,69**	
				Unit Price (TRY)	**2.719,56**	

Item No	Analysis Name					UoM
35.160.1601	**The service line shall be laid through a peschel, bergman or PVC pipe, and outlet line conductors shall be laid as regular power socket outlet lines through a gas pipe with plastic-insulated conductors. / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	36	11,13	400,68	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	7	8,01	56,07	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,12	165,00		349,80
10.100.1081	Master electrician	h	4,18	250,00		1.045,00
10.100.1083	Master electrician’s helper	h	3,04	185,00		562,40
		Total Excluding Profit (TRY)			942,36	1.957,20
		Material and Installation w/o Profit (TRY)			2.899,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.446,50**	
		Unit Price (TRY)			**3.624,45**	

Item No	Analysis Name					UoM
35.160.1602	**The service line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated conductors, and outlet lines shall be laid as regular power socket outlet lines with a material of lead-free, antigron, (NVV), (NYM) type / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	21	11,13	233,73	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	7	8,01	56,07	
30.140.2508	3 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	5	37,44	187,20	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,41	165,00		232,65
10.100.1081	Master electrician	h	2,86	250,00		715,00
10.100.1083	Master electrician’s helper	h	1,93	185,00		357,05
		Total Excluding Profit (TRY)			622,61	1.304,70
		Material and Installation w/o Profit (TRY)			1.927,31	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.630,88**	
		Unit Price (TRY)			**2.409,14**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.1611	**Service and outlet lines made as regular power socket outlet lines of lead-free antigron. / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2508	3 x 2.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	12	37,44	449,28	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,94	165,00		155,10
10.100.1081	Master electrician	h	1,92	250,00		480,00
10.100.1083	Master electrician’s helper	h	1,29	185,00		238,65
		Total Excluding Profit (TRY)			594,89	873,75
		Material and Installation w/o Profit (TRY)			1.468,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.092,19**	
		Unit Price (TRY)			**1.835,80**	

Item No	Analysis Name					UoM
35.160.1612	**Service and outlet lines shall be laid through galvanized gas pipes, and plastic-insulated conductors shall be laid as regular power socket outlet lines. / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2402	1 x 2.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	36	11,13	400,68	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	12	68,00	816,00	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,64	165,00		435,60
10.100.1081	Master electrician	h	5,09	250,00		1.272,50
10.100.1083	Master electrician’s helper	h	3,95	185,00		730,75
		Total Excluding Profit (TRY)			1.362,29	2.438,85
		Material and Installation w/o Profit (TRY)			3.801,14	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.048,56**	
		Unit Price (TRY)			**4.751,43**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3101	**Single-switch Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	11,13	111,30	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	6,97	69,70	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,17	165,00		193,05
10.100.1081	Master electrician	h	2,28	250,00		570,00
10.100.1083	Master electrician’s helper	h	1,67	185,00		308,95
		Total Excluding Profit (TRY)			329,27	1.072,00
		Material and Installation w/o Profit (TRY)			1.401,27	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.340,00**	
		Unit Price (TRY)			**1.751,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3102	**Dual Switch Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	11,13	111,30	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	20	6,97	139,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	12,5	8,18	102,25	
30.185.1102	Flush-mounted commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	44,39	44,39	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,53	165,00		252,45
10.100.1081	Master electrician	h	3,1	250,00		775,00
10.100.1083	Master electrician’s helper	h	2,19	185,00		405,15
		Total Excluding Profit (TRY)			418,34	1.432,60
		Material and Installation w/o Profit (TRY)			1.850,94	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.790,75**	
		Unit Price (TRY)			**2.313,67**	

Item No	Analysis Name					UoM
35.160.3103	**Two-way Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	11,13	111,30	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	20	6,97	139,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	12,5	8,18	102,25	
30.185.1103	Flush-mounted two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	43,85	87,70	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,53	165,00		252,45
10.100.1081	Master electrician	h	3,1	250,00		775,00
10.100.1083	Master electrician's helper	h	2,19	185,00		405,15
			Total Excluding Profit (TRY)		461,65	1.432,60
			Material and Installation w/o Profit (TRY)		1.894,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.790,75**	
				Unit Price (TRY)	**2.367,81**	

Item No	Analysis Name					UoM
35.160.3104	**Parallel Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	6,97	69,70	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,57	165,00		94,05
10.100.1081	Master electrician	h	1,15	250,00		287,50
10.100.1083	Master electrician's helper	h	0,85	185,00		157,25
			Total Excluding Profit (TRY)		131,60	538,80
			Material and Installation w/o Profit (TRY)		670,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**673,50**	
				Unit Price (TRY)	**838,00**	

Item No	Analysis Name					UoM
35.160.3105	**Chandelier Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	11,13	111,30	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1102	Flush-mounted commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	44,39	44,39	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,17	165,00		193,05
10.100.1081	Master electrician	h	2,68	250,00		670,00
10.100.1083	Master electrician's helper	h	1,77	185,00		327,45
		Total Excluding Profit (TRY)			363,04	1.190,50
		Material and Installation w/o Profit (TRY)			1.553,54	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.488,13**	
		Unit Price (TRY)			**1.941,92**	

Item No	Analysis Name					UoM
35.160.3106	**Parallel Chandelier Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,93	165,00		153,45
10.100.1081	Master electrician	h	1,45	250,00		362,50
10.100.1083	Master electrician's helper	h	1,27	185,00		234,95
		Total Excluding Profit (TRY)			166,45	750,90
		Material and Installation w/o Profit (TRY)			917,35	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**938,63**	
		Unit Price (TRY)			**1.146,69**	

Item No	Analysis Name					UoM
35.160.3107	**3-phase Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	20	11,13	222,60	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	20	6,97	139,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,47	165,00		242,55
10.100.1081	Master electrician	h	2,9	250,00		725,00
10.100.1083	Master electrician's helper	h	1,97	185,00		364,45
				Total Excluding Profit (TRY)	510,27	1.332,00
				Material and Installation w/o Profit (TRY)	1.842,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.665,00**	
				Unit Price (TRY)	**2.302,84**	

Item No	Analysis Name					UoM
35.160.3108	**3-phase Parallel Outlet Branch / Lighting Outlet Line with Halogen-free Cables**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	20	6,97	139,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,72	165,00		118,80
10.100.1081	Master electrician	h	1,45	250,00		362,50
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	201,30	666,30
				Material and Installation w/o Profit (TRY)	867,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**832,88**	
				Unit Price (TRY)	**1.084,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3201	**Single-switch Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,47	165,00		242,55
10.100.1081	Master electrician	h	2,9	250,00		725,00
10.100.1083	Master electrician’s helper	h	1,97	185,00		364,45
		Total Excluding Profit (TRY)			419,77	1.332,00
		Material and Installation w/o Profit (TRY)			1.751,77	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.665,00**	
		Unit Price (TRY)			**2.189,71**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3202	**Commutator Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	30	6,97	209,10	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	12,5	8,18	102,25	
30.185.1102	Flush-mounted commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	44,39	44,39	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,98	165,00		326,70
10.100.1081	Master electrician	h	4,02	250,00		1.005,00
10.100.1083	Master electrician’s helper	h	2,65	185,00		490,25
		Total Excluding Profit (TRY)			543,69	1.821,95
		Material and Installation w/o Profit (TRY)			2.365,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.277,44**	
		Unit Price (TRY)			**2.957,05**	

Item No	Analysis Name					UoM
35.160.3203	**Two-way Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	30	6,97	209,10	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	12,5	8,18	102,25	
30.185.1103	Flush-mounted two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	43,85	87,70	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,98	165,00		326,70
10.100.1081	Master electrician	h	4,02	250,00		1.005,00
10.100.1083	Master electrician's helper	h	2,65	185,00		490,25
				Total Excluding Profit (TRY)	587,00	1.821,95
				Material and Installation w/o Profit (TRY)	2.408,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.277,44**	
				Unit Price (TRY)	**3.011,19**	

Item No	Analysis Name					UoM
35.160.3204	**Parallel Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,72	165,00		118,80
10.100.1081	Master electrician	h	1,45	250,00		362,50
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	166,45	666,30
				Material and Installation w/o Profit (TRY)	832,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**832,88**	
				Unit Price (TRY)	**1.040,94**	

Item No	Analysis Name					UoM
35.160.3205	**Chandelier Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	20	6,97	139,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,62	165,00		267,30
10.100.1081	Master electrician	h	3,29	250,00		822,50
10.100.1083	Master electrician's helper	h	2,22	185,00		410,70
				Total Excluding Profit (TRY)	454,62	1.500,50
				Material and Installation w/o Profit (TRY)	1.955,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.875,63**	
				Unit Price (TRY)	**2.443,90**	

Item No	Analysis Name					UoM
35.160.3206	**Parallel Chandelier Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	20	6,97	139,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,87	165,00		143,55
10.100.1081	Master electrician	h	1,74	250,00		435,00
10.100.1083	Master electrician's helper	h	1,15	185,00		212,75
				Total Excluding Profit (TRY)	201,30	791,30
				Material and Installation w/o Profit (TRY)	992,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**989,13**	
				Unit Price (TRY)	**1.240,75**	

Item No	Analysis Name					UoM
35.160.3207	**3-phase Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	25	11,13	278,25	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	25	6,97	174,25	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,78	165,00		293,70
10.100.1081	Master electrician	h	3,51	250,00		877,50
10.100.1083	Master electrician's helper	h	2,28	185,00		421,80
			Total Excluding Profit (TRY)		600,77	1.593,00
			Material and Installation w/o Profit (TRY)		2.193,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.991,25**	
				Unit Price (TRY)	**2.742,21**	

Item No	Analysis Name					UoM
35.160.3208	**3-phase Parallel Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	25	6,97	174,25	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,87	165,00		143,55
10.100.1081	Master electrician	h	1,74	250,00		435,00
10.100.1083	Master electrician's helper	h	1,15	185,00		212,75
			Total Excluding Profit (TRY)		236,15	791,30
			Material and Installation w/o Profit (TRY)		1.027,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**989,13**	
				Unit Price (TRY)	**1.284,31**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3280	**3-phase Parallel Outlet Branch / Safety line lighting outlet branches**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	11,13	111,30	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	10	6,97	69,70	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,12	165,00		184,80
10.100.1081	Master electrician	h	2,03	250,00		507,50
10.100.1083	Master electrician’s helper	h	1,62	185,00		299,70
		Total Excluding Profit (TRY)			283,80	992,00
		Material and Installation w/o Profit (TRY)			1.275,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.240,00**	
		Unit Price (TRY)			**1.594,75**	

Item No	Analysis Name					UoM
35.160.3311	**Single switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z,O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,85	165,00		305,25
10.100.1081	Master electrician	h	3,4	250,00		850,00
10.100.1083	Master electrician’s helper	h	2,47	185,00		456,95
		Total Excluding Profit (TRY)			715,19	1.612,20
		Material and Installation w/o Profit (TRY)			2.327,39	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.015,25**	
		Unit Price (TRY)			**2.909,24**	

Item No	Analysis Name					UoM
35.160.3312	**Dual switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z,O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	30	6,97	209,10	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,96	165,00		323,40
10.100.1081	Master electrician	h	3,62	250,00		905,00
10.100.1083	Master electrician’s helper	h	2,59	185,00		479,15
		Total Excluding Profit (TRY)			957,24	1.707,55
		Material and Installation w/o Profit (TRY)			2.664,79	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.134,44**	
		Unit Price (TRY)			**3.330,99**	

Item No	Analysis Name					UoM
35.160.3313	**Two-way outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z,O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	30	6,97	209,10	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,07	165,00		341,55
10.100.1081	Master electrician	h	3,94	250,00		985,00
10.100.1083	Master electrician’s helper	h	2,8	185,00		518,00
		Total Excluding Profit (TRY)			1.028,63	1.844,55
		Material and Installation w/o Profit (TRY)			2.873,18	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.305,69**	
		Unit Price (TRY)			**3.591,48**	

Item No	Analysis Name					UoM
35.160.3314	**Parallel outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe, and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z,O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,25	165,00		206,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	1,85	185,00		342,25
		Total Excluding Profit (TRY)			451,07	1.123,50
		Material and Installation w/o Profit (TRY)			1.574,57	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.404,38**	
		Unit Price (TRY)			**1.968,21**	

Item No	Analysis Name					UoM
35.160.3321	**Single switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	26,62	133,10	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,15	165,00		189,75
10.100.1081	Master electrician	h	2,24	250,00		560,00
10.100.1083	Master electrician’s helper	h	1,52	185,00		281,20
				Total Excluding Profit (TRY)	468,74	1.030,95
				Material and Installation w/o Profit (TRY)	1.499,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.288,69**	
				Unit Price (TRY)	**1.874,61**	

Item No	Analysis Name					UoM
35.160.3322	**Dual switch outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated (HO7Z,O7Z1) conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	10	26,62	266,20	
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,39	165,00		229,35
10.100.1081	Master electrician	h	2,84	250,00		710,00
10.100.1083	Master electrician’s helper	h	1,72	185,00		318,20
		Total Excluding Profit (TRY)			608,32	1.257,55
		Material and Installation w/o Profit (TRY)			1.865,87	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.571,94**	
		Unit Price (TRY)			**2.332,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3323	**Two-way outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated (HO7Z,O7Z1) conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	10	26,62	266,20	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,54	165,00		254,10
10.100.1081	Master electrician	h	3,19	250,00		797,50
10.100.1083	Master electrician’s helper	h	2,22	185,00		410,70
				Total Excluding Profit (TRY)	673,23	1.462,30
				Material and Installation w/o Profit (TRY)	2.135,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.827,88**	
				Unit Price (TRY)	**2.669,41**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3324	**Parallel outlet branch / The branch line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated (HO7Z,O7Z1) conductors, and outlet lines shall be laid with a material of lead-free, antigron, (NVV), (NYM) type / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	26,62	133,10	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,79	250,00		197,50
10.100.1083	Master electrician’s helper	h	0,55	185,00		101,75
		Total Excluding Profit (TRY)			204,62	365,25
		Material and Installation w/o Profit (TRY)			569,87	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**456,56**	
		Unit Price (TRY)			**712,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3331	**Single-switch Outlet Branch / Branch and outlet lines made of lead-free antigron (NHXMH) / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1531	3 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	39,62	198,10	
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	26,62	133,10	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,81	165,00		133,65
10.100.1081	Master electrician	h	1,57	250,00		392,50
10.100.1083	Master electrician’s helper	h	1,06	185,00		196,10
				Total Excluding Profit (TRY)	458,99	722,25
				Material and Installation w/o Profit (TRY)	1.181,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**902,81**	
				Unit Price (TRY)	**1.476,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3332	**Dual switch Outlet Branch / Branch and outlet lines made of lead-free antigron (NHXMH) / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1531	3 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	39,62	198,10	
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	10	26,62	266,20	
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,05	165,00		173,25
10.100.1081	Master electrician	h	2,16	250,00		540,00
10.100.1083	Master electrician’s helper	h	1,4	185,00		259,00
			Total Excluding Profit (TRY)		598,57	972,25
			Material and Installation w/o Profit (TRY)		1.570,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.215,31**	
				Unit Price (TRY)	**1.963,53**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3333	**Two-way Outlet Branch / Branch and outlet lines made of lead-free antigron (NHXMH) / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1531	3 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	39,62	198,10	
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	10	26,62	266,20	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,2	165,00		198,00
10.100.1081	Master electrician	h	2,51	250,00		627,50
10.100.1083	Master electrician’s helper	h	1,75	185,00		323,75
		Total Excluding Profit (TRY)			663,48	1.149,25
		Material and Installation w/o Profit (TRY)			1.812,73	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.436,56**	
		Unit Price (TRY)			**2.265,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3334	**Parallel Outlet Branch / Branch and outlet lines made of lead-free antigron (NHXMH) / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1530	3 x 1,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	26,62	133,10	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,79	250,00		197,50
10.100.1083	Master electrician’s helper	h	0,55	185,00		101,75
		Total Excluding Profit (TRY)			204,62	365,25
		Material and Installation w/o Profit (TRY)			569,87	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**456,56**	
		Unit Price (TRY)			**712,34**	

Item No	Analysis Name					UoM
35.160.3341	**Single Switch Outlet Branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z, O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,22	165,00		366,30
10.100.1081	Master electrician	h	4,05	250,00		1.012,50
10.100.1083	Master electrician’s helper	h	3,12	185,00		577,20
				Total Excluding Profit (TRY)	1.014,29	1.956,00
				Material and Installation w/o Profit (TRY)	2.970,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.445,00**	
				Unit Price (TRY)	**3.712,86**	

Item No	Analysis Name					UoM
35.160.3342	**Dual Switch Outlet Branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z, O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	30	6,97	209,10	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,92	165,00		481,80
10.100.1081	Master electrician	h	5,42	250,00		1.355,00
10.100.1083	Master electrician’s helper	h	4,05	185,00		749,25
		Total Excluding Profit (TRY)			1.262,82	2.586,05
		Material and Installation w/o Profit (TRY)			3.848,87	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.232,56**	
		Unit Price (TRY)			**4.811,09**	

Item No	Analysis Name					UoM
35.160.3343	**Two-way Outlet Branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z, O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	11,13	166,95	
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	30	6,97	209,10	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	7,5	55,00	412,50	
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	2	63,83	127,66	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	3,07	165,00		506,55
10.100.1081	Master electrician	h	5,77	250,00		1.442,50
10.100.1083	Master electrician’s helper	h	4,4	185,00		814,00
				Total Excluding Profit (TRY)	1.327,73	2.763,05
				Material and Installation w/o Profit (TRY)	4.090,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.453,81**	
				Unit Price (TRY)	**5.113,48**	

Item No	Analysis Name					UoM
35.160.3344	**Parallel Outlet Branch / The branch and outlet lines shall be laid through a gas pipe with plastic-insulated (HO7Z, O7Z1) conductors. / Weatherproof Lighting Outlet Line (with Safety Line)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1401	1 x 1.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	15	6,97	104,55	
20.300.1401	1/2″ ----- 15 ----- 21.3/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	55,00	275,00	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,1	165,00		181,50
10.100.1081	Master electrician	h	1,95	250,00		487,50
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	451,07	946,50
				Material and Installation w/o Profit (TRY)	1.397,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.183,13**	
				Unit Price (TRY)	**1.746,96**	

Item No	Analysis Name					UoM
35.160.3401	**Power socket outlet branch for the security line. / Power Socket Outlet Line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	36	11,13	400,68	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	12	8,18	98,16	
30.185.1201	Flush-mounted earthed socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	47,09	47,09	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,74	165,00		287,10
10.100.1081	Master electrician	h	3,53	250,00		882,50
10.100.1083	Master electrician’s helper	h	2,39	185,00		442,15
				Total Excluding Profit (TRY)	566,93	1.611,75
				Material and Installation w/o Profit (TRY)	2.178,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.014,69**	
				Unit Price (TRY)	**2.723,35**	

Item No	Analysis Name					UoM
35.160.3501	**The service line shall be laid through a peschel, bergman or PVC pipe, and outlet line conductors shall be laid as regular power socket outlet lines through a gas pipe with plastic-insulated (HO7Z, O7Z1) conductors. / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	36	11,13	400,68	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	7	8,18	57,26	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	5	68,00	340,00	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,12	165,00		349,80
10.100.1081	Master electrician	h	4,18	250,00		1.045,00
10.100.1083	Master electrician’s helper	h	3,04	185,00		562,40
				Total Excluding Profit (TRY)	943,55	1.957,20
				Material and Installation w/o Profit (TRY)	2.900,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.446,50**	
				Unit Price (TRY)	**3.625,94**	

Item No	Analysis Name					UoM
35.160.3502	**The service line shall be laid through a peschel, bergman or PVC pipe with plastic-insulated (HO7Z, O7Z1) conductors, and outlet lines shall be laid as regular power socket outlet lines with a material of lead-free, antigron, (NHXMH) type / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	21	11,13	233,73	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	7	8,18	57,26	
30.150.1531	3 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	5	39,62	198,10	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1,4	165,00		231,00
10.100.1081	Master electrician	h	2,85	250,00		712,50
10.100.1083	Master electrician’s helper	h	1,93	185,00		357,05
				Total Excluding Profit (TRY)	634,70	1.300,55
				Material and Installation w/o Profit (TRY)	1.935,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.625,69**	
				Unit Price (TRY)	**2.419,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.3503	**Service and outlet lines made as regular power socket outlet lines of lead-free antigron (NHXMH). / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1531	3 x 2,5 mm² / Installation of a supply line with halogen-free, flame-retardant, isolated, multi-core NHXMH cables / Halogen-Free Cables (Market price)	m	12	39,62	475,44	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,82	165,00		135,30
10.100.1081	Master electrician	h	1,7	250,00		425,00
10.100.1083	Master electrician’s helper	h	1,17	185,00		216,45
		Total Excluding Profit (TRY)			621,05	776,75
		Material and Installation w/o Profit (TRY)			1.397,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**970,94**	
		Unit Price (TRY)			**1.747,25**	

Item No	Analysis Name					UoM
35.160.3504	**Service and outlet lines shall be laid through galvanized gas pipes, and plastic-insulated (HO7Z, O7Z1) conductors shall be laid as regular power socket outlet lines. / Weather-proof power socket outlet (with safety line) (Using materials with TS compliance certificate)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1402	1 x 2.5 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	36	11,13	400,68	
20.300.1402	3/4 ----- 20 -----26.9/2.65 (Nominal Unit (inch)-----Ø (mm)-----Average external diameter/ Wall Thickness (mm/mm)) / Welded galvanized pipes, in compliance with TS EN 10255, made of Fe33-2 / Steel Pipes (Market price)	m	12	68,00	816,00	
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	2,64	165,00		435,60
10.100.1081	Master electrician	h	5,09	250,00		1.272,50
10.100.1083	Master electrician’s helper	h	3,95	185,00		730,75
		Total Excluding Profit (TRY)			1.362,29	2.438,85
		Material and Installation w/o Profit (TRY)			3.801,14	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.048,56**	
		Unit Price (TRY)			**4.751,43**	

Item No	Analysis Name					UoM
35.160.6101	**Supply, installation, including any material and labor, of a 14- to 20-mm peschel, bergman or PVC hollow pipes on the reinforced concrete ceilings and walls, and laying a guide wire in the pipe.**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,05	250,00		12,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			8,01	26,70
		Material and Installation w/o Profit (TRY)			34,71	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**33,38**	
		Unit Price (TRY)			**43,39**	

Item No	Analysis Name					UoM
35.160.6102	**Unit Price No.: Same as 729-101 except that 26 to 37-mm pipes shall be used. Unit: Pipe length is measured. / Installation of hollow pipes (using materials certified for compliance with TS).**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	14,61	37,05
				Material and Installation w/o Profit (TRY)	51,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**46,31**	
				Unit Price (TRY)	**64,57**	

Item No	Analysis Name					UoM
35.160.6103	**Unit Price No.: Same as 729-101 except that 26 to 37-mm pipes shall be used. Unit: Pipe length is measured. / Installation of hollow pipes (using materials certified for compliance with TS).**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6103	40-50 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	26,11	26,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	26,11	41,40
				Material and Installation w/o Profit (TRY)	67,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**51,75**	
				Unit Price (TRY)	**84,39**	

Item No	Analysis Name					UoM
35.160.6201	**16-20 mm PE HFFR pipe / Halogen-free flame-retardant pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	8,18	8,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,05	250,00		12,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	8,18	26,70
				Material and Installation w/o Profit (TRY)	34,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**33,38**	
				Unit Price (TRY)	**43,60**	

Item No	Analysis Name					UoM
35.160.6202	**25-32 mm PE HFFR pipe / Halogen-free flame-retardant pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6202	25-32 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	16,72	16,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	16,72	37,05
				Material and Installation w/o Profit (TRY)	53,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**46,31**	
				Unit Price (TRY)	**67,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.6203	**40-50 mm PE HFFR pipe / Halogen-free flame-retardant pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6203	40-50 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	34,06	34,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	34,06	41,40
				Material and Installation w/o Profit (TRY)	75,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**51,75**	
				Unit Price (TRY)	**94,33**	

Item No	Analysis Name					UoM
35.160.6204	**63-75 mm PE HFFR pipe / Halogen-free flame-retardant pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6204	63-75 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	1	58,70	58,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	58,70	51,75
				Material and Installation w/o Profit (TRY)	110,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**138,06**	

Item No	Analysis Name					UoM
35.160.6300	**Hollow pipe installation outlet / Installation of hollow pipes (using materials certified for compliance with TS).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	2	20,01	40,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,55	165,00		90,75
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
		Total Excluding Profit (TRY)			120,12	569,25
		Material and Installation w/o Profit (TRY)			689,37	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**711,56**	
		Unit Price (TRY)			**861,71**	

Item No	Analysis Name					UoM
35.160.6310	**Hollow pipe installation outlet / Installation of hollow pipes (using materials certified for compliance with TS).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	2	21,00	42,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,55	165,00		90,75
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
		Total Excluding Profit (TRY)			123,80	569,25
		Material and Installation w/o Profit (TRY)			693,05	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**711,56**	
		Unit Price (TRY)			**866,31**	

Item No	Analysis Name					UoM
35.160.6350	**INSTALLATION DECK PIPE CLIPS**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6350	INSTALLATION DECK PIPE CLIPS / PIPES AND FITTINGS / OUTLET BRANCHES, PIPES AND FITTINGS (Market price)	Qty	1	5,00	5,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,03	250,00		7,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	5,00	14,70
				Material and Installation w/o Profit (TRY)	19,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**18,38**	
				Unit Price (TRY)	**24,63**	

Item No	Analysis Name					UoM
35.160.6501	**Ø50 mm PE corrugated pipe / Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6501	Ø50 mm PE corrugated pipe / Cable Protection Pipes / PIPES AND FITTINGS (Market price)	m	1	17,60	17,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	17,60	53,40
				Material and Installation w/o Profit (TRY)	71,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,75**	
				Unit Price (TRY)	**88,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.6502	**Ø75 mm PE corrugated pipe / Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6502	Ø75 mm PE corrugated pipe / Cable Protection Pipes / PIPES AND FITTINGS (Market price)	m	1	25,87	25,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	25,87	63,75
				Material and Installation w/o Profit (TRY)	89,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**79,69**	
				Unit Price (TRY)	**112,03**	

Item No	Analysis Name					UoM
35.160.6503	**Ø90 mm PE corrugated pipe / Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6503	Ø90 mm PE corrugated pipe / Cable Protection Pipes / PIPES AND FITTINGS (Market price)	m	1	33,70	33,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	33,70	69,75
				Material and Installation w/o Profit (TRY)	103,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**87,19**	
				Unit Price (TRY)	**129,31**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.6504	**Ø110 mm PE corrugated pipe / Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.6504	Ø110 mm PE corrugated pipe / Cable Protection Pipes / PIPES AND FITTINGS (Market price)	m	1	39,42	39,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,14	185,00		25,90
				Total Excluding Profit (TRY)	39,42	75,75
				Material and Installation w/o Profit (TRY)	115,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**94,69**	
				Unit Price (TRY)	**143,96**	

Item No	Analysis Name					UoM
35.160.7105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7105	20 x 20 x 20 cm / PVC Manhole (Underground Junction Box) / PIPES AND FITTINGS (Market price)	Qty	1	170,02	170,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	170,02	375,75
				Material and Installation w/o Profit (TRY)	545,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**469,69**	
				Unit Price (TRY)	**682,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.7110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7110	30 x 30 x 30 cm / PVC Manhole (Underground Junction Box) / PIPES AND FITTINGS (Market price)	Qty	1	347,75	347,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			347,75	484,50
		Material and Installation w/o Profit (TRY)			832,25	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**605,63**	
		Unit Price (TRY)			**1.040,31**	

Item No	Analysis Name					UoM
35.160.7115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7115	40 x 40 x 40 cm / PVC Manhole (Underground Junction Box) / PIPES AND FITTINGS (Market price)	Qty	1	730,02	730,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
		Total Excluding Profit (TRY)			730,02	626,25
		Material and Installation w/o Profit (TRY)			1.356,27	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**782,81**	
		Unit Price (TRY)			**1.695,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.7120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7120	50 x 50 x 50 cm / PVC Manhole (Underground Junction Box) / PIPES AND FITTINGS (Market price)	Qty	1	1.469,75	1.469,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.469,75	735,00
				Material and Installation w/o Profit (TRY)	2.204,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**2.755,94**	

Item No	Analysis Name					UoM
35.160.7212						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7212	D400 (Group 4) / Composite Manhole (480 x 480 x 410 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	3.975,00	3.975,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	3.975,00	735,00
				Material and Installation w/o Profit (TRY)	4.710,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**5.887,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.7214						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7214	C250 (Group 3) / Composite Manhole (480 x 480 x 410 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	3.675,00	3.675,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	3.675,00	735,00
				Material and Installation w/o Profit (TRY)	4.410,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**5.512,50**	

Item No	Analysis Name					UoM
35.160.7216						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7216	B125 (Group 2) / Composite Manhole (480 x 480 x 410 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	2.700,00	2.700,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	2.700,00	735,00
				Material and Installation w/o Profit (TRY)	3.435,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**4.293,75**	

Item No	Analysis Name					UoM
35.160.7218						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7218	A15 (Group 1) / Composite Manhole (480 x 480 x 410 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	2.400,00	2.400,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	2.400,00	735,00
				Material and Installation w/o Profit (TRY)	3.135,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**3.918,75**	

Item No	Analysis Name					UoM
35.160.7232						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7232	D400 (Group 4) / Composite Manhole (480 x 480 x 650 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	5.100,00	5.100,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	5.100,00	735,00
				Material and Installation w/o Profit (TRY)	5.835,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**7.293,75**	

Item No	Analysis Name					UoM
35.160.7234						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7234	C250 (Group 3) / Composite Manhole (480 x 480 x 650 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	4.500,00	4.500,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	4.500,00	735,00
				Material and Installation w/o Profit (TRY)	5.235,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**6.543,75**	

Item No	Analysis Name					UoM
35.160.7236						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7236	B125 (Group 2) / Composite Manhole (480 x 480 x 650 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	3.525,00	3.525,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	3.525,00	735,00
				Material and Installation w/o Profit (TRY)	4.260,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**5.325,00**	

Item No	Analysis Name					UoM
35.160.7238						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7238	A15 (Group 1) / Composite Manhole (480 x 480 x 650 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	3.225,00	3.225,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	3.225,00	735,00
				Material and Installation w/o Profit (TRY)	3.960,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**4.950,00**	

Item No	Analysis Name					UoM
35.160.7242						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7242	B125 / Composite Manhole (250 x 250 x 300 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	780,00	780,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	780,00	484,50
				Material and Installation w/o Profit (TRY)	1.264,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**605,63**	
				Unit Price (TRY)	**1.580,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.7252						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7252	B125 / Composite Manhole (350 x 350 x 410 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	2.430,00	2.430,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	2.430,00	484,50
				Material and Installation w/o Profit (TRY)	2.914,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**605,63**	
				Unit Price (TRY)	**3.643,13**	

Item No	Analysis Name					UoM
35.160.7254						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7254	A15 / Composite Manhole (350 x 350 x 410 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	2.100,00	2.100,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	2.100,00	484,50
				Material and Installation w/o Profit (TRY)	2.584,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**605,63**	
				Unit Price (TRY)	**3.230,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.7272						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7272	B125 / Composite Manhole (Q560 x 450 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	2.490,00	2.490,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	2.490,00	735,00
				Material and Installation w/o Profit (TRY)	3.225,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**4.031,25**	

Item No	Analysis Name					UoM
35.160.7274						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7274	A15 / Composite Manhole (Q560 x 450 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	2.250,00	2.250,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	2.250,00	735,00
				Material and Installation w/o Profit (TRY)	2.985,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**3.731,25**	

Item No	Analysis Name					UoM
35.160.7280						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.7280	Composite Manhole Booster Element (480 x 480 x 50 mm) / Composite Manhole (Additional Chamber) / PIPES AND FITTINGS (Market price)	Qty	1	810,00	810,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	810,00	250,50
				Material and Installation w/o Profit (TRY)	1.060,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**313,13**	
				Unit Price (TRY)	**1.325,63**	

Item No	Analysis Name					UoM
35.160.8001	**Max. 2 x 25 A / Underground cable terminal box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8001	Up to 2 x 25 A. / Underground Cable Terminal Box / PIPES AND FITTINGS (Market price)	Qty	1	194,48	194,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	194,48	258,75
				Material and Installation w/o Profit (TRY)	453,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**566,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8002	**Max. 3 x 25 A / Underground cable terminal box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8002	Up to 3 x 25 A. / Underground Cable Terminal Box / PIPES AND FITTINGS (Market price)	Qty	1	212,16	212,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			212,16	258,75
		Material and Installation w/o Profit (TRY)			470,91	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**588,64**	

Item No	Analysis Name					UoM
35.160.8003	**Max. 3 x 63 A / Underground cable terminal box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8003	Up to 3 x 63 A. / Underground Cable Terminal Box / PIPES AND FITTINGS (Market price)	Qty	1	538,72	538,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			538,72	258,75
		Material and Installation w/o Profit (TRY)			797,47	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**996,84**	

Item No	Analysis Name					UoM
35.160.8004	**Max. 3 x 100 A / Underground cable terminal box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8004	3 x 100 A. / Underground Cable Terminal Box / PIPES AND FITTINGS (Market price)	Qty	1	633,36	633,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	633,36	408,75
				Material and Installation w/o Profit (TRY)	1.042,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**1.302,64**	

Item No	Analysis Name					UoM
35.160.8005	**Max. 3 x 200 A / Underground cable terminal box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8005	Up to 3 x 200 A. / Underground Cable Terminal Box / PIPES AND FITTINGS (Market price)	Qty	1	1.199,12	1.199,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	1.199,12	408,75
				Material and Installation w/o Profit (TRY)	1.607,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**2.009,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8101	**Up to 4 x 10 mm² / Underground cable cap**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8101	Up to 4 x 10 mm² / Underground Cable Caps / PIPES AND FITTINGS (Market price)	Qty	1	369,60	369,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	369,60	258,75
				Material and Installation w/o Profit (TRY)	628,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**785,44**	

Item No	Analysis Name					UoM
35.160.8102	**Up to 3 x 35 + 16 mm² / Underground cable cap**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8102	Up to 3 x 35+16 mm² / Underground Cable Caps / PIPES AND FITTINGS (Market price)	Qty	1	369,60	369,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	369,60	258,75
				Material and Installation w/o Profit (TRY)	628,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**785,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8103	**Up to 3 x 70 + 35 mm² / Underground cable cap**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8103	Up to 3 x 70+35 mm² / Underground Cable Caps / PIPES AND FITTINGS (Market price)	Qty	1	563,20	563,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	563,20	258,75
				Material and Installation w/o Profit (TRY)	821,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.027,44**	

Item No	Analysis Name					UoM
35.160.8104	**Up to 3 x 120 + 70 mm² / Underground cable cap**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8104	Up to 3 x 120+70 mm² / Underground Cable Caps / PIPES AND FITTINGS (Market price)	Qty	1	623,04	623,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	623,04	408,75
				Material and Installation w/o Profit (TRY)	1.031,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**1.289,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8105	**Up to 3 x 185 + 95 mm² / Underground cable cap**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8105	Up to 3 x 185+95 mm² / Underground Cable Caps / PIPES AND FITTINGS (Market price)	Qty	1	1.008,48	1.008,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	1.008,48	408,75
				Material and Installation w/o Profit (TRY)	1.417,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**1.771,54**	

Item No	Analysis Name					UoM
35.160.8106	**Up to 3 x 240 + 120 mm² / Underground cable cap**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8106	Up to 3 x 240+120 mm² / Underground Cable Caps / PIPES AND FITTINGS (Market price)	Qty	1	1.122,88	1.122,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	1.122,88	408,75
				Material and Installation w/o Profit (TRY)	1.531,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**1.914,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8201	**Up to 3 x 4 + 4 mm² / Underground cable junction box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8201	Up to 3 x 4+4 mm² / Underground Cable Junction Box / PIPES AND FITTINGS (Market price)	Qty	1	197,12	197,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	197,12	258,75
				Material and Installation w/o Profit (TRY)	455,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**569,84**	

Item No	Analysis Name					UoM
35.160.8202	**Up to 3 x 16 + 10 mm² / Underground cable junction box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8202	Up to 3 x 16+10 mm² / Underground Cable Junction Box / PIPES AND FITTINGS (Market price)	Qty	1	197,12	197,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	197,12	258,75
				Material and Installation w/o Profit (TRY)	455,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**569,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8203	**Up to 3 x 35 + 16 mm² / Underground cable junction box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8203	Up to 3 x 35+16 mm² / Underground Cable Junction Box / PIPES AND FITTINGS (Market price)	Qty	1	406,56	406,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			406,56	258,75
		Material and Installation w/o Profit (TRY)			665,31	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**831,64**	

Item No	Analysis Name					UoM
35.160.8204	**Up to 3 x 70 + 35 mm² / Underground cable junction box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8204	Up to 3 x 70+35 mm² / Underground Cable Junction Box / PIPES AND FITTINGS (Market price)	Qty	1	748,00	748,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			748,00	258,75
		Material and Installation w/o Profit (TRY)			1.006,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.258,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8205	**Up to 3 x 120 + 70 mm² / Underground cable junction box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8205	Up to 3 x 120+70 mm² / Underground Cable Junction Box / PIPES AND FITTINGS (Market price)	Qty	1	1.020,80	1.020,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
		Total Excluding Profit (TRY)			1.020,80	408,75
		Material and Installation w/o Profit (TRY)			1.429,55	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**510,94**	
		Unit Price (TRY)			**1.786,94**	

Item No	Analysis Name					UoM
35.160.8206	**Up to 3 x 185 + 95 mm² / Underground cable junction box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8206	Up to 3 x 185+95 mm² / Underground Cable Junction Box / PIPES AND FITTINGS (Market price)	Qty	1	1.223,20	1.223,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
		Total Excluding Profit (TRY)			1.223,20	408,75
		Material and Installation w/o Profit (TRY)			1.631,95	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**510,94**	
		Unit Price (TRY)			**2.039,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.160.8207	**Up to 3 x 240 + 120 mm² / Underground cable junction box**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.160.8207	Up to 3 x 240+120 mm² / Underground Cable Junction Box / PIPES AND FITTINGS (Market price)	Qty	1	1.777,60	1.777,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	1.777,60	408,75
				Material and Installation w/o Profit (TRY)	2.186,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**2.732,94**	

Item No	Analysis Name					UoM
35.170.1101	**Surface-mounted LED ceiling fixtures sized minimum 30x30 (with minimum 1000 lm light flux, and maximum 12 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1101	Surface-mounted LED ceiling fixtures sized minimum 30x30 (with minimum 1000 lm light flux, and maximum 12 W consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	1.228,24	1.228,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.228,24	169,01
				Material and Installation w/o Profit (TRY)	1.397,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.746,56**	

Item No	Analysis Name					UoM
35.170.1102	**Flush-mounted LED ceiling fixtures sized minimum 30x30 (with minimum 1000 lm light flux, and maximum 12 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1102	Flush-mounted LED ceiling fixtures sized minimum 30x30 (with minimum 1000 lm light flux, and maximum 12 W consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	1.051,44	1.051,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.051,44	169,01
				Material and Installation w/o Profit (TRY)	1.220,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.525,56**	

Item No	Analysis Name					UoM
35.170.1103	**Surface-mounted LED ceiling fixtures sized minimum 30 x 60 (with minimum 1,500 lm light flux, and maximum 18 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1103	Surface-mounted LED ceiling fixtures sized minimum 30x60 (with minimum 1500 lm light flux, and maximum 18 w consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	1.537,12	1.537,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.537,12	169,01
				Material and Installation w/o Profit (TRY)	1.706,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.132,66**	

Item No	Analysis Name					UoM
35.170.1104	**Flush-mounted LED ceiling fixtures sized minimum 30 x 60 (with minimum 1,500 lm light flux, and maximum 18 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1104	Flush-mounted LED ceiling fixtures sized minimum 30x60 (with minimum 1500 lm light flux, and maximum 18 w consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	1.339,52	1.339,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.339,52	169,01
				Material and Installation w/o Profit (TRY)	1.508,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.885,66**	

Item No	Analysis Name					UoM
35.170.1105	**Surface-mounted LED ceiling fixtures sized minimum 60 x 60 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1105	Surface-mounted LED ceiling fixtures sized minimum 60x60 (with minimum 3300 lm light flux, and maximum 36 w consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	1.870,96	1.870,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.870,96	169,01
				Material and Installation w/o Profit (TRY)	2.039,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.549,96**	

Item No	Analysis Name					UoM
35.170.1106	**Flush-mounted LED ceiling fixtures sized minimum 60 x 60 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1106	Flush-mounted LED ceiling fixtures sized minimum 60x60 (with minimum 3300 lm light flux, and maximum 36 w consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	1.350,96	1.350,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.350,96	169,01
				Material and Installation w/o Profit (TRY)	1.519,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.899,96**	

Item No	Analysis Name					UoM
35.170.1107	**Surface-mounted LED ceiling fixtures sized minimum 30 x 120 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1107	Surface-mounted LED ceiling fixtures sized minimum 30x120 (with minimum 3300 lm light flux, and maximum 36 W consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	2.110,16	2.110,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.110,16	169,01
				Material and Installation w/o Profit (TRY)	2.279,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.848,96**	

Item No	Analysis Name					UoM
35.170.1108	**Flush-mounted LED ceiling fixtures sized minimum 30 x 120 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Ceiling Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1108	Flush-mounted LED ceiling fixtures sized minimum 30x120 (with minimum 3300 lm light flux, and maximum 36 W consumption). / LED Ceiling Fixtures / LED Fixtures (Market price)	Qty	1	1.902,16	1.902,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.902,16	169,01
				Material and Installation w/o Profit (TRY)	2.071,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.588,96**	

Item No	Analysis Name					UoM
35.170.1201	**Minimum 2,000 lm light flux, maximum 30 W consumption. / LED Indirect Lighting Fixture / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1201	Minimum 2000 lm light flux, maximum 30 W consumption. / LED Indirect Lighting Fixtures / LED Fixtures (Market price)	Qty	1	2.203,76	2.203,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.203,76	169,01
				Material and Installation w/o Profit (TRY)	2.372,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.965,96**	

Item No	Analysis Name					UoM
35.170.1202	**Minimum 3,000 lm light flux, maximum 50 W consumption. / LED Indirect Lighting Fixture / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1202	Minimum 3000 lm light flux, maximum 50 W consumption. / LED Indirect Lighting Fixtures / LED Fixtures (Market price)	Qty	1	2.390,96	2.390,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			2.390,96	169,01
		Material and Installation w/o Profit (TRY)			2.559,97	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**3.199,96**	

Item No	Analysis Name					UoM
35.170.1301	**Surface-mounted LED ceiling fixtures sized minimum 60 x 60 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Clean Room Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1301	Surface-mounted LED ceiling fixtures sized minimum 60x60 (with minimum 3300 lm light flux, and maximum 36 w consumption). / LED Clean Room Ceiling Fixture / LED Fixtures (Market price)	Qty	1	3.630,12	3.630,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			3.630,12	169,01
		Material and Installation w/o Profit (TRY)			3.799,13	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**4.748,91**	

Item No	Analysis Name					UoM
35.170.1302	**Flush-mounted LED ceiling fixtures sized minimum 60 x 60 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Clean Room Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1302	Flush-mounted LED ceiling fixtures sized minimum 60x60 (with minimum 3300 lm light flux, and maximum 36 w consumption). / LED Clean Room Ceiling Fixture / LED Fixtures (Market price)	Qty	1	3.297,32	3.297,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	3.297,32	169,01
				Material and Installation w/o Profit (TRY)	3.466,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**4.332,91**	

Item No	Analysis Name					UoM
35.170.1303	**Surface-mounted LED ceiling fixtures sized minimum 30 x 120 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Clean Room Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1303	Surface-mounted LED ceiling fixtures sized minimum 30x120 (with minimum 3300 lm light flux, and maximum 36 W consumption). / LED Clean Room Ceiling Fixture / LED Fixtures (Market price)	Qty	1	3.921,32	3.921,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	3.921,32	169,01
				Material and Installation w/o Profit (TRY)	4.090,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**5.112,91**	

Item No	Analysis Name					UoM
35.170.1304	**Flush-mounted LED ceiling fixtures sized minimum 30 x 120 (with minimum 3,300 lm light flux, and maximum 36 w consumption). / LED Clean Room Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1304	Flush-mounted LED ceiling fixtures sized minimum 30x120 (with minimum 3300 lm light flux, and maximum 36 W consumption). / LED Clean Room Ceiling Fixture / LED Fixtures (Market price)	Qty	1	4.004,52	4.004,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	4.004,52	169,01
				Material and Installation w/o Profit (TRY)	4.173,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**5.216,91**	

Item No	Analysis Name					UoM
35.170.1501	**Flush-mounted, circular LED (downlight) fixtures (with minimum 800 lm light flux, maximum 12 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1501	Flush-mounted, circular LED (downlight) fixtures (with minimum 800 lm light flux, maximum 12 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures (Market price)	Qty	1	714,48	714,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	714,48	169,01
				Material and Installation w/o Profit (TRY)	883,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.104,36**	

Item No	Analysis Name					UoM
35.170.1502	**Flush-mounted, circular LED (downlight) fixtures (with minimum 1,700 lm light flux, maximum 24 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1502	Flush-mounted, circular LED (downlight) fixtures (with minimum 1700 lm light flux, maximum 24 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures (Market price)	Qty	1	940,16	940,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			940,16	169,01
		Material and Installation w/o Profit (TRY)			1.109,17	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**1.386,46**	

Item No	Analysis Name					UoM
35.170.1503	**Surface-mounted, circular (downlight) fixtures (with minimum 800 lm light flux, maximum 12 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1503	Surface-mounted, circular (downlight) fixtures (with minimum 800 lm light flux, maximum 12 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures (Market price)	Qty	1	1.164,80	1.164,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.164,80	169,01
		Material and Installation w/o Profit (TRY)			1.333,81	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**1.667,26**	

Item No	Analysis Name					UoM
35.170.1504	**Surface-mounted, circular (downlight) fixtures (with minimum 1,700 lm light flux, maximum 24 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1504	Surface-mounted, circular (downlight) fixtures (with minimum 1700 lm light flux, maximum 24 W consumption). / LED Circular (Downlight) Fixtures / LED Fixtures (Market price)	Qty	1	1.456,00	1.456,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.456,00	169,01
				Material and Installation w/o Profit (TRY)	1.625,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.031,26**	

Item No	Analysis Name					UoM
35.170.1601	**Minimum 1800 lm light flux, maximum 20 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1601	Minimum 1800 lm light flux, maximum 20 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures (Market price)	Qty	1	932,88	932,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	932,88	169,01
				Material and Installation w/o Profit (TRY)	1.101,89	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.377,36**	

Item No	Analysis Name					UoM
35.170.1602	**Minimum 2,700 lm light flux, maximum 30 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1602	Minimum 2700 lm light flux, maximum 30 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures (Market price)	Qty	1	1.358,24	1.358,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.358,24	169,01
				Material and Installation w/o Profit (TRY)	1.527,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.909,06**	

Item No	Analysis Name					UoM
35.170.1603	**Minimum 3,600 lm light flux, maximum 40 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1603	Minimum 3600 lm light flux, maximum 40 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures (Market price)	Qty	1	1.501,76	1.501,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.501,76	169,01
				Material and Installation w/o Profit (TRY)	1.670,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.088,46**	

Item No	Analysis Name					UoM
35.170.1701	**Minimum 1,800 lm light flux, maximum 20 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1701	Minimum 1800 lm light flux, maximum 20 W consumption. / LED Surface-mounted Weather-proof Fixtures (with aluminum body) / LED Fixtures (Market price)	Qty	1	1.535,04	1.535,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.535,04	169,01
				Material and Installation w/o Profit (TRY)	1.704,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.130,06**	

Item No	Analysis Name					UoM
35.170.1702	**Minimum 2,700 lm light flux, maximum 30 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1702	Minimum 2700 lm light flux, maximum 30 W consumption. / LED Surface-mounted Weather-proof Fixtures (with aluminum body) / LED Fixtures (Market price)	Qty	1	1.732,64	1.732,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.732,64	169,01
				Material and Installation w/o Profit (TRY)	1.901,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.377,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.1703	**Minimum 3,600 lm light flux, maximum 40 W consumption. / LED Surface-mounted Weather-proof Fixtures (with polycarbonate body) / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1703	Minimum 3600 lm light flux, maximum 40 W consumption. / LED Surface-mounted Weather-proof Fixtures (with aluminum body) / LED Fixtures (Market price)	Qty	1	1.896,96	1.896,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.896,96	169,01
				Material and Installation w/o Profit (TRY)	2.065,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**2.582,46**	

Item No	Analysis Name					UoM
35.170.1751						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1751	LED globe fixture (with polycarbonate body) with minimum 1800 lm light flux, and minimum fixture luminous efficacy of 100 lm/w (minimum IP40 protection grade) / LED Globe Fixture (with polycarbonate body) / LED FIXTURES (Market price)	Qty	1	749,95	749,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	749,95	169,01
				Material and Installation w/o Profit (TRY)	918,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**1.148,70**	

Item No	Analysis Name					UoM
35.170.1752						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1752	LED globe fixture (with polycarbonate body) with minimum 1800 lm light flux, and minimum fixture luminous efficacy of 100 lm/w (minimum IP65 protection grade) / LED Globe Fixture (with polycarbonate body) / LED FIXTURES (Market price)	Qty	1	968,13	968,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			968,13	169,01
		Material and Installation w/o Profit (TRY)			1.137,14	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**1.421,42**	

Item No	Analysis Name					UoM
35.170.1801	**Minimum 1800 lm light flux, maximum 20 W consumption (minimum IP 40 degree of protection). / LED Globe Fixtures / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1801	LED globe fixture (with aluminum body) with minimum 1800 lm light flux, and minimum fixture luminous efficacy of 100 lm/w (minimum IP40 protection grade) / LED Globe Fixture (with aluminum body) / LED FIXTURES (Market price)	Qty	1	1.248,00	1.248,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.248,00	169,01
		Material and Installation w/o Profit (TRY)			1.417,01	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**1.771,26**	

Item No	Analysis Name					UoM
35.170.1901	**Minimum 10,000 lm light flux, maximum 120 W consumption. / LED High Ceiling Fixture / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1901	Minimum 10,000 lm light flux, maximum 120 W consumption / LED High Ceiling Fixture / LED Fixtures (Market price)	Qty	1	4.314,96	4.314,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
				Total Excluding Profit (TRY)	4.314,96	362,05
				Material and Installation w/o Profit (TRY)	4.677,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**452,56**	
				Unit Price (TRY)	**5.846,26**	

Item No	Analysis Name					UoM
35.170.1902	**Minimum 15,000 lm light flux, maximum 160 W consumption. / LED High Ceiling Fixture / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.1902	Minimum 15,000 lm light flux, maximum 160 W consumption / LED High Ceiling Fixture / LED Fixtures (Market price)	Qty	1	5.230,16	5.230,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
				Total Excluding Profit (TRY)	5.230,16	362,05
				Material and Installation w/o Profit (TRY)	5.592,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**452,56**	
				Unit Price (TRY)	**6.990,26**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2010						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2010	Surface-mounted, minimum 1800 lm light flux, luminous efficacy of radiation minimum of 100 lm/w, LED Linear fixture / LED FIXTURES / LIGHTING FIXTURES (Market price)	Qty	1	1.867,84	1.867,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.867,84	169,01
		Material and Installation w/o Profit (TRY)			2.036,85	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**2.546,06**	

Item No	Analysis Name					UoM
35.170.2011						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2011	Surface-mounted, minimum 2900 lm light flux, luminous efficacy of radiation minimum of 100 lm/w, LED Linear fixture / LED FIXTURES / LIGHTING FIXTURES (Market price)	Qty	1	2.377,44	2.377,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			2.377,44	169,01
		Material and Installation w/o Profit (TRY)			2.546,45	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**3.183,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2012						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2012	Surface-mounted, minimum 4200 lm light flux, luminous efficacy of radiation minimum of 100 lm/w, LED Linear fixture / LED FIXTURES / LIGHTING FIXTURES (Market price)	Qty	1	3.178,24	3.178,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			3.178,24	169,01
		Material and Installation w/o Profit (TRY)			3.347,25	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**4.184,06**	

Item No	Analysis Name					UoM
35.170.2020						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2020	Flush-mounted, minimum 1800 lm light flux, luminous efficacy of radiation minimum of 100 lm/w, LED Linear fixture / LED FIXTURES / LIGHTING FIXTURES (Market price)	Qty	1	1.951,04	1.951,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			1.951,04	169,01
		Material and Installation w/o Profit (TRY)			2.120,05	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**2.650,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2021						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2021	Flush-mounted, minimum 2900 lm light flux, luminous efficacy of radiation minimum of 100 lm/w, LED Linear fixture / LED FIXTURES / LIGHTING FIXTURES (Market price)	Qty	1	2.533,44	2.533,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			2.533,44	169,01
		Material and Installation w/o Profit (TRY)			2.702,45	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**3.378,06**	

Item No	Analysis Name					UoM
35.170.2022						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2022	Flush-mounted, minimum 4200 lm light flux, luminous efficacy of radiation minimum of 100 lm/w, LED Linear fixture / LED FIXTURES / LIGHTING FIXTURES (Market price)	Qty	1	3.147,04	3.147,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			3.147,04	169,01
		Material and Installation w/o Profit (TRY)			3.316,05	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**211,26**	
		Unit Price (TRY)			**4.145,06**	

Item No	Analysis Name					UoM
35.170.2110						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2110	LED bar fixture, minimum 700 lm light flux, luminous efficacy of radiation minimum of 80 lm/w (min. IP40) (min. IK07) / LED Bar Lighting Fixture / LED FIXTURES (Market price)	m	1	547,12	547,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	547,12	125,25
				Material and Installation w/o Profit (TRY)	672,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**840,46**	

Item No	Analysis Name					UoM
35.170.2112						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2112	LED bar fixture, minimum 1400 lm light flux, luminous efficacy of radiation minimum of 80 lm/w (min. IP40) (min. IK07) / LED Bar Lighting Fixture / LED FIXTURES (Market price)	m	1	656,54	656,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	656,54	125,25
				Material and Installation w/o Profit (TRY)	781,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**977,24**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2114						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2114	LED bar fixture, minimum 2000 lm light flux, luminous efficacy of radiation minimum of 80 lm/w (min. IP40) (min. IK07) / LED Bar Lighting Fixture / LED FIXTURES (Market price)	m	1	750,34	750,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	750,34	125,25
				Material and Installation w/o Profit (TRY)	875,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**1.094,49**	

Item No	Analysis Name					UoM
35.170.2116						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2116	LED bar fixture, minimum 700 lm light flux, luminous efficacy of radiation minimum of 100 lm/w (min. IP40) (min. IK07) / LED Bar Lighting Fixture / LED FIXTURES (Market price)	m	1	578,39	578,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	578,39	125,25
				Material and Installation w/o Profit (TRY)	703,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**879,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2118						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2118	LED bar fixture, minimum 1400 lm light flux, luminous efficacy of radiation minimum of 100 lm/w (min. IP40) (min. IK07) / LED Bar Lighting Fixture / LED FIXTURES (Market price)	m	1	703,44	703,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	703,44	125,25
				Material and Installation w/o Profit (TRY)	828,69	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**1.035,86**	

Item No	Analysis Name					UoM
35.170.2120						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2120	LED bar fixture, minimum 2000 lm light flux, luminous efficacy of radiation minimum of 100 lm/w (min. IP40) (min. IK07) / LED Bar Lighting Fixture / LED FIXTURES (Market price)	m	1	797,23	797,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	797,23	125,25
				Material and Installation w/o Profit (TRY)	922,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**1.153,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2210	Min. 100W / Driver (Power Supply) / LED FIXTURES (Market price)	Qty	1	1.719,50	1.719,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	1.719,50	155,25
				Material and Installation w/o Profit (TRY)	1.874,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**2.343,44**	

Item No	Analysis Name					UoM
35.170.2220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2220	Min. 200W / Driver (Power Supply) / LED FIXTURES (Market price)	Qty	1	2.344,78	2.344,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	2.344,78	155,25
				Material and Installation w/o Profit (TRY)	2.500,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**3.125,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2230	Min. 300W / Driver (Power Supply) / LED FIXTURES (Market price)	Qty	1	3.751,65	3.751,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	3.751,65	155,25
				Material and Installation w/o Profit (TRY)	3.906,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**4.883,63**	

Item No	Analysis Name					UoM
35.170.2310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2310	Min. 100 cm / Pendant Suspension / LED FIXTURES (Market price)	Qty	1	117,24	117,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	117,24	125,25
				Material and Installation w/o Profit (TRY)	242,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**303,11**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2320	Min. 150 cm / Pendant Suspension / LED FIXTURES (Market price)	Qty	1	135,28	135,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	135,28	125,25
				Material and Installation w/o Profit (TRY)	260,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**325,66**	

Item No	Analysis Name					UoM
35.170.2330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2330	Min. 200 cm / Pendant Suspension / LED FIXTURES (Market price)	Qty	1	162,34	162,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	162,34	125,25
				Material and Installation w/o Profit (TRY)	287,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**359,49**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2410						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2410	E27 socket globe fixture, min. IP40 / LED FIXTURES (Market price)	Qty	1	270,55	270,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	270,55	169,01
				Material and Installation w/o Profit (TRY)	439,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**549,45**	

Item No	Analysis Name					UoM
35.170.2420						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2420	E27 socket globe fixture, min. IP65 / LED FIXTURES (Market price)	Qty	1	450,92	450,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	450,92	169,01
				Material and Installation w/o Profit (TRY)	619,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**211,26**	
				Unit Price (TRY)	**774,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2510						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2510	LED light bulb, light flux of minimum 800 lm, luminous efficacy of minimum 90 lm/w / LED Light Bulb / LED FIXTURES (Market price)	Qty	1	78,16	78,16	
	Installation Components					
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	78,16	65,25
				Material and Installation w/o Profit (TRY)	143,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,56**	
				Unit Price (TRY)	**179,26**	

Item No	Analysis Name					UoM
35.170.2520						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2520	LED light bulb, light flux of minimum 1400 lm, luminous efficacy of minimum 90 lm/w / LED Light Bulb / LED FIXTURES (Market price)	Qty	1	101,61	101,61	
	Installation Components					
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	101,61	65,25
				Material and Installation w/o Profit (TRY)	166,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,56**	
				Unit Price (TRY)	**208,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.2530						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2530	LED light bulb, light flux of minimum 2000 lm, luminous efficacy of minimum 90 lm/w / LED Light Bulb / LED FIXTURES (Market price)	Qty	1	195,40	195,40	
	Installation Components					
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
		Total Excluding Profit (TRY)			195,40	65,25
		Material and Installation w/o Profit (TRY)			260,65	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**81,56**	
		Unit Price (TRY)			**325,81**	

Item No	Analysis Name					UoM
35.170.2600						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.2600	E27 Socket Pendant Fixture / LED FIXTURES (Market price)	Quantity	1	65,66	65,66	
	Installation Components					
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
		Total Excluding Profit (TRY)			65,66	65,25
		Material and Installation w/o Profit (TRY)			130,91	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**81,56**	
		Unit Price (TRY)			**163,64**	

Item No	Analysis Name					UoM
35.170.3000	**Price difference of LED lighting fixtures in compliance with the DALI protocol / LED Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.170.3000	**Material Components** Price difference of LED lighting fixtures in compliance with the DALI protocol / LED Fixtures (Market price)	Qty	1	1.289,60	1.289,60	
		Total Excluding Profit (TRY)			1.289,60	
		Material and Installation w/o Profit (TRY)			1.289,60	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.612,00**	

Item No	Analysis Name					UoM
35.170.3050	**Price difference of emergency lighting kits for LED lighting fixtures / LED Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.170.3050	**Material Components** Price difference of emergency lighting kits for LED lighting fixtures / LED Lighting Fixtures (Market price)	Qty	1	1.133,60	1.133,60	
		Total Excluding Profit (TRY)			1.133,60	
		Material and Installation w/o Profit (TRY)			1.133,60	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.417,00**	

Item No	Analysis Name					UoM
35.170.3110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.170.3110	**Material Components** 180º motion sensor / Price difference of LED lighting fixtures with sensor / LED FIXTURES (Market price)	Qty	1	504,51	504,51	
		Total Excluding Profit (TRY)			504,51	
		Material and Installation w/o Profit (TRY)			504,51	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**630,64**	

Item No	Analysis Name					UoM
35.170.3120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.170.3120	**Material Components** 360º motion sensor / Price difference of LED lighting fixtures with sensor / LED FIXTURES (Market price)	Qty	1	572,70	572,70	
		Total Excluding Profit (TRY)			572,70	
		Material and Installation w/o Profit (TRY)			572,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**715,88**	

Item No	Analysis Name					UoM
35.170.3130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.170.3130	**Material Components** Presence sensor / Price difference of LED lighting fixtures with sensor / LED FIXTURES (Market price)	Qty	1	886,31	886,31	
		Total Excluding Profit (TRY)			886,31	
		Material and Installation w/o Profit (TRY)			886,31	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.107,89**	

Item No	Analysis Name					UoM
35.170.3140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.170.3140	**Material Components** Radar sensor / Price difference of LED lighting fixtures with sensor / LED FIXTURES (Market price)	Qty	1	613,60	613,60	
		Total Excluding Profit (TRY)			613,60	
		Material and Installation w/o Profit (TRY)			613,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**767,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.4001	**Minimum 2,500 lm light flux, maximum 30 W consumption. / LED Projectors ( )**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.4001	Minimum 2,500 lm light flux, maximum 30 W consumption / LED Projectors / LED FIXTURES (Market price)	Qty	1	3.446,56	3.446,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
		Total Excluding Profit (TRY)			3.446,56	302,05
		Material and Installation w/o Profit (TRY)			3.748,61	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**377,56**	
		Unit Price (TRY)			**4.685,76**	

Item No	Analysis Name					UoM
35.170.4002	**Minimum 5,100 lm light flux, maximum 60 W consumption. / LED Projectors ( )**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.4002	Minimum 5,100 lm light flux, maximum 60 W consumption / LED Projectors / LED FIXTURES (Market price)	Qty	1	5.193,76	5.193,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
		Total Excluding Profit (TRY)			5.193,76	302,05
		Material and Installation w/o Profit (TRY)			5.495,81	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**377,56**	
		Unit Price (TRY)			**6.869,76**	

Item No	Analysis Name					UoM
35.170.4003	**Minimum 6,800 lm light flux, maximum 80 W consumption. / LED Projectors ( )**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.4003	Minimum 6,800 lm light flux, maximum 80 W consumption / LED Projectors / LED FIXTURES (Market price)	Qty	1	6.140,16	6.140,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
		Total Excluding Profit (TRY)			6.140,16	302,05
		Material and Installation w/o Profit (TRY)			6.442,21	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**377,56**	
		Unit Price (TRY)			**8.052,76**	

Item No	Analysis Name					UoM
35.170.4004	**Minimum 8,500 lm light flux, maximum 100 W consumption. / LED Projectors ( )**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.4004	Minimum 8,500 lm light flux, maximum 100 W consumption / LED Projectors / LED FIXTURES (Market price)	Qty	1	6.680,96	6.680,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
		Total Excluding Profit (TRY)			6.680,96	302,05
		Material and Installation w/o Profit (TRY)			6.983,01	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**377,56**	
		Unit Price (TRY)			**8.728,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.4005	**Minimum 12,750 lm light flux, maximum 150 W consumption. / LED Projectors ( )**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.4005	Minimum 12,750 lm light flux, maximum 150 W consumption / LED Projectors / LED FIXTURES (Market price)	Qty	1	7.304,96	7.304,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
		Total Excluding Profit (TRY)			7.304,96	302,05
		Material and Installation w/o Profit (TRY)			7.607,01	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**377,56**	
		Unit Price (TRY)			**9.508,76**	

Item No	Analysis Name					UoM
35.170.4006	**Minimum 17,000 lm light flux, maximum 200 W consumption. / LED Projectors ( )**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.4006	Minimum 17,000 lm light flux, maximum 200 W consumption / LED Projectors / LED FIXTURES (Market price)	Qty	1	8.334,56	8.334,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
19.100.1112	Forklift	h	0,02	687,95		13,76
19.100.1113	Mobile crane	h	0,06	1.079,77		64,79
		Total Excluding Profit (TRY)			8.334,56	302,05
		Material and Installation w/o Profit (TRY)			8.636,61	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**377,56**	
		Unit Price (TRY)			**10.795,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.5201	**180º wall-type, surface-mounted motion sensor / Motion Sensors**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.5201	180º wall-type, surface-mounted motion sensor / Motion Sensors / LED FIXTURES (Market price)	Qty	1	406,64	406,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	406,64	155,25
				Material and Installation w/o Profit (TRY)	561,89	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**702,36**	

Item No	Analysis Name					UoM
35.170.5202	**360º ceiling-type, surface-mounted motion sensor / Motion Sensors**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.5202	360º ceiling-type, surface-mounted motion sensor / Motion Sensors / LED FIXTURES (Market price)	Qty	1	374,40	374,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	374,40	155,25
				Material and Installation w/o Profit (TRY)	529,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**662,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.5203	**360º ceiling-type, flush-mounted motion sensor / Motion Sensors**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.5203	360º ceiling-type, flush-mounted motion sensor / Motion Sensors / LED FIXTURES (Market price)	Qty	1	430,56	430,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
		Total Excluding Profit (TRY)			430,56	155,25
		Material and Installation w/o Profit (TRY)			585,81	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**194,06**	
		Unit Price (TRY)			**732,26**	

Item No	Analysis Name					UoM
35.170.5210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.5210	360º radar sensor / Motion Sensors / LED FIXTURES (Market price)	Qty	1	572,02	572,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
		Total Excluding Profit (TRY)			572,02	155,25
		Material and Installation w/o Profit (TRY)			727,27	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**194,06**	
		Unit Price (TRY)			**909,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.8105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.8105	LED surface-mounted fixture suitable for potentially explosive atmospheres (Ex-Proof), at least 60 cm long, minimum 1000 lm light flux, luminous efficacy of minimum of 100 lm/w / LED Surface-mounted Fixture Suitable for Potentially Explosive Atmospheres (Ex-Proof) / LED Fixtures (Market price)	Qty	1	9.720,00	9.720,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	9.720,00	381,26
				Material and Installation w/o Profit (TRY)	10.101,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**476,57**	
				Unit Price (TRY)	**12.626,58**	

Item No	Analysis Name					UoM
35.170.8110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.8110	LED surface-mounted fixture suitable for potentially explosive atmospheres (Ex-Proof), at least 90 cm long, minimum 1500 lm light flux, luminous efficacy of minimum of 100 lm/w / LED Surface-mounted Fixture Suitable for Potentially Explosive Atmospheres (Ex-Proof) / LED Fixtures (Market price)	Qty	1	10.260,00	10.260,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	10.260,00	381,26
				Material and Installation w/o Profit (TRY)	10.641,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**476,57**	
				Unit Price (TRY)	**13.301,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.170.8115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.8115	LED surface-mounted fixture suitable for potentially explosive atmospheres (Ex-Proof), at least 120 cm long, minimum 3300 lm light flux, luminous efficacy of minimum of 100 lm/w / LED Surface-mounted Fixture Suitable for Potentially Explosive Atmospheres (Ex-Proof) / LED Fixtures (Market price)	Qty	1	11.617,50	11.617,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	11.617,50	381,26
				Material and Installation w/o Profit (TRY)	11.998,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**476,57**	
				Unit Price (TRY)	**14.998,45**	

Item No	Analysis Name					UoM
35.170.8120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.170.8120	LED surface-mounted fixture suitable for potentially explosive atmospheres (Ex-Proof), at least 150 cm long, minimum 5500 lm light flux, luminous efficacy of minimum of 100 lm/w / LED Surface-mounted Fixture Suitable for Potentially Explosive Atmospheres (Ex-Proof) / LED Fixtures (Market price)	Qty	1	13.687,50	13.687,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	13.687,50	381,26
				Material and Installation w/o Profit (TRY)	14.068,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**476,57**	
				Unit Price (TRY)	**17.585,95**	

Item No	Analysis Name					UoM
35.180.1101	**6 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1101	6 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	38.896,08	38.896,08	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,6	700,00		1.120,00
				Total Excluding Profit (TRY)	38.896,08	1.754,40
				Material and Installation w/o Profit (TRY)	40.650,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.193,00**	
				Unit Price (TRY)	**50.813,10**	

Item No	Analysis Name					UoM
35.180.1102	**6 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1102	6 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	51.383,28	51.383,28	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,11	687,95		75,67
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,6	700,00		1.120,00
				Total Excluding Profit (TRY)	51.383,28	1.795,67
				Material and Installation w/o Profit (TRY)	53.178,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.244,59**	
				Unit Price (TRY)	**66.473,69**	

Item No	Analysis Name					UoM
35.180.1103	**10 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1103	10 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	63.375,12	63.375,12	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,08	687,95		55,04
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,2	700,00		2.240,00
				Total Excluding Profit (TRY)	63.375,12	2.895,04
				Material and Installation w/o Profit (TRY)	66.270,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.618,80**	
				Unit Price (TRY)	**82.837,70**	

Item No	Analysis Name					UoM
35.180.1104	**10 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1104	10 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	94.200,96	94.200,96	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,15	687,95		103,19
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,2	700,00		2.240,00
				Total Excluding Profit (TRY)	94.200,96	2.943,19
				Material and Installation w/o Profit (TRY)	97.144,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.678,99**	
				Unit Price (TRY)	**121.430,19**	

Item No	Analysis Name					UoM
35.180.1105	**15 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1105	15 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	119.897,76	119.897,76	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,11	687,95		75,67
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,2	700,00		2.240,00
				Total Excluding Profit (TRY)	119.897,76	2.915,67
				Material and Installation w/o Profit (TRY)	122.813,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.644,59**	
				Unit Price (TRY)	**153.516,79**	

Item No	Analysis Name					UoM
35.180.1106	**15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1106	15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	169.640,16	169.640,16	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,19	687,95		130,71
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,2	700,00		2.240,00
				Total Excluding Profit (TRY)	169.640,16	3.135,71
				Material and Installation w/o Profit (TRY)	172.775,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.919,64**	
				Unit Price (TRY)	**215.969,84**	

Item No	Analysis Name					UoM
35.180.1151	**15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1151	1 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	8.270,04	8.270,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	8.270,04	538,14
				Material and Installation w/o Profit (TRY)	8.808,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**11.010,23**	

Item No	Analysis Name					UoM
35.180.1155	**15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1155	2 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	14.702,28	14.702,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	14.702,28	538,14
				Material and Installation w/o Profit (TRY)	15.240,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**19.050,53**	

Item No	Analysis Name					UoM
35.180.1158	**15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1158	3 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with one-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	16.999,52	16.999,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	16.999,52	538,14
				Material and Installation w/o Profit (TRY)	17.537,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**21.922,08**	

Item No	Analysis Name					UoM
35.180.1201	**10 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1201	10 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	106.244,40	106.244,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,15	687,95		103,19
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	106.244,40	3.503,19
				Material and Installation w/o Profit (TRY)	109.747,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.378,99**	
				Unit Price (TRY)	**137.184,49**	

Item No	Analysis Name					UoM
35.180.1202	**10 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1202	10 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	113.778,00	113.778,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,3	687,95		206,39
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			113.778,00	3.771,39
		Material and Installation w/o Profit (TRY)			117.549,39	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.714,24**	
		Unit Price (TRY)			**146.936,74**	

Item No	Analysis Name					UoM
35.180.1203	**15 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1203	15 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	121.002,00	121.002,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,23	687,95		158,23
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			121.002,00	3.723,23
		Material and Installation w/o Profit (TRY)			124.725,23	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.654,04**	
		Unit Price (TRY)			**155.906,54**	

Item No	Analysis Name					UoM
35.180.1204	**15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1204	15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	160.011,60	160.011,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,38	687,95		261,42
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			160.011,60	3.991,42
		Material and Installation w/o Profit (TRY)			164.003,02	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.989,27**	
		Unit Price (TRY)			**205.003,78**	

Item No	Analysis Name					UoM
35.180.1205	**20 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1205	20 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	146.286,00	146.286,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,3	687,95		206,39
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			146.286,00	3.771,39
		Material and Installation w/o Profit (TRY)			150.057,39	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.714,24**	
		Unit Price (TRY)			**187.571,74**	

Item No	Analysis Name					UoM
35.180.1206	**20 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1206	20 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	210.682,80	210.682,80	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,53	687,95		364,61
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			210.682,80	4.259,61
		Material and Installation w/o Profit (TRY)			214.942,41	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**5.324,51**	
		Unit Price (TRY)			**268.678,01**	

Item No	Analysis Name					UoM
35.180.1207	**40 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1207	40 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	248.412,72	248.412,72	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,6	687,95		412,77
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
		Total Excluding Profit (TRY)			248.412,72	6.307,77
		Material and Installation w/o Profit (TRY)			254.720,49	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**7.884,71**	
		Unit Price (TRY)			**318.400,61**	

Item No	Analysis Name					UoM
35.180.1208	**40 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1208	40 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and one-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	365.173,20	365.173,20	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	1,05	687,95		722,35
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	365.173,20	7.112,35
				Material and Installation w/o Profit (TRY)	372.285,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.890,44**	
				Unit Price (TRY)	**465.356,94**	

Item No	Analysis Name					UoM
35.180.1301	**10 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1301	10 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	116.523,12	116.523,12	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	0,15	687,95		103,19
				Total Excluding Profit (TRY)	116.523,12	3.503,19
				Material and Installation w/o Profit (TRY)	120.026,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.378,99**	
				Unit Price (TRY)	**150.032,89**	

Item No	Analysis Name					UoM
35.180.1302	**10 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1302	10 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	124.263,12	124.263,12	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	124.263,12	3.771,39
				Material and Installation w/o Profit (TRY)	128.034,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.714,24**	
				Unit Price (TRY)	**160.043,14**	

Item No	Analysis Name					UoM
35.180.1303	**15 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1303	15 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	126.739,92	126.739,92	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	0,23	687,95		158,23
				Total Excluding Profit (TRY)	126.739,92	3.723,23
				Material and Installation w/o Profit (TRY)	130.463,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.654,04**	
				Unit Price (TRY)	**163.078,94**	

Item No	Analysis Name					UoM
35.180.1304	**15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1304	15 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	163.788,72	163.788,72	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	0,38	687,95		261,42
				Total Excluding Profit (TRY)	163.788,72	3.991,42
				Material and Installation w/o Profit (TRY)	167.780,14	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.989,27**	
				Unit Price (TRY)	**209.725,18**	

Item No	Analysis Name					UoM
35.180.1305	**20 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1305	20 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	145.935,12	145.935,12	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	145.935,12	3.771,39
				Material and Installation w/o Profit (TRY)	149.706,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.714,24**	
				Unit Price (TRY)	**187.133,14**	

Item No	Analysis Name					UoM
35.180.1306	**20 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1306	20 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	167.916,72	167.916,72	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	0,53	687,95		364,61
				Total Excluding Profit (TRY)	167.916,72	5.659,61
				Material and Installation w/o Profit (TRY)	173.576,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**7.074,51**	
				Unit Price (TRY)	**216.970,41**	

Item No	Analysis Name					UoM
35.180.1307	**30 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1307	30 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	195.931,12	195.931,12	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	0,45	687,95		309,58
				Total Excluding Profit (TRY)	195.931,12	5.604,58
				Material and Installation w/o Profit (TRY)	201.535,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**7.005,73**	
				Unit Price (TRY)	**251.919,62**	

Item No	Analysis Name					UoM
35.180.1308	**30 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1308	30 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	219.310,32	219.310,32	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	0,68	687,95		467,81
				Total Excluding Profit (TRY)	219.310,32	5.927,81
				Material and Installation w/o Profit (TRY)	225.238,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.409,76**	
				Unit Price (TRY)	**281.547,66**	

Item No	Analysis Name					UoM
35.180.1309	**40 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1309	40 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	231.591,12	231.591,12	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	0,6	687,95		412,77
				Total Excluding Profit (TRY)	231.591,12	6.307,77
				Material and Installation w/o Profit (TRY)	237.898,89	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.884,71**	
				Unit Price (TRY)	**297.373,61**	

Item No	Analysis Name					UoM
35.180.1310	**40 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1310	40 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	349.135,92	349.135,92	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1112	Forklift	h	1,05	687,95		722,35
				Total Excluding Profit (TRY)	349.135,92	8.512,35
				Material and Installation w/o Profit (TRY)	357.648,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**10.640,44**	
				Unit Price (TRY)	**447.060,34**	

Item No	Analysis Name					UoM
35.180.1311	**60 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1311	60 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	371.685,12	371.685,12	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1112	Forklift	h	0,9	687,95		619,16
				Total Excluding Profit (TRY)	371.685,12	8.244,16
				Material and Installation w/o Profit (TRY)	379.929,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**10.305,20**	
				Unit Price (TRY)	**474.911,60**	

Item No	Analysis Name					UoM
35.180.1312	**60 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1312	60 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	411.107,52	411.107,52	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1112	Forklift	h	1,5	687,95		1.031,93
				Total Excluding Profit (TRY)	411.107,52	10.881,93
				Material and Installation w/o Profit (TRY)	421.989,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.602,41**	
				Unit Price (TRY)	**527.486,81**	

Item No	Analysis Name					UoM
35.180.1313	**80 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1313	80 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	483.037,92	483.037,92	
	Installation Components					
10.100.1062	Unskilled worker	h	10	165,00		1.650,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1112	Forklift	h	1,2	687,95		825,54
				Total Excluding Profit (TRY)	483.037,92	10.345,54
				Material and Installation w/o Profit (TRY)	493.383,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**12.931,93**	
				Unit Price (TRY)	**616.729,32**	

Item No	Analysis Name					UoM
35.180.1314	**80 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1314	80 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	569.725,92	569.725,92	
	Installation Components					
10.100.1062	Unskilled worker	h	17	165,00		2.805,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1112	Forklift	h	2,1	687,95		1.444,70
				Total Excluding Profit (TRY)	569.725,92	12.119,70
				Material and Installation w/o Profit (TRY)	581.845,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.149,63**	
				Unit Price (TRY)	**727.307,03**	

Item No	Analysis Name					UoM
35.180.1315	**100 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1315	100 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	571.046,88	571.046,88	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	1,5	687,95		1.031,93
				Total Excluding Profit (TRY)	571.046,88	12.281,93
				Material and Installation w/o Profit (TRY)	583.328,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.352,41**	
				Unit Price (TRY)	**729.161,01**	

Item No	Analysis Name					UoM
35.180.1316	**100 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1316	100 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	709.747,68	709.747,68	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	2,55	687,95		1.754,27
				Total Excluding Profit (TRY)	709.747,68	14.324,27
				Material and Installation w/o Profit (TRY)	724.071,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.905,34**	
				Unit Price (TRY)	**905.089,94**	

Item No	Analysis Name					UoM
35.180.1317	**120 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1317	120 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	664.236,48	664.236,48	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	1,8	687,95		1.238,31
				Total Excluding Profit (TRY)	664.236,48	14.653,31
				Material and Installation w/o Profit (TRY)	678.889,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**18.316,64**	
				Unit Price (TRY)	**848.612,24**	

Item No	Analysis Name					UoM
35.180.1318	**120 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1318	120 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	897.772,80	897.772,80	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	3,08	687,95		2.118,89
				Total Excluding Profit (TRY)	897.772,80	17.348,89
				Material and Installation w/o Profit (TRY)	915.121,69	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**21.686,11**	
				Unit Price (TRY)	**1.143.902,11**	

Item No	Analysis Name					UoM
35.180.1319	**160 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1319	160 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	726.259,68	726.259,68	
	Installation Components					
10.100.1062	Unskilled worker	h	19	165,00		3.135,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	2,4	687,95		1.651,08
				Total Excluding Profit (TRY)	726.259,68	15.891,08
				Material and Installation w/o Profit (TRY)	742.150,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**19.863,85**	
				Unit Price (TRY)	**927.688,45**	

Item No	Analysis Name					UoM
35.180.1320	**160 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1320	160 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	920.069,28	920.069,28	
	Installation Components					
10.100.1062	Unskilled worker	h	26	165,00		4.290,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	3,19	687,95		2.194,56
				Total Excluding Profit (TRY)	920.069,28	17.589,56
				Material and Installation w/o Profit (TRY)	937.658,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**21.986,95**	
				Unit Price (TRY)	**1.172.073,55**	

Item No	Analysis Name					UoM
35.180.1321	**160 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1321	160 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.034.518,08	1.034.518,08	
	Installation Components					
10.100.1062	Unskilled worker	h	32	165,00		5.280,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	3,94	687,95		2.710,52
				Total Excluding Profit (TRY)	1.034.518,08	19.095,52
				Material and Installation w/o Profit (TRY)	1.053.613,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**23.869,40**	
				Unit Price (TRY)	**1.317.017,00**	

Item No	Analysis Name					UoM
35.180.1322	**160 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1322	160 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.106.448,48	1.106.448,48	
	Installation Components					
10.100.1062	Unskilled worker	h	38	165,00		6.270,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	4,69	687,95		3.226,49
				Total Excluding Profit (TRY)	1.106.448,48	20.601,49
				Material and Installation w/o Profit (TRY)	1.127.049,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**25.751,86**	
				Unit Price (TRY)	**1.408.812,46**	

Item No	Analysis Name					UoM
35.180.1323	**200 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1323	200 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	986.530,08	986.530,08	
	Installation Components					
10.100.1062	Unskilled worker	h	24	165,00		3.960,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	986.530,08	18.963,85
				Material and Installation w/o Profit (TRY)	1.005.493,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**23.704,81**	
				Unit Price (TRY)	**1.256.867,41**	

Item No	Analysis Name					UoM
35.180.1324	**200 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1324	200 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.106.448,48	1.106.448,48	
	Installation Components					
10.100.1062	Unskilled worker	h	32	165,00		5.280,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	3,94	687,95		2.710,52
				Total Excluding Profit (TRY)	1.106.448,48	20.930,52
				Material and Installation w/o Profit (TRY)	1.127.379,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**26.163,15**	
				Unit Price (TRY)	**1.409.223,75**	

Item No	Analysis Name					UoM
35.180.1325	**200 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1325	200 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.181.784,48	1.181.784,48	
	Installation Components					
10.100.1062	Unskilled worker	h	39	165,00		6.435,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	4,88	687,95		3.357,20
				Total Excluding Profit (TRY)	1.181.784,48	22.732,20
				Material and Installation w/o Profit (TRY)	1.204.516,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**28.415,25**	
				Unit Price (TRY)	**1.505.645,85**	

Item No	Analysis Name					UoM
35.180.1326	**200 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1326	200 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.404.386,88	1.404.386,88	
	Installation Components					
10.100.1062	Unskilled worker	h	48	165,00		7.920,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	6	687,95		4.127,70
				Total Excluding Profit (TRY)	1.404.386,88	24.987,70
				Material and Installation w/o Profit (TRY)	1.429.374,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.234,63**	
				Unit Price (TRY)	**1.786.718,22**	

Item No	Analysis Name					UoM
35.180.1327	**250 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1327	250 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.222.858,08	1.222.858,08	
	Installation Components					
10.100.1062	Unskilled worker	h	30	165,00		4.950,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	3,75	687,95		2.579,81
				Total Excluding Profit (TRY)	1.222.858,08	23.269,81
				Material and Installation w/o Profit (TRY)	1.246.127,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**29.087,26**	
				Unit Price (TRY)	**1.557.659,86**	

Item No	Analysis Name					UoM
35.180.1328	**250 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1328	250 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.281.166,08	1.281.166,08	
	Installation Components					
10.100.1062	Unskilled worker	h	39	165,00		6.435,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	4,88	687,95		3.357,20
				Total Excluding Profit (TRY)	1.281.166,08	25.532,20
				Material and Installation w/o Profit (TRY)	1.306.698,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.915,25**	
				Unit Price (TRY)	**1.633.372,85**	

Item No	Analysis Name					UoM
35.180.1329	**250 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1329	250 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.575.698,88	1.575.698,88	
	Installation Components					
10.100.1062	Unskilled worker	h	48	165,00		7.920,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	6	687,95		4.127,70
				Total Excluding Profit (TRY)	1.575.698,88	27.787,70
				Material and Installation w/o Profit (TRY)	1.603.486,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**34.734,63**	
				Unit Price (TRY)	**2.004.358,22**	

Item No	Analysis Name					UoM
35.180.1330	**250 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1330	250 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.695.617,28	1.695.617,28	
	Installation Components					
10.100.1062	Unskilled worker	h	56	165,00		9.240,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	7,05	687,95		4.850,05
				Total Excluding Profit (TRY)	1.695.617,28	29.830,05
				Material and Installation w/o Profit (TRY)	1.725.447,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**37.287,56**	
				Unit Price (TRY)	**2.156.809,16**	

Item No	Analysis Name					UoM
35.180.1331	**300 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1331	300 kVA, and minimum 5 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.435.243,68	1.435.243,68	
	Installation Components					
10.100.1062	Unskilled worker	h	36	165,00		5.940,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	4,5	687,95		3.095,78
				Total Excluding Profit (TRY)	1.435.243,68	25.210,78
				Material and Installation w/o Profit (TRY)	1.460.454,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.513,47**	
				Unit Price (TRY)	**1.825.568,07**	

Item No	Analysis Name					UoM
35.180.1332	**300 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1332	300 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.777.764,48	1.777.764,48	
	Installation Components					
10.100.1062	Unskilled worker	h	47	165,00		7.755,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	5,81	687,95		3.996,99
				Total Excluding Profit (TRY)	1.777.764,48	30.726,99
				Material and Installation w/o Profit (TRY)	1.808.491,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**38.408,74**	
				Unit Price (TRY)	**2.260.614,34**	

Item No	Analysis Name					UoM
35.180.1333	**300 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1333	300 kVA, and minimum 15 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	1.860.014,88	1.860.014,88	
	Installation Components					
10.100.1062	Unskilled worker	h	57	165,00		9.405,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	7,13	687,95		4.905,08
				Total Excluding Profit (TRY)	1.860.014,88	33.285,08
				Material and Installation w/o Profit (TRY)	1.893.299,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**41.606,35**	
				Unit Price (TRY)	**2.366.624,95**	

Item No	Analysis Name					UoM
35.180.1334	**300 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1334	300 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	2.325.859,68	2.325.859,68	
	Installation Components					
10.100.1062	Unskilled worker	h	66	165,00		10.890,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	8,25	687,95		5.675,59
				Total Excluding Profit (TRY)	2.325.859,68	35.540,59
				Material and Installation w/o Profit (TRY)	2.361.400,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**44.425,74**	
				Unit Price (TRY)	**2.951.750,34**	

Item No	Analysis Name					UoM
35.180.1335	**400 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1335	400 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	2.405.622,96	2.405.622,96	
	Installation Components					
10.100.1062	Unskilled worker	h	63	165,00		10.395,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	28	700,00		19.600,00
19.100.1112	Forklift	h	7,88	687,95		5.421,05
				Total Excluding Profit (TRY)	2.405.622,96	38.026,05
				Material and Installation w/o Profit (TRY)	2.443.649,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**47.532,56**	
				Unit Price (TRY)	**3.054.561,26**	

Item No	Analysis Name					UoM
35.180.1336	**400 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1336	400 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	2.562.177,36	2.562.177,36	
	Installation Components					
10.100.1062	Unskilled worker	h	84	165,00		13.860,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	28	700,00		19.600,00
19.100.1112	Forklift	h	10,5	687,95		7.223,48
				Total Excluding Profit (TRY)	2.562.177,36	43.293,48
				Material and Installation w/o Profit (TRY)	2.605.470,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**54.116,85**	
				Unit Price (TRY)	**3.256.838,55**	

Item No	Analysis Name					UoM
35.180.1337	**500 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1337	500 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	3.387.674,16	3.387.674,16	
	Installation Components					
10.100.1062	Unskilled worker	h	78	165,00		12.870,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician's helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	32	700,00		22.400,00
19.100.1112	Forklift	h	9,75	687,95		6.707,51
				Total Excluding Profit (TRY)	3.387.674,16	45.022,51
				Material and Installation w/o Profit (TRY)	3.432.696,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56.278,14**	
				Unit Price (TRY)	**4.290.870,84**	

Item No	Analysis Name					UoM
35.180.1338	**500 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1338	500 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	3.901.506,96	3.901.506,96	
	Installation Components					
10.100.1062	Unskilled worker	h	102	165,00		16.830,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician's helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	32	700,00		22.400,00
19.100.1112	Forklift	h	12,75	687,95		8.771,36
				Total Excluding Profit (TRY)	3.901.506,96	51.046,36
				Material and Installation w/o Profit (TRY)	3.952.553,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63.807,95**	
				Unit Price (TRY)	**4.940.691,65**	

Item No	Analysis Name					UoM
35.180.1339	**600 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1339	600 kVA, and minimum 10 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	3.843.302,16	3.843.302,16	
	Installation Components					
10.100.1062	Unskilled worker	h	93	165,00		15.345,00
10.100.1081	Master electrician	h	9	250,00		2.250,00
10.100.1083	Master electrician's helper	h	9	185,00		1.665,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	11,63	687,95		8.000,86
				Total Excluding Profit (TRY)	3.843.302,16	52.460,86
				Material and Installation w/o Profit (TRY)	3.895.763,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**65.576,07**	
				Unit Price (TRY)	**4.869.703,78**	

Item No	Analysis Name					UoM
35.180.1340	**600 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (TS EN 50091-2) Compliance with the Regulation on Amendment of Energy Market Customer Services published in the Official Gazette No. 26558 dated June 20, 2007, is required.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1340	600 kVA, and minimum 20 minutes of battery supply time / Uninterruptible Power Supply with 3-phase input and 3-phase output / Uninterruptible Power Supply (UPS) (Market price)	Qty	1	5.086.655,76	5.086.655,76	
	Installation Components					
10.100.1062	Unskilled worker	h	120	165,00		19.800,00
10.100.1081	Master electrician	h	9	250,00		2.250,00
10.100.1083	Master electrician’s helper	h	9	185,00		1.665,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	15	687,95		10.319,25
				Total Excluding Profit (TRY)	5.086.655,76	59.234,25
				Material and Installation w/o Profit (TRY)	5.145.890,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74.042,81**	
				Unit Price (TRY)	**6.432.362,51**	

Item No	Analysis Name					UoM
35.180.1401	**For 10 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1401	For 10 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	3.952,56	3.952,56	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.952,56	1.635,00
				Material and Installation w/o Profit (TRY)	5.587,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**6.984,45**	

Item No	Analysis Name					UoM
35.180.1402	**For 15 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1402	For 15 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	4.850,40	4.850,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	4.850,40	1.635,00
				Material and Installation w/o Profit (TRY)	6.485,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**8.106,75**	

Item No	Analysis Name					UoM
35.180.1403	**For 20 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1403	For 20 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	5.572,80	5.572,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	5.572,80	1.635,00
				Material and Installation w/o Profit (TRY)	7.207,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**9.009,75**	

Item No	Analysis Name					UoM
35.180.1404	**For 30 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1404	For 30 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	7.048,56	7.048,56	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	7.048,56	1.635,00
				Material and Installation w/o Profit (TRY)	8.683,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**10.854,45**	

Item No	Analysis Name					UoM
35.180.1405	**For 40 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1405	For 40 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	10.887,60	10.887,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	10.887,60	1.635,00
				Material and Installation w/o Profit (TRY)	12.522,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**15.653,25**	

Item No	Analysis Name					UoM
35.180.1407	**For 60 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1407	For 60 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	12.920,64	12.920,64	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	12.920,64	1.635,00
				Material and Installation w/o Profit (TRY)	14.555,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**18.194,55**	

Item No	Analysis Name					UoM
35.180.1408	**For 80 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1408	For 80 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	18.111,60	18.111,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	18.111,60	1.635,00
				Material and Installation w/o Profit (TRY)	19.746,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**24.683,25**	

Item No	Analysis Name					UoM
35.180.1409	**For 100 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1409	For 100 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	24.406,80	24.406,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	24.406,80	1.635,00
				Material and Installation w/o Profit (TRY)	26.041,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**32.552,25**	

Item No	Analysis Name					UoM
35.180.1410	**For 120 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1410	For 120 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	24.995,04	24.995,04	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	24.995,04	1.635,00
				Material and Installation w/o Profit (TRY)	26.630,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**33.287,55**	

Item No	Analysis Name					UoM
35.180.1411	**For 160 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1411	For 160 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	66.615,60	66.615,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	66.615,60	1.635,00
				Material and Installation w/o Profit (TRY)	68.250,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**85.313,25**	

Item No	Analysis Name					UoM
35.180.1412	**For 200 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1412	For 200 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	77.111,04	77.111,04	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	77.111,04	1.635,00
				Material and Installation w/o Profit (TRY)	78.746,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**98.432,55**	

Item No	Analysis Name					UoM
35.180.1413	**For 250 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1413	For 250 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	88.772,64	88.772,64	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	88.772,64	1.635,00
				Material and Installation w/o Profit (TRY)	90.407,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**113.009,55**	

Item No	Analysis Name					UoM
35.180.1414	**For 300 kVA UPS / Mechanical by-pass (including the external enclosure)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1414	For 300 kVA UPS / Mechanical by-pass (including the external enclosure) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	103.746,96	103.746,96	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	103.746,96	1.635,00
				Material and Installation w/o Profit (TRY)	105.381,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**131.727,45**	

Item No	Analysis Name					UoM
35.180.1501	**For 10 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1501	For 10 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	11.449,20	11.449,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	11.449,20	1.635,00
				Material and Installation w/o Profit (TRY)	13.084,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**16.355,25**	

Item No	Analysis Name					UoM
35.180.1502	**For 15 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1502	For 15 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	11.533,20	11.533,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	11.533,20	1.635,00
				Material and Installation w/o Profit (TRY)	13.168,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**16.460,25**	

Item No	Analysis Name					UoM
35.180.1503	**For 20 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1503	For 20 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	11.508,00	11.508,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	11.508,00	1.635,00
				Material and Installation w/o Profit (TRY)	13.143,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**16.428,75**	

Item No	Analysis Name					UoM
35.180.1504	**For 30 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1504	For 30 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	11.760,00	11.760,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	11.760,00	1.635,00
				Material and Installation w/o Profit (TRY)	13.395,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**16.743,75**	

Item No	Analysis Name					UoM
35.180.1505	**For 40 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1505	For 40 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	11.844,00	11.844,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	11.844,00	1.635,00
				Material and Installation w/o Profit (TRY)	13.479,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**16.848,75**	

Item No	Analysis Name					UoM
35.180.1506	**For 60 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1506	For 60 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	12.138,00	12.138,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	12.138,00	1.635,00
				Material and Installation w/o Profit (TRY)	13.773,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**17.216,25**	

Item No	Analysis Name					UoM
35.180.1507	**For 80 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1507	For 80 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	12.457,20	12.457,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	12.457,20	1.635,00
				Material and Installation w/o Profit (TRY)	14.092,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**17.615,25**	

Item No	Analysis Name					UoM
35.180.1508	**For 100 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1508	For 100 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	12.583,20	12.583,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	12.583,20	1.635,00
				Material and Installation w/o Profit (TRY)	14.218,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**17.772,75**	

Item No	Analysis Name					UoM
35.180.1509	**For 120 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1509	For 120 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	13.104,00	13.104,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	13.104,00	1.635,00
				Material and Installation w/o Profit (TRY)	14.739,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**18.423,75**	

Item No	Analysis Name					UoM
35.180.1510	**For 160 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1510	For 160 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	13.356,00	13.356,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	13.356,00	1.635,00
				Material and Installation w/o Profit (TRY)	14.991,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**18.738,75**	

Item No	Analysis Name					UoM
35.180.1511	**For 200 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1511	For 200 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	16.590,00	16.590,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	16.590,00	1.635,00
				Material and Installation w/o Profit (TRY)	18.225,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**22.781,25**	

Item No	Analysis Name					UoM
35.180.1512	**For 250 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1512	For 250 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	16.564,80	16.564,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	16.564,80	1.635,00
				Material and Installation w/o Profit (TRY)	18.199,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**22.749,75**	

Item No	Analysis Name					UoM
35.180.1513	**For 300 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1513	For 300 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	16.590,00	16.590,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	16.590,00	1.635,00
				Material and Installation w/o Profit (TRY)	18.225,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**22.781,25**	

Item No	Analysis Name					UoM
35.180.1514	**For 400 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1514	For 400 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	16.590,00	16.590,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	16.590,00	1.635,00
				Material and Installation w/o Profit (TRY)	18.225,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**22.781,25**	

Item No	Analysis Name					UoM
35.180.1515	**For 500 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1515	For 500 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	21.109,20	21.109,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	21.109,20	1.635,00
				Material and Installation w/o Profit (TRY)	22.744,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**28.430,25**	

Item No	Analysis Name					UoM
35.180.1516	**For 600 kVA UPS / Paralleling kit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1516	For 600 kVA UPS / Paralleling kit / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	21.109,20	21.109,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	21.109,20	1.635,00
				Material and Installation w/o Profit (TRY)	22.744,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**28.430,25**	

Item No	Analysis Name					UoM
35.180.1600	**Uninterruptible power supply remote monitoring panel**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1600	Uninterruptible power supply remote monitoring panel / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	6.701,81	6.701,81	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
		Total Excluding Profit (TRY)			6.701,81	1.035,00
		Material and Installation w/o Profit (TRY)			7.736,81	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.293,75**	
		Unit Price (TRY)			**9.671,01**	

Item No	Analysis Name					UoM
35.180.1601	**SNMP software and adapter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.1601	SNMP software and adapter / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	11.558,40	11.558,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
		Total Excluding Profit (TRY)			11.558,40	11.717,50
		Material and Installation w/o Profit (TRY)			23.275,90	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**14.646,88**	
		Unit Price (TRY)			**29.094,88**	

Item No	Analysis Name					UoM
35.180.2101	**40 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2101	40 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	596.103,84	596.103,84	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	0,6	687,95		412,77
				Total Excluding Profit (TRY)	596.103,84	6.307,77
				Material and Installation w/o Profit (TRY)	602.411,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.884,71**	
				Unit Price (TRY)	**753.014,51**	

Item No	Analysis Name					UoM
35.180.2102	**60 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2102	60 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	624.669,60	624.669,60	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1112	Forklift	h	0,9	687,95		619,16
				Total Excluding Profit (TRY)	624.669,60	8.244,16
				Material and Installation w/o Profit (TRY)	632.913,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**10.305,20**	
				Unit Price (TRY)	**791.142,20**	

Item No	Analysis Name					UoM
35.180.2103	**80 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2103	80 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	835.816,80	835.816,80	
	Installation Components					
10.100.1062	Unskilled worker	h	10	165,00		1.650,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1112	Forklift	h	1,2	687,95		825,54
				Total Excluding Profit (TRY)	835.816,80	10.345,54
				Material and Installation w/o Profit (TRY)	846.162,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**12.931,93**	
				Unit Price (TRY)	**1.057.702,93**	

Item No	Analysis Name					UoM
35.180.2104	**100 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2104	100 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	862.132,80	862.132,80	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	1,5	687,95		1.031,93
				Total Excluding Profit (TRY)	862.132,80	12.281,93
				Material and Installation w/o Profit (TRY)	874.414,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**15.352,41**	
				Unit Price (TRY)	**1.093.018,41**	

Item No	Analysis Name					UoM
35.180.2105	**120 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2105	120 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.267.399,20	1.267.399,20	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	1,8	687,95		1.238,31
				Total Excluding Profit (TRY)	1.267.399,20	14.653,31
				Material and Installation w/o Profit (TRY)	1.282.052,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**18.316,64**	
				Unit Price (TRY)	**1.602.565,64**	

Item No	Analysis Name					UoM
35.180.2106	**140 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2106	140 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.306.821,60	1.306.821,60	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	2,5	687,95		1.719,88
				Total Excluding Profit (TRY)	1.306.821,60	16.342,38
				Material and Installation w/o Profit (TRY)	1.323.163,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**20.427,97**	
				Unit Price (TRY)	**1.653.954,98**	

Item No	Analysis Name					UoM
35.180.2107	**160 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2107	160 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.471.219,20	1.471.219,20	
	Installation Components					
10.100.1062	Unskilled worker	h	26	165,00		4.290,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	3,19	687,95		2.194,56
				Total Excluding Profit (TRY)	1.471.219,20	17.589,56
				Material and Installation w/o Profit (TRY)	1.488.808,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**21.986,95**	
				Unit Price (TRY)	**1.861.010,95**	

Item No	Analysis Name					UoM
35.180.2108	**180 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2108	180 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.551.715,20	1.551.715,20	
	Installation Components					
10.100.1062	Unskilled worker	h	29	165,00		4.785,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	3,5	687,95		2.407,83
				Total Excluding Profit (TRY)	1.551.715,20	19.215,33
				Material and Installation w/o Profit (TRY)	1.570.930,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**24.019,16**	
				Unit Price (TRY)	**1.963.663,16**	

Item No	Analysis Name					UoM
35.180.2109	**200 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2109	200 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.610.952,00	1.610.952,00	
	Installation Components					
10.100.1062	Unskilled worker	h	32	165,00		5.280,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	3,94	687,95		2.710,52
				Total Excluding Profit (TRY)	1.610.952,00	20.930,52
				Material and Installation w/o Profit (TRY)	1.631.882,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**26.163,15**	
				Unit Price (TRY)	**2.039.853,15**	

Item No	Analysis Name					UoM
35.180.2110	**300 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2110	300 kVA, and minimum 10 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	2.281.855,20	2.281.855,20	
	Installation Components					
10.100.1062	Unskilled worker	h	47	165,00		7.755,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	5,81	687,95		3.996,99
				Total Excluding Profit (TRY)	2.281.855,20	30.726,99
				Material and Installation w/o Profit (TRY)	2.312.582,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**38.408,74**	
				Unit Price (TRY)	**2.890.727,74**	

Item No	Analysis Name					UoM
35.180.2111	**400 kVA, and minimum 10 minutes of battery supply time, minimum 25% power increase capacity / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2111	400 kVA, and minimum 10 minutes of battery supply time, minimum 25% power increase capacity / Modular Uninterruptible Power Supply (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	3.274.639,20	3.274.639,20	
	Installation Components					
10.100.1062	Unskilled worker	h	63	165,00		10.395,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	28	700,00		19.600,00
19.100.1112	Forklift	h	7,88	687,95		5.421,05
				Total Excluding Profit (TRY)	3.274.639,20	38.026,05
				Material and Installation w/o Profit (TRY)	3.312.665,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**47.532,56**	
				Unit Price (TRY)	**4.140.831,56**	

Item No	Analysis Name					UoM
35.180.2112	**500 kVA, and minimum 10 minutes of battery supply time / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2112	500 kVA, and minimum 10 minutes of battery supply time / Modular Uninterruptible Power Supply (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	3.887.853,60	3.887.853,60	
	Installation Components					
10.100.1062	Unskilled worker	h	78	165,00		12.870,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	32	700,00		22.400,00
19.100.1112	Forklift	h	9,75	687,95		6.707,51
				Total Excluding Profit (TRY)	3.887.853,60	45.022,51
				Material and Installation w/o Profit (TRY)	3.932.876,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56.278,14**	
				Unit Price (TRY)	**4.916.095,14**	

Item No	Analysis Name					UoM
35.180.2200	**40 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2200	40 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	668.034,24	668.034,24	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1112	Forklift	h	1,05	687,95		722,35
				Total Excluding Profit (TRY)	668.034,24	8.512,35
				Material and Installation w/o Profit (TRY)	676.546,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**10.640,44**	
				Unit Price (TRY)	**845.683,24**	

Item No	Analysis Name					UoM
35.180.2201	**60 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2201	60 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	778.437,60	778.437,60	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1112	Forklift	h	1,5	687,95		1.031,93
				Total Excluding Profit (TRY)	778.437,60	10.881,93
				Material and Installation w/o Profit (TRY)	789.319,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**13.602,41**	
				Unit Price (TRY)	**986.649,41**	

Item No	Analysis Name					UoM
35.180.2202	**80 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2202	80 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.018.274,40	1.018.274,40	
	Installation Components					
10.100.1062	Unskilled worker	h	17	165,00		2.805,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1112	Forklift	h	2,1	687,95		1.444,70
				Total Excluding Profit (TRY)	1.018.274,40	12.119,70
				Material and Installation w/o Profit (TRY)	1.030.394,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**15.149,63**	
				Unit Price (TRY)	**1.287.992,63**	

Item No	Analysis Name					UoM
35.180.2203	**100 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2203	100 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.057.593,60	1.057.593,60	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	2,55	687,95		1.754,27
				Total Excluding Profit (TRY)	1.057.593,60	14.324,27
				Material and Installation w/o Profit (TRY)	1.071.917,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**17.905,34**	
				Unit Price (TRY)	**1.339.897,34**	

Item No	Analysis Name					UoM
35.180.2204	**120 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2204	120 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.500.321,60	1.500.321,60	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	3,08	687,95		2.118,89
				Total Excluding Profit (TRY)	1.500.321,60	17.348,89
				Material and Installation w/o Profit (TRY)	1.517.670,49	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**21.686,11**	
				Unit Price (TRY)	**1.897.088,11**	

Item No	Analysis Name					UoM
35.180.2205	**140 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2205	140 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.572.252,00	1.572.252,00	
	Installation Components					
10.100.1062	Unskilled worker	h	32	165,00		5.280,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	3,9	687,95		2.683,01
				Total Excluding Profit (TRY)	1.572.252,00	19.068,01
				Material and Installation w/o Profit (TRY)	1.591.320,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**23.835,01**	
				Unit Price (TRY)	**1.989.150,01**	

Item No	Analysis Name					UoM
35.180.2206	**160 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2206	160 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.911.367,20	1.911.367,20	
	Installation Components					
10.100.1062	Unskilled worker	h	38	165,00		6.270,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1112	Forklift	h	4,69	687,95		3.226,49
				Total Excluding Profit (TRY)	1.911.367,20	20.601,49
				Material and Installation w/o Profit (TRY)	1.931.968,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**25.751,86**	
				Unit Price (TRY)	**2.414.960,86**	

Item No	Analysis Name					UoM
35.180.2207	**180 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2207	180 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.753.780,80	1.753.780,80	
	Installation Components					
10.100.1062	Unskilled worker	h	43	165,00		7.095,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	5	687,95		3.439,75
				Total Excluding Profit (TRY)	1.753.780,80	22.557,25
				Material and Installation w/o Profit (TRY)	1.776.338,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**28.196,56**	
				Unit Price (TRY)	**2.220.422,56**	

Item No	Analysis Name					UoM
35.180.2208	**200 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2208	200 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	1.849.756,80	1.849.756,80	
	Installation Components					
10.100.1062	Unskilled worker	h	48	165,00		7.920,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	6	687,95		4.127,70
				Total Excluding Profit (TRY)	1.849.756,80	24.987,70
				Material and Installation w/o Profit (TRY)	1.874.744,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31.234,63**	
				Unit Price (TRY)	**2.343.430,63**	

Item No	Analysis Name					UoM
35.180.2209	**300 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2209	300 kVA, and minimum 20 minutes of battery supply time, minimum 50% power increase capacity / MODULAR UNINTERRUPTIBLE POWER SUPPLY (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	2.808.794,40	2.808.794,40	
	Installation Components					
10.100.1062	Unskilled worker	h	66	165,00		10.890,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	8,25	687,95		5.675,59
				Total Excluding Profit (TRY)	2.808.794,40	35.540,59
				Material and Installation w/o Profit (TRY)	2.844.334,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**44.425,74**	
				Unit Price (TRY)	**3.555.418,74**	

Item No	Analysis Name					UoM
35.180.2210	**400 kVA, and minimum 20 minutes of battery supply time, minimum 25% power increase capacity / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2210	400 kVA, and minimum 20 minutes of battery supply time, minimum 25% power increase capacity / Modular Uninterruptible Power Supply (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	3.923.767,20	3.923.767,20	
	Installation Components					
10.100.1062	Unskilled worker	h	84	165,00		13.860,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	28	700,00		19.600,00
19.100.1112	Forklift	h	10,5	687,95		7.223,48
				Total Excluding Profit (TRY)	3.923.767,20	43.293,48
				Material and Installation w/o Profit (TRY)	3.967.060,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**54.116,85**	
				Unit Price (TRY)	**4.958.825,85**	

Item No	Analysis Name					UoM
35.180.2211	**500 kVA, and minimum 20 minutes of battery supply time / Modular Uninterruptible Power Supply (UPS)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.2211	500 kVA, and minimum 20 minutes of battery supply time. / Modular Uninterruptible Power Supply (UPS) / UNINTERRUPTIBLE POWER SUPPLY (UPS) (Market price)	Qty	1	4.864.022,40	4.864.022,40	
	Installation Components					
10.100.1062	Unskilled worker	h	102	165,00		16.830,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	32	700,00		22.400,00
19.100.1112	Forklift	h	12,75	687,95		8.771,36
				Total Excluding Profit (TRY)	4.864.022,40	51.046,36
				Material and Installation w/o Profit (TRY)	4.915.068,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63.807,95**	
				Unit Price (TRY)	**6.143.835,95**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.180.3001	**3.15 kVA insulation power enclosure / Protection and safety insulation power system**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.3001	3,15 kVA insulation power enclosure / Protection and safety insulation power system (Market price)	Qty	1	66.791,04	66.791,04	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	66.791,04	8.340,00
				Material and Installation w/o Profit (TRY)	75.131,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**10.425,00**	
				Unit Price (TRY)	**93.913,80**	

Item No	Analysis Name					UoM
35.180.3002	**4 kVA insulation power enclosure / Protection and safety insulation power system**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.3002	4 kVA insulation power enclosure / Protection and safety insulation power system (Market price)	Qty	1	68.504,16	68.504,16	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician's helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	68.504,16	9.375,00
				Material and Installation w/o Profit (TRY)	77.879,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**11.718,75**	
				Unit Price (TRY)	**97.348,95**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.180.3003	**5 kVA insulation power enclosure / Protection and safety insulation power system**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.3003	5 kVA insulation power enclosure / Protection and safety insulation power system (Market price)	Qty	1	70.217,28	70.217,28	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	70.217,28	10.410,00
				Material and Installation w/o Profit (TRY)	80.627,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.012,50**	
				Unit Price (TRY)	**100.784,10**	

Item No	Analysis Name					UoM
35.180.3004	**6.13 kVA insulation power enclosure / Protection and safety insulation power system**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.3004	6,13 kVA insulation power enclosure / Protection and safety insulation power system (Market price)	Qty	1	71.930,40	71.930,40	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	71.930,40	11.445,00
				Material and Installation w/o Profit (TRY)	83.375,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.306,25**	
				Unit Price (TRY)	**104.219,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.180.3005	**8 kVA insulation power enclosure / Protection and safety insulation power system**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.3005	8 kVA insulation power enclosure / Protection and safety insulation power system (Market price)	Qty	1	73.643,52	73.643,52	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	73.643,52	12.480,00
				Material and Installation w/o Profit (TRY)	86.123,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.600,00**	
				Unit Price (TRY)	**107.654,40**	

Item No	Analysis Name					UoM
35.180.3006	**10 kVA insulation power enclosure / Protection and safety insulation power system**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.180.3006	10 kVA insulation power enclosure / Protection and safety insulation power system (Market price)	Qty	1	75.356,64	75.356,64	
	Installation Components					
10.100.1062	Unskilled worker	h	9	165,00		1.485,00
10.100.1081	Master electrician	h	18	250,00		4.500,00
10.100.1083	Master electrician's helper	h	18	185,00		3.330,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	75.356,64	13.515,00
				Material and Installation w/o Profit (TRY)	88.871,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**16.893,75**	
				Unit Price (TRY)	**111.089,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.1101	**Flush-mounted regular switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			45,47	133,50
		Material and Installation w/o Profit (TRY)			178,97	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**166,88**	
		Unit Price (TRY)			**223,71**	

Item No	Analysis Name					UoM
35.185.1102	**Flush-mounted commutator switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1102	Flush-mounted commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	44,39	44,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
		Total Excluding Profit (TRY)			44,39	177,00
		Material and Installation w/o Profit (TRY)			221,39	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**221,25**	
		Unit Price (TRY)			**276,74**	

Item No	Analysis Name					UoM
35.185.1103	**Flush-mounted two-way switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1103	Flush-mounted two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	43,85	43,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	43,85	177,00
				Material and Installation w/o Profit (TRY)	220,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**276,06**	

Item No	Analysis Name					UoM
35.185.1104	**Flush-mounted deviator switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1104	Flush-mounted deviator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	48,17	48,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	48,17	177,00
				Material and Installation w/o Profit (TRY)	225,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**281,46**	

Item No	Analysis Name					UoM
35.185.1110	**Surface-mounted regular switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1110	Surface-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	41,69	41,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	41,69	133,50
				Material and Installation w/o Profit (TRY)	175,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**166,88**	
				Unit Price (TRY)	**218,99**	

Item No	Analysis Name					UoM
35.185.1111	**Surface-mounted commutator switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1111	Surface-mounted commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	47,63	47,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	47,63	177,00
				Material and Installation w/o Profit (TRY)	224,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**280,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.1112	**Surface-mounted two-way switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1112	Surface-mounted two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
		Total Excluding Profit (TRY)			45,47	177,00
		Material and Installation w/o Profit (TRY)			222,47	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**221,25**	
		Unit Price (TRY)			**278,09**	

Item No	Analysis Name					UoM
35.185.1113	**Surface-mounted deviator switch (. (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1113	Surface-mounted deviator switch (. (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	47,63	47,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
		Total Excluding Profit (TRY)			47,63	177,00
		Material and Installation w/o Profit (TRY)			224,63	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**221,25**	
		Unit Price (TRY)			**280,79**	

Item No	Analysis Name					UoM
35.185.1120	**Weather-proof regular switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1120	Weather-proof regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	56,27	56,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	56,27	133,50
				Material and Installation w/o Profit (TRY)	189,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**166,88**	
				Unit Price (TRY)	**237,21**	

Item No	Analysis Name					UoM
35.185.1121	**Weather-proof commutator switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1121	Weather-proof commutator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,75	62,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	62,75	177,00
				Material and Installation w/o Profit (TRY)	239,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**299,69**	

Item No	Analysis Name					UoM
35.185.1122	**Weather-proof two-way switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1122	Weather-proof two-way switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	63,83	63,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	63,83	177,00
				Material and Installation w/o Profit (TRY)	240,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**301,04**	

Item No	Analysis Name					UoM
35.185.1123	**Weather-proof deviator switch (TS-4915 EN 60669-1) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1123	Weather-proof deviator switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	62,21	62,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician’s helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	62,21	177,00
				Material and Installation w/o Profit (TRY)	239,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**299,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.1201	**Flush-mounted earthed socket (TS-40) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1201	Flush-mounted earthed socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	47,09	47,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
		Total Excluding Profit (TRY)			47,09	177,00
		Material and Installation w/o Profit (TRY)			224,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**221,25**	
		Unit Price (TRY)			**280,11**	

Item No	Analysis Name					UoM
35.185.1202	**Surface-mounted earthed socket (TS-40) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1202	Surface-mounted earthed socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	52,49	52,49	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
		Total Excluding Profit (TRY)			52,49	177,00
		Material and Installation w/o Profit (TRY)			229,49	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**221,25**	
		Unit Price (TRY)			**286,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.1203	**Weather-proof power socket (TS-40) / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1203	Weather-proof power socket (TS-40) / Sockets / Separate Installation Parts (Market price)	Qty	1	74,09	74,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
		Total Excluding Profit (TRY)			74,09	177,00
		Material and Installation w/o Profit (TRY)			251,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**221,25**	
		Unit Price (TRY)			**313,86**	

Item No	Analysis Name					UoM
35.185.1230	**Flush-mounted junction box / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1230	Price difference for switch or socket with decorative frame / Separate Installation Parts (Market price)	Qty	1	48,00	48,00	
		Total Excluding Profit (TRY)			48,00	
		Material and Installation w/o Profit (TRY)			48,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**60,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.1250	**Flush-mounted junction box / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	20,01	155,25
				Material and Installation w/o Profit (TRY)	175,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**219,07**	

Item No	Analysis Name					UoM
35.185.1251	**Surface-mounted junction box / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1251	Surface-mounted junction box / Separate Installation Parts (Market price)	Qty	1	55,02	55,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	55,02	155,25
				Material and Installation w/o Profit (TRY)	210,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**262,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.1252	**Weather-proof junction box / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
			Total Excluding Profit (TRY)		71,52	155,25
			Material and Installation w/o Profit (TRY)		226,77	
% 25 Contractor’s Profit and Overheads Included			**Instal. Cost (TRY)**		**194,06**	
			Unit Price (TRY)		**283,46**	

Item No	Analysis Name					UoM
35.185.1260	**Supply to the work site and installation of regular start-stop buttons. / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1260	Supply to the work site and installation of regular start-stop buttons / Separate Installation Parts (Market price)	Qty	1	103,20	103,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
			Total Excluding Profit (TRY)		103,20	111,75
			Material and Installation w/o Profit (TRY)		214,95	
% 25 Contractor’s Profit and Overheads Included			**Instal. Cost (TRY)**		**139,69**	
			Unit Price (TRY)		**268,69**	

Item No	Analysis Name					UoM
35.185.1261	**Supply to the work site and installation of weather-proof start-stop buttons. / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1261	Supply to the work site and installation of weather-proof start-stop buttons. / Separate Installation Parts (Market price)	Qty	1	124,32	124,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	124,32	111,75
				Material and Installation w/o Profit (TRY)	236,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**139,69**	
				Unit Price (TRY)	**295,09**	

Item No	Analysis Name					UoM
35.185.1350	**Flush-mounted junction box / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
				Total Excluding Profit (TRY)	21,00	155,25
				Material and Installation w/o Profit (TRY)	176,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**194,06**	
				Unit Price (TRY)	**220,31**	

Item No	Analysis Name					UoM
35.185.1370	**Surface-mounted junction box / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1370	Surface-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	57,75	57,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician's helper	h	0,3	185,00		55,50
		Total Excluding Profit (TRY)			57,75	155,25
		Material and Installation w/o Profit (TRY)			213,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**194,06**	
		Unit Price (TRY)			**266,25**	

Item No	Analysis Name					UoM
35.185.1701	**2-pole (1NA+1NK contact), Max. Ø40 mm, mushroom head / Emergency (Emergency Stop) Button / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1701	2-pole (1NA+1NK contact), Max. Ø40 mm, mushroom head / Emergency (Emergency Stop) Button / Separate Installation Parts (Market price)	Qty	1	312,05	312,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			312,05	133,50
		Material and Installation w/o Profit (TRY)			445,55	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**166,88**	
		Unit Price (TRY)			**556,94**	

Item No	Analysis Name					UoM
35.185.1702	**2-pole (1NA+1NK contact), Max. Ø60 mm, mushroom head / Emergency (Emergency Stop) Button / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1702	2-pole (1NA+1NK contact), Max. Ø60 mm, mushroom head / Emergency (Emergency Stop) Button / Separate Installation Parts (Market price)	Qty	1	449,16	449,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	449,16	133,50
				Material and Installation w/o Profit (TRY)	582,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**166,88**	
				Unit Price (TRY)	**728,33**	

Item No	Analysis Name					UoM
35.185.1751	**Single button casing / Emergency (Emergency Stop) Button / Separate Installation Parts**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1751	Single button casing / Emergency Button Casing / Separate Installation Parts (Market price)	Qty	1	119,78	119,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	119,78	133,50
				Material and Installation w/o Profit (TRY)	253,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**166,88**	
				Unit Price (TRY)	**316,60**	

Item No	Analysis Name					UoM
35.185.1811	**Up to 3 x 25 A / Supply and installation in designated locations, including any material and labor, of 3-phase bakelite power sockets and plugs with covers and earth contacts. (TS-40). / 3-phase Plugs, Sockets and Installation (TS-40).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1811	Up to 3 x 25 A / Supply and installation in designated locations, including any material and labor, of 3-phase bakelite power sockets and plugs with covers and earth contacts. (TS-40) / 3-phase Plugs, Sockets and Installation (TS-40) (Market price)	Qty	1	133,06	133,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	133,06	207,00
				Material and Installation w/o Profit (TRY)	340,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**425,07**	

Item No	Analysis Name					UoM
35.185.1812	**Up to 3 x 60 A / Supply and installation in designated locations, including any material and labor, of 3-phase bakelite power sockets and plugs with covers and earth contacts. (TS-40). / 3-phase Plugs, Sockets and Installation (TS-40).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.1812	Up to 3 x 60 A / Supply and installation in designated locations, including any material and labor, of 3-phase bakelite power sockets and plugs with covers and earth contacts. (TS-40) / 3-phase Plugs, Sockets and Installation (TS-40) (Market price)	Qty	1	207,94	207,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	207,94	207,00
				Material and Installation w/o Profit (TRY)	414,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**518,67**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.2105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.2105	2P+E, 16-25 A, 220 V / Plug-Socket Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	7.986,40	7.986,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	7.986,40	207,00
				Material and Installation w/o Profit (TRY)	8.193,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**10.241,75**	

Item No	Analysis Name					UoM
35.185.2110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.2110	3P+E, 16-25 A, 380 V / Plug-Socket Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	8.316,00	8.316,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	8.316,00	207,00
				Material and Installation w/o Profit (TRY)	8.523,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**10.653,75**	

Item No	Analysis Name					UoM
35.185.2115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.2115	3P+N+E, 16-25 A, 380 V / Plug-Socket Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	8.491,50	8.491,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	8.491,50	207,00
				Material and Installation w/o Profit (TRY)	8.698,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**10.873,13**	

Item No	Analysis Name					UoM
35.185.2120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.2120	2P+E, 32 A, 220 V / Plug-Socket Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	9.016,80	9.016,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	9.016,80	207,00
				Material and Installation w/o Profit (TRY)	9.223,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**11.529,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.2125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.2125	3P+E, 32 A, 380 V / Plug-Socket Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	11.026,65	11.026,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	11.026,65	207,00
				Material and Installation w/o Profit (TRY)	11.233,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**14.042,06**	

Item No	Analysis Name					UoM
35.185.2130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.2130	3P+N+E, 32 A, 380 V / Plug-Socket Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	11.220,00	11.220,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	11.220,00	207,00
				Material and Installation w/o Profit (TRY)	11.427,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**14.283,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.3105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3105	Starting unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	2.695,52	2.695,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.695,52	207,00
				Material and Installation w/o Profit (TRY)	2.902,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.628,15**	

Item No	Analysis Name					UoM
35.185.3110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3110	Stopping unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	2.695,52	2.695,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.695,52	207,00
				Material and Installation w/o Profit (TRY)	2.902,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.628,15**	

Item No	Analysis Name					UoM
35.185.3115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3115	Emergency stopping unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	2.893,72	2.893,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.893,72	207,00
				Material and Installation w/o Profit (TRY)	3.100,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.875,90**	

Item No	Analysis Name					UoM
35.185.3120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3120	Starting+stopping unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	2.988,85	2.988,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.988,85	207,00
				Material and Installation w/o Profit (TRY)	3.195,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.994,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.3125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3125	Starting+stopping+emergency stopping unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	4.888,00	4.888,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	4.888,00	207,00
				Material and Installation w/o Profit (TRY)	5.095,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**6.368,75**	

Item No	Analysis Name					UoM
35.185.3130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3130	Starting+signaling unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	3.438,50	3.438,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.438,50	207,00
				Material and Installation w/o Profit (TRY)	3.645,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.556,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.3135						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3135	Starting+stopping+signaling unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	4.888,00	4.888,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	4.888,00	207,00
				Material and Installation w/o Profit (TRY)	5.095,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**6.368,75**	

Item No	Analysis Name					UoM
35.185.3140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3140	Starting+stopping+signaling+emergency stopping unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	6.474,00	6.474,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	6.474,00	207,00
				Material and Installation w/o Profit (TRY)	6.681,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**8.351,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.3145						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3145	Signaling unit / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	2.695,52	2.695,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.695,52	207,00
				Material and Installation w/o Profit (TRY)	2.902,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.628,15**	

Item No	Analysis Name					UoM
35.185.3150						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3150	Regular switch 0-1 state / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	2.977,00	2.977,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	2.977,00	207,00
				Material and Installation w/o Profit (TRY)	3.184,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**3.980,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.3155						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3155	Two-way switch 1-0-1 state / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	3.178,50	3.178,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.178,50	207,00
				Material and Installation w/o Profit (TRY)	3.385,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.231,88**	

Item No	Analysis Name					UoM
35.185.3160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.3160	Dual switch 0-1-2 state / Junction Box Suitable for Potentially Explosive Atmospheres (Ex-Proof) / Separate Installation Parts (Market price)	Qty	1	3.237,00	3.237,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	3.237,00	207,00
				Material and Installation w/o Profit (TRY)	3.444,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**4.305,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.5103						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5103	120 x 240 x 120 / Combination Box (Hollow) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	207,18	207,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	207,18	272,51
				Material and Installation w/o Profit (TRY)	479,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**340,64**	
				Unit Price (TRY)	**599,61**	

Item No	Analysis Name					UoM
35.185.5106						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5106	150 x 240 x 130 / Combination Box (Hollow) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	256,48	256,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	256,48	272,51
				Material and Installation w/o Profit (TRY)	528,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**340,64**	
				Unit Price (TRY)	**661,24**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.5109						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5109	210 x 290 x 120 / Combination Box (Hollow) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	369,07	369,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	369,07	324,26
				Material and Installation w/o Profit (TRY)	693,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**405,32**	
				Unit Price (TRY)	**866,66**	

Item No	Analysis Name					UoM
35.185.5112						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5112	240 x 290 x 130 / Combination Box (Hollow) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	461,00	461,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	461,00	374,64
				Material and Installation w/o Profit (TRY)	835,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**468,30**	
				Unit Price (TRY)	**1.044,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.5115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5115	300 x 310 x 140 / Combination Box (Hollow) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	607,56	607,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	607,56	441,52
				Material and Installation w/o Profit (TRY)	1.049,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**551,90**	
				Unit Price (TRY)	**1.311,35**	

Item No	Analysis Name					UoM
35.185.5118						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5118	340 x 330 x 140 / Combination Box (Hollow) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	920,01	920,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician’s helper	h	0,9	185,00		166,50
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	920,01	485,02
				Material and Installation w/o Profit (TRY)	1.405,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**606,27**	
				Unit Price (TRY)	**1.756,29**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.5121						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5121	300 x 500 x 140 / Combination Box (Hollow) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	1.524,25	1.524,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	1.524,25	551,90
				Material and Installation w/o Profit (TRY)	2.076,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**689,88**	
				Unit Price (TRY)	**2.595,19**	

Item No	Analysis Name					UoM
35.185.5203						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5203	120 x 240 x 120 / Combination Box (Hollow) (HF) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	251,15	251,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	251,15	272,51
				Material and Installation w/o Profit (TRY)	523,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**340,64**	
				Unit Price (TRY)	**654,57**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.5206						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5206	150 x 240 x 130 / Combination Box (Hollow) (HF) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	276,47	276,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			276,47	272,51
		Material and Installation w/o Profit (TRY)			548,98	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**340,64**	
		Unit Price (TRY)			**686,23**	

Item No	Analysis Name					UoM
35.185.5209						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5209	210 x 290 x 120 / Combination Box (Hollow) (HF) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	461,00	461,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,02	687,95		13,76
		Total Excluding Profit (TRY)			461,00	324,26
		Material and Installation w/o Profit (TRY)			785,26	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**405,32**	
		Unit Price (TRY)			**981,58**	

Item No	Analysis Name					UoM
35.185.5212						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5212	240 x 290 x 130 / Combination Box (Hollow) (HF) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	531,62	531,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,7	250,00		175,00
10.100.1083	Master electrician’s helper	h	0,7	185,00		129,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			531,62	374,64
		Material and Installation w/o Profit (TRY)			906,26	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**468,30**	
		Unit Price (TRY)			**1.132,83**	

Item No	Analysis Name					UoM
35.185.5215						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5215	300 x 310 x 140 / Combination Box (Hollow) (HF) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	714,82	714,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician’s helper	h	0,8	185,00		148,00
19.100.1112	Forklift	h	0,04	687,95		27,52
		Total Excluding Profit (TRY)			714,82	441,52
		Material and Installation w/o Profit (TRY)			1.156,34	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**551,90**	
		Unit Price (TRY)			**1.445,43**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.5218						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5218	340 x 330 x 140 / Combination Box (Hollow) (HF) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	1.027,27	1.027,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,9	250,00		225,00
10.100.1083	Master electrician’s helper	h	0,9	185,00		166,50
19.100.1112	Forklift	h	0,04	687,95		27,52
		Total Excluding Profit (TRY)			1.027,27	485,02
		Material and Installation w/o Profit (TRY)			1.512,29	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**606,27**	
		Unit Price (TRY)			**1.890,36**	

Item No	Analysis Name					UoM
35.185.5221						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.185.5221	300 x 500 x 140 / Combination Box (Hollow) (HF) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	1.804,05	1.804,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
		Total Excluding Profit (TRY)			1.804,05	551,90
		Material and Installation w/o Profit (TRY)			2.355,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**689,88**	
		Unit Price (TRY)			**2.944,94**	

Item No	Analysis Name					UoM
35.185.5303						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5303	**Material Components** 2P+E, 16-25 A, 220 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	133,33	133,33	
				Total Excluding Profit (TRY)	133,33	
				Material and Installation w/o Profit (TRY)	133,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**166,66**	

Item No	Analysis Name					UoM
35.185.5309						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5309	**Material Components** 3P+E, 16-25 A, 380 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	156,66	156,66	
				Total Excluding Profit (TRY)	156,66	
				Material and Installation w/o Profit (TRY)	156,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**195,82**	

Item No	Analysis Name					UoM
35.185.5315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5315	**Material Components** 3P+N+E, 16-25 A, 380 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	197,33	197,33	
				Total Excluding Profit (TRY)	197,33	
				Material and Installation w/o Profit (TRY)	197,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**246,66**	

Item No	Analysis Name					UoM
35.185.5321						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5321	**Material Components** 2P+E, 32 A, 220-380 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	194,66	194,66	
				Total Excluding Profit (TRY)	194,66	
				Material and Installation w/o Profit (TRY)	194,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**243,32**	

Item No	Analysis Name					UoM
35.185.5327						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5327	**Material Components** 3P+E, 32 A, 380 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	216,66	216,66	
				Total Excluding Profit (TRY)	216,66	
				Material and Installation w/o Profit (TRY)	216,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**270,82**	

Item No	Analysis Name					UoM
35.185.5330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5330	**Material Components** 3P+E, 63 A, 380 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	668,66	668,66	
				Total Excluding Profit (TRY)	668,66	
				Material and Installation w/o Profit (TRY)	668,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**835,82**	

Item No	Analysis Name					UoM
35.185.5333						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5333	**Material Components** 3P+N+E, 32 A, 380 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	244,66	244,66	
				Total Excluding Profit (TRY)	244,66	
				Material and Installation w/o Profit (TRY)	244,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**305,82**	

Item No	Analysis Name					UoM
35.185.5336						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5336	**Material Components** 3P+N+E, 63 A, 380 V / Price difference for sockets suitable for combination boxes: (IP44) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	862,00	862,00	
				Total Excluding Profit (TRY)	862,00	
				Material and Installation w/o Profit (TRY)	862,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**1.077,50**	

Item No	Analysis Name					UoM
35.185.5403						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5403	**Material Components** 2P+E, 16-25 A, 220 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	216,00	216,00	
				Total Excluding Profit (TRY)	216,00	
				Material and Installation w/o Profit (TRY)	216,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**270,00**	

Item No	Analysis Name					UoM
35.185.5409						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5409	**Material Components** 3P+E, 16-25 A, 380 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	258,66	258,66	
				Total Excluding Profit (TRY)	258,66	
				Material and Installation w/o Profit (TRY)	258,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**323,33**	

Item No	Analysis Name					UoM
35.185.5415						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5415	**Material Components** 3P+N+E, 16-25 A, 380 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	276,00	276,00	
				Total Excluding Profit (TRY)	276,00	
				Material and Installation w/o Profit (TRY)	276,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**345,00**	

Item No	Analysis Name					UoM
35.185.5421						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5421	**Material Components** 2P+E, 32 A, 220-380 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	280,00	280,00	
				Total Excluding Profit (TRY)	280,00	
				Material and Installation w/o Profit (TRY)	280,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**350,00**	

Item No	Analysis Name					UoM
35.185.5427						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5427	**Material Components** 3P+E, 32 A, 380 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	302,00	302,00	
			Total Excluding Profit (TRY)		302,00	
			Material and Installation w/o Profit (TRY)		302,00	
% 25 Contractor’s Profit and Overheads Included			**Instal. Cost (TRY)**			
			Unit Price (TRY)		**377,50**	

Item No	Analysis Name					UoM
35.185.5430						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5430	**Material Components** 3P+E, 63 A, 380 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	787,33	787,33	
			Total Excluding Profit (TRY)		787,33	
			Material and Installation w/o Profit (TRY)		787,33	
% 25 Contractor’s Profit and Overheads Included			**Instal. Cost (TRY)**			
			Unit Price (TRY)		**984,16**	

Item No	Analysis Name					UoM
35.185.5433						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5433	**Material Components** 3P+N+E, 32 A, 380 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	326,66	326,66	
			Total Excluding Profit (TRY)		326,66	
			Material and Installation w/o Profit (TRY)		326,66	
% 25 Contractor’s Profit and Overheads Included			**Instal. Cost (TRY)**			
			Unit Price (TRY)		**408,33**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.185.5436						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.185.5436	**Material Components** 3P+N+E, 63 A, 380 V / Price difference for sockets suitable for combination boxes: (IP66) / SEPARATE INSTALLATION PARTS (Market price)	Qty	1	1.006,66	1.006,66	
		Total Excluding Profit (TRY)			1.006,66	
		Material and Installation w/o Profit (TRY)			1.006,66	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.258,33**	

Item No	Analysis Name					UoM
35.190.1100	**Cable Tray Systems / Cable Tray Systems / Cable Carriage Systems**					**Kg**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1100	Cable Tray Systems / CABLE CARRIAGE SYSTEMS (Market price)	Kg	1	135,51	135,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,05	250,00		12,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			135,51	26,70
		Material and Installation w/o Profit (TRY)			162,21	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**33,38**	
		Unit Price (TRY)			**202,76**	

Item No	Analysis Name					UoM
35.190.1101	**Cable Tray Systems Sheet Metal Cover / Cable Tray Systems Sheet Metal Cover / Cable Tray Systems Sheet Metal Cover**					**Kg**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1101	Cable Tray Systems, Sheet Metal Cover / CABLE CARRIAGE SYSTEMS (Market price)	Kg	1	110,34	110,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,03	250,00		7,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			110,34	14,70
		Material and Installation w/o Profit (TRY)			125,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**18,38**	
		Unit Price (TRY)			**156,30**	

Item No	Analysis Name					UoM
35.190.1102	**Cable Ladders / Cable Ladders / Cable Ladders**					**Kg**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1102	Cable Ladders / CABLE CARRIAGE SYSTEMS (Market price)	Kg	1	140,19	140,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,05	250,00		12,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			140,19	26,70
		Material and Installation w/o Profit (TRY)			166,89	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**33,38**	
		Unit Price (TRY)			**208,61**	

Item No	Analysis Name					UoM
35.190.1200	**Under-floor (Under-screed) Cable Ducts / Under-floor (Under-screed) Cable Ducts / Cable Carriage Systems**					**Kg**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1200	Under-floor (Under-screed) Cable Ducts / CABLE CARRIAGE SYSTEMS (Market price)	Kg	1	149,76	149,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,05	250,00		12,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			149,76	26,70
		Material and Installation w/o Profit (TRY)			176,46	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**33,38**	
		Unit Price (TRY)			**220,57**	

Item No	Analysis Name					UoM
35.190.1201	**Underfloor Cable Duct Junction Box / Under-floor (Under-screed) Cable Ducts / Cable Carriage Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1201	Underfloor Cable Duct Junction Box / CABLE CARRIAGE SYSTEMS (Market price)	Qty	1	574,72	574,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
		Total Excluding Profit (TRY)			574,72	207,00
		Material and Installation w/o Profit (TRY)			781,72	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**258,75**	
		Unit Price (TRY)			**977,15**	

Item No	Analysis Name					UoM
35.190.1202	**Under-Screed or Elevated Floor Multi-Socket Box / Under-floor (Under-screed) Cable Ducts / Cable Carriage Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1202	Under-Screed or Elevated Floor Multi-Socket Box / CABLE CARRIAGE SYSTEMS (Market price)	Qty	1	556,80	556,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
		Total Excluding Profit (TRY)			556,80	207,00
		Material and Installation w/o Profit (TRY)			763,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**258,75**	
		Unit Price (TRY)			**954,75**	

Item No	Analysis Name					UoM
35.190.1301						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1301	Min. 20 x 12 mm (single cell) / PVC Cable Ducts / CABLE CARRIAGE SYSTEMS (Market price)	m	1	26,14	26,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			26,14	51,75
		Material and Installation w/o Profit (TRY)			77,89	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**64,69**	
		Unit Price (TRY)			**97,36**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.190.1302						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1302	Min. 40 x 16 mm (double-cell) / PVC Cable Ducts / CABLE CARRIAGE SYSTEMS (Market price)	m	1	35,38	35,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	35,38	51,75
				Material and Installation w/o Profit (TRY)	87,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**108,91**	

Item No	Analysis Name					UoM
35.190.1303						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1303	Min. 80 x 20 mm (triple-cell) / PVC Cable Ducts / CABLE CARRIAGE SYSTEMS (Market price)	m	1	82,90	82,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	82,90	51,75
				Material and Installation w/o Profit (TRY)	134,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**168,31**	

Item No	Analysis Name					UoM
35.190.1304						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1304	Min. 100 x 35 mm (triple-cell) / PVC Cable Ducts / CABLE CARRIAGE SYSTEMS (Market price)	m	1	147,52	147,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			147,52	103,50
		Material and Installation w/o Profit (TRY)			251,02	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**313,78**	

Item No	Analysis Name					UoM
35.190.1305						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1305	Min. 100 x 50 mm (triple-cell) / PVC Cable Ducts / CABLE CARRIAGE SYSTEMS (Market price)	m	1	248,00	248,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			248,00	103,50
		Material and Installation w/o Profit (TRY)			351,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**439,38**	

Item No	Analysis Name					UoM
35.190.1351	**50 x 12-mm Herringbone cable duct / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1351	50 x 12-mm Herringbone cable duct / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems (Market price)	m	1	66,64	66,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	66,64	51,75
				Material and Installation w/o Profit (TRY)	118,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**147,99**	

Item No	Analysis Name					UoM
35.190.1352	**Herringbone cable ducts sized 50 x 12 mm to 60 x 15 mm / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1352	Min. 60 x 15 mm / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems (Market price)	m	1	82,56	82,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	82,56	51,75
				Material and Installation w/o Profit (TRY)	134,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**167,89**	

Item No	Analysis Name					UoM
35.190.1353	**Herringbone cable ducts sized 75 x 18 mm to 75x 20 mm / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1353	Min. 75 x 20 mm / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems (Market price)	m	1	96,16	96,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	96,16	51,75
				Material and Installation w/o Profit (TRY)	147,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**184,89**	

Item No	Analysis Name					UoM
35.190.1354	**90 x 20-mm Herringbone cable duct / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1354	Min. 75 x 20 mm / Floor-mounted (herringbone) PVC cable ducts / Cable Carriage Systems (Market price)	m	1	117,76	117,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	117,76	51,75
				Material and Installation w/o Profit (TRY)	169,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**211,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.190.1401						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1401	Min. 100 x 50 mm (triple-cell) / Halogen-free Plastic Cable Ducts / CABLE CARRIAGE SYSTEMS (Market price)	m	1	263,52	263,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	263,52	103,50
				Material and Installation w/o Profit (TRY)	367,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**458,77**	

Item No	Analysis Name					UoM
35.190.1701	**Earthed socket 16 A. - 250 V. (45 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1701	Earthed socket 16 A. - 250 V. (45 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems (Market price)	Qty	1	78,06	78,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	78,06	103,50
				Material and Installation w/o Profit (TRY)	181,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**226,95**	

Item No	Analysis Name					UoM
35.190.1702	**Earthed socket 16 A. - 250 V. (45 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1702	Earthed UPS socket (red) 16 A. - 250 V. (45 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems (Market price)	Qty	1	86,86	86,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	86,86	103,50
				Material and Installation w/o Profit (TRY)	190,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**237,95**	

Item No	Analysis Name					UoM
35.190.1703	**RJ-11 or RJ-12 telephone sockets (6 contacts) (22.5 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1703	RJ-11 or RJ-12 telephone sockets (6 contacts) (22.5 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems (Market price)	Qty	1	98,30	98,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	98,30	103,50
				Material and Installation w/o Profit (TRY)	201,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**252,25**	

Item No	Analysis Name					UoM
35.190.1704	**CAT 5e or CAT 6e RJ-45 data sockets (8 contacts) (22.5 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.190.1704	CAT 5e or CAT 6e RJ-45 data sockets (8 contacts) (22.5 x 45 mm) / Cable Duct Sockets / Cable Carriage Systems (Market price)	Qty	1	134,38	134,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	134,38	103,50
				Material and Installation w/o Profit (TRY)	237,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**297,35**	

Item No	Analysis Name					UoM
35.195.1101	**Max. 0.18 kW / 3-phase, 3000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Note: It shall comply with the Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and be CE certified.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1101	Max. 0.18 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.731,52	1.731,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.731,52	524,38
				Material and Installation w/o Profit (TRY)	2.255,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**655,48**	
				Unit Price (TRY)	**2.819,88**	

Item No	Analysis Name					UoM
35.195.1102	**Max. 0.25 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1102	Max. 0.25 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.753,92	1.753,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.753,92	524,38
				Material and Installation w/o Profit (TRY)	2.278,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**655,48**	
				Unit Price (TRY)	**2.847,88**	

Item No	Analysis Name					UoM
35.195.1103	**Max. 0.37 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1103	Max. 0.37 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.921,92	1.921,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.921,92	531,26
				Material and Installation w/o Profit (TRY)	2.453,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.066,48**	

Item No	Analysis Name					UoM
35.195.1104	**Max. 0.55 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1104	Max. 0.55 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.089,92	2.089,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.089,92	531,26
				Material and Installation w/o Profit (TRY)	2.621,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.276,48**	

Item No	Analysis Name					UoM
35.195.1105	**Max. 0.75 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1105	Max. 0.75 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.308,32	2.308,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.308,32	531,26
				Material and Installation w/o Profit (TRY)	2.839,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.549,47**	

Item No	Analysis Name					UoM
35.195.1106	**Max. 1.1 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1106	Max. 1.1 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.532,32	2.532,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.532,32	531,26
				Material and Installation w/o Profit (TRY)	3.063,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.829,47**	

Item No	Analysis Name					UoM
35.195.1107	**Max. 1.5 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1107	Max. 1.5 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.731,68	2.731,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.731,68	538,14
				Material and Installation w/o Profit (TRY)	3.269,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**4.087,27**	

Item No	Analysis Name					UoM
35.195.1108	**Max. 2.2 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1108	Max. 2.2 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	3.280,48	3.280,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	3.280,48	545,02
				Material and Installation w/o Profit (TRY)	3.825,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**681,27**	
				Unit Price (TRY)	**4.781,88**	

Item No	Analysis Name					UoM
35.195.1109	**Max. 3 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1109	Max. 3 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	4.161,92	4.161,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	4.161,92	769,40
				Material and Installation w/o Profit (TRY)	4.931,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**961,75**	
				Unit Price (TRY)	**6.164,15**	

Item No	Analysis Name					UoM
35.195.1110	**Max. 4 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1110	Max. 4 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	5.830,72	5.830,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,06	687,95		41,28
				Total Excluding Profit (TRY)	5.830,72	776,28
				Material and Installation w/o Profit (TRY)	6.607,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**970,35**	
				Unit Price (TRY)	**8.258,75**	

Item No	Analysis Name					UoM
35.195.1111	**Max. 5.5 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1111	Max. 5.5 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	8.290,24	8.290,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,08	687,95		55,04
				Total Excluding Profit (TRY)	8.290,24	790,04
				Material and Installation w/o Profit (TRY)	9.080,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**987,55**	
				Unit Price (TRY)	**11.350,35**	

Item No	Analysis Name					UoM
35.195.1112	**Max. 7.5 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1112	Max. 7.5 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	9.365,44	9.365,44	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	9.365,44	886,30
				Material and Installation w/o Profit (TRY)	10.251,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.107,88**	
				Unit Price (TRY)	**12.814,67**	

Item No	Analysis Name					UoM
35.195.1113	**Max. 11 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1113	Max. 11 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	13.255,20	13.255,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,12	687,95		82,55
				Total Excluding Profit (TRY)	13.255,20	1.117,55
				Material and Installation w/o Profit (TRY)	14.372,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.396,94**	
				Unit Price (TRY)	**17.965,94**	

Item No	Analysis Name					UoM
35.195.1114	**Max. 15 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1114	Max. 15 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	15.640,80	15.640,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,15	687,95		103,19
				Total Excluding Profit (TRY)	15.640,80	1.138,19
				Material and Installation w/o Profit (TRY)	16.778,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.422,74**	
				Unit Price (TRY)	**20.973,74**	

Item No	Analysis Name					UoM
35.195.1115	**Max. 18.5 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1115	Max. 18.5 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	18.224,64	18.224,64	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,18	687,95		123,83
				Total Excluding Profit (TRY)	18.224,64	1.158,83
				Material and Installation w/o Profit (TRY)	19.383,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.448,54**	
				Unit Price (TRY)	**24.229,34**	

Item No	Analysis Name					UoM
35.195.1116	**Max. 22 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1116	Max. 22 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	23.878,40	23.878,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,22	687,95		151,35
				Total Excluding Profit (TRY)	23.878,40	1.186,35
				Material and Installation w/o Profit (TRY)	25.064,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.482,94**	
				Unit Price (TRY)	**31.330,94**	

Item No	Analysis Name					UoM
35.195.1117	**Max. 30 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1117	Max. 30 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	32.233,60	32.233,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	32.233,60	1.458,89
				Material and Installation w/o Profit (TRY)	33.692,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.823,61**	
				Unit Price (TRY)	**42.115,61**	

Item No	Analysis Name					UoM
35.195.1118	**Max. 37 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1118	Max. 37 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	36.232,00	36.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,35	687,95		240,78
				Total Excluding Profit (TRY)	36.232,00	1.658,28
				Material and Installation w/o Profit (TRY)	37.890,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.072,85**	
				Unit Price (TRY)	**47.362,85**	

Item No	Analysis Name					UoM
35.195.1119	**Max. 45 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1119	Max. 45 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	51.520,00	51.520,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,4	687,95		275,18
				Total Excluding Profit (TRY)	51.520,00	1.692,68
				Material and Installation w/o Profit (TRY)	53.212,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.115,85**	
				Unit Price (TRY)	**66.515,85**	

Item No	Analysis Name					UoM
35.195.1120	**Max. 55 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1120	Max. 55 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	66.819,20	66.819,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	66.819,20	1.761,48
				Material and Installation w/o Profit (TRY)	68.580,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.201,85**	
				Unit Price (TRY)	**85.725,85**	

Item No	Analysis Name					UoM
35.195.1121	**Max. 75 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1121	Max. 75 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	82.073,60	82.073,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,6	687,95		412,77
				Total Excluding Profit (TRY)	82.073,60	1.830,27
				Material and Installation w/o Profit (TRY)	83.903,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.287,84**	
				Unit Price (TRY)	**104.879,84**	

Item No	Analysis Name					UoM
35.195.1122	**Max. 100 kW / 3-phase, 3,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1122	Max. 100 kW / 3-phase 3000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	123.345,60	123.345,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
19.100.1112	Forklift	h	0,8	687,95		550,36
				Total Excluding Profit (TRY)	123.345,60	2.185,36
				Material and Installation w/o Profit (TRY)	125.530,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.731,70**	
				Unit Price (TRY)	**156.913,70**	

Item No	Analysis Name					UoM
35.195.1201	**Max. 0.12 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1201	Max. 0.12 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.485,12	1.485,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.485,12	524,38
				Material and Installation w/o Profit (TRY)	2.009,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**655,48**	
				Unit Price (TRY)	**2.511,88**	

Item No	Analysis Name					UoM
35.195.1202	**Max. 0.18 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1202	Max. 0.18 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.675,52	1.675,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.675,52	524,38
				Material and Installation w/o Profit (TRY)	2.199,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**655,48**	
				Unit Price (TRY)	**2.749,88**	

Item No	Analysis Name					UoM
35.195.1203	**Max. 0.25 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1203	Max. 0.25 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.809,92	1.809,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.809,92	524,38
				Material and Installation w/o Profit (TRY)	2.334,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**655,48**	
				Unit Price (TRY)	**2.917,88**	

Item No	Analysis Name					UoM
35.195.1204	**Max. 0.37 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1204	Max. 0.37 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.921,92	1.921,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	1.921,92	531,26
				Material and Installation w/o Profit (TRY)	2.453,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.066,48**	

Item No	Analysis Name					UoM
35.195.1205	**Max. 0.55 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1205	Max. 0.55 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.123,52	2.123,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.123,52	531,26
				Material and Installation w/o Profit (TRY)	2.654,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.318,47**	

Item No	Analysis Name					UoM
35.195.1206	**Max. 0.75 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1206	Max. 0.75 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.532,32	2.532,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.532,32	538,14
				Material and Installation w/o Profit (TRY)	3.070,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**3.838,07**	

Item No	Analysis Name					UoM
35.195.1207	**Max. 1.1 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1207	Max. 1.1 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.913,12	2.913,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.913,12	538,14
				Material and Installation w/o Profit (TRY)	3.451,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**4.314,07**	

Item No	Analysis Name					UoM
35.195.1208	**Max. 1.5 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1208	Max. 1.5 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	3.336,48	3.336,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	3.336,48	545,02
				Material and Installation w/o Profit (TRY)	3.881,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**681,27**	
				Unit Price (TRY)	**4.851,88**	

Item No	Analysis Name					UoM
35.195.1209	**Max. 2.2 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1209	Max. 2.2 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	4.187,68	4.187,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,06	687,95		41,28
				Total Excluding Profit (TRY)	4.187,68	776,28
				Material and Installation w/o Profit (TRY)	4.963,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**970,35**	
				Unit Price (TRY)	**6.204,95**	

Item No	Analysis Name					UoM
35.195.1210	**Max. 3 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1210	Max. 3 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	5.001,92	5.001,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,07	687,95		48,16
		Total Excluding Profit (TRY)			5.001,92	783,16
		Material and Installation w/o Profit (TRY)			5.785,08	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**978,95**	
		Unit Price (TRY)			**7.231,35**	

Item No	Analysis Name					UoM
35.195.1211	**Max. 4 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1211	Max. 4 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	6.401,92	6.401,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,08	687,95		55,04
		Total Excluding Profit (TRY)			6.401,92	790,04
		Material and Installation w/o Profit (TRY)			7.191,96	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**987,55**	
		Unit Price (TRY)			**8.989,95**	

Item No	Analysis Name					UoM
35.195.1212	**Max. 5.5 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1212	Max. 5.5 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	8.547,84	8.547,84	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	8.547,84	886,30
				Material and Installation w/o Profit (TRY)	9.434,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.107,88**	
				Unit Price (TRY)	**11.792,67**	

Item No	Analysis Name					UoM
35.195.1213	**Max. 7.5 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1213	Max. 7.5 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	10.395,84	10.395,84	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,13	687,95		89,43
				Total Excluding Profit (TRY)	10.395,84	1.124,43
				Material and Installation w/o Profit (TRY)	11.520,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.405,54**	
				Unit Price (TRY)	**14.400,34**	

Item No	Analysis Name					UoM
35.195.1214	**Max. 11 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1214	Max. 11 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	14.756,00	14.756,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,16	687,95		110,07
				Total Excluding Profit (TRY)	14.756,00	1.145,07
				Material and Installation w/o Profit (TRY)	15.901,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.431,34**	
				Unit Price (TRY)	**19.876,34**	

Item No	Analysis Name					UoM
35.195.1215	**Max. 15 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1215	Max. 15 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	17.925,60	17.925,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	17.925,60	1.172,59
				Material and Installation w/o Profit (TRY)	19.098,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.465,74**	
				Unit Price (TRY)	**23.872,74**	

Item No	Analysis Name					UoM
35.195.1216	**Max. 18.5 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1216	Max. 18.5 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	20.722,24	20.722,24	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,25	687,95		171,99
				Total Excluding Profit (TRY)	20.722,24	1.206,99
				Material and Installation w/o Profit (TRY)	21.929,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.508,74**	
				Unit Price (TRY)	**27.411,54**	

Item No	Analysis Name					UoM
35.195.1217	**Max. 22 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1217	Max. 22 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	24.875,20	24.875,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	24.875,20	1.623,89
				Material and Installation w/o Profit (TRY)	26.499,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.029,86**	
				Unit Price (TRY)	**33.123,86**	

Item No	Analysis Name					UoM
35.195.1218	**Max. 30 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1218	Max. 30 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	34.115,20	34.115,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,4	687,95		275,18
				Total Excluding Profit (TRY)	34.115,20	1.692,68
				Material and Installation w/o Profit (TRY)	35.807,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.115,85**	
				Unit Price (TRY)	**44.759,85**	

Item No	Analysis Name					UoM
35.195.1219	**Max. 37 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1219	Max. 37 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	42.336,00	42.336,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	42.336,00	1.761,48
				Material and Installation w/o Profit (TRY)	44.097,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.201,85**	
				Unit Price (TRY)	**55.121,85**	

Item No	Analysis Name					UoM
35.195.1220	**Max. 45 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1220	Max. 45 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	47.454,40	47.454,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,6	687,95		412,77
				Total Excluding Profit (TRY)	47.454,40	1.830,27
				Material and Installation w/o Profit (TRY)	49.284,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.287,84**	
				Unit Price (TRY)	**61.605,84**	

Item No	Analysis Name					UoM
35.195.1221	**Max. 55 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1221	Max. 55 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	53.536,00	53.536,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,75	687,95		515,96
				Total Excluding Profit (TRY)	53.536,00	1.933,46
				Material and Installation w/o Profit (TRY)	55.469,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.416,82**	
				Unit Price (TRY)	**69.336,82**	

Item No	Analysis Name					UoM
35.195.1222	**Max. 75 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1222	Max. 75 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	72.060,80	72.060,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
19.100.1112	Forklift	h	0,9	687,95		619,16
				Total Excluding Profit (TRY)	72.060,80	2.254,16
				Material and Installation w/o Profit (TRY)	74.314,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.817,70**	
				Unit Price (TRY)	**92.893,70**	

Item No	Analysis Name					UoM
35.195.1223	**Max. 100 kW / 3-phase, 1,500 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1223	Max. 100 kW / 3-PHASE 1500 rpm / ELECTRIC MOTORS (Market price)	Qty	1	112.929,60	112.929,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
19.100.1112	Forklift	h	1,1	687,95		756,75
				Total Excluding Profit (TRY)	112.929,60	2.391,75
				Material and Installation w/o Profit (TRY)	115.321,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.989,69**	
				Unit Price (TRY)	**144.151,69**	

Item No	Analysis Name					UoM
35.195.1301	**Max. 0.18 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1301	Max. 0.18 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	1.907,36	1.907,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,01	687,95		6,88
				Total Excluding Profit (TRY)	1.907,36	524,38
				Material and Installation w/o Profit (TRY)	2.431,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**655,48**	
				Unit Price (TRY)	**3.039,67**	

Item No	Analysis Name					UoM
35.195.1302	**Max. 0.25 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1302	Max. 0.25 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.086,56	2.086,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.086,56	531,26
				Material and Installation w/o Profit (TRY)	2.617,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.272,27**	

Item No	Analysis Name					UoM
35.195.1303	**Max. 0.37 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1303	Max. 0.37 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.526,72	2.526,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,02	687,95		13,76
				Total Excluding Profit (TRY)	2.526,72	531,26
				Material and Installation w/o Profit (TRY)	3.057,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**664,08**	
				Unit Price (TRY)	**3.822,47**	

Item No	Analysis Name					UoM
35.195.1304	**Max. 0.55 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1304	Max. 0.55 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	2.739,52	2.739,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.739,52	538,14
				Material and Installation w/o Profit (TRY)	3.277,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**4.097,07**	

Item No	Analysis Name					UoM
35.195.1305	**Max. 0.75 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1305	Max. 0.75 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	3.249,12	3.249,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.249,12	538,14
				Material and Installation w/o Profit (TRY)	3.787,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**672,67**	
				Unit Price (TRY)	**4.734,07**	

Item No	Analysis Name					UoM
35.195.1306	**Max. 1.1 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1306	Max. 1.1 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	3.865,12	3.865,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,04	687,95		27,52
				Total Excluding Profit (TRY)	3.865,12	545,02
				Material and Installation w/o Profit (TRY)	4.410,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**681,27**	
				Unit Price (TRY)	**5.512,67**	

Item No	Analysis Name					UoM
35.195.1307	**Max. 1.5 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1307	Max. 1.5 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	4.994,08	4.994,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,05	687,95		34,40
				Total Excluding Profit (TRY)	4.994,08	551,90
				Material and Installation w/o Profit (TRY)	5.545,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**689,88**	
				Unit Price (TRY)	**6.932,47**	

Item No	Analysis Name					UoM
35.195.1308	**Max. 2.2 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1308	Max. 2.2 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	6.494,88	6.494,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,06	687,95		41,28
				Total Excluding Profit (TRY)	6.494,88	776,28
				Material and Installation w/o Profit (TRY)	7.271,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**970,35**	
				Unit Price (TRY)	**9.088,95**	

Item No	Analysis Name					UoM
35.195.1309	**Max. 3 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1309	Max. 3 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	8.440,32	8.440,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,08	687,95		55,04
				Total Excluding Profit (TRY)	8.440,32	790,04
				Material and Installation w/o Profit (TRY)	9.230,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**987,55**	
				Unit Price (TRY)	**11.537,95**	

Item No	Analysis Name					UoM
35.195.1310	**Max. 4 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1310	Max. 4 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	9.313,92	9.313,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	9.313,92	796,92
				Material and Installation w/o Profit (TRY)	10.110,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**996,15**	
				Unit Price (TRY)	**12.638,55**	

Item No	Analysis Name					UoM
35.195.1311	**Max. 5.5 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1311	Max. 5.5 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	10.395,84	10.395,84	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,11	687,95		75,67
				Total Excluding Profit (TRY)	10.395,84	1.110,67
				Material and Installation w/o Profit (TRY)	11.506,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.388,34**	
				Unit Price (TRY)	**14.383,14**	

Item No	Analysis Name					UoM
35.195.1312	**Max. 7.5 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1312	Max. 7.5 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	14.651,84	14.651,84	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,15	687,95		103,19
				Total Excluding Profit (TRY)	14.651,84	1.138,19
				Material and Installation w/o Profit (TRY)	15.790,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.422,74**	
				Unit Price (TRY)	**19.737,54**	

Item No	Analysis Name					UoM
35.195.1313	**Max. 11 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1313	Max. 11 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	17.645,60	17.645,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	17.645,60	1.172,59
				Material and Installation w/o Profit (TRY)	18.818,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.465,74**	
				Unit Price (TRY)	**23.522,74**	

Item No	Analysis Name					UoM
35.195.1314	**Max. 15 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1314	Max. 15 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	24.959,20	24.959,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
19.100.1112	Forklift	h	0,25	687,95		171,99
				Total Excluding Profit (TRY)	24.959,20	1.206,99
				Material and Installation w/o Profit (TRY)	26.166,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.508,74**	
				Unit Price (TRY)	**32.707,74**	

Item No	Analysis Name					UoM
35.195.1315	**Max. 18.5 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1315	Max. 18.5 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	31.149,44	31.149,44	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	31.149,44	1.623,89
				Material and Installation w/o Profit (TRY)	32.773,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.029,86**	
				Unit Price (TRY)	**40.966,66**	

Item No	Analysis Name					UoM
35.195.1316	**Max. 22 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1316	Max. 22 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	37.396,80	37.396,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,35	687,95		240,78
				Total Excluding Profit (TRY)	37.396,80	1.658,28
				Material and Installation w/o Profit (TRY)	39.055,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.072,85**	
				Unit Price (TRY)	**48.818,85**	

Item No	Analysis Name					UoM
35.195.1317	**Max. 30 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1317	Max. 30 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	47.465,60	47.465,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,5	687,95		343,98
				Total Excluding Profit (TRY)	47.465,60	1.761,48
				Material and Installation w/o Profit (TRY)	49.227,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.201,85**	
				Unit Price (TRY)	**61.533,85**	

Item No	Analysis Name					UoM
35.195.1318	**Max. 37 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1318	Max. 37 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	58.766,40	58.766,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
19.100.1112	Forklift	h	0,6	687,95		412,77
				Total Excluding Profit (TRY)	58.766,40	2.047,77
				Material and Installation w/o Profit (TRY)	60.814,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.559,71**	
				Unit Price (TRY)	**76.017,71**	

Item No	Analysis Name					UoM
35.195.1319	**Max. 45 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1319	Max. 45 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	75.924,80	75.924,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
19.100.1112	Forklift	h	0,7	687,95		481,57
				Total Excluding Profit (TRY)	75.924,80	2.116,57
				Material and Installation w/o Profit (TRY)	78.041,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.645,71**	
				Unit Price (TRY)	**97.551,71**	

Item No	Analysis Name					UoM
35.195.1320	**Max. 55 kW / 3-phase, 1,000 rpm / Electric Motors (TS EN 50347 -3067, TS EN 50347-4239) Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), Certified Appropriately for Compliance with CE Requirements.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.195.1320	Max. 55 kW / 3-PHASE 1000 rpm / ELECTRIC MOTORS (Market price)	Qty	1	92.478,40	92.478,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
19.100.1112	Forklift	h	0,85	687,95		584,76
				Total Excluding Profit (TRY)	92.478,40	2.219,76
				Material and Installation w/o Profit (TRY)	94.698,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.774,70**	
				Unit Price (TRY)	**118.372,70**	

Item No	Analysis Name					UoM
35.200.1101	**Photovoltaic panel with minimum 270 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1101	Photovoltaic panel with minimum 270 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.087,68	2.087,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.087,68	279,39
		Material and Installation w/o Profit (TRY)			2.367,07	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**2.958,84**	

Item No	Analysis Name					UoM
35.200.1102	**Photovoltaic panel with minimum 275 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1102	Photovoltaic panel with minimum 275 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.138,88	2.138,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.138,88	279,39
		Material and Installation w/o Profit (TRY)			2.418,27	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.022,84**	

Item No	Analysis Name					UoM
35.200.1103	**Photovoltaic panel with minimum 280 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1103	Photovoltaic panel with minimum 280 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.164,48	2.164,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.164,48	279,39
		Material and Installation w/o Profit (TRY)			2.443,87	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.054,84**	

Item No	Analysis Name					UoM
35.200.1104	**Photovoltaic panel with minimum 285 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1104	Photovoltaic panel with minimum 285 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.222,08	2.222,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.222,08	279,39
		Material and Installation w/o Profit (TRY)			2.501,47	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.126,84**	

Item No	Analysis Name					UoM
35.200.1105	**Photovoltaic panel with minimum 290 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1105	Photovoltaic panel with minimum 290 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.254,08	2.254,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.254,08	279,39
				Material and Installation w/o Profit (TRY)	2.533,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.166,84**	

Item No	Analysis Name					UoM
35.200.1106	**Photovoltaic panel with minimum 295 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1106	Photovoltaic panel with minimum 295 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.362,88	2.362,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.362,88	279,39
				Material and Installation w/o Profit (TRY)	2.642,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.302,84**	

Item No	Analysis Name					UoM
35.200.1107	**Photovoltaic panel with minimum 300 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1107	Photovoltaic panel with minimum 300 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.394,88	2.394,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.394,88	279,39
		Material and Installation w/o Profit (TRY)			2.674,27	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.342,84**	

Item No	Analysis Name					UoM
35.200.1108	**Photovoltaic panel with minimum 305 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1108	Photovoltaic panel with minimum 305 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.458,88	2.458,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.458,88	279,39
		Material and Installation w/o Profit (TRY)			2.738,27	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.422,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1109	**Photovoltaic panel with minimum 310 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1109	Photovoltaic panel with minimum 310 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.490,88	2.490,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.490,88	279,39
				Material and Installation w/o Profit (TRY)	2.770,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.462,84**	

Item No	Analysis Name					UoM
35.200.1110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1110	Photovoltaic panel with minimum 315 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.529,28	2.529,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.529,28	279,39
				Material and Installation w/o Profit (TRY)	2.808,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.510,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1111						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1111	Photovoltaic panel with minimum 320 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.586,88	2.586,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.586,88	279,39
				Material and Installation w/o Profit (TRY)	2.866,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.582,84**	

Item No	Analysis Name					UoM
35.200.1112						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1112	Photovoltaic panel with minimum 325 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.638,08	2.638,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.638,08	279,39
				Material and Installation w/o Profit (TRY)	2.917,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.646,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1113						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1113	Photovoltaic panel with minimum 330 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.708,48	2.708,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.708,48	279,39
		Material and Installation w/o Profit (TRY)			2.987,87	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.734,84**	

Item No	Analysis Name					UoM
35.200.1114						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1114	Photovoltaic panel with minimum 335 Wp output power / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels (Market price)	Qty	1	2.766,08	2.766,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.766,08	279,39
		Material and Installation w/o Profit (TRY)			3.045,47	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.806,84**	

Item No	Analysis Name					UoM
35.200.1201	**Photovoltaic panel with minimum 320 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1201	Photovoltaic panel with minimum 320 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.289,92	2.289,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.289,92	279,39
		Material and Installation w/o Profit (TRY)			2.569,31	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.211,64**	

Item No	Analysis Name					UoM
35.200.1202	**Photovoltaic panel with minimum 325 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1202	Photovoltaic panel with minimum 325 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.353,92	2.353,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.353,92	279,39
		Material and Installation w/o Profit (TRY)			2.633,31	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.291,64**	

Item No	Analysis Name					UoM
35.200.1203	**Photovoltaic panel with minimum 330 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1203	Photovoltaic panel with minimum 330 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.366,72	2.366,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.366,72	279,39
				Material and Installation w/o Profit (TRY)	2.646,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.307,64**	

Item No	Analysis Name					UoM
35.200.1204	**Photovoltaic panel with minimum 335 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1204	Photovoltaic panel with minimum 335 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.405,12	2.405,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.405,12	279,39
				Material and Installation w/o Profit (TRY)	2.684,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.355,64**	

Item No	Analysis Name					UoM
35.200.1205	**Photovoltaic panel with minimum 340 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1205	Photovoltaic panel with minimum 340 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.449,92	2.449,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.449,92	279,39
				Material and Installation w/o Profit (TRY)	2.729,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.411,64**	

Item No	Analysis Name					UoM
35.200.1206	**Photovoltaic panel with minimum 345 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1206	Photovoltaic panel with minimum 345 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.494,72	2.494,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.494,72	279,39
				Material and Installation w/o Profit (TRY)	2.774,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.467,64**	

Item No	Analysis Name					UoM
35.200.1207	**Photovoltaic panel with minimum 350 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1207	Photovoltaic panel with minimum 350 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.558,72	2.558,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.558,72	279,39
		Material and Installation w/o Profit (TRY)			2.838,11	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.547,64**	

Item No	Analysis Name					UoM
35.200.1208	**Photovoltaic panel with minimum 355 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1208	Photovoltaic panel with minimum 355 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.597,12	2.597,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.597,12	279,39
		Material and Installation w/o Profit (TRY)			2.876,51	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.595,64**	

Item No	Analysis Name					UoM
35.200.1209	**Photovoltaic panel with minimum 360 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1209	Photovoltaic panel with minimum 360 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.641,92	2.641,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.641,92	279,39
		Material and Installation w/o Profit (TRY)			2.921,31	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.651,64**	

Item No	Analysis Name					UoM
35.200.1210	**Photovoltaic panel with minimum 365 Wp output power. / Photovoltaic Panels with minimum 60 cells / Photovoltaic Panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1210	Photovoltaic panel with minimum 365 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.693,12	2.693,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.693,12	279,39
		Material and Installation w/o Profit (TRY)			2.972,51	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.715,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1211						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1211	Photovoltaic panel with minimum 370 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.744,32	2.744,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.744,32	279,39
		Material and Installation w/o Profit (TRY)			3.023,71	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.779,64**	

Item No	Analysis Name					UoM
35.200.1212						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1212	Photovoltaic panel with minimum 375 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.808,32	2.808,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.808,32	279,39
		Material and Installation w/o Profit (TRY)			3.087,71	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.859,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1213						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1213	Photovoltaic panel with minimum 380 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.840,32	2.840,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.840,32	279,39
		Material and Installation w/o Profit (TRY)			3.119,71	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.899,64**	

Item No	Analysis Name					UoM
35.200.1214						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1214	Photovoltaic panel with minimum 385 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.929,92	2.929,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.929,92	279,39
		Material and Installation w/o Profit (TRY)			3.209,31	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**4.011,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1215						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1215	Photovoltaic panel with minimum 385 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	2.974,72	2.974,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.974,72	279,39
		Material and Installation w/o Profit (TRY)			3.254,11	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**4.067,64**	

Item No	Analysis Name					UoM
35.200.1216						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1216	Photovoltaic panel with minimum 395 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.032,32	3.032,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.032,32	279,39
		Material and Installation w/o Profit (TRY)			3.311,71	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**4.139,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1217						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1217	Photovoltaic panel with minimum 400 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.109,12	3.109,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.109,12	322,89
				Material and Installation w/o Profit (TRY)	3.432,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.290,01**	

Item No	Analysis Name					UoM
35.200.1219						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1219	Photovoltaic panel with minimum 410 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.230,72	3.230,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.230,72	322,89
				Material and Installation w/o Profit (TRY)	3.553,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.442,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1221						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1221	Photovoltaic panel with minimum 420 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.358,72	3.358,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.358,72	322,89
				Material and Installation w/o Profit (TRY)	3.681,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.602,01**	

Item No	Analysis Name					UoM
35.200.1223						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1223	Photovoltaic panel with minimum 430 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.493,12	3.493,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.493,12	322,89
				Material and Installation w/o Profit (TRY)	3.816,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.770,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1225						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1225	Photovoltaic panel with minimum 440 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.621,12	3.621,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.621,12	322,89
				Material and Installation w/o Profit (TRY)	3.944,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.930,01**	

Item No	Analysis Name					UoM
35.200.1227						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1227	Photovoltaic panel with minimum 450 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.768,32	3.768,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.768,32	322,89
				Material and Installation w/o Profit (TRY)	4.091,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.114,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1229						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1229	Photovoltaic panel with minimum 460 Wp output power / Photovoltaic Panels with minimum 72 cells / Photovoltaic Panels (Market price)	Qty	1	3.909,12	3.909,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.909,12	322,89
				Material and Installation w/o Profit (TRY)	4.232,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.290,01**	

Item No	Analysis Name					UoM
35.200.1420						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1420	Photovoltaic panel with minimum 440 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	3.473,92	3.473,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.473,92	322,89
				Material and Installation w/o Profit (TRY)	3.796,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.746,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1422						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1422	Photovoltaic panel with minimum 450 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	3.557,12	3.557,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.557,12	322,89
				Material and Installation w/o Profit (TRY)	3.880,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.850,01**	

Item No	Analysis Name					UoM
35.200.1424						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1424	Photovoltaic panel with minimum 460 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	3.736,32	3.736,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.736,32	322,89
				Material and Installation w/o Profit (TRY)	4.059,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.074,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1426						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1426	Photovoltaic panel with minimum 470 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	3.819,52	3.819,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.819,52	322,89
				Material and Installation w/o Profit (TRY)	4.142,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.178,01**	

Item No	Analysis Name					UoM
35.200.1428						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1428	Photovoltaic panel with minimum 480 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	3.902,72	3.902,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.902,72	322,89
				Material and Installation w/o Profit (TRY)	4.225,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.282,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1430						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1430	Photovoltaic panel with minimum 490 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	3.992,32	3.992,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.992,32	322,89
				Material and Installation w/o Profit (TRY)	4.315,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.394,01**	

Item No	Analysis Name					UoM
35.200.1432						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1432	Photovoltaic panel with minimum 500 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.005,12	4.005,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.005,12	388,14
				Material and Installation w/o Profit (TRY)	4.393,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.491,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1434						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1434	Photovoltaic panel with minimum 510 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.081,92	4.081,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.081,92	388,14
				Material and Installation w/o Profit (TRY)	4.470,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.587,58**	

Item No	Analysis Name					UoM
35.200.1436						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1436	Photovoltaic panel with minimum 520 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.165,12	4.165,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.165,12	388,14
				Material and Installation w/o Profit (TRY)	4.553,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.691,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1438						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1438	Photovoltaic panel with minimum 530 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.248,32	4.248,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.248,32	388,14
				Material and Installation w/o Profit (TRY)	4.636,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.795,57**	

Item No	Analysis Name					UoM
35.200.1440						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1440	Photovoltaic panel with minimum 540 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.273,92	4.273,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.273,92	388,14
				Material and Installation w/o Profit (TRY)	4.662,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.827,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1442						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1442	Photovoltaic panel with minimum 550 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.453,12	4.453,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.453,12	388,14
				Material and Installation w/o Profit (TRY)	4.841,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.051,58**	

Item No	Analysis Name					UoM
35.200.1444						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1444	Photovoltaic panel with minimum 560 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.536,32	4.536,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.536,32	388,14
				Material and Installation w/o Profit (TRY)	4.924,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.155,57**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1446						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1446	Photovoltaic panel with minimum 570 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.632,32	4.632,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.632,32	388,14
				Material and Installation w/o Profit (TRY)	5.020,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.275,57**	

Item No	Analysis Name					UoM
35.200.1448						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1448	Photovoltaic panel with minimum 580 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.721,92	4.721,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.721,92	388,14
				Material and Installation w/o Profit (TRY)	5.110,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.387,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1450						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1450	Photovoltaic panel with minimum 590 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.817,92	4.817,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.817,92	388,14
				Material and Installation w/o Profit (TRY)	5.206,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.507,58**	

Item No	Analysis Name					UoM
35.200.1452						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1452	Photovoltaic panel with minimum 600 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	4.913,92	4.913,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.913,92	388,14
				Material and Installation w/o Profit (TRY)	5.302,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.627,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.1456						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1456	Photovoltaic panel with minimum 620 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	5.112,32	5.112,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	5.112,32	388,14
				Material and Installation w/o Profit (TRY)	5.500,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.875,57**	

Item No	Analysis Name					UoM
35.200.1460						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.1460	Photovoltaic panel with minimum 640 Wp output power / Photovoltaic Panels with minimum 108 cells / Photovoltaic Panels (Market price)	Qty	1	5.317,12	5.317,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	5.317,12	388,14
				Material and Installation w/o Profit (TRY)	5.705,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**7.131,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4201						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4201	Photovoltaic panel with minimum front panel output power of 300 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.516,48	2.516,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.516,48	279,39
				Material and Installation w/o Profit (TRY)	2.795,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.494,84**	

Item No	Analysis Name					UoM
35.200.4202						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4202	Photovoltaic panel with minimum front panel output power of 305 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.593,28	2.593,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.593,28	279,39
				Material and Installation w/o Profit (TRY)	2.872,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.590,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4203						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4203	Photovoltaic panel with minimum front panel output power of 310 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.625,28	2.625,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.625,28	279,39
		Material and Installation w/o Profit (TRY)			2.904,67	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.630,84**	

Item No	Analysis Name					UoM
35.200.4204						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4204	Photovoltaic panel with minimum front panel output power of 315 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.670,08	2.670,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.670,08	279,39
		Material and Installation w/o Profit (TRY)			2.949,47	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.686,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4205						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4205	Photovoltaic panel with minimum front panel output power of 320 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.727,68	2.727,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.727,68	279,39
		Material and Installation w/o Profit (TRY)			3.007,07	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.758,84**	

Item No	Analysis Name					UoM
35.200.4206						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4206	Photovoltaic panel with minimum front panel output power of 325 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.785,28	2.785,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.785,28	279,39
		Material and Installation w/o Profit (TRY)			3.064,67	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.830,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4207						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4207	Photovoltaic panel with minimum front panel output power of 330 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.855,68	2.855,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.855,68	279,39
		Material and Installation w/o Profit (TRY)			3.135,07	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.918,84**	

Item No	Analysis Name					UoM
35.200.4208						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4208	Photovoltaic panel with minimum front panel output power of 335 Wp / Two-sided Photovoltaic Panels with minimum 60 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.913,28	2.913,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.913,28	279,39
		Material and Installation w/o Profit (TRY)			3.192,67	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.990,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4301						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4301	Photovoltaic panel with minimum front panel output power of 360 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.789,12	2.789,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.789,12	279,39
				Material and Installation w/o Profit (TRY)	3.068,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.835,64**	

Item No	Analysis Name					UoM
35.200.4302						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4302	Photovoltaic panel with minimum front panel output power of 365 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.840,32	2.840,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.840,32	279,39
				Material and Installation w/o Profit (TRY)	3.119,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**3.899,64**	

Item No	Analysis Name					UoM
35.200.4303						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4303	Photovoltaic panel with minimum front panel output power of 370 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.891,52	2.891,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.891,52	279,39
		Material and Installation w/o Profit (TRY)			3.170,91	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**3.963,64**	

Item No	Analysis Name					UoM
35.200.4304						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4304	Photovoltaic panel with minimum front panel output power of 375 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.961,92	2.961,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			2.961,92	279,39
		Material and Installation w/o Profit (TRY)			3.241,31	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**4.051,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4305						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4305	Photovoltaic panel with minimum front panel output power of 380 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	2.993,92	2.993,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	2.993,92	279,39
				Material and Installation w/o Profit (TRY)	3.273,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**4.091,64**	

Item No	Analysis Name					UoM
35.200.4306						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4306	Photovoltaic panel with minimum front panel output power of 385 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.089,92	3.089,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.089,92	279,39
				Material and Installation w/o Profit (TRY)	3.369,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**349,24**	
				Unit Price (TRY)	**4.211,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4307						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4307	Photovoltaic panel with minimum front panel output power of 390 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.128,32	3.128,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.128,32	279,39
		Material and Installation w/o Profit (TRY)			3.407,71	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**4.259,64**	

Item No	Analysis Name					UoM
35.200.4308						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4308	Photovoltaic panel with minimum front panel output power of 395 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.192,32	3.192,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.192,32	279,39
		Material and Installation w/o Profit (TRY)			3.471,71	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**349,24**	
		Unit Price (TRY)			**4.339,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4309						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4309	Photovoltaic panel with minimum front panel output power of 400 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.275,52	3.275,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.275,52	322,89
				Material and Installation w/o Profit (TRY)	3.598,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.498,01**	

Item No	Analysis Name					UoM
35.200.4311						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4311	Photovoltaic panel with minimum front panel output power of 410 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.403,52	3.403,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.403,52	322,89
				Material and Installation w/o Profit (TRY)	3.726,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.658,01**	

Item No	Analysis Name					UoM
35.200.4313						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4313	Photovoltaic panel with minimum front panel output power of 420 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.537,92	3.537,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.537,92	322,89
				Material and Installation w/o Profit (TRY)	3.860,81	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.826,01**	

Item No	Analysis Name					UoM
35.200.4315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4315	Photovoltaic panel with minimum front panel output power of 430 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.672,32	3.672,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	3.672,32	322,89
				Material and Installation w/o Profit (TRY)	3.995,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**4.994,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4317						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4317	Photovoltaic panel with minimum front panel output power of 440 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.819,52	3.819,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.819,52	322,89
		Material and Installation w/o Profit (TRY)			4.142,41	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**403,61**	
		Unit Price (TRY)			**5.178,01**	

Item No	Analysis Name					UoM
35.200.4319						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4319	Photovoltaic panel with minimum front panel output power of 450 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.966,72	3.966,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.966,72	322,89
		Material and Installation w/o Profit (TRY)			4.289,61	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**403,61**	
		Unit Price (TRY)			**5.362,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4321						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4321	Photovoltaic panel with minimum front panel output power of 460 Wp / Two-sided Photovoltaic Panels with minimum 72 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.126,72	4.126,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			4.126,72	322,89
		Material and Installation w/o Profit (TRY)			4.449,61	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**403,61**	
		Unit Price (TRY)			**5.562,01**	

Item No	Analysis Name					UoM
35.200.4520						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4520	Photovoltaic panel with minimum front panel output power of 440 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.659,52	3.659,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.659,52	322,89
		Material and Installation w/o Profit (TRY)			3.982,41	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**403,61**	
		Unit Price (TRY)			**4.978,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.4522						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4522	Photovoltaic panel with minimum front panel output power of 450 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.749,12	3.749,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.749,12	322,89
		Material and Installation w/o Profit (TRY)			4.072,01	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**403,61**	
		Unit Price (TRY)			**5.090,01**	

Item No	Analysis Name					UoM
35.200.4524						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4524	Photovoltaic panel with minimum front panel output power of 460 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	3.941,12	3.941,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
		Total Excluding Profit (TRY)			3.941,12	322,89
		Material and Installation w/o Profit (TRY)			4.264,01	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**403,61**	
		Unit Price (TRY)			**5.330,01**	

Item No	Analysis Name					UoM
35.200.4526						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4526	Photovoltaic panel with minimum front panel output power of 470 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.024,32	4.024,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.024,32	322,89
				Material and Installation w/o Profit (TRY)	4.347,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.434,01**	

Item No	Analysis Name					UoM
35.200.4528						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4528	Photovoltaic panel with minimum front panel output power of 480 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.113,92	4.113,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.113,92	322,89
				Material and Installation w/o Profit (TRY)	4.436,81	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.546,01**	

Item No	Analysis Name					UoM
35.200.4530						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4530	Photovoltaic panel with minimum front panel output power of 490 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.203,52	4.203,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.203,52	322,89
				Material and Installation w/o Profit (TRY)	4.526,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403,61**	
				Unit Price (TRY)	**5.658,01**	

Item No	Analysis Name					UoM
35.200.4532						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4532	Photovoltaic panel with minimum front panel output power of 500 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.222,72	4.222,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.222,72	388,14
				Material and Installation w/o Profit (TRY)	4.610,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.763,58**	

Item No	Analysis Name					UoM
35.200.4534						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4534	Photovoltaic panel with minimum front panel output power of 510 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.305,92	4.305,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.305,92	388,14
				Material and Installation w/o Profit (TRY)	4.694,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.867,58**	

Item No	Analysis Name					UoM
35.200.4536						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4536	Photovoltaic panel with minimum front panel output power of 520 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.389,12	4.389,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.389,12	388,14
				Material and Installation w/o Profit (TRY)	4.777,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**5.971,58**	

Item No	Analysis Name					UoM
35.200.4538						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4538	Photovoltaic panel with minimum front panel output power of 530 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.478,72	4.478,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.478,72	388,14
				Material and Installation w/o Profit (TRY)	4.866,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.083,58**	

Item No	Analysis Name					UoM
35.200.4540						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4540	Photovoltaic panel with minimum front panel output power of 540 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.497,92	4.497,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.497,92	388,14
				Material and Installation w/o Profit (TRY)	4.886,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.107,58**	

Item No	Analysis Name					UoM
35.200.4542						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4542	Photovoltaic panel with minimum front panel output power of 550 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.689,92	4.689,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.689,92	388,14
				Material and Installation w/o Profit (TRY)	5.078,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.347,58**	

Item No	Analysis Name					UoM
35.200.4544						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4544	Photovoltaic panel with minimum front panel output power of 560 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.779,52	4.779,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.779,52	388,14
				Material and Installation w/o Profit (TRY)	5.167,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.459,58**	

Item No	Analysis Name					UoM
35.200.4546						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4546	Photovoltaic panel with minimum front panel output power of 570 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.881,92	4.881,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.881,92	388,14
				Material and Installation w/o Profit (TRY)	5.270,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.587,58**	

Item No	Analysis Name					UoM
35.200.4548						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4548	Photovoltaic panel with minimum front panel output power of 580 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	4.977,92	4.977,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	4.977,92	388,14
				Material and Installation w/o Profit (TRY)	5.366,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.707,58**	

Item No	Analysis Name					UoM
35.200.4550						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4550	Photovoltaic panel with minimum front panel output power of 590 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	5.073,92	5.073,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	5.073,92	388,14
				Material and Installation w/o Profit (TRY)	5.462,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.827,58**	

Item No	Analysis Name					UoM
35.200.4552						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4552	Photovoltaic panel with minimum front panel output power of 600 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	5.169,92	5.169,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	5.169,92	388,14
				Material and Installation w/o Profit (TRY)	5.558,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**6.947,58**	

Item No	Analysis Name					UoM
35.200.4556						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4556	Photovoltaic panel with minimum front panel output power of 620 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	5.387,52	5.387,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	5.387,52	388,14
				Material and Installation w/o Profit (TRY)	5.775,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**7.219,58**	

Item No	Analysis Name					UoM
35.200.4560						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.4560	Photovoltaic panel with minimum front panel output power of 640 Wp / Two-sided Photovoltaic Panels with minimum 108 cells / Two-sided (glass-glass) Photovoltaic Panels (Market price)	Qty	1	5.598,72	5.598,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
19.100.1112	Forklift	h	0,03	687,95		20,64
				Total Excluding Profit (TRY)	5.598,72	388,14
				Material and Installation w/o Profit (TRY)	5.986,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**485,17**	
				Unit Price (TRY)	**7.483,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5001	**Min. 3 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5001	Min. 3 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	37.700,00	37.700,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,04	687,95		27,52
		Total Excluding Profit (TRY)			37.700,00	1.245,02
		Material and Installation w/o Profit (TRY)			38.945,02	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.556,28**	
		Unit Price (TRY)			**48.681,27**	

Item No	Analysis Name					UoM
35.200.5002	**Min. 5 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5002	Min. 5 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	47.860,80	47.860,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,04	687,95		27,52
		Total Excluding Profit (TRY)			47.860,80	1.245,02
		Material and Installation w/o Profit (TRY)			49.105,82	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.556,28**	
		Unit Price (TRY)			**61.382,28**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5003	**Min. 7 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5003	Min. 7 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	65.468,00	65.468,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,05	687,95		34,40
		Total Excluding Profit (TRY)			65.468,00	1.251,90
		Material and Installation w/o Profit (TRY)			66.719,90	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.564,88**	
		Unit Price (TRY)			**83.399,88**	

Item No	Analysis Name					UoM
35.200.5004	**Min. 10 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5004	Min. 10 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	70.522,40	70.522,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,05	687,95		34,40
		Total Excluding Profit (TRY)			70.522,40	1.251,90
		Material and Installation w/o Profit (TRY)			71.774,30	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.564,88**	
		Unit Price (TRY)			**89.717,87**	

Item No	Analysis Name					UoM
35.200.5005	**Min. 15 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5005	Min. 15 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	95.700,80	95.700,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,06	687,95		41,28
		Total Excluding Profit (TRY)			95.700,80	1.776,28
		Material and Installation w/o Profit (TRY)			97.477,08	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.220,35**	
		Unit Price (TRY)			**121.846,35**	

Item No	Analysis Name					UoM
35.200.5006	**Min. 20 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5006	Min. 20 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	109.460,00	109.460,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,06	687,95		41,28
		Total Excluding Profit (TRY)			109.460,00	1.776,28
		Material and Installation w/o Profit (TRY)			111.236,28	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.220,35**	
		Unit Price (TRY)			**139.045,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5007	**Min. 25 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5007	Min. 25 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	117.260,00	117.260,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,07	687,95		48,16
		Total Excluding Profit (TRY)			117.260,00	1.783,16
		Material and Installation w/o Profit (TRY)			119.043,16	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.228,95**	
		Unit Price (TRY)			**148.803,95**	

Item No	Analysis Name					UoM
35.200.5008	**Min. 30 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5008	Min. 30 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	125.892,00	125.892,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,08	687,95		55,04
		Total Excluding Profit (TRY)			125.892,00	1.790,04
		Material and Installation w/o Profit (TRY)			127.682,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.237,55**	
		Unit Price (TRY)			**159.602,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5009	**Min. 35 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5009	Min. 35 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	138.600,80	138.600,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,08	687,95		55,04
				Total Excluding Profit (TRY)	138.600,80	2.307,54
				Material and Installation w/o Profit (TRY)	140.908,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.884,43**	
				Unit Price (TRY)	**176.135,42**	

Item No	Analysis Name					UoM
35.200.5010	**Min. 40 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5010	Min. 40 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	146.088,80	146.088,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	146.088,80	2.314,42
				Material and Installation w/o Profit (TRY)	148.403,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.893,03**	
				Unit Price (TRY)	**185.504,02**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5011	**Min. 50 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5011	Min. 50 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	167.512,80	167.512,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	167.512,80	2.321,30
				Material and Installation w/o Profit (TRY)	169.834,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.901,63**	
				Unit Price (TRY)	**212.292,62**	

Item No	Analysis Name					UoM
35.200.5012	**Min. 60 kW solar inverter / Solar inverters with minimum 1 independent MPPT / Solar Inverter**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5012	Min. 60 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	186.752,80	186.752,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
19.100.1112	Forklift	h	0,14	687,95		96,31
				Total Excluding Profit (TRY)	186.752,80	2.348,81
				Material and Installation w/o Profit (TRY)	189.101,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.936,01**	
				Unit Price (TRY)	**236.377,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5020						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5020	Min. 100 kW solar inverter (Up to 2 mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	228.280,00	228.280,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
19.100.1112	Forklift	h	0,17	687,95		116,95
		Total Excluding Profit (TRY)			228.280,00	3.586,95
		Material and Installation w/o Profit (TRY)			231.866,95	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**4.483,69**	
		Unit Price (TRY)			**289.833,69**	

Item No	Analysis Name					UoM
35.200.5040						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5040	Min. 30 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	135.564,00	135.564,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
19.100.1112	Forklift	h	0,08	687,95		55,04
		Total Excluding Profit (TRY)			135.564,00	2.925,04
		Material and Installation w/o Profit (TRY)			138.489,04	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**3.656,30**	
		Unit Price (TRY)			**173.111,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5045						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5045	Min. 40 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	154.928,80	154.928,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
19.100.1112	Forklift	h	0,09	687,95		61,92
				Total Excluding Profit (TRY)	154.928,80	2.931,92
				Material and Installation w/o Profit (TRY)	157.860,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.664,90**	
				Unit Price (TRY)	**197.325,90**	

Item No	Analysis Name					UoM
35.200.5050						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5050	Min. 50 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	177.704,80	177.704,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,5	700,00		1.750,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	177.704,80	3.806,30
				Material and Installation w/o Profit (TRY)	181.511,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.757,88**	
				Unit Price (TRY)	**226.888,87**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5055						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5055	Min. 60 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	201.728,80	201.728,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	0,14	687,95		96,31
		Total Excluding Profit (TRY)			201.728,80	4.883,81
		Material and Installation w/o Profit (TRY)			206.612,61	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**6.104,76**	
		Unit Price (TRY)			**258.265,76**	

Item No	Analysis Name					UoM
35.200.5060						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5060	Min. 100 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage below 400 VAC) (Market price)	Qty	1	250.952,00	250.952,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician's helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
19.100.1112	Forklift	h	0,17	687,95		116,95
		Total Excluding Profit (TRY)			250.952,00	6.121,95
		Material and Installation w/o Profit (TRY)			257.073,95	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**7.652,44**	
		Unit Price (TRY)			**321.342,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5210	Min. 200 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage above 400 VAC) (Market price)	Qty	1	346.829,60	346.829,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	346.829,60	7.511,39
				Material and Installation w/o Profit (TRY)	354.340,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**9.389,24**	
				Unit Price (TRY)	**442.926,24**	

Item No	Analysis Name					UoM
35.200.5220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5220	Min. 250 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage above 400 VAC) (Market price)	Qty	1	394.669,60	394.669,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician's helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
19.100.1112	Forklift	h	0,4	687,95		275,18
				Total Excluding Profit (TRY)	394.669,60	8.715,18
				Material and Installation w/o Profit (TRY)	403.384,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**10.893,98**	
				Unit Price (TRY)	**504.230,97**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.5230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.5230	Min. 300 kW solar inverter (3 or more mppts) / Solar Inverter (output voltage above 400 VAC) (Market price)	Qty	1	442.998,40	442.998,40	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1112	Forklift	h	0,5	687,95		343,98
		Total Excluding Profit (TRY)			442.998,40	9.918,98
		Material and Installation w/o Profit (TRY)			452.917,38	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**12.398,72**	
		Unit Price (TRY)			**566.146,72**	

Item No	Analysis Name					UoM
35.200.7001	**1.5-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7001	1.5-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	13,38	13,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			13,38	31,50
		Material and Installation w/o Profit (TRY)			44,88	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**39,38**	
		Unit Price (TRY)			**56,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7002	**2.5-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7002	2.5-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	19,21	19,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,21	31,50
				Material and Installation w/o Profit (TRY)	50,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**63,39**	

Item No	Analysis Name					UoM
35.200.7003	**4-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7003	4-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	28,45	28,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	28,45	34,00
				Material and Installation w/o Profit (TRY)	62,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**78,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7004	**6-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7004	6-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	40,49	40,49	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	40,49	34,00
				Material and Installation w/o Profit (TRY)	74,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**93,11**	

Item No	Analysis Name					UoM
35.200.7005	**10-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7005	10-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	67,85	67,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	67,85	36,50
				Material and Installation w/o Profit (TRY)	104,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**130,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7006	**16-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7006	16-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	104,33	104,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	104,33	42,50
				Material and Installation w/o Profit (TRY)	146,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**183,54**	

Item No	Analysis Name					UoM
35.200.7007	**25-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7007	25-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	160,27	160,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	160,27	48,50
				Material and Installation w/o Profit (TRY)	208,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**260,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7008	**35-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7008	35-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	223,14	223,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	223,14	51,00
				Material and Installation w/o Profit (TRY)	274,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**342,67**	

Item No	Analysis Name					UoM
35.200.7009	**50-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7009	50-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	328,93	328,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	328,93	57,00
				Material and Installation w/o Profit (TRY)	385,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**482,41**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7010	**70-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7010	70-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	457,82	457,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	457,82	62,00
				Material and Installation w/o Profit (TRY)	519,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**649,77**	

Item No	Analysis Name					UoM
35.200.7011	**95-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7011	95-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	604,96	604,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	604,96	68,00
				Material and Installation w/o Profit (TRY)	672,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**841,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7012	**120-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7012	120-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	775,20	775,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	775,20	74,00
				Material and Installation w/o Profit (TRY)	849,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**1.061,50**	

Item No	Analysis Name					UoM
35.200.7013	**150-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7013	150-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	977,06	977,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	977,06	79,00
				Material and Installation w/o Profit (TRY)	1.056,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**1.320,07**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7014	**185-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7014	185-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	1.155,81	1.155,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	1.155,81	87,50
				Material and Installation w/o Profit (TRY)	1.243,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**109,38**	
				Unit Price (TRY)	**1.554,14**	

Item No	Analysis Name					UoM
35.200.7015	**240-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7015	240-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	1.549,79	1.549,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	1.549,79	93,50
				Material and Installation w/o Profit (TRY)	1.643,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**2.054,11**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.200.7016	**300-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.200.7016	300-mm² solar cable / H1Z2Z2-K Solar Cable / Photovoltaic Solar Power Systems (Market price)	m	1	1.865,95	1.865,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
		Total Excluding Profit (TRY)			1.865,95	102,00
		Material and Installation w/o Profit (TRY)			1.967,95	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**127,50**	
		Unit Price (TRY)			**2.459,94**	

Item No	Analysis Name					UoM
35.210.1010						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.210.1010	11 kW NG 16 amps AA charging unit / AC TYPE ELECTRIC VEHICLE CHARGING UNIT (Market price)	Qty	1	15.957,50	15.957,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			15.957,50	517,50
		Material and Installation w/o Profit (TRY)			16.475,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**20.593,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.210.1020						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.210.1020	22 kW NG 32 amps AA charging unit / AC TYPE ELECTRIC VEHICLE CHARGING UNIT (Market price)	Qty	1	23.923,21	23.923,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	23.923,21	517,50
				Material and Installation w/o Profit (TRY)	24.440,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**30.550,89**	

Item No	Analysis Name					UoM
35.400.1001						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1001	Nurse Call Panel / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	63.830,00	63.830,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	63.830,00	1.917,50
				Material and Installation w/o Profit (TRY)	65.747,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.396,88**	
				Unit Price (TRY)	**82.184,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.400.1002						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1002	Room Control Panel / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	14.242,80	14.242,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			14.242,80	1.652,50
		Material and Installation w/o Profit (TRY)			15.895,30	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.065,63**	
		Unit Price (TRY)			**19.869,13**	

Item No	Analysis Name					UoM
35.400.1003						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1003	Patient Bedside Call Unit / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	1.419,60	1.419,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.419,60	608,75
		Material and Installation w/o Profit (TRY)			2.028,35	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**760,94**	
		Unit Price (TRY)			**2.535,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.400.1004						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1004	Patient Handset Call Unit / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	1.076,40	1.076,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	1.076,40	475,25
				Material and Installation w/o Profit (TRY)	1.551,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**594,06**	
				Unit Price (TRY)	**1.939,56**	

Item No	Analysis Name					UoM
35.400.1005						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1005	Patient WC-Bathroom Call Unit / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	1.242,80	1.242,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	1.242,80	608,75
				Material and Installation w/o Profit (TRY)	1.851,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**2.314,44**	

Item No	Analysis Name					UoM
35.400.1006						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1006	Over Door Light / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	1.076,40	1.076,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	1.076,40	125,25
				Material and Installation w/o Profit (TRY)	1.201,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**1.502,06**	

Item No	Analysis Name					UoM
35.400.1007						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1007	Hospital Server / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	151.632,00	151.632,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	151.632,00	2.352,50
				Material and Installation w/o Profit (TRY)	153.984,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.940,63**	
				Unit Price (TRY)	**192.480,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.400.1008						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.400.1008	**Material Components** Personnel Smart Card / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	142,48	142,48	
		Total Excluding Profit (TRY)			142,48	
		Material and Installation w/o Profit (TRY)			142,48	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**178,10**	

Item No	Analysis Name					UoM
35.400.1009						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.400.1009	**Material Components** Pager / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	10.649,60	10.649,60	
		Total Excluding Profit (TRY)			10.649,60	
		Material and Installation w/o Profit (TRY)			10.649,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**13.312,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.400.1010						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1010	Wireless Transmitter / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	21.283,60	21.283,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			21.283,60	1.217,50
		Material and Installation w/o Profit (TRY)			22.501,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.521,88**	
		Unit Price (TRY)			**28.126,38**	

Item No	Analysis Name					UoM
35.400.1011						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.1011	Emergency Service Call Panel / HOSPITAL CALL SYSTEM (IP SYSTEM) / HOSPITAL CALL SYSTEM (Market price)	Qty	1	97.463,60	97.463,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			97.463,60	1.217,50
		Material and Installation w/o Profit (TRY)			98.681,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.521,88**	
		Unit Price (TRY)			**123.351,38**	

Item No	Analysis Name					UoM
35.400.2002	**24 address capacity / Nurse Call Console; / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2002	24 address capacity / Nurse Call Console / Nurse Call System (Market price)	Qty	1	13.499,20	13.499,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	13.499,20	3.035,00
				Material and Installation w/o Profit (TRY)	16.534,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.793,75**	
				Unit Price (TRY)	**20.667,75**	

Item No	Analysis Name					UoM
35.400.2003	**31 address capacity / Nurse Call Console; / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2003	31 address capacity / Nurse Call Console / Nurse Call System (Market price)	Qty	1	14.747,20	14.747,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,5	700,00		1.750,00
				Total Excluding Profit (TRY)	14.747,20	4.690,00
				Material and Installation w/o Profit (TRY)	19.437,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**5.862,50**	
				Unit Price (TRY)	**24.296,50**	

Item No	Analysis Name					UoM
35.400.2004	**62 address capacity / Nurse Call Console; / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2004	62 address capacity / Nurse Call Console / Nurse Call System (Market price)	Qty	1	18.480,80	18.480,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
		Total Excluding Profit (TRY)			18.480,80	5.910,00
		Material and Installation w/o Profit (TRY)			24.390,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**7.387,50**	
		Unit Price (TRY)			**30.488,50**	

Item No	Analysis Name					UoM
35.400.2005	**Room / bed address control module / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2005	Room / bed address control module / Nurse Call System (Market price)	Qty	1	6.485,44	6.485,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			6.485,44	234,00
		Material and Installation w/o Profit (TRY)			6.719,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**292,50**	
		Unit Price (TRY)			**8.399,30**	

Item No	Analysis Name					UoM
35.400.2006	**Call / reset unit / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2006	Call / reset unit / Nurse Call System (Market price)	Qty	1	1.424,80	1.424,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	1.424,80	125,25
				Material and Installation w/o Profit (TRY)	1.550,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**1.937,56**	

Item No	Analysis Name					UoM
35.400.2007	**Call handset / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2007	Call handset / Nurse Call System (Market price)	Qty	1	1.071,20	1.071,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	1.071,20	125,25
				Material and Installation w/o Profit (TRY)	1.196,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**1.495,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.400.2008	**WC / Bathroom emergency call button with a cord / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2008	WC / Bathroom emergency call button with a cord / Nurse Call System (Market price)	Qty	1	1.248,00	1.248,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			1.248,00	125,25
		Material and Installation w/o Profit (TRY)			1.373,25	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**156,56**	
		Unit Price (TRY)			**1.716,56**	

Item No	Analysis Name					UoM
35.400.2009	**Over-door warning light / Nurse Call System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.400.2009	Over-door warning light / Nurse Call System (Market price)	Qty	1	1.198,08	1.198,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			1.198,08	125,25
		Material and Installation w/o Profit (TRY)			1.323,33	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**156,56**	
		Unit Price (TRY)			**1.654,16**	

Item No	Analysis Name					UoM
35.405.1010	**Regular master clock / Master Clock and Its Installation (TS 3930)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1010	Regular master clock / Master Clock and Its Installation / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	29.286,40	29.286,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	29.286,40	2.435,00
				Material and Installation w/o Profit (TRY)	31.721,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.043,75**	
				Unit Price (TRY)	**39.651,75**	

Item No	Analysis Name					UoM
35.405.1020	**Compensated master clock / Master Clock and Its Installation (TS 3930)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1020	Compensated master clock / Master Clock and Its Installation / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	37.835,20	37.835,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	37.835,20	2.435,00
				Material and Installation w/o Profit (TRY)	40.270,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.043,75**	
				Unit Price (TRY)	**50.337,75**	

Item No	Analysis Name					UoM
35.405.1030	**Signal clock (that can also control the bell circuit when necessary) / Master Clock and Its Installation (TS 3930)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1030	Signal clock (that can also control the bell circuit when necessary) / Master Clock and Its Installation / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	43.700,80	43.700,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			43.700,80	2.170,00
		Material and Installation w/o Profit (TRY)			45.870,80	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.712,50**	
		Unit Price (TRY)			**57.338,50**	

Item No	Analysis Name					UoM
35.405.1110	**Ø30 cm, single sided / Slave clock and installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1110	30 cm. single sided / Slave clock and installation / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	3.986,32	3.986,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			3.986,32	867,50
		Material and Installation w/o Profit (TRY)			4.853,82	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**6.067,27**	

Item No	Analysis Name					UoM
35.405.1120	**Ø30 cm, single sided / Slave clock and installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1120	30 cm. single sided, with the second hand / Slave clock and installation / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	5.421,52	5.421,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	5.421,52	867,50
				Material and Installation w/o Profit (TRY)	6.289,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**7.861,28**	

Item No	Analysis Name					UoM
35.405.1130	**Ø30 cm, single sided / Slave clock and installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1130	30 cm. single sided, weather-proof / Slave clock and installation / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	3.944,72	3.944,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	3.944,72	867,50
				Material and Installation w/o Profit (TRY)	4.812,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**6.015,27**	

Item No	Analysis Name					UoM
35.405.1140	**Ø30 cm, single sided, 110/220 V or 1.5 battery powered / Slave clock and installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1140	30 cm. Ø single-sided 110/220 V or 1.5-V battery-powered	Qty	1	3.695,12	3.695,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	3.695,12	867,50
				Material and Installation w/o Profit (TRY)	4.562,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**5.703,27**	

Item No	Analysis Name					UoM
35.405.1150	**Signal clock / Slave Clock and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.1150	Signal clock / Slave clock and installation / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	28.790,32	28.790,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	28.790,32	867,50
				Material and Installation w/o Profit (TRY)	29.657,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**37.072,28**	

Item No	Analysis Name					UoM
35.405.1160	**Clock supply line**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2401	1 x 1.5 mm² section / NV (NYA) cable / MAIN LINE AND SUPPLY LINES (Market price)	m	2	6,66	13,32	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
		Total Excluding Profit (TRY)			21,33	77,70
		Material and Installation w/o Profit (TRY)			99,03	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**97,13**	
		Unit Price (TRY)			**123,79**	

Item No	Analysis Name					UoM
35.405.1170	**Weather-proof clock supply line**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.140.2501	2 x 1.5 mm² / Installation of a supply line with NVV (NYM) lead-free, PVC-insulated cables / MAIN LINE AND SUPPLY LINES (Market price)	m	1	17,78	17,78	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			25,79	65,05
		Material and Installation w/o Profit (TRY)			90,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**81,31**	
		Unit Price (TRY)			**113,55**	

Item No	Analysis Name					UoM
35.405.2000	**IP Master Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2000	IP Master Clock / SYNCHRONIZED CLOCK SYSTEM (Market price)	Qty	1	99.108,80	99.108,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
		Total Excluding Profit (TRY)			99.108,80	3.570,00
		Material and Installation w/o Profit (TRY)			102.678,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.462,50**	
		Unit Price (TRY)			**128.348,50**	

Item No	Analysis Name					UoM
35.405.2110	**Min. Ø30 cm, single-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2110	Min. Ø30 cm, single-sided / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	10.184,72	10.184,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			10.184,72	867,50
		Material and Installation w/o Profit (TRY)			11.052,22	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**13.815,27**	

Item No	Analysis Name					UoM
35.405.2120	**Min. Ø30 cm, double-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2120	Min. Ø30 cm, double-sided / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	22.539,92	22.539,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			22.539,92	867,50
		Material and Installation w/o Profit (TRY)			23.407,42	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**29.259,27**	

Item No	Analysis Name					UoM
35.405.2130	**Min. Ø40 cm, single-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2130	Min. Ø40 cm, single-sided / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	13.783,12	13.783,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			13.783,12	867,50
		Material and Installation w/o Profit (TRY)			14.650,62	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**18.313,28**	

Item No	Analysis Name					UoM
35.405.2140	**Min. Ø40 cm, double-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2140	Min. Ø40 cm, double-sided / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	27.906,32	27.906,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	27.906,32	867,50
				Material and Installation w/o Profit (TRY)	28.773,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**35.967,28**	

Item No	Analysis Name					UoM
35.405.2150	**Min. Ø40 cm, double-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2150	Min. Ø30 cm, single-sided, outdoor environment (min. IP65) / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	12.212,93	12.212,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	12.212,93	867,50
				Material and Installation w/o Profit (TRY)	13.080,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**16.350,54**	

Item No	Analysis Name					UoM
35.405.2160	**Min. Ø40 cm, double-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2160	Min. Ø30 cm, double-sided, outdoor environment (min. IP65) / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	27.039,17	27.039,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	27.039,17	867,50
				Material and Installation w/o Profit (TRY)	27.906,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**34.883,34**	

Item No	Analysis Name					UoM
35.405.2170	**Min. Ø40 cm, double-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2170	Min. Ø40 cm, single-sided, outdoor environment (min. IP65) / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	16.537,25	16.537,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	16.537,25	867,50
				Material and Installation w/o Profit (TRY)	17.404,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**21.755,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.405.2180	**Min. Ø40 cm, double-sided / IP Analog Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2180	Min. Ø40 cm, double-sided, outdoor environment (min. IP65) / IP Analog Slave Clock / Synchronized Clock System (Market price)	Qty	1	33.478,85	33.478,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	33.478,85	867,50
				Material and Installation w/o Profit (TRY)	34.346,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**42.932,94**	

Item No	Analysis Name					UoM
35.405.2210	**Min. 5-cm-high digits, single sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2210	Min. 5-cm-high digits, single sided / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	14.344,72	14.344,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	14.344,72	867,50
				Material and Installation w/o Profit (TRY)	15.212,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**19.015,27**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.405.2220	**Min. 5-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2220	Min. 5-cm-high digits, double-sided / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	32.274,32	32.274,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	32.274,32	867,50
				Material and Installation w/o Profit (TRY)	33.141,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**41.427,28**	

Item No	Analysis Name					UoM
35.405.2230	**Min. 7-cm-high digits, single sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2230	Min. 7-cm-high digits, single sided / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	17.017,52	17.017,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	17.017,52	867,50
				Material and Installation w/o Profit (TRY)	17.885,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**22.356,28**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.405.2240	**Min. 7-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2240	Min. 7-cm-high digits, double-sided / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	37.578,32	37.578,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	37.578,32	867,50
				Material and Installation w/o Profit (TRY)	38.445,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**48.057,28**	

Item No	Analysis Name					UoM
35.405.2250	**Min. 10-cm-high digits, single sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2250	Min. 10-cm-high digits, single sided / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	25.815,92	25.815,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	25.815,92	867,50
				Material and Installation w/o Profit (TRY)	26.683,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**33.354,27**	

Item No	Analysis Name					UoM
35.405.2260	**Min. 10-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2260	Min. 10-cm-high digits, double-sided / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	55.705,52	55.705,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			55.705,52	867,50
		Material and Installation w/o Profit (TRY)			56.573,02	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**70.716,27**	

Item No	Analysis Name					UoM
35.405.2265	**Min. 10-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2265	Min. 5-cm-high digits, single sided, outdoor environment (min. IP65) / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	17.211,17	17.211,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			17.211,17	867,50
		Material and Installation w/o Profit (TRY)			18.078,67	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**22.598,34**	

Item No	Analysis Name					UoM
35.405.2270	**Min. 10-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2270	Min. 5-cm-high digits, double-sided, outdoor environment (min. IP65) / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	38.720,45	38.720,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	38.720,45	867,50
				Material and Installation w/o Profit (TRY)	39.587,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**49.484,94**	

Item No	Analysis Name					UoM
35.405.2275	**Min. 10-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2275	Min. 7-cm-high digits, single sided, outdoor environment (min. IP65) / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	20.412,29	20.412,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	20.412,29	867,50
				Material and Installation w/o Profit (TRY)	21.279,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**26.599,74**	

Item No	Analysis Name					UoM
35.405.2280	**Min. 10-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2280	Min. 7-cm-high digits, double-sided, outdoor environment (min. IP65) / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	45.085,25	45.085,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	45.085,25	867,50
				Material and Installation w/o Profit (TRY)	45.952,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**57.440,94**	

Item No	Analysis Name					UoM
35.405.2285	**Min. 10-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2285	Min. 10-cm-high digits, single sided, outdoor environment (min. IP65) / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	30.970,37	30.970,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	30.970,37	867,50
				Material and Installation w/o Profit (TRY)	31.837,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**39.797,34**	

Item No	Analysis Name					UoM
35.405.2290	**Min. 10-cm-high digits, double-sided / IP Digital Slave Clock**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2290	Min. 10-cm-high digits, double-sided, outdoor environment (min. IP65) / IP Digital Slave Clock / Synchronized Clock System (Market price)	Qty	1	66.837,89	66.837,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	66.837,89	867,50
				Material and Installation w/o Profit (TRY)	67.705,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.084,38**	
				Unit Price (TRY)	**84.631,74**	

Item No	Analysis Name					UoM
35.405.2300	**GPS Antenna / GPS Antenna**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.405.2300	GPS Antenna / Synchronized Clock System (Market price)	Qty	1	16.861,52	16.861,52	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	16.861,52	1.735,00
				Material and Installation w/o Profit (TRY)	18.596,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.168,75**	
				Unit Price (TRY)	**23.245,65**	

Item No	Analysis Name					UoM
35.410.1101	**Single-cycle, addressable fire alarm control panel, with min. 120 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1101	Single-cycle, addressable fire alarm control panel, with min. 120 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	55.993,60	55.993,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
				Total Excluding Profit (TRY)	55.993,60	8.970,00
				Material and Installation w/o Profit (TRY)	64.963,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.212,50**	
				Unit Price (TRY)	**81.204,50**	

Item No	Analysis Name					UoM
35.410.1102	**2-cycle, addressable fire alarm control panel, with min. 240 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1102	Two-cycle, addressable fire alarm control panel, with min. 240 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	59.488,00	59.488,00	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	59.488,00	9.670,00
				Material and Installation w/o Profit (TRY)	69.158,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**12.087,50**	
				Unit Price (TRY)	**86.447,50**	

Item No	Analysis Name					UoM
35.410.1103	**3-cycle, addressable fire alarm control panel, with min. 360 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1103	Three-cycle, addressable fire alarm control panel, with min. 360 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	70.886,40	70.886,40	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	11	700,00		7.700,00
		Total Excluding Profit (TRY)			70.886,40	10.805,00
		Material and Installation w/o Profit (TRY)			81.691,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**13.506,25**	
		Unit Price (TRY)			**102.114,25**	

Item No	Analysis Name					UoM
35.410.1104	**4-cycle, addressable fire alarm control panel, with min. 480 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1104	Four-cycle, addressable fire alarm control panel, with min. 480 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	76.741,60	76.741,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
		Total Excluding Profit (TRY)			76.741,60	11.505,00
		Material and Installation w/o Profit (TRY)			88.246,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**14.381,25**	
		Unit Price (TRY)			**110.308,25**	

Item No	Analysis Name					UoM
35.410.1105	**5-cycle, addressable fire alarm control panel, with min. 600 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1105	Five-cycle, addressable fire alarm control panel, with min. 600 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	87.890,40	87.890,40	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	13	700,00		9.100,00
		Total Excluding Profit (TRY)			87.890,40	12.205,00
		Material and Installation w/o Profit (TRY)			100.095,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**15.256,25**	
		Unit Price (TRY)			**125.119,25**	

Item No	Analysis Name					UoM
35.410.1106	**6-cycle, addressable fire alarm control panel, with min. 720 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1106	Six-cycle, addressable fire alarm control panel, with min. 720 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	100.110,40	100.110,40	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
		Total Excluding Profit (TRY)			100.110,40	12.905,00
		Material and Installation w/o Profit (TRY)			113.015,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**16.131,25**	
		Unit Price (TRY)			**141.269,25**	

Item No	Analysis Name					UoM
35.410.1107	**7-cycle, addressable fire alarm control panel, with min. 840 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1107	Seven-cycle, addressable fire alarm control panel, with min. 840 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	110.645,60	110.645,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
		Total Excluding Profit (TRY)			110.645,60	13.605,00
		Material and Installation w/o Profit (TRY)			124.250,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**17.006,25**	
		Unit Price (TRY)			**155.313,25**	

Item No	Analysis Name					UoM
35.410.1108	**8-cycle, addressable fire alarm control panel, with min. 960 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1108	Eight-cycle, addressable fire alarm control panel, with min. 960 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	123.167,20	123.167,20	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
		Total Excluding Profit (TRY)			123.167,20	14.740,00
		Material and Installation w/o Profit (TRY)			137.907,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**18.425,00**	
		Unit Price (TRY)			**172.384,00**	

Item No	Analysis Name					UoM
35.410.1109	**9-cycle, addressable fire alarm control panel, with min. 1,080 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1109	Nine-cycle, addressable fire alarm control panel, with min. 1080 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	139.900,80	139.900,80	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician's helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	17	700,00		11.900,00
				Total Excluding Profit (TRY)	139.900,80	15.440,00
				Material and Installation w/o Profit (TRY)	155.340,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**19.300,00**	
				Unit Price (TRY)	**194.176,00**	

Item No	Analysis Name					UoM
35.410.1110	**10-cycle, addressable fire alarm control panel, with min. 1,200 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1110	10-cycle, addressable fire alarm control panel, with min. 1200 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	149.853,60	149.853,60	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician's helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
				Total Excluding Profit (TRY)	149.853,60	16.305,00
				Material and Installation w/o Profit (TRY)	166.158,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**20.381,25**	
				Unit Price (TRY)	**207.698,25**	

Item No	Analysis Name					UoM
35.410.1111	**11-cycle, addressable fire alarm control panel, with min. 1,320 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1111	11-cycle, addressable fire alarm control panel, with min. 1320 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	159.827,20	159.827,20	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	19	700,00		13.300,00
		Total Excluding Profit (TRY)			159.827,20	17.005,00
		Material and Installation w/o Profit (TRY)			176.832,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**21.256,25**	
		Unit Price (TRY)			**221.040,25**	

Item No	Analysis Name					UoM
35.410.1112	**12-cycle, addressable fire alarm control panel, with min. 1,440 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1112	12-cycle, addressable fire alarm control panel, with min. 1440 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	170.071,20	170.071,20	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
		Total Excluding Profit (TRY)			170.071,20	17.705,00
		Material and Installation w/o Profit (TRY)			187.776,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**22.131,25**	
		Unit Price (TRY)			**234.720,25**	

Item No	Analysis Name					UoM
35.410.1113	**13-cycle, addressable fire alarm control panel, with min. 1,560 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1113	13-cycle, addressable fire alarm control panel, with min. 1560 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	179.878,40	179.878,40	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
		Total Excluding Profit (TRY)			179.878,40	18.840,00
		Material and Installation w/o Profit (TRY)			198.718,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**23.550,00**	
		Unit Price (TRY)			**248.398,00**	

Item No	Analysis Name					UoM
35.410.1114	**14-cycle, addressable fire alarm control panel, with min. 1,680 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1114	14-cycle, addressable fire alarm control panel, with min. 1680 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	190.257,60	190.257,60	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	22	700,00		15.400,00
		Total Excluding Profit (TRY)			190.257,60	19.540,00
		Material and Installation w/o Profit (TRY)			209.797,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**24.425,00**	
		Unit Price (TRY)			**262.247,00**	

Item No	Analysis Name					UoM
35.410.1115	**15-cycle, addressable fire alarm control panel, with min. 1,800 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1115	15-cycle, addressable fire alarm control panel, with min. 1800 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	200.304,00	200.304,00	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	23	700,00		16.100,00
		Total Excluding Profit (TRY)			200.304,00	20.240,00
		Material and Installation w/o Profit (TRY)			220.544,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**25.300,00**	
		Unit Price (TRY)			**275.680,00**	

Item No	Analysis Name					UoM
35.410.1116	**16-cycle, addressable fire alarm control panel, with min. 1,920 address capacity. / Addressable fire alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1116	16-cycle, addressable fire alarm control panel, with min. 1920 address capacity. / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	209.736,80	209.736,80	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
		Total Excluding Profit (TRY)			209.736,80	20.940,00
		Material and Installation w/o Profit (TRY)			230.676,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**26.175,00**	
		Unit Price (TRY)			**288.346,00**	

Item No	Analysis Name					UoM
35.410.1117	**Network interface card (to be installed on each control panel or repeater panel) should be able to operate on up to 32 addressable alarm panels and repeater panel network. / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1117	Network interface card / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	7.072,00	7.072,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	7.072,00	258,75
				Material and Installation w/o Profit (TRY)	7.330,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**9.163,44**	

Item No	Analysis Name					UoM
35.410.1118	**Mini thermal printer / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1118	Mini thermal printer / Addressable fire alarm control panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	6.340,88	6.340,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	6.340,88	258,75
				Material and Installation w/o Profit (TRY)	6.599,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**8.249,54**	

Item No	Analysis Name					UoM
35.410.1501	**RS-232 Communication Module / Addressable fire alarm control panel RS communication module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1501	RS-232 Communication Module / Addressable fire alarm control panel RS communication module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	4.440,80	4.440,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	4.440,80	958,75
				Material and Installation w/o Profit (TRY)	5.399,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.198,44**	
				Unit Price (TRY)	**6.749,44**	

Item No	Analysis Name					UoM
35.410.1502	**RS-485 Communication Module / Addressable fire alarm control panel RS communication module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1502	RS-485 Communication Module / Addressable fire alarm control panel RS communication module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.002,40	5.002,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	5.002,40	958,75
				Material and Installation w/o Profit (TRY)	5.961,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.198,44**	
				Unit Price (TRY)	**7.451,44**	

Item No	Analysis Name					UoM
35.410.1510	**Addressable fire alarm control panel TCP/IP communication module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1510	Addressable fire alarm control panel TCP/IP communication module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	15.423,20	15.423,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			15.423,20	958,75
		Material and Installation w/o Profit (TRY)			16.381,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**20.477,44**	

Item No	Analysis Name					UoM
35.410.1520	**Addressable fire alarm control panel GPRS communication module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1520	Addressable fire alarm control panel GPRS communication module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	19.697,60	19.697,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			19.697,60	958,75
		Material and Installation w/o Profit (TRY)			20.656,35	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**25.820,44**	

Item No	Analysis Name					UoM
35.410.1530	**Addressable fire alarm control panel MODBUS communication module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1530	Addressable fire alarm control panel MODBUS communication module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	20.727,20	20.727,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			20.727,20	958,75
		Material and Installation w/o Profit (TRY)			21.685,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**27.107,44**	

Item No	Analysis Name					UoM
35.410.1540	**Addressable fire alarm control panel BACnet communication module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.1540	Addressable fire alarm control panel BACnet communication module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	20.727,20	20.727,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			20.727,20	958,75
		Material and Installation w/o Profit (TRY)			21.685,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**27.107,44**	

Item No	Analysis Name					UoM
35.410.2000	**Addressable fire alarm repeater panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2000	Addressable fire alarm repeater panel / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	23.628,80	23.628,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	23.628,80	6.270,00
				Material and Installation w/o Profit (TRY)	29.898,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**7.837,50**	
				Unit Price (TRY)	**37.373,50**	

Item No	Analysis Name					UoM
35.410.2011	**12 fire telephone capacity / Analog addressable fire alarm system fire telephone control module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2011	12 fire telephone capacity / Analog addressable fire alarm system fire telephone control module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	53.175,20	53.175,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	53.175,20	4.870,00
				Material and Installation w/o Profit (TRY)	58.045,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**6.087,50**	
				Unit Price (TRY)	**72.556,50**	

Item No	Analysis Name					UoM
35.410.2012	**16 fire telephone capacity / Analog addressable fire alarm system fire telephone control module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2012	16 fire telephone capacity / Analog addressable fire alarm system fire telephone control module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	66.934,40	66.934,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	66.934,40	6.270,00
				Material and Installation w/o Profit (TRY)	73.204,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.837,50**	
				Unit Price (TRY)	**91.505,50**	

Item No	Analysis Name					UoM
35.410.2013	**32 fire telephone capacity / Analog addressable fire alarm system fire telephone control module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2013	32 fire telephone capacity / Analog addressable fire alarm system fire telephone control module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	91.405,60	91.405,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	91.405,60	7.670,00
				Material and Installation w/o Profit (TRY)	99.075,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**9.587,50**	
				Unit Price (TRY)	**123.844,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.410.2020	**Addressable optical smoke detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2020	Addressable optical smoke detector / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	959,92	959,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	959,92	258,75
				Material and Installation w/o Profit (TRY)	1.218,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.523,34**	

Item No	Analysis Name					UoM
35.410.2030	**Addressable optical smoke detector with short circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2030	Addressable optical smoke detector with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	1.209,52	1.209,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.209,52	258,75
				Material and Installation w/o Profit (TRY)	1.468,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.835,34**	

Item No	Analysis Name					UoM
35.410.2040	**Addressable temperature detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2040	Addressable temperature detector / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	959,92	959,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			959,92	258,75
		Material and Installation w/o Profit (TRY)			1.218,67	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.523,34**	

Item No	Analysis Name					UoM
35.410.2050	**Addressable temperature detector with short circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2050	Addressable temperature detector with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	1.209,52	1.209,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.209,52	258,75
		Material and Installation w/o Profit (TRY)			1.468,27	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.835,34**	

Item No	Analysis Name					UoM
35.410.2060	**Addressable combined optical smoke and temperature detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2060	Addressable combined optical smoke and temperature detector / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	1.071,20	1.071,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.071,20	258,75
				Material and Installation w/o Profit (TRY)	1.329,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.662,44**	

Item No	Analysis Name					UoM
35.410.2070	**Addressable combined optical smoke and temperature detector with short circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2070	Addressable combined optical smoke and temperature detector with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	1.518,40	1.518,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.518,40	258,75
				Material and Installation w/o Profit (TRY)	1.777,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.221,44**	

Item No	Analysis Name					UoM
35.410.2501	**A system with active air sampling precision smoke detector and a protection area of min. 500 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2501	A system with active sampling precision smoke detector with a protection area of min. 500 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Alarm Systems (Market price)	Qty	1	18.418,40	18.418,40	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
		Total Excluding Profit (TRY)			18.418,40	13.280,00
		Material and Installation w/o Profit (TRY)			31.698,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**16.600,00**	
		Unit Price (TRY)			**39.623,00**	

Item No	Analysis Name					UoM
35.410.2502	**A system with active sampling precision smoke detector with a protection area of min. 750 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2502	A system with active sampling precision smoke detector with a protection area of min. 750 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Alarm Systems (Market price)	Qty	1	20.716,80	20.716,80	
	Installation Components					
10.100.1062	Unskilled worker	h	9	165,00		1.485,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	20	185,00		3.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
		Total Excluding Profit (TRY)			20.716,80	18.585,00
		Material and Installation w/o Profit (TRY)			39.301,80	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**23.231,25**	
		Unit Price (TRY)			**49.127,25**	

Item No	Analysis Name					UoM
35.410.2503	**A system with active sampling precision smoke detector with a protection area of min. 1,250 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2503	A system with active sampling precision smoke detector with a protection area of min. 1250 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Alarm Systems (Market price)	Qty	1	28.704,00	28.704,00	
	Installation Components					
10.100.1062	Unskilled worker	h	13	165,00		2.145,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician's helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
		Total Excluding Profit (TRY)			28.704,00	26.395,00
		Material and Installation w/o Profit (TRY)			55.099,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**32.993,75**	
		Unit Price (TRY)			**68.873,75**	

Item No	Analysis Name					UoM
35.410.2504	**A system with active sampling precision smoke detector with a protection area of min. 2,000 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2504	A system with active sampling precision smoke detector with a protection area of min. 2000 m² in configuration class C. / Active air sampling precision smoke detector / Fire Detection, Extinction and Alarm Systems (Market price)	Qty	1	37.731,20	37.731,20	
	Installation Components					
10.100.1062	Unskilled worker	h	15	165,00		2.475,00
10.100.1081	Master electrician	h	45	250,00		11.250,00
10.100.1083	Master electrician's helper	h	45	185,00		8.325,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
		Total Excluding Profit (TRY)			37.731,20	36.050,00
		Material and Installation w/o Profit (TRY)			73.781,20	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**45.062,50**	
		Unit Price (TRY)			**92.226,50**	

Item No	Analysis Name					UoM
35.410.2510	**Ventilation duct sampling device with an addressable optical smoke detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2510	Ventilation duct sampling device with an addressable optical smoke detector / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.210,40	5.210,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	5.210,40	2.952,50
				Material and Installation w/o Profit (TRY)	8.162,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.690,63**	
				Unit Price (TRY)	**10.203,63**	

Item No	Analysis Name					UoM
35.410.2520	**Addressable water leak detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2520	Addressable water leak detector / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	906,88	906,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	906,88	258,75
				Material and Installation w/o Profit (TRY)	1.165,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.457,04**	

Item No	Analysis Name					UoM
35.410.2530	**Addressable fire alarm button (resettable) / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2530	Resettable addressable fire alarm button / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	1.081,60	1.081,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.081,60	258,75
				Material and Installation w/o Profit (TRY)	1.340,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.675,44**	

Item No	Analysis Name					UoM
35.410.2540	**Addressable, weather-proof fire alarm button (resettable) / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2540	Resettable, weather-proof, addressable fire alarm button / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.486,64	2.486,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.486,64	258,75
				Material and Installation w/o Profit (TRY)	2.745,39	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.431,74**	

Item No	Analysis Name					UoM
35.410.2550	**Addressable fire alarm button (resettable) with short circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2550	Resettable, addressable fire alarm button with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	1.405,04	1.405,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.405,04	258,75
				Material and Installation w/o Profit (TRY)	1.663,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.079,74**	

Item No	Analysis Name					UoM
35.410.2560	**Resettable, weather-proof, addressable fire alarm button with short circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2560	Resettable, weather-proof, addressable fire alarm button with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.871,44	2.871,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.871,44	258,75
				Material and Installation w/o Profit (TRY)	3.130,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.912,74**	

Item No	Analysis Name					UoM
35.410.2570	**Addressable, audible alarm control module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2570	Addressable audible alarm control module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.686,32	2.686,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.686,32	383,75
				Material and Installation w/o Profit (TRY)	3.070,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**3.837,59**	

Item No	Analysis Name					UoM
35.410.2580	**Addressable short circuit insulator audible alarm control module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2580	Addressable short circuit insulator audible alarm control module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	3.164,72	3.164,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.164,72	383,75
				Material and Installation w/o Profit (TRY)	3.548,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**4.435,59**	

Item No	Analysis Name					UoM
35.410.2590	**Addressable zone control module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2590	Addressable zone control module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.748,72	2.748,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.748,72	383,75
				Material and Installation w/o Profit (TRY)	3.132,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**3.915,59**	

Item No	Analysis Name					UoM
35.410.2600	**Addressable zone control module with short circuit insulator**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2600	Addressable zone control module with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.915,12	2.915,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.915,12	383,75
				Material and Installation w/o Profit (TRY)	3.298,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**4.123,59**	

Item No	Analysis Name					UoM
35.410.2610	**Addressable, intrinsically safe zone control module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2610	Addressable, intrinsically safe zone control module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	3.442,40	3.442,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			3.442,40	1.783,75
		Material and Installation w/o Profit (TRY)			5.226,15	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.229,69**	
		Unit Price (TRY)			**6.532,69**	

Item No	Analysis Name					UoM
35.410.2620	**Addressable relay module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2620	Addressable relay module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.613,52	2.613,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			2.613,52	383,75
		Material and Installation w/o Profit (TRY)			2.997,27	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**479,69**	
		Unit Price (TRY)			**3.746,59**	

Item No	Analysis Name					UoM
35.410.2630	**Addressable relay module with short circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2630	Addressable relay module with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.811,12	2.811,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.811,12	383,75
				Material and Installation w/o Profit (TRY)	3.194,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**3.993,59**	

Item No	Analysis Name					UoM
35.410.2640	**Addressable relay module resistant to high current / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2640	Addressable relay module resistant to high current / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.933,84	2.933,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.933,84	383,75
				Material and Installation w/o Profit (TRY)	3.317,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**4.146,99**	

Item No	Analysis Name					UoM
35.410.2650	**Addressable contact monitoring module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2650	Addressable contact monitoring module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.415,92	2.415,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.415,92	383,75
				Material and Installation w/o Profit (TRY)	2.799,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**3.499,59**	

Item No	Analysis Name					UoM
35.410.2660	**Addressable contact monitoring module with short circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2660	Addressable contact monitoring module with short circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.915,12	2.915,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.915,12	383,75
				Material and Installation w/o Profit (TRY)	3.298,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**479,69**	
				Unit Price (TRY)	**4.123,59**	

Item No	Analysis Name					UoM
35.410.2670	**Addressable short circuit insulator module / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.2670	Addressable short circuit insulator module / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	1.240,72	1.240,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.240,72	383,75
		Material and Installation w/o Profit (TRY)			1.624,47	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**479,69**	
		Unit Price (TRY)			**2.030,59**	

Item No	Analysis Name					UoM
35.410.3000	**Addressable loop-powered fire siren / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3000	Addressable loop-powered fire siren / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.399,28	2.399,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			2.399,28	258,75
		Material and Installation w/o Profit (TRY)			2.658,03	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**3.322,54**	

Item No	Analysis Name					UoM
35.410.3010	**Addressable cycle-powered fire siren with short-circuit insulator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3010	Addressable cycle-powered fire siren with short-circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.763,28	2.763,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.763,28	258,75
				Material and Installation w/o Profit (TRY)	3.022,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.777,54**	

Item No	Analysis Name					UoM
35.410.3020	**Addressable loop-powered fire siren / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3020	Addressable loop-powered fire siren with strobe light / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.736,24	2.736,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.736,24	258,75
				Material and Installation w/o Profit (TRY)	2.994,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.743,74**	

Item No	Analysis Name					UoM
35.410.3030	**Addressable cycle-powered fire siren with short-circuit insulator and strobe light / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3030	Addressable cycle-powered fire siren with short-circuit insulator and strobe light / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	3.079,44	3.079,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.079,44	258,75
				Material and Installation w/o Profit (TRY)	3.338,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**4.172,74**	

Item No	Analysis Name					UoM
35.410.3040						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3040	Addressable loop-powered fire strobe light / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.390,96	2.390,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.390,96	258,75
				Material and Installation w/o Profit (TRY)	2.649,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.312,14**	

Item No	Analysis Name					UoM
35.410.3050						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3050	Addressable cycle-powered fire strobe light with short-circuit insulator / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.757,04	2.757,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.757,04	258,75
				Material and Installation w/o Profit (TRY)	3.015,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.769,74**	

Item No	Analysis Name					UoM
35.410.3100	**Addressable fire alarm system fire zone telephone / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3100	Addressable fire alarm system fire zone telephone / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	10.202,40	10.202,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	10.202,40	1.917,50
				Material and Installation w/o Profit (TRY)	12.119,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.396,88**	
				Unit Price (TRY)	**15.149,88**	

Item No	Analysis Name					UoM
35.410.3110	**Linear wire temperature sensor control unit for the addressable fire alarm system / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3110	Linear wire temperature sensor control unit for the addressable fire alarm system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	50.481,60	50.481,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	50.481,60	7.070,00
				Material and Installation w/o Profit (TRY)	57.551,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**8.837,50**	
				Unit Price (TRY)	**71.939,50**	

Item No	Analysis Name					UoM
35.410.3120	**Linear wire temperature detector for the addressable fire alarm system / Fire Detection, Extinction and Fire Alarm Systems**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3120	Linear wire temperature detector for the addressable fire alarm system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	m	1	921,44	921,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	921,44	103,50
				Material and Installation w/o Profit (TRY)	1.024,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**1.281,18**	

Item No	Analysis Name					UoM
35.410.3130	**External wire temperature sensor for the addressable fire alarm system / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.3130	External wire temperature sensor for the addressable fire alarm system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	2.283,84	2.283,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,2	185,00		37,00
				Total Excluding Profit (TRY)	2.283,84	103,50
				Material and Installation w/o Profit (TRY)	2.387,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129,38**	
				Unit Price (TRY)	**2.984,18**	

Item No	Analysis Name					UoM
35.410.4001	**Addressable fire detection system, graphical monitoring/management software and hardware for 1 control panel / Addressable fire detection system, graphical monitoring/management software and hardware / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.4001	Addressable fire detection system, graphical monitoring/management software and hardware for 1 Control Panel	Qty	1	37.076,00	37.076,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	37.076,00	4.870,00
				Material and Installation w/o Profit (TRY)	41.946,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**6.087,50**	
				Unit Price (TRY)	**52.432,50**	

Item No	Analysis Name					UoM
35.410.4002	**Addressable fire detection system, graphical monitoring/management software and hardware for 4 control panel / Addressable fire detection system, graphical monitoring/management software and hardware / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.4002	Addressable fire detection system, graphical monitoring/management software and hardware for 4 Control Panels	Qty	1	51.989,60	51.989,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
		Total Excluding Profit (TRY)			51.989,60	7.670,00
		Material and Installation w/o Profit (TRY)			59.659,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**9.587,50**	
		Unit Price (TRY)			**74.574,50**	

Item No	Analysis Name					UoM
35.410.4003	**Addressable fire detection system, graphical monitoring/management software and hardware for 8 control panel / Addressable fire detection system, graphical monitoring/management software and hardware / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.4003	Addressable fire detection system, graphical monitoring/management software and hardware for 8 Control Panels	Qty	1	67.464,80	67.464,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
		Total Excluding Profit (TRY)			67.464,80	10.470,00
		Material and Installation w/o Profit (TRY)			77.934,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**13.087,50**	
		Unit Price (TRY)			**97.418,50**	

Item No	Analysis Name					UoM
35.410.4004	**Addressable fire detection system, graphical monitoring/management software and hardware for 16 control panel / Addressable fire detection system, graphical monitoring/management software and hardware / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.4004	Addressable fire detection system, graphical monitoring/management software and hardware for 16 Control Panels	Qty	1	80.870,40	80.870,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
		Total Excluding Profit (TRY)			80.870,40	13.270,00
		Material and Installation w/o Profit (TRY)			94.140,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**16.587,50**	
		Unit Price (TRY)			**117.675,50**	

Item No	Analysis Name					UoM
35.410.4006	**Graphic monitoring/management user software for 10 users / Addressable fire detection system, graphical monitoring/management software and hardware / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.4006	Graphic monitoring/management user software for 10 users	Qty	1	20.530,64	20.530,64	
	Installation Components					
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			20.530,64	1.400,00
		Material and Installation w/o Profit (TRY)			21.930,64	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.750,00**	
		Unit Price (TRY)			**27.413,30**	

Item No	Analysis Name					UoM
35.410.4007	**Graphic monitoring/management user software for 25 users / Addressable fire detection system, graphical monitoring/management software and hardware / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.4007	Graphic monitoring/management user software for 25 users	Qty	1	40.914,64	40.914,64	
	Installation Components					
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	40.914,64	1.400,00
				Material and Installation w/o Profit (TRY)	42.314,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.750,00**	
				Unit Price (TRY)	**52.893,30**	

Item No	Analysis Name					UoM
35.410.4008	**Graphic monitoring/management user software for 50 users / Addressable fire detection system, graphical monitoring/management software and hardware / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.4008	Graphic monitoring/management user software for 50 users	Qty	1	71.657,04	71.657,04	
	Installation Components					
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	71.657,04	1.400,00
				Material and Installation w/o Profit (TRY)	73.057,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.750,00**	
				Unit Price (TRY)	**91.321,30**	

Item No	Analysis Name					UoM
35.410.5001	**Software and hardware for integration of the fire detection and alarm system with the CCTV system for 1 control panel / Software and hardware for integration of the fire detection and alarm system with the CCTV system / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.5001	Software for integration of the fire detection and alarm system for 1 Control Panel with the CCTV system / Software for integration of the fire detection and alarm system with the CCTV system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	25.781,60	25.781,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	25.781,60	3.835,00
				Material and Installation w/o Profit (TRY)	29.616,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.793,75**	
				Unit Price (TRY)	**37.020,75**	

Item No	Analysis Name					UoM
35.410.5002	**Software for integration of the fire detection and alarm system for 4 Control Panel with the CCTV system / Software and hardware for integration of the fire detection and alarm system with the CCTV system / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.5002	Software for integration of the fire detection and alarm system for 4 Control Panels with the CCTV system / Software for integration of the fire detection and alarm system with the CCTV system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	31.127,20	31.127,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	31.127,20	6.635,00
				Material and Installation w/o Profit (TRY)	37.762,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.293,75**	
				Unit Price (TRY)	**47.202,75**	

Item No	Analysis Name					UoM
35.410.5003	**Software for integration of the fire detection and alarm system for 8 Control Panel with the CCTV system / Software and hardware for integration of the fire detection and alarm system with the CCTV system / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.5003	Software for integration of the fire detection and alarm system for 8 Control Panels with the CCTV system / Software for integration of the fire detection and alarm system with the CCTV system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	37.481,60	37.481,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	37.481,60	9.435,00
				Material and Installation w/o Profit (TRY)	46.916,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.793,75**	
				Unit Price (TRY)	**58.645,75**	

Item No	Analysis Name					UoM
35.410.5004	**Software for integration of the fire detection and alarm system for 16 Control Panel with the CCTV system / Software and hardware for integration of the fire detection and alarm system with the CCTV system / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.5004	Software for integration of the fire detection and alarm system for 16 Control Panels with the CCTV system / Software for integration of the fire detection and alarm system with the CCTV system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	44.969,60	44.969,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
				Total Excluding Profit (TRY)	44.969,60	12.235,00
				Material and Installation w/o Profit (TRY)	57.204,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**15.293,75**	
				Unit Price (TRY)	**71.505,75**	

Item No	Analysis Name					UoM
35.410.5005	**Software for integration of the fire detection and alarm system for 32 Control Panel with the CCTV system / Software and hardware for integration of the fire detection and alarm system with the CCTV system / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.5005	Software for integration of the fire detection and alarm system for 32 Control Panels with the CCTV system / Software for integration of the fire detection and alarm system with the CCTV system / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	54.631,20	54.631,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
				Total Excluding Profit (TRY)	54.631,20	15.035,00
				Material and Installation w/o Profit (TRY)	69.666,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**18.793,75**	
				Unit Price (TRY)	**87.082,75**	

Item No	Analysis Name					UoM
35.410.6001	**Switch-mode power supply unit; 1 Ah / Switch-mode power supply unit (TS EN 54-4) / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.6001	Switch-mode power supply unit; 1 Ah / Switch-mode power supply unit (TS EN 54-4) / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	4.348,24	4.348,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.348,24	258,75
				Material and Installation w/o Profit (TRY)	4.606,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.758,74**	

Item No	Analysis Name					UoM
35.410.6002	**Switch-mode power supply unit; 3 Ah / Switch-mode power supply unit (TS EN 54-4) / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.6002	Switch-mode power supply unit; 3 Ah / Switch-mode power supply unit (TS EN 54-4) / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.048,16	5.048,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.048,16	258,75
				Material and Installation w/o Profit (TRY)	5.306,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.633,64**	

Item No	Analysis Name					UoM
35.410.6003	**Switch-mode power supply unit; 5 Ah / Switch-mode power supply unit (TS EN 54-4) / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.6003	Switch-mode power supply unit; 5 Ah / Switch-mode power supply unit (TS EN 54-4) / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.876,00	5.876,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.876,00	258,75
				Material and Installation w/o Profit (TRY)	6.134,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.668,44**	

Item No	Analysis Name					UoM
35.410.6004	**Switch-mode power supply unit; 10 Ah / Switch-mode power supply unit (TS EN 54-4) / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.6004	Switch-mode power supply unit; 10 Ah / Switch-mode power supply unit (TS EN 54-4) / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	9.703,20	9.703,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	9.703,20	258,75
				Material and Installation w/o Profit (TRY)	9.961,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**12.452,44**	

Item No	Analysis Name					UoM
35.410.7010						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7010	Addressable Wireless Fire Alarm Transceiver Unit / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	6.691,36	6.691,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	6.691,36	1.217,50
				Material and Installation w/o Profit (TRY)	7.908,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.521,88**	
				Unit Price (TRY)	**9.886,07**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.410.7020						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7020	Addressable Wireless Fire Alarm Expansion Module / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	6.280,56	6.280,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			6.280,56	1.217,50
		Material and Installation w/o Profit (TRY)			7.498,06	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.521,88**	
		Unit Price (TRY)			**9.372,58**	

Item No	Analysis Name					UoM
35.410.7030						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7030	Addressable Wireless Smoke Detector / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.212,48	5.212,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			5.212,48	258,75
		Material and Installation w/o Profit (TRY)			5.471,23	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**6.839,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.410.7040						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7040	Addressable Wireless Temperature Detector / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.035,68	5.035,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.035,68	258,75
				Material and Installation w/o Profit (TRY)	5.294,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.618,04**	

Item No	Analysis Name					UoM
35.410.7050						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7050	Addressable Wireless Fire, Smoke and Temperature Detector / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.399,68	5.399,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.399,68	258,75
				Material and Installation w/o Profit (TRY)	5.658,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.073,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.410.7060						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7060	Addressable Wireless Resettable Fire Alarm Button / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	6.096,48	6.096,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	6.096,48	258,75
				Material and Installation w/o Profit (TRY)	6.355,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.944,04**	

Item No	Analysis Name					UoM
35.410.7070						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7070	Addressable Wireless Fire Alarm Input Module / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	4.682,08	4.682,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.682,08	258,75
				Material and Installation w/o Profit (TRY)	4.940,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.176,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.410.7080						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7080	Addressable Wireless Fire Alarm Output Module / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	4.546,88	4.546,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.546,88	258,75
				Material and Installation w/o Profit (TRY)	4.805,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.007,04**	

Item No	Analysis Name					UoM
35.410.7090						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.410.7090	Addressable Wireless Fire Siren with Strobe Light / WIRELESS FIRE DETECTION AND WARNING SYSTEMS / ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM (Market price)	Qty	1	5.534,88	5.534,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.534,88	258,75
				Material and Installation w/o Profit (TRY)	5.793,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.242,04**	

Item No	Analysis Name					UoM
35.415.1110	**Up to 4 zones (inclusive) / Conventional Fire Alarm Control Panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1110	Up to 4 zones (inclusive) / Conventional Fire Alarm Control Panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	7.837,20	7.837,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			7.837,20	4.352,50
		Material and Installation w/o Profit (TRY)			12.189,70	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**5.440,63**	
		Unit Price (TRY)			**15.237,13**	

Item No	Analysis Name					UoM
35.415.1111	**Up to 8 zones (inclusive) / Conventional Fire Alarm Control Panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1111	Up to 8 zones (inclusive) / Conventional Fire Alarm Control Panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	9.447,60	9.447,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
		Total Excluding Profit (TRY)			9.447,60	5.052,50
		Material and Installation w/o Profit (TRY)			14.500,10	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**6.315,63**	
		Unit Price (TRY)			**18.125,13**	

Item No	Analysis Name					UoM
35.415.1112	**Up to 12 zones (inclusive) / Conventional Fire Alarm Control Panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1112	Up to 12 zones (inclusive) / Conventional Fire Alarm Control Panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	15.120,00	15.120,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
		Total Excluding Profit (TRY)			15.120,00	5.752,50
		Material and Installation w/o Profit (TRY)			20.872,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**7.190,63**	
		Unit Price (TRY)			**26.090,63**	

Item No	Analysis Name					UoM
35.415.1113	**Up to 16 zones (inclusive) / Conventional Fire Alarm Control Panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1113	Up to 16 zones (inclusive) / Conventional Fire Alarm Control Panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	16.188,00	16.188,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
		Total Excluding Profit (TRY)			16.188,00	6.452,50
		Material and Installation w/o Profit (TRY)			22.640,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**8.065,63**	
		Unit Price (TRY)			**28.300,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.415.1200	**Conventional panel driver card / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1200	Conventional panel driver card / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	4.210,80	4.210,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.210,80	258,75
				Material and Installation w/o Profit (TRY)	4.469,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.586,94**	

Item No	Analysis Name					UoM
35.415.1300	**Conventional fire alarm repeater panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1300	Conventional fire alarm repeater panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	10.454,40	10.454,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	10.454,40	3.470,00
				Material and Installation w/o Profit (TRY)	13.924,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**4.337,50**	
				Unit Price (TRY)	**17.405,50**	

Item No	Analysis Name					UoM
35.415.1400	**Conventional fire alarm button and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1400	Conventional fire button and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	293,40	293,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	293,40	258,75
				Material and Installation w/o Profit (TRY)	552,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**690,19**	

Item No	Analysis Name					UoM
35.415.1410	**Conventional resettable fire button and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1410	Conventional resettable fire button and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	460,20	460,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	460,20	258,75
				Material and Installation w/o Profit (TRY)	718,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**898,69**	

Item No	Analysis Name					UoM
35.415.1420	**Conventional, resettable, exterior fire button and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1420	Conventional, resettable, exterior fire button and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	2.011,80	2.011,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.011,80	258,75
				Material and Installation w/o Profit (TRY)	2.270,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.838,19**	

Item No	Analysis Name					UoM
35.415.1430	**Conventional fixed temperature detector and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1430	Conventional fixed temperature detector and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	724,20	724,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	724,20	258,75
				Material and Installation w/o Profit (TRY)	982,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.228,69**	

Item No	Analysis Name					UoM
35.415.1440	**Conventional temperature increase rate detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1440	Conventional temperature increase rate detector / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	829,80	829,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	829,80	258,75
				Material and Installation w/o Profit (TRY)	1.088,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.360,69**	

Item No	Analysis Name					UoM
35.415.1450	**Conventional optical smoke detector and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1450	Conventional optical smoke detector and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	974,40	974,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	974,40	258,75
				Material and Installation w/o Profit (TRY)	1.233,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.541,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.415.1460	**Parallel remote indicator / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1460	Parallel remote indicator / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	129,60	129,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	129,60	258,75
				Material and Installation w/o Profit (TRY)	388,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**485,44**	

Item No	Analysis Name					UoM
35.415.1470	**Conventional optical smoke and temperature detector and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1470	Conventional optical smoke and temperature detector and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	1.587,60	1.587,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.587,60	258,75
				Material and Installation w/o Profit (TRY)	1.846,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.307,94**	

Item No	Analysis Name					UoM
35.415.1501	**Transceiver type with a range of 10 to 100 m between the transmitter and the receiver / Conventional beam-type smoke detector and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1501	Transceiver type with a range of 10 to 100 m between the transmitter and the receiver / Conventional beam-type smoke detector and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	28.356,00	28.356,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	28.356,00	2.435,00
				Material and Installation w/o Profit (TRY)	30.791,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.043,75**	
				Unit Price (TRY)	**38.488,75**	

Item No	Analysis Name					UoM
35.415.1502	**Transceiver type with a range of 10 to 50 m between the transmitter and the receiver / Conventional beam-type smoke detector and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1502	Transceiver - reflector type with a range of 10 to 50 m between the transmitter and the receiver / Conventional beam-type smoke detector and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	17.604,00	17.604,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
				Total Excluding Profit (TRY)	17.604,00	3.135,00
				Material and Installation w/o Profit (TRY)	20.739,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.918,75**	
				Unit Price (TRY)	**25.923,75**	

Item No	Analysis Name					UoM
35.415.1503	**Transceiver type with a range of 10 to 100 m between the transmitter and the receiver / Conventional beam-type smoke detector and its installation / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1503	Transceiver - reflector type with a range of 10 to 100 m between the transmitter and the receiver / Conventional beam-type smoke detector and its installation / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	20.328,00	20.328,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	20.328,00	3.835,00
				Material and Installation w/o Profit (TRY)	24.163,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.793,75**	
				Unit Price (TRY)	**30.203,75**	

Item No	Analysis Name					UoM
35.415.1550	**Ventilation duct sampling device with a conventional optical smoke detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1550	Ventilation duct sampling device with a conventional optical smoke detector / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	10.344,00	10.344,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	10.344,00	1.817,50
				Material and Installation w/o Profit (TRY)	12.161,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.271,88**	
				Unit Price (TRY)	**15.201,88**	

Item No	Analysis Name					UoM
35.415.1560	**Internal electronic fire siren / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1560	Internal electronic fire siren / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	772,80	772,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			772,80	258,75
		Material and Installation w/o Profit (TRY)			1.031,55	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.289,44**	

Item No	Analysis Name					UoM
35.415.1570	**Internal electronic fire strobe light / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1570	Internal electronic fire strobe light / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	984,00	984,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			984,00	258,75
		Material and Installation w/o Profit (TRY)			1.242,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.553,44**	

Item No	Analysis Name					UoM
35.415.1580	**Internal electronic fire siren with strobe light / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1580	Internal electronic fire siren with strobe light / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	1.476,00	1.476,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.476,00	258,75
				Material and Installation w/o Profit (TRY)	1.734,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.168,44**	

Item No	Analysis Name					UoM
35.415.1590	**External electronic fire siren / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1590	External electronic fire siren / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	1.176,00	1.176,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.176,00	258,75
				Material and Installation w/o Profit (TRY)	1.434,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.793,44**	

Item No	Analysis Name					UoM
35.415.1600	**External electronic fire siren with strobe light / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1600	External electronic fire siren with strobe light / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	2.112,00	2.112,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.112,00	258,75
				Material and Installation w/o Profit (TRY)	2.370,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.963,44**	

Item No	Analysis Name					UoM
35.415.1610	**Conventional fire alarm button / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1610	Conventional external fire alarm button / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	849,60	849,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	849,60	258,75
				Material and Installation w/o Profit (TRY)	1.108,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.385,44**	

Item No	Analysis Name					UoM
35.415.1620	**Fire alarm detector for installation on the ceiling / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1620	Fire alarm detector kit for installation on suspended ceiling / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	165,60	165,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	165,60	258,75
				Material and Installation w/o Profit (TRY)	424,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**530,44**	

Item No	Analysis Name					UoM
35.415.1630	**Detector flush mounting box / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1630	Detector flush mounting box / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	168,00	168,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	168,00	258,75
				Material and Installation w/o Profit (TRY)	426,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**533,44**	

Item No	Analysis Name					UoM
35.415.1640	**Internal electronic fire bell / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.1640	Internal electronic fire bell / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	871,20	871,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	871,20	258,75
				Material and Installation w/o Profit (TRY)	1.129,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.412,44**	

Item No	Analysis Name					UoM
35.415.2001	**2 detection circuits and 1 extinction circuit / Conventional fire extinguishing control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.2001	2 detection circuits and 1 extinction circuit / Conventional fire extinguishing control panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	18.600,00	18.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	18.600,00	5.905,00
				Material and Installation w/o Profit (TRY)	24.505,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**7.381,25**	
				Unit Price (TRY)	**30.631,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.415.2002	**3 detection circuits and 1 extinction circuit / Conventional fire extinguishing control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.2002	3 detection circuits and 1 extinction circuit / Conventional fire extinguishing control panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	19.032,00	19.032,00	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	19.032,00	7.305,00
				Material and Installation w/o Profit (TRY)	26.337,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**9.131,25**	
				Unit Price (TRY)	**32.921,25**	

Item No	Analysis Name					UoM
35.415.2003	**4 detection circuits and 1 extinction circuit / Conventional fire extinguishing control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.2003	4 detection circuits and 1 extinction circuit / Conventional fire extinguishing control panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	24.504,00	24.504,00	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	24.504,00	9.740,00
				Material and Installation w/o Profit (TRY)	34.244,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**12.175,00**	
				Unit Price (TRY)	**42.805,00**	

Item No	Analysis Name					UoM
35.415.2004	**4 detection circuits and 2 extinction circuits / Conventional fire extinguishing control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.2004	4 detection circuits and 2 extinction circuits / Conventional fire extinguishing control panel / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	30.864,00	30.864,00	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
		Total Excluding Profit (TRY)			30.864,00	11.140,00
		Material and Installation w/o Profit (TRY)			42.004,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**13.925,00**	
		Unit Price (TRY)			**52.505,00**	

Item No	Analysis Name					UoM
35.415.2050	**Start extinguishing button / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.2050	Start extinguishing button / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	624,00	624,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			624,00	258,75
		Material and Installation w/o Profit (TRY)			882,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.103,44**	

Item No	Analysis Name					UoM
35.415.2060	**Stop (pause) extinguishing button / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.415.2060	Stop (pause) extinguishing button / CONVENTIONAL FIRE DETECTION, EXTINCTION AND ALARM SYSTEM (Market price)	Qty	1	624,00	624,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			624,00	258,75
		Material and Installation w/o Profit (TRY)			882,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.103,44**	

Item No	Analysis Name					UoM
35.417.1001						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1001	1-channel, 1x1000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	751.878,40	751.878,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
		Total Excluding Profit (TRY)			751.878,40	7.070,00
		Material and Installation w/o Profit (TRY)			758.948,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**8.837,50**	
		Unit Price (TRY)			**948.685,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1002						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1002	2-channel, 2x1000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	798.054,40	798.054,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	798.054,40	8.687,50
				Material and Installation w/o Profit (TRY)	806.741,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**10.859,38**	
				Unit Price (TRY)	**1.008.427,38**	

Item No	Analysis Name					UoM
35.417.1003						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1003	4-channel, 4x1000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	868.046,40	868.046,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	868.046,40	8.905,00
				Material and Installation w/o Profit (TRY)	876.951,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.131,25**	
				Unit Price (TRY)	**1.096.189,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1004						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1004	1-channel, 1x2000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	851.822,40	851.822,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
				Total Excluding Profit (TRY)	851.822,40	7.770,00
				Material and Installation w/o Profit (TRY)	859.592,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**9.712,50**	
				Unit Price (TRY)	**1.074.490,50**	

Item No	Analysis Name					UoM
35.417.1005						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1005	2-channel, 2x2000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	879.382,40	879.382,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	11	700,00		7.700,00
				Total Excluding Profit (TRY)	879.382,40	9.387,50
				Material and Installation w/o Profit (TRY)	888.769,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.734,38**	
				Unit Price (TRY)	**1.110.962,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1006						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1006	4-channel, 4x2000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	937.414,40	937.414,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	11	700,00		7.700,00
		Total Excluding Profit (TRY)			937.414,40	9.605,00
		Material and Installation w/o Profit (TRY)			947.019,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**12.006,25**	
		Unit Price (TRY)			**1.183.774,25**	

Item No	Analysis Name					UoM
35.417.1007						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1007	1-channel, 1x4000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.047.862,40	1.047.862,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
		Total Excluding Profit (TRY)			1.047.862,40	8.470,00
		Material and Installation w/o Profit (TRY)			1.056.332,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**10.587,50**	
		Unit Price (TRY)			**1.320.415,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1008						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1008	2-channel, 2x4000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.198.038,40	1.198.038,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	1.198.038,40	10.087,50
				Material and Installation w/o Profit (TRY)	1.208.125,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**12.609,38**	
				Unit Price (TRY)	**1.510.157,38**	

Item No	Analysis Name					UoM
35.417.1009						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1009	4-channel, 4x4000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.348.318,40	1.348.318,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	1.348.318,40	10.305,00
				Material and Installation w/o Profit (TRY)	1.358.623,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**12.881,25**	
				Unit Price (TRY)	**1.698.279,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1010						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1010	1-channel, 1x6000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.444.830,40	1.444.830,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	11	700,00		7.700,00
				Total Excluding Profit (TRY)	1.444.830,40	9.170,00
				Material and Installation w/o Profit (TRY)	1.454.000,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.462,50**	
				Unit Price (TRY)	**1.817.500,50**	

Item No	Analysis Name					UoM
35.417.1011						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1011	2-channel, 2x6000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.602.182,40	1.602.182,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	13	700,00		9.100,00
				Total Excluding Profit (TRY)	1.602.182,40	10.787,50
				Material and Installation w/o Profit (TRY)	1.612.969,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**13.484,38**	
				Unit Price (TRY)	**2.016.212,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1012						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1012	4-channel, 4x6000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.760.054,40	1.760.054,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	13	700,00		9.100,00
				Total Excluding Profit (TRY)	1.760.054,40	11.005,00
				Material and Installation w/o Profit (TRY)	1.771.059,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**13.756,25**	
				Unit Price (TRY)	**2.213.824,25**	

Item No	Analysis Name					UoM
35.417.1013						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1013	1-channel, 1x8000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.683.094,40	1.683.094,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	1.683.094,40	9.870,00
				Material and Installation w/o Profit (TRY)	1.692.964,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**12.337,50**	
				Unit Price (TRY)	**2.116.205,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1014						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1014	2-channel, 2x8000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.687.150,40	1.687.150,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
				Total Excluding Profit (TRY)	1.687.150,40	11.487,50
				Material and Installation w/o Profit (TRY)	1.698.637,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**14.359,38**	
				Unit Price (TRY)	**2.123.297,38**	

Item No	Analysis Name					UoM
35.417.1015						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1015	4-channel, 4x8000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.838.158,40	1.838.158,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
				Total Excluding Profit (TRY)	1.838.158,40	11.705,00
				Material and Installation w/o Profit (TRY)	1.849.863,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**14.631,25**	
				Unit Price (TRY)	**2.312.329,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1016						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1016	1-channel, 1x10000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.856.046,40	1.856.046,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	13	700,00		9.100,00
				Total Excluding Profit (TRY)	1.856.046,40	10.570,00
				Material and Installation w/o Profit (TRY)	1.866.616,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**13.212,50**	
				Unit Price (TRY)	**2.333.270,50**	

Item No	Analysis Name					UoM
35.417.1017						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1017	2-channel, 2x10000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.845.126,40	1.845.126,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
				Total Excluding Profit (TRY)	1.845.126,40	12.187,50
				Material and Installation w/o Profit (TRY)	1.857.313,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**15.234,38**	
				Unit Price (TRY)	**2.321.642,38**	

Item No	Analysis Name					UoM
35.417.1018						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1018	4-channel, 4x10000 m coverage area / Smart analogue linear fiber optic heat detection cable control unit / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	Qty	1	1.995.510,40	1.995.510,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
		Total Excluding Profit (TRY)			1.995.510,40	13.105,00
		Material and Installation w/o Profit (TRY)			2.008.615,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**16.381,25**	
		Unit Price (TRY)			**2.510.769,25**	

Item No	Analysis Name					UoM
35.417.1200						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1200	Plastic linear fiber optic cable standard temperature sensor / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	m	1	41,91	41,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			41,91	51,75
		Material and Installation w/o Profit (TRY)			93,66	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**64,69**	
		Unit Price (TRY)			**117,07**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.417.1300						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.417.1200	Plastic linear fiber optic cable standard temperature sensor / FIBER OPTIC HEAT DETECTION SYSTEM (Market price)	m	1	41,91	41,91	
20.300.1501	External Diameter/wall thickness mm 10.2/1.6 / Weldless pipes, (Patent drawn steel) (in compliance with TS EN 10216-1, made of Fe33) / Steel Pipes (Market price)	m	1	43,30	43,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,13	165,00		21,45
10.100.1081	Master electrician	h	0,3	250,00		75,00
10.100.1083	Master electrician’s helper	h	0,3	185,00		55,50
			Total Excluding Profit (TRY)		85,21	151,95
			Material and Installation w/o Profit (TRY)		237,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189,94**	
				Unit Price (TRY)	**296,45**	

Item No	Analysis Name					UoM
35.420.1001	**1-cycle / Addressable Combined CO-NO-NO2 Gas Control Panel / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1001	1-cycle / Addressable Combined CO-NO-NO2 Gas Control Panel / Gas Control Systems (Market price)	Qty	1	21.552,00	21.552,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
			Total Excluding Profit (TRY)		21.552,00	4.870,00
			Material and Installation w/o Profit (TRY)		26.422,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**6.087,50**	
				Unit Price (TRY)	**33.027,50**	

Item No	Analysis Name					UoM
35.420.1002	**2-cycle / Addressable Combined CO-NO-NO2 Gas Control Panel / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1002	2-cycle / Addressable Combined CO-NO-NO2 Gas Control Panel / Gas Control Systems (Market price)	Qty	1	26.232,00	26.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
		Total Excluding Profit (TRY)			26.232,00	7.670,00
		Material and Installation w/o Profit (TRY)			33.902,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**9.587,50**	
		Unit Price (TRY)			**42.377,50**	

Item No	Analysis Name					UoM
35.420.1050	**Addressable electrochemical carbon monoxide (CO) gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1050	Addressable electrochemical carbon monoxide (CO) gas detector / Gas Control Systems (Market price)	Qty	1	3.288,00	3.288,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			3.288,00	517,50
		Material and Installation w/o Profit (TRY)			3.805,50	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**4.756,88**	

Item No	Analysis Name					UoM
35.420.1100	**Addressable Nitrogen dioxide (NO2) gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1100	Addressable Nitrogen dioxide (NO2) gas detector / Gas Control Systems (Market price)	Qty	1	7.370,40	7.370,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			7.370,40	517,50
		Material and Installation w/o Profit (TRY)			7.887,90	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**9.859,88**	

Item No	Analysis Name					UoM
35.420.1150	**Addressable LPG - Natural Gas (Methane - CH4) gas panel / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1150	Addressable LPG - Natural Gas (Methane - CH4) gas panel / Gas Control Systems (Market price)	Qty	1	23.712,00	23.712,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			23.712,00	4.870,00
		Material and Installation w/o Profit (TRY)			28.582,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**6.087,50**	
		Unit Price (TRY)			**35.727,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.420.1200	**Addressable LPG gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1200	Addressable LPG gas detector / Gas Control Systems (Market price)	Qty	1	2.126,40	2.126,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	2.126,40	517,50
				Material and Installation w/o Profit (TRY)	2.643,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**3.304,88**	

Item No	Analysis Name					UoM
35.420.1250	**LPG gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1250	LPG gas detector / Gas Control Systems (Market price)	Qty	1	1.704,00	1.704,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.704,00	517,50
				Material and Installation w/o Profit (TRY)	2.221,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**2.776,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.420.1300	**Addressable LPG gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1300	Addressable LPG gas detector / Gas Control Systems (Market price)	Qty	1	2.126,40	2.126,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	2.126,40	517,50
				Material and Installation w/o Profit (TRY)	2.643,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**3.304,88**	

Item No	Analysis Name					UoM
35.420.1350	**Natural gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1350	Natural gas detector / Gas Control Systems (Market price)	Qty	1	1.704,00	1.704,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.704,00	517,50
				Material and Installation w/o Profit (TRY)	2.221,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**2.776,88**	

Item No	Analysis Name					UoM
35.420.1400	**Addressable Carbon monoxide gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1400	Addressable Carbon monoxide gas detector / Gas Control Systems (Market price)	Qty	1	3.878,40	3.878,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	3.878,40	517,50
				Material and Installation w/o Profit (TRY)	4.395,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**5.494,88**	

Item No	Analysis Name					UoM
35.420.1450	**Carbon monoxide gas detector / Gas Control Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.1450	Carbon monoxide gas detector / Gas Control Systems (Market price)	Qty	1	3.711,60	3.711,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	3.711,60	517,50
				Material and Installation w/o Profit (TRY)	4.229,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**5.286,38**	

Item No	Analysis Name					UoM
35.420.2001	**1 channel / Industrial combined gas alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.2001	1 channel / Industrial combined gas alarm control panel / GAS CONTROL SYSTEMS (Market price)	Qty	1	73.284,00	73.284,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	73.284,00	7.670,00
				Material and Installation w/o Profit (TRY)	80.954,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**9.587,50**	
				Unit Price (TRY)	**101.192,50**	

Item No	Analysis Name					UoM
35.420.2002	**2 channel / Industrial combined gas alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.2002	2 channel / Industrial combined gas alarm control panel / GAS CONTROL SYSTEMS (Market price)	Qty	1	80.100,00	80.100,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	80.100,00	9.070,00
				Material and Installation w/o Profit (TRY)	89.170,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.337,50**	
				Unit Price (TRY)	**111.462,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.420.2003	**3 channel / Industrial combined gas alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.2003	3 channel / Industrial combined gas alarm control panel / GAS CONTROL SYSTEMS (Market price)	Qty	1	86.832,00	86.832,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	86.832,00	10.470,00
				Material and Installation w/o Profit (TRY)	97.302,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**13.087,50**	
				Unit Price (TRY)	**121.627,50**	

Item No	Analysis Name					UoM
35.420.2004	**4 channel / Industrial combined gas alarm control panel / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.2004	4 channel / Industrial combined gas alarm control panel / GAS CONTROL SYSTEMS (Market price)	Qty	1	92.928,00	92.928,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
				Total Excluding Profit (TRY)	92.928,00	13.270,00
				Material and Installation w/o Profit (TRY)	106.198,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**16.587,50**	
				Unit Price (TRY)	**132.747,50**	

Item No	Analysis Name					UoM
35.420.2050	**Flame-proof infrared (IR) gas detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.2050	Flame-proof infrared (IR) gas detector / GAS CONTROL SYSTEMS (Market price)	Qty	1	57.768,00	57.768,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	57.768,00	3.317,50
				Material and Installation w/o Profit (TRY)	61.085,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.146,88**	
				Unit Price (TRY)	**76.356,88**	

Item No	Analysis Name					UoM
35.420.2100	**Flame-proof infrared (IR) gas detector / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.2100	Flame-proof infrared (IR) flame detector / GAS CONTROL SYSTEMS (Market price)	Qty	1	79.080,00	79.080,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	79.080,00	3.317,50
				Material and Installation w/o Profit (TRY)	82.397,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.146,88**	
				Unit Price (TRY)	**102.996,88**	

Item No	Analysis Name					UoM
35.420.2150	**Automatic gas and power cut-off device that detects earthquakes / Fire Detection, Extinction and Fire Alarm Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.420.2150	Automatic gas and power cutoff device that detects earthquakes / GAS CONTROL SYSTEMS (Market price)	Qty	1	3.840,00	3.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			3.840,00	1.917,50
		Material and Installation w/o Profit (TRY)			5.757,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.396,88**	
		Unit Price (TRY)			**7.196,88**	

Item No	Analysis Name					UoM
35.430.1001	**Emergency public address system control unit, min. 8 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1001	Emergency public address system control unit, min. 8 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems (Market price)	Qty	1	76.793,60	76.793,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			76.793,60	4.870,00
		Material and Installation w/o Profit (TRY)			81.663,60	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**6.087,50**	
		Unit Price (TRY)			**102.079,50**	

Item No	Analysis Name					UoM
35.430.1002	**Emergency public address system control unit, min. 16 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1002	Emergency public address system control unit, min. 16 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems (Market price)	Qty	1	86.184,80	86.184,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
		Total Excluding Profit (TRY)			86.184,80	8.105,00
		Material and Installation w/o Profit (TRY)			94.289,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**10.131,25**	
		Unit Price (TRY)			**117.862,25**	

Item No	Analysis Name					UoM
35.430.1003	**Emergency public address system control unit, min. 24 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1003	Emergency public address system control unit, min. 24 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems (Market price)	Qty	1	130.187,20	130.187,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
		Total Excluding Profit (TRY)			130.187,20	11.422,50
		Material and Installation w/o Profit (TRY)			141.609,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**14.278,13**	
		Unit Price (TRY)			**177.012,13**	

Item No	Analysis Name					UoM
35.430.1004	**Emergency public address system control unit, min. 32 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1004	Emergency public address system control unit, min. 32 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems (Market price)	Qty	1	139.588,80	139.588,80	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician’s helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
		Total Excluding Profit (TRY)			139.588,80	14.740,00
		Material and Installation w/o Profit (TRY)			154.328,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**18.425,00**	
		Unit Price (TRY)			**192.911,00**	

Item No	Analysis Name					UoM
35.430.1005	**Emergency public address system control unit, min. 40 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1005	Emergency public address system control unit, min. 40 zones / Digital Emergency Public Address System Control Unit / Emergency Public Address Systems (Market price)	Qty	1	183.632,80	183.632,80	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
		Total Excluding Profit (TRY)			183.632,80	17.975,00
		Material and Installation w/o Profit (TRY)			201.607,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**22.468,75**	
		Unit Price (TRY)			**252.009,75**	

Item No	Analysis Name					UoM
35.430.1101	**Emergency digital public address call station, min. 8 zones / Digital Emergency Public Call Station / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1101	Digital emergency public address call station, min. 8 zones / Digital Emergency Public Call Station / Emergency Public Address Systems (Market price)	Qty	1	24.696,00	24.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	24.696,00	3.317,50
				Material and Installation w/o Profit (TRY)	28.013,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.146,88**	
				Unit Price (TRY)	**35.016,88**	

Item No	Analysis Name					UoM
35.430.1102	**Emergency digital public address call station, min. 16 zones / Digital Emergency Public Call Station / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1102	Digital emergency public address call station, min. 16 zones / Digital Emergency Public Call Station / Emergency Public Address Systems (Market price)	Qty	1	24.696,00	24.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	24.696,00	6.226,25
				Material and Installation w/o Profit (TRY)	30.922,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.782,81**	
				Unit Price (TRY)	**38.652,81**	

Item No	Analysis Name					UoM
35.430.1103	**Emergency digital public address call station, min. 24 zones / Digital Emergency Public Call Station / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1103	Digital emergency public address call station, min. 24 zones / Digital Emergency Public Call Station / Emergency Public Address Systems (Market price)	Qty	1	24.718,40	24.718,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,6	165,00		99,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	24.718,40	9.151,50
				Material and Installation w/o Profit (TRY)	33.869,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.439,38**	
				Unit Price (TRY)	**42.337,38**	

Item No	Analysis Name					UoM
35.430.1104	**Emergency digital public address call station, min. 32 zones / Digital Emergency Public Call Station / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1104	Digital emergency public address call station, min. 32 zones / Digital Emergency Public Call Station / Emergency Public Address Systems (Market price)	Qty	1	24.696,00	24.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,7	165,00		115,50
10.100.1081	Master electrician	h	1,75	250,00		437,50
10.100.1083	Master electrician’s helper	h	1,75	185,00		323,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
				Total Excluding Profit (TRY)	24.696,00	12.076,75
				Material and Installation w/o Profit (TRY)	36.772,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**15.095,94**	
				Unit Price (TRY)	**45.965,94**	

Item No	Analysis Name					UoM
35.430.1105	**Emergency digital public address call station, min. 40 zones / Digital Emergency Public Call Station / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1105	Digital emergency public address call station, min. 40 zones / Digital Emergency Public Call Station / Emergency Public Address Systems (Market price)	Qty	1	24.696,00	24.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,7	165,00		115,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
		Total Excluding Profit (TRY)			24.696,00	14.985,50
		Material and Installation w/o Profit (TRY)			39.681,50	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**18.731,88**	
		Unit Price (TRY)			**49.601,88**	

Item No	Analysis Name					UoM
35.430.1201	**120 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1201	120 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	15.069,60	15.069,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
		Total Excluding Profit (TRY)			15.069,60	952,50
		Material and Installation w/o Profit (TRY)			16.022,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.190,63**	
		Unit Price (TRY)			**20.027,63**	

Item No	Analysis Name					UoM
35.430.1202	**240 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1202	240 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	26.613,60	26.613,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	26.613,60	952,50
				Material and Installation w/o Profit (TRY)	27.566,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**34.457,63**	

Item No	Analysis Name					UoM
35.430.1203	**300 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1203	300 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	28.454,40	28.454,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	28.454,40	952,50
				Material and Installation w/o Profit (TRY)	29.406,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**36.758,63**	

Item No	Analysis Name					UoM
35.430.1204	**400 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1204	400 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	29.598,40	29.598,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	29.598,40	952,50
				Material and Installation w/o Profit (TRY)	30.550,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**38.188,63**	

Item No	Analysis Name					UoM
35.430.1205	**500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1205	500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	30.316,00	30.316,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	30.316,00	952,50
				Material and Installation w/o Profit (TRY)	31.268,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**39.085,63**	

Item No	Analysis Name					UoM
35.430.1206	**4x125 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1206	4 x 125 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	36.452,00	36.452,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	36.452,00	1.387,50
				Material and Installation w/o Profit (TRY)	37.839,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.734,38**	
				Unit Price (TRY)	**47.299,38**	

Item No	Analysis Name					UoM
35.430.1207	**2x500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1207	2 x 500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	51.240,80	51.240,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	51.240,80	1.170,00
				Material and Installation w/o Profit (TRY)	52.410,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**65.513,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.430.1215	**2x500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1215	4x250 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	76.854,96	76.854,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	76.854,96	1.387,50
				Material and Installation w/o Profit (TRY)	78.242,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.734,38**	
				Unit Price (TRY)	**97.803,08**	

Item No	Analysis Name					UoM
35.430.1220	**2x500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1220	4x300 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	85.394,40	85.394,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	85.394,40	1.387,50
				Material and Installation w/o Profit (TRY)	86.781,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.734,38**	
				Unit Price (TRY)	**108.477,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.430.1225	**2x500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1225	4x500 W (rms) Power Amplifier / Power Amplifiers / Emergency Public Address Systems (Market price)	Qty	1	93.933,84	93.933,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	93.933,84	1.387,50
				Material and Installation w/o Profit (TRY)	95.321,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.734,38**	
				Unit Price (TRY)	**119.151,67**	

Item No	Analysis Name					UoM
35.430.1300	**Remote Controllers and Firefighter Panel for the Emergency Public Address System / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1300	Remote Controller and Firefighter Panel for the Emergency Public Address System / Emergency Public Address Systems (Market price)	Qty	1	18.470,40	18.470,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	18.470,40	2.787,50
				Material and Installation w/o Profit (TRY)	21.257,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.484,38**	
				Unit Price (TRY)	**26.572,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.430.1310	**Ceiling Speaker / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1310	Ceiling Speaker (surface-mounted) / Emergency Public Address Systems (Market price)	Qty	1	927,68	927,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	927,68	258,75
				Material and Installation w/o Profit (TRY)	1.186,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.483,04**	

Item No	Analysis Name					UoM
35.430.1315	**Ceiling Speaker / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1315	Ceiling Speaker (flush-mounted) / Emergency Public Address Systems (Market price)	Qty	1	828,88	828,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	828,88	258,75
				Material and Installation w/o Profit (TRY)	1.087,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.359,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.430.1320	**Wall Speaker / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1320	Wall Speaker / Emergency Public Address Systems (Market price)	Qty	1	1.179,36	1.179,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	1.179,36	367,50
				Material and Installation w/o Profit (TRY)	1.546,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**459,38**	
				Unit Price (TRY)	**1.933,57**	

Item No	Analysis Name					UoM
35.430.1325	**Wall Speaker / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1325	Projector Speaker / Emergency Public Address Systems (Market price)	Qty	1	2.466,67	2.466,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	2.466,67	367,50
				Material and Installation w/o Profit (TRY)	2.834,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**459,38**	
				Unit Price (TRY)	**3.542,71**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.430.1328	**Wall Speaker / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1328	Horn Speaker / Emergency Public Address Systems (Market price)	Qty	1	3.701,15	3.701,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
		Total Excluding Profit (TRY)			3.701,15	367,50
		Material and Installation w/o Profit (TRY)			4.068,65	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**459,38**	
		Unit Price (TRY)			**5.085,81**	

Item No	Analysis Name					UoM
35.430.1331	**Power supply unit; 55 Ah / Power supply unit (TS EN 54-4) / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1331	Power supply unit; 55 Ah / Power supply unit (TS EN 54-4) / Emergency Public Address Systems (Market price)	Qty	1	43.305,60	43.305,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			43.305,60	2.435,00
		Material and Installation w/o Profit (TRY)			45.740,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.043,75**	
		Unit Price (TRY)			**57.175,75**	

Item No	Analysis Name					UoM
35.430.1332	**Power supply unit; 100 Ah / Power supply unit (TS EN 54-4) / Emergency Public Address Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.430.1332	Power supply unit; 100 Ah / Power supply unit (TS EN 54-4) / Emergency Public Address Systems (Market price)	Qty	1	43.295,20	43.295,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			43.295,20	4.352,50
		Material and Installation w/o Profit (TRY)			47.647,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**5.440,63**	
		Unit Price (TRY)			**59.559,63**	

Item No	Analysis Name					UoM
35.440.2001	**Surface-mounted emergency lighting fixture that operates for an hour in case of outage (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2001	Surface-mounted emergency lighting fixture that operates for an hour in case of outage (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.419,52	1.419,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.419,52	258,75
		Material and Installation w/o Profit (TRY)			1.678,27	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**2.097,84**	

Item No	Analysis Name					UoM
35.440.2002	**Surface-mounted emergency lighting fixture that operates for three hours in case of outage (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2002	Surface-mounted emergency lighting fixture that operates for three hours in case of outage (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.509,12	1.509,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.509,12	258,75
				Material and Installation w/o Profit (TRY)	1.767,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.209,84**	

Item No	Analysis Name					UoM
35.440.2003	**Flush-mounted emergency lighting fixture that operates for an hour in case of outage (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2003	Flush-mounted emergency lighting fixture that operates for an hour in case of outage (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.547,52	1.547,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.547,52	258,75
				Material and Installation w/o Profit (TRY)	1.806,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.257,84**	

Item No	Analysis Name					UoM
35.440.2004	**Flush-mounted emergency lighting fixture that operates for 3-hour in case of outage (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2004	Flush-mounted emergency lighting fixture that operates for three hours in case of outage (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.649,92	1.649,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.649,92	258,75
				Material and Installation w/o Profit (TRY)	1.908,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.385,84**	

Item No	Analysis Name					UoM
35.440.2005	**Surface-mounted emergency lighting fixture with 1-hour timer that operates continuously (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2005	Surface-mounted emergency lighting fixture with 1-hour timer that operates continuously (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.496,32	1.496,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.496,32	258,75
				Material and Installation w/o Profit (TRY)	1.755,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.193,84**	

Item No	Analysis Name					UoM
35.440.2006	**Surface-mounted emergency lighting fixture with 3-hour timer that operates continuously (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2006	Surface-mounted emergency lighting fixture with 3-hour timer that operates continuously (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.598,72	1.598,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.598,72	258,75
				Material and Installation w/o Profit (TRY)	1.857,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.321,84**	

Item No	Analysis Name					UoM
35.440.2007	**Flush-mounted emergency lighting fixture that operates for an hour in case of outage (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2007	Flush-mounted emergency lighting fixture that operates for an hour in case of outage (LED, provides min. 130 lm of light for 1 hour) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.777,92	1.777,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.777,92	258,75
				Material and Installation w/o Profit (TRY)	2.036,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.545,84**	

Item No	Analysis Name					UoM
35.440.2008	**Surface-mounted emergency lighting fixture that operates for three hours in case of outage (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2008	Surface-mounted emergency lighting fixture that operates for three hours in case of outage (LED, provides min. 130 lm of light for 3 hours) / LED Emergency lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.585,92	1.585,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.585,92	258,75
				Material and Installation w/o Profit (TRY)	1.844,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.305,84**	

Item No	Analysis Name					UoM
35.440.2101	**Emergency directional light fixture (with LED) with a single side, which operates for 1 hour in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2101	Emergency directional light fixture (with LED) with a single side, which operates for 1 hour in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.049,36	1.049,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.049,36	258,75
				Material and Installation w/o Profit (TRY)	1.308,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.635,14**	

Item No	Analysis Name					UoM
35.440.2102	**Emergency directional light fixture (with LED) with a single side, which operates for 3 hour in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2102	Emergency directional light fixture (with LED) with a single side, which operates for 3 hours in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.246,96	1.246,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.246,96	258,75
				Material and Installation w/o Profit (TRY)	1.505,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.882,14**	

Item No	Analysis Name					UoM
35.440.2103	**Emergency directional light fixture (with LED) with two sides, which operates for 1 hour in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2103	Emergency directional light fixture (with LED) with two sides, which operates for 1 hour in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.090,96	1.090,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.090,96	258,75
				Material and Installation w/o Profit (TRY)	1.349,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.687,14**	

Item No	Analysis Name					UoM
35.440.2104	**Emergency directional light fixture (with LED) with two sides, which operates for 3 hour in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2104	Emergency directional light fixture (with LED) with two sides, which operates for 3 hours in case of a power outage / Emergency LED directional lighting fixture / Emergency Lighting Fixtures (Market price)	Qty	1	1.246,96	1.246,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.246,96	258,75
				Material and Installation w/o Profit (TRY)	1.505,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.882,14**	

Item No	Analysis Name					UoM
35.440.2201	**2 x 9 W, LED, 3 hours of operation / Emergency lighting fixtures (portable) / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2201	2 x 9 W, LED, 3 hours of operation / Emergency lighting fixtures (portable) / Emergency Lighting Fixtures (Market price)	Qty	1	3.200,00	3.200,00	
				Total Excluding Profit (TRY)	3.200,00	
				Material and Installation w/o Profit (TRY)	3.200,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**4.000,00**	

Item No	Analysis Name					UoM
35.440.2202	**2 x 15 W, LED, 3 hours of operation / Emergency lighting fixtures (portable) / Emergency Lighting Fixtures**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.440.2202	2 x 15 W, LED, 3 hours of operation / Emergency lighting fixtures (portable) / Emergency Lighting Fixtures (Market price)	Qty	1	3.920,00	3.920,00	
				Total Excluding Profit (TRY)	3.920,00	
				Material and Installation w/o Profit (TRY)	3.920,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**4.900,00**	

Item No	Analysis Name					UoM
35.445.1100						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1100	Outdoor Bullet Camera, Type 1 / IP CAMERA SYSTEMS (Market price)	Qty	1	14.796,32	14.796,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	14.796,32	1.092,25
				Material and Installation w/o Profit (TRY)	15.888,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.365,31**	
				Unit Price (TRY)	**19.860,71**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.445.1200						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1200	Outdoor Bullet Camera, Type 2 / IP CAMERA SYSTEMS (Market price)	Qty	1	17.204,32	17.204,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	17.204,32	1.092,25
				Material and Installation w/o Profit (TRY)	18.296,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.365,31**	
				Unit Price (TRY)	**22.870,71**	

Item No	Analysis Name					UoM
35.445.1301						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1301	Minimum 2-MP Interior Dome Camera / INTERIOR DOME CAMERA / IP CAMERA SYSTEMS (Market price)	Qty	1	14.267,88	14.267,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	14.267,88	1.092,25
				Material and Installation w/o Profit (TRY)	15.360,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.365,31**	
				Unit Price (TRY)	**19.200,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.445.1302						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1302	Minimum 4-MP Interior Dome Camera / INTERIOR DOME CAMERA / IP CAMERA SYSTEMS (Market price)	Qty	1	16.589,88	16.589,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	16.589,88	1.092,25
				Material and Installation w/o Profit (TRY)	17.682,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.365,31**	
				Unit Price (TRY)	**22.102,66**	

Item No	Analysis Name					UoM
35.445.1400						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1400	Pan-Tilt-Zoom (PTZ) Camera / IP CAMERA SYSTEMS (Market price)	Qty	1	95.828,72	95.828,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,4	165,00		66,00
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	95.828,72	1.092,25
				Material and Installation w/o Profit (TRY)	96.920,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.365,31**	
				Unit Price (TRY)	**121.151,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.445.1501						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1501	8-channel Network Video Recorder / NETWORK VIDEO RECORDER (NVR) / IP CAMERA SYSTEMS (Market price)	Qty	1	38.739,20	38.739,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			38.739,20	2.870,00
		Material and Installation w/o Profit (TRY)			41.609,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.587,50**	
		Unit Price (TRY)			**52.011,50**	

Item No	Analysis Name					UoM
35.445.1502						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1502	16-channel Network Video Recorder / NETWORK VIDEO RECORDER (NVR) / IP CAMERA SYSTEMS (Market price)	Qty	1	73.361,20	73.361,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
		Total Excluding Profit (TRY)			73.361,20	4.005,00
		Material and Installation w/o Profit (TRY)			77.366,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**5.006,25**	
		Unit Price (TRY)			**96.707,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.445.1503						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1503	32-channel Network Video Recorder / NETWORK VIDEO RECORDER (NVR) / IP CAMERA SYSTEMS (Market price)	Qty	1	89.177,44	89.177,44	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			89.177,44	5.140,00
		Material and Installation w/o Profit (TRY)			94.317,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**6.425,00**	
		Unit Price (TRY)			**117.896,80**	

Item No	Analysis Name					UoM
35.445.1504						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1504	64-channel Network Video Recorder / NETWORK VIDEO RECORDER (NVR) / IP CAMERA SYSTEMS (Market price)	Qty	1	150.835,68	150.835,68	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
		Total Excluding Profit (TRY)			150.835,68	6.275,00
		Material and Installation w/o Profit (TRY)			157.110,68	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**7.843,75**	
		Unit Price (TRY)			**196.388,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.445.1505						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1505	128-channel Network Video Recorder / NETWORK VIDEO RECORDER (NVR) / IP CAMERA SYSTEMS (Market price)	Qty	1	268.146,40	268.146,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	7	250,00		1.750,00
10.100.1083	Master electrician's helper	h	7	185,00		1.295,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	268.146,40	7.410,00
				Material and Installation w/o Profit (TRY)	275.556,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**9.262,50**	
				Unit Price (TRY)	**344.445,50**	

Item No	Analysis Name					UoM
35.445.1601						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1601	8-port Controllable POE Network Switch, minimum 8 x 10/100/1000 Ethernet PoE ports, minimum 2 x 1000 Base-X SFP ports, at least 120W total PoE power / CONTROLLABLE POE NETWORK SWITCHES / IP CAMERA SYSTEMS (Market price)	Qty	1	13.840,96	13.840,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	13.840,96	958,75
				Material and Installation w/o Profit (TRY)	14.799,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.198,44**	
				Unit Price (TRY)	**18.499,64**	

Item No	Analysis Name					UoM
35.445.1602						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1602	16-port Controllable POE Network Switch, minimum 16 x 10/100/1000 Ethernet PoE ports, minimum 2 x 1000 Base-X SFP ports, at least 240W total PoE power, 18 active ports / CONTROLLABLE POE NETWORK SWITCHES / IP CAMERA SYSTEMS (Market price)	Qty	1	21.501,76	21.501,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	21.501,76	1.308,75
				Material and Installation w/o Profit (TRY)	22.810,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.635,94**	
				Unit Price (TRY)	**28.513,14**	

Item No	Analysis Name					UoM
35.445.1603						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1603	24-port Controllable POE Network Switch, minimum 24 x 10/100/1000 Ethernet PoE ports, minimum 4 x 1000 Base-X SFP ports, at least 360W total PoE power, 28 active ports / CONTROLLABLE POE NETWORK SWITCHES / IP CAMERA SYSTEMS (Market price)	Qty	1	28.110,88	28.110,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	28.110,88	1.767,50
				Material and Installation w/o Profit (TRY)	29.878,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.209,38**	
				Unit Price (TRY)	**37.347,97**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.445.1610						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1610	48-port Controllable POE Network Switch, minimum 48 x 10/100/1000 PoE ports, minimum 4 x 10 GB SFP ports, at least 600W total PoE power, 52 active ports / CONTROLLABLE POE NETWORK SWITCHES / IP CAMERA SYSTEMS (Market price)	Qty	1	69.907,60	69.907,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,5	700,00		1.750,00
		Total Excluding Profit (TRY)			69.907,60	2.226,25
		Material and Installation w/o Profit (TRY)			72.133,85	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.782,81**	
		Unit Price (TRY)			**90.167,31**	

Item No	Analysis Name					UoM
35.445.1700						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.445.1700	Control Keyboard / IP CAMERA SYSTEMS (Market price)	Qty	1	21.490,56	21.490,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,8	700,00		560,00
		Total Excluding Profit (TRY)			21.490,56	818,75
		Material and Installation w/o Profit (TRY)			22.309,31	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.023,44**	
		Unit Price (TRY)			**27.886,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.1110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.1110	8-port POE Network Switch, minimum 8 x 10/100/1000 Ethernet PoE ports, minimum 2 x 1000 Base-X SFP ports, at least 120W total PoE power / POE NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	11.052,83	11.052,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
			Total Excluding Profit (TRY)		11.052,83	958,75
			Material and Installation w/o Profit (TRY)		12.011,58	
% 25 Contractor's Profit and Overheads Included			**Instal. Cost (TRY)**		**1.198,44**	
			Unit Price (TRY)		**15.014,48**	

Item No	Analysis Name					UoM
35.446.1120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.1120	16-port POE Network Switch, minimum 16 x 10/100/1000 Ethernet PoE ports, minimum 2 x 1000 Base-X SFP ports, at least 240W total PoE power, 18 active ports / POE NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	12.008,53	12.008,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
			Total Excluding Profit (TRY)		12.008,53	1.308,75
			Material and Installation w/o Profit (TRY)		13.317,28	
% 25 Contractor's Profit and Overheads Included			**Instal. Cost (TRY)**		**1.635,94**	
			Unit Price (TRY)		**16.646,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.1130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.1130	24-port POE Network Switch, minimum 24 x 10/100/1000 Ethernet PoE ports, minimum 4 x 1000 Base-X SFP ports, at least 360W total PoE power, 28 active ports / POE NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	19.737,20	19.737,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			19.737,20	1.767,50
		Material and Installation w/o Profit (TRY)			21.504,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.209,38**	
		Unit Price (TRY)			**26.880,88**	

Item No	Analysis Name					UoM
35.446.2110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.2110	8-port Controllable Network Switch, minimum 8 x 10/100/1000 Ethernet ports, minimum 2 x 1000 Base-X SFP ports / CONTROLLABLE NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	7.728,67	7.728,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			7.728,67	958,75
		Material and Installation w/o Profit (TRY)			8.687,42	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**10.859,27**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.2120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.2120	16-port Controllable Network Switch, minimum 16 x 10/100/1000 Ethernet ports, minimum 2 x 1000 Base-X SFP ports / CONTROLLABLE NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	8.750,85	8.750,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	8.750,85	1.308,75
				Material and Installation w/o Profit (TRY)	10.059,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.635,94**	
				Unit Price (TRY)	**12.574,50**	

Item No	Analysis Name					UoM
35.446.2130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.2130	24-port Controllable Network Switch, minimum 24 x 10/100/1000 Ethernet ports, minimum 4 x 1000 Base-X SFP ports / CONTROLLABLE NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	11.917,11	11.917,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	11.917,11	1.767,50
				Material and Installation w/o Profit (TRY)	13.684,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.209,38**	
				Unit Price (TRY)	**17.105,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.2140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.2140	48-port Controllable Network Switch, minimum 48 x 10/100/1000 Ethernet ports, minimum 4 x 10 GB SFP ports / CONTROLLABLE NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	46.671,21	46.671,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
		Total Excluding Profit (TRY)			46.671,21	2.576,25
		Material and Installation w/o Profit (TRY)			49.247,46	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.220,31**	
		Unit Price (TRY)			**61.559,32**	

Item No	Analysis Name					UoM
35.446.3110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.3110	8-port Network Switch, minimum 8 x 10/100/1000 Ethernet ports, minimum 2 x 1000 Base-X SFP ports / NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	6.440,56	6.440,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			6.440,56	958,75
		Material and Installation w/o Profit (TRY)			7.399,31	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**9.249,14**	

Item No	Analysis Name					UoM
35.446.3120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.3120	16-port Network Switch, minimum 16 x 10/100/1000 Ethernet ports, minimum 2 x 1000 Base-X SFP ports / NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	7.292,38	7.292,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
		Total Excluding Profit (TRY)			7.292,38	1.308,75
		Material and Installation w/o Profit (TRY)			8.601,13	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.635,94**	
		Unit Price (TRY)			**10.751,41**	

Item No	Analysis Name					UoM
35.446.3130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.3130	24-port Network Switch, minimum 24 x 10/100/1000 Ethernet ports, minimum 4 x 1000 Base-X SFP ports / NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	9.930,93	9.930,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			9.930,93	1.767,50
		Material and Installation w/o Profit (TRY)			11.698,43	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.209,38**	
		Unit Price (TRY)			**14.623,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.3140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.3140	48-port Network Switch, minimum 48 x 10/100/1000 Ethernet ports, minimum 4 x 10 GB SFP ports / NETWORK SWITCHES / NETWORK SYSTEMS (Market price)	Qty	1	38.892,67	38.892,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
		Total Excluding Profit (TRY)			38.892,67	2.576,25
		Material and Installation w/o Profit (TRY)			41.468,92	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**3.220,31**	
		Unit Price (TRY)			**51.836,15**	

Item No	Analysis Name					UoM
35.446.7103						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7103	Min. AC600 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	885,00	885,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			885,00	548,75
		Material and Installation w/o Profit (TRY)			1.433,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**1.792,19**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7106						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7106	Min. AC867 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	1.239,00	1.239,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.239,00	548,75
		Material and Installation w/o Profit (TRY)			1.787,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**2.234,69**	

Item No	Analysis Name					UoM
35.446.7109						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7109	Min. AC1200 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	1.416,00	1.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.416,00	548,75
		Material and Installation w/o Profit (TRY)			1.964,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**2.455,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7112						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7112	Min. AC1350 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	2.478,00	2.478,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			2.478,00	548,75
		Material and Installation w/o Profit (TRY)			3.026,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**3.783,44**	

Item No	Analysis Name					UoM
35.446.7115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7115	Min. AC1750 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	2.832,00	2.832,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			2.832,00	548,75
		Material and Installation w/o Profit (TRY)			3.380,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**4.225,94**	

Item No	Analysis Name					UoM
35.446.7118						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7118	Min. AX1800 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	3.469,20	3.469,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			3.469,20	548,75
		Material and Installation w/o Profit (TRY)			4.017,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**5.022,44**	

Item No	Analysis Name					UoM
35.446.7121						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7121	Min. AX3000 Min. 1 x 10/100/1000 Mbps Ethernet PoE+-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	5.310,00	5.310,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			5.310,00	548,75
		Material and Installation w/o Profit (TRY)			5.858,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**7.323,44**	

Item No	Analysis Name					UoM
35.446.7124						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7124	Min. AX3600 Min. 1 x 10M/100M/1G/2.5G Ethernet PoE+-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	7.965,00	7.965,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			7.965,00	548,75
		Material and Installation w/o Profit (TRY)			8.513,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**10.642,19**	

Item No	Analysis Name					UoM
35.446.7127						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7127	Min. AX5400 Min. 1 x 10M/100M/1G/2.5G Ethernet PoE+-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	10.620,00	10.620,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician's helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			10.620,00	548,75
		Material and Installation w/o Profit (TRY)			11.168,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**13.960,94**	

Item No	Analysis Name					UoM
35.446.7130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7130	Min. AX6000 Min. 1 x 10M/100M/1G/2.5G Ethernet PoE+-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	14.514,00	14.514,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			14.514,00	548,75
		Material and Installation w/o Profit (TRY)			15.062,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**18.828,44**	

Item No	Analysis Name					UoM
35.446.7133						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7133	Min. BE3600 Min. 1 x 10M/100M/1G/2.5G Ethernet PoE++-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	8.319,00	8.319,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			8.319,00	548,75
		Material and Installation w/o Profit (TRY)			8.867,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**11.084,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7136						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7136	Min. BE9300 Min. 1 x 10M/100M/1G/2.5G/10G Ethernet PoE++-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	19.576,20	19.576,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			19.576,20	548,75
		Material and Installation w/o Profit (TRY)			20.124,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**25.156,19**	

Item No	Analysis Name					UoM
35.446.7139						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7139	Min. BE19000 Min. 1 x 10M/100M/1G/2.5G/10G Ethernet PoE++-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	40.710,00	40.710,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			40.710,00	548,75
		Material and Installation w/o Profit (TRY)			41.258,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**51.573,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7203						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7203	Min. AC600 Min. 1 x 10/100 Mbps Ethernet PoE-supported port min. IP67 / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	1.062,00	1.062,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.062,00	548,75
		Material and Installation w/o Profit (TRY)			1.610,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**2.013,44**	

Item No	Analysis Name					UoM
35.446.7206						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7206	Min. AC1200 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port min. IP67 / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	1.699,20	1.699,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.699,20	548,75
		Material and Installation w/o Profit (TRY)			2.247,95	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**2.809,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7209						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7209	Min. AC1750 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port min. IP67 / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	3.398,40	3.398,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	3.398,40	548,75
				Material and Installation w/o Profit (TRY)	3.947,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**685,94**	
				Unit Price (TRY)	**4.933,94**	

Item No	Analysis Name					UoM
35.446.7212						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7212	Min. AX1800 Min. 1 x 10/100/1000 Mbps Ethernet PoE-supported port min. IP67 / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	4.163,04	4.163,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	4.163,04	548,75
				Material and Installation w/o Profit (TRY)	4.711,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**685,94**	
				Unit Price (TRY)	**5.889,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7215						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7215	Min. AX3000 Min. 1 x 10/100/1000 Mbps Ethernet PoE+-supported port min. IP67 / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	6.372,00	6.372,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
			Total Excluding Profit (TRY)		6.372,00	548,75
			Material and Installation w/o Profit (TRY)		6.920,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**685,94**	
				Unit Price (TRY)	**8.650,94**	

Item No	Analysis Name					UoM
35.446.7303						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7303	Min. AC1200 Min. 2 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	1.699,20	1.699,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
			Total Excluding Profit (TRY)		1.699,20	548,75
			Material and Installation w/o Profit (TRY)		2.247,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**685,94**	
				Unit Price (TRY)	**2.809,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7306						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7306	Min. AC1750 Min. 2 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	3.398,40	3.398,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			3.398,40	548,75
		Material and Installation w/o Profit (TRY)			3.947,15	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**4.933,94**	

Item No	Analysis Name					UoM
35.446.7309						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7309	Min. AX1800 Min. 2 x 10/100/1000 Mbps Ethernet PoE-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	4.163,04	4.163,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			4.163,04	548,75
		Material and Installation w/o Profit (TRY)			4.711,79	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**5.889,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7312						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7312	Min. AX3000 Min. 2 x 10/100/1000 Mbps Ethernet PoE+-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	6.372,00	6.372,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	6.372,00	548,75
				Material and Installation w/o Profit (TRY)	6.920,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**685,94**	
				Unit Price (TRY)	**8.650,94**	

Item No	Analysis Name					UoM
35.446.7315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7315	Min. AX3600 Min. 2 x 10M/100M/1G/2.5G Ethernet PoE+-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	9.558,00	9.558,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	9.558,00	548,75
				Material and Installation w/o Profit (TRY)	10.106,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**685,94**	
				Unit Price (TRY)	**12.633,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.446.7318						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7318	Min. BE3600 Min. 2 x 10M/100M/1G/2.5G Ethernet PoE++-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	9.982,80	9.982,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			9.982,80	548,75
		Material and Installation w/o Profit (TRY)			10.531,55	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**13.164,44**	

Item No	Analysis Name					UoM
35.446.7321						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.446.7321	Min. BE19000 Min. 2 x 10M/100M/1G/2.5G/10G Ethernet PoE++-supported port / Access Point / NETWORK SYSTEMS (Market price)	Qty	1	48.852,00	48.852,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			48.852,00	548,75
		Material and Installation w/o Profit (TRY)			49.400,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**685,94**	
		Unit Price (TRY)			**61.750,94**	

Item No	Analysis Name					UoM
35.450.1001	**12-channel Audio Mixer / AUDIO CONTROL AND RECORDING MIXERS / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1001	12-channel Audio Mixer	Qty	1	12.326,40	12.326,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			12.326,40	2.352,50
		Material and Installation w/o Profit (TRY)			14.678,90	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.940,63**	
		Unit Price (TRY)			**18.348,63**	

Item No	Analysis Name					UoM
35.450.1002	**16-channel Audio Mixer / AUDIO CONTROL AND RECORDING MIXERS / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1002	16-channel Audio Mixer	Qty	1	16.435,20	16.435,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,5	700,00		1.750,00
		Total Excluding Profit (TRY)			16.435,20	3.137,50
		Material and Installation w/o Profit (TRY)			19.572,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**3.921,88**	
		Unit Price (TRY)			**24.465,88**	

Item No	Analysis Name					UoM
35.450.1003	**24-channel Audio Mixer / AUDIO CONTROL AND RECORDING MIXERS / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1003	24-channel Audio Mixer	Qty	1	26.678,40	26.678,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
				Total Excluding Profit (TRY)	26.678,40	3.922,50
				Material and Installation w/o Profit (TRY)	30.600,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.903,13**	
				Unit Price (TRY)	**38.251,13**	

Item No	Analysis Name					UoM
35.450.1004	**32-channel Audio Mixer / AUDIO CONTROL AND RECORDING MIXERS / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1004	32-channel Audio Mixer	Qty	1	32.803,20	32.803,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,5	700,00		2.450,00
				Total Excluding Profit (TRY)	32.803,20	4.707,50
				Material and Installation w/o Profit (TRY)	37.510,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**5.884,38**	
				Unit Price (TRY)	**46.888,38**	

Item No	Analysis Name					UoM
35.450.1101	**1 x 31 Band Graphic Equalizer / GRAPHIC EQUALIZER / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1101	1 x 31 Band Graphic Equalizer	Qty	1	5.673,36	5.673,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			5.673,36	1.652,50
		Material and Installation w/o Profit (TRY)			7.325,86	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.065,63**	
		Unit Price (TRY)			**9.157,32**	

Item No	Analysis Name					UoM
35.450.1102	**2 x 15 Band Graphic Equalizer / GRAPHIC EQUALIZER / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1102	2 x 15 Band Graphic Equalizer	Qty	1	5.111,04	5.111,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
		Total Excluding Profit (TRY)			5.111,04	2.220,00
		Material and Installation w/o Profit (TRY)			7.331,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.775,00**	
		Unit Price (TRY)			**9.163,80**	

Item No	Analysis Name					UoM
35.450.1103	**2 x 31 Band Graphic Equalizer / GRAPHIC EQUALIZER / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1103	2 x 31 Band Graphic Equalizer	Qty	1	8.324,80	8.324,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			8.324,80	3.222,50
		Material and Installation w/o Profit (TRY)			11.547,30	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.028,13**	
		Unit Price (TRY)			**14.434,13**	

Item No	Analysis Name					UoM
35.450.1200	**OPERATOR MONITOR / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1200	OPERATOR MONITOR: (Unit: Qty., Materials on construction site: 60%)	Qty	1	12.821,60	12.821,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			12.821,60	517,50
		Material and Installation w/o Profit (TRY)			13.339,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**16.673,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.1301	**Internal type / Line transformer and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1301	Internal type	Qty	1	353,32	353,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	353,32	150,00
				Material and Installation w/o Profit (TRY)	503,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**629,15**	

Item No	Analysis Name					UoM
35.450.1302	**External type / Line transformer and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1302	External type	Qty	1	442,20	442,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	442,20	150,00
				Material and Installation w/o Profit (TRY)	592,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**740,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.1401	**3 to 5-Watt, single-sided speaker. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1401	3 to 5-Watt, single-sided speaker.	Qty	1	446,60	446,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			446,60	608,75
		Material and Installation w/o Profit (TRY)			1.055,35	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**760,94**	
		Unit Price (TRY)			**1.319,19**	

Item No	Analysis Name					UoM
35.450.1402	**3 to 5-Watt, double-sided speaker. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1402	3 to 5-Watt, double-side speaker.	Qty	1	1.133,88	1.133,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.133,88	608,75
		Material and Installation w/o Profit (TRY)			1.742,63	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**760,94**	
		Unit Price (TRY)			**2.178,29**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.1403	**5-Watt, single-sided speaker resistant to external impact. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1403	5-Watt, impact-resistant, single-sided speaker.	Qty	1	484,44	484,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	484,44	608,75
				Material and Installation w/o Profit (TRY)	1.093,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**1.366,49**	

Item No	Analysis Name					UoM
35.450.1404	**5-Watt, double-sided speaker resistant to external impact. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1404	5-Watt, impact-resistant, double-side speaker.	Qty	1	1.215,72	1.215,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	1.215,72	608,75
				Material and Installation w/o Profit (TRY)	1.824,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**2.280,59**	

Item No	Analysis Name					UoM
35.450.1405	**External-type, isobaric loudspeakers, up to 10 W. / Speaker and installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1405	External-type, isobaric loudspeakers up to 10 W.	Qty	1	1.541,32	1.541,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	1.541,32	1.108,75
				Material and Installation w/o Profit (TRY)	2.650,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.385,94**	
				Unit Price (TRY)	**3.312,59**	

Item No	Analysis Name					UoM
35.450.1406	**3 x 6-Watt, column-type speaker. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1406	3 x 6-Watt, column-type speaker.	Qty	1	1.370,60	1.370,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	1.370,60	1.217,50
				Material and Installation w/o Profit (TRY)	2.588,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.521,88**	
				Unit Price (TRY)	**3.235,13**	

Item No	Analysis Name					UoM
35.450.1407	**3 x 10-Watt, column-type speaker. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1407	3 x 10-Watt, column-type speaker.	Qty	1	1.458,60	1.458,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			1.458,60	1.217,50
		Material and Installation w/o Profit (TRY)			2.676,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.521,88**	
		Unit Price (TRY)			**3.345,13**	

Item No	Analysis Name					UoM
35.450.1408	**10-Watt, single-sided speaker. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1408	10 W, single-sided speaker	Qty	1	444,84	444,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			444,84	608,75
		Material and Installation w/o Profit (TRY)			1.053,59	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**760,94**	
		Unit Price (TRY)			**1.316,99**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.1409	**10-Watt, double-sided speaker. / Speaker and its installation / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.1409	10 W, double-side speaker	Qty	1	1.133,00	1.133,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.133,00	608,75
		Material and Installation w/o Profit (TRY)			1.741,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**760,94**	
		Unit Price (TRY)			**2.177,19**	

Item No	Analysis Name					UoM
35.450.2000	**DIGITAL PROCESSOR CROSSOVER / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2000	DIGITAL PROCESSOR CROSSOVER: (Unit: Qty., Materials on construction site: 60%)	Qty	1	12.872,64	12.872,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
		Total Excluding Profit (TRY)			12.872,64	3.052,50
		Material and Installation w/o Profit (TRY)			15.925,14	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**3.815,63**	
		Unit Price (TRY)			**19.906,42**	

Item No	Analysis Name					UoM
35.450.2101	**10″ Monitor Speaker / Monitor Speaker / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2101	10″ Monitor Speaker	Qty	1	18.066,40	18.066,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			18.066,40	867,50
		Material and Installation w/o Profit (TRY)			18.933,90	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**23.667,38**	

Item No	Analysis Name					UoM
35.450.2102	**12″ Monitor Speaker / Monitor Speaker / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2102	12″ Monitor Speaker	Qty	1	22.079,20	22.079,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			22.079,20	867,50
		Material and Installation w/o Profit (TRY)			22.946,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**28.683,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.2103	**15″ Monitor Speaker / Monitor Speaker / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2103	15″ Monitor Speaker	Qty	1	24.103,20	24.103,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			24.103,20	1.435,00
		Material and Installation w/o Profit (TRY)			25.538,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.793,75**	
		Unit Price (TRY)			**31.922,75**	

Item No	Analysis Name					UoM
35.450.2201	**15″ Subwoofer Speaker / Subwoofer Speaker / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2201	15″ Subwoofer Speaker	Qty	1	26.118,40	26.118,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			26.118,40	1.217,50
		Material and Installation w/o Profit (TRY)			27.335,90	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.521,88**	
		Unit Price (TRY)			**34.169,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.2202	**18″ Subwoofer Speaker / Subwoofer Speaker / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2202	18″ Subwoofer Speaker	Qty	1	32.111,20	32.111,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			32.111,20	1.435,00
		Material and Installation w/o Profit (TRY)			33.546,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.793,75**	
		Unit Price (TRY)			**41.932,75**	

Item No	Analysis Name					UoM
35.450.2301	**12″ Range Speaker / Full-range Speaker / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2301	12″ Range Speaker	Qty	1	22.079,20	22.079,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			22.079,20	867,50
		Material and Installation w/o Profit (TRY)			22.946,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.084,38**	
		Unit Price (TRY)			**28.683,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.2302	**15″ Range Speaker / Full-range Speaker / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2302	15″ Range Speaker	Qty	1	24.094,40	24.094,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			24.094,40	1.435,00
		Material and Installation w/o Profit (TRY)			25.529,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.793,75**	
		Unit Price (TRY)			**31.911,75**	

Item No	Analysis Name					UoM
35.450.2400	**SPEAKER HANGING KIT / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2400	SPEAKER HANGING KIT: (Unit: Qty., Materials on construction site: 60%)	Qty	1	915,20	915,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,25	700,00		175,00
		Total Excluding Profit (TRY)			915,20	692,50
		Material and Installation w/o Profit (TRY)			1.607,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**865,63**	
		Unit Price (TRY)			**2.009,63**	

Item No	Analysis Name					UoM
35.450.2800	**STAGE BOX / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.2800	STAGE BOX: (Unit: Qty., Materials on construction site: 60%)	Qty	1	4.424,64	4.424,64	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			4.424,64	1.735,00
		Material and Installation w/o Profit (TRY)			6.159,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.168,75**	
		Unit Price (TRY)			**7.699,55**	

Item No	Analysis Name					UoM
35.450.3000	**(NEUTRIK CONNECTORS) / Hall Sound Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.3000	(NEUTRIK CONNECTORS): (Unit: Qty., Materials on construction site: 60%)	Qty	1	81,84	81,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			81,84	150,00
		Material and Installation w/o Profit (TRY)			231,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**187,50**	
		Unit Price (TRY)			**289,80**	

Item No	Analysis Name					UoM
35.450.3100	**Potentiometer and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.3100	Potentiometer and its wiring: (Unit: Qty., Materials on construction site: 60%)	Qty	1	550,00	550,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
		Total Excluding Profit (TRY)			550,00	150,00
		Material and Installation w/o Profit (TRY)			700,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**187,50**	
		Unit Price (TRY)			**875,00**	

Item No	Analysis Name					UoM
35.450.3200	**Channel selector (three channels) / Potentiometer and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.3200	Channel selector (three channels)	Qty	1	658,24	658,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			658,24	600,50
		Material and Installation w/o Profit (TRY)			1.258,74	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**750,63**	
		Unit Price (TRY)			**1.573,42**	

Item No	Analysis Name					UoM
35.450.5001	**Desktop microphone. / Microphone**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5001	Desktop microphone.	Qty	1	926,64	926,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			926,64	600,50
		Material and Installation w/o Profit (TRY)			1.527,14	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**750,63**	
		Unit Price (TRY)			**1.908,92**	

Item No	Analysis Name					UoM
35.450.5002	**Free-standing microphone. / Microphone**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5002	Free-standing microphone.	Qty	1	1.401,84	1.401,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.401,84	600,50
		Material and Installation w/o Profit (TRY)			2.002,34	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**750,63**	
		Unit Price (TRY)			**2.502,92**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.5003	**Hand-held microphone. / Microphone**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5003	Hand-held microphone.	Qty	1	693,44	693,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			693,44	491,75
		Material and Installation w/o Profit (TRY)			1.185,19	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**614,69**	
		Unit Price (TRY)			**1.481,49**	

Item No	Analysis Name					UoM
35.450.5100	**Microphone line installation**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5100	Microphone line installation / HALL SOUND SYSTEMS (Market price)	m	1	40,00	40,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,2	185,00		37,00
		Total Excluding Profit (TRY)			40,00	103,50
		Material and Installation w/o Profit (TRY)			143,50	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**129,38**	
		Unit Price (TRY)			**179,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.5201	**Handheld / 16-channel UHF Wireless Microphone Set**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5201	Hand type	Qty	1	5.605,60	5.605,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			5.605,60	600,50
		Material and Installation w/o Profit (TRY)			6.206,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**750,63**	
		Unit Price (TRY)			**7.757,63**	

Item No	Analysis Name					UoM
35.450.5202	**Lapel type / 16-channel UHF Wireless Microphone Set**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5202	Lapel type	Qty	1	5.605,60	5.605,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			5.605,60	600,50
		Material and Installation w/o Profit (TRY)			6.206,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**750,63**	
		Unit Price (TRY)			**7.757,63**	

Item No	Analysis Name					UoM
35.450.5203	**Handheld / 16-channel UHF Wireless Microphone Set**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5203	Head type	Qty	1	5.984,00	5.984,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			5.984,00	600,50
		Material and Installation w/o Profit (TRY)			6.584,50	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**750,63**	
		Unit Price (TRY)			**8.230,63**	

Item No	Analysis Name					UoM
35.450.5300	**MICROPHONE STAND**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5300	MICROPHONE STAND (Unit: Qty., Materials on construction site: 60%)	Qty	1	1.231,12	1.231,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			1.231,12	650,00
		Material and Installation w/o Profit (TRY)			1.881,12	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**812,50**	
		Unit Price (TRY)			**2.351,40**	

Item No	Analysis Name					UoM
35.450.5400	**VOCAL DYNAMIC MICROPHONE**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5400	VOCAL DYNAMIC MICROPHONE: (Unit: Qty., Materials on construction site: 60%)	Qty	1	1.232,00	1.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
		Total Excluding Profit (TRY)			1.232,00	1.350,00
		Material and Installation w/o Profit (TRY)			2.582,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.687,50**	
		Unit Price (TRY)			**3.227,50**	

Item No	Analysis Name					UoM
35.450.5500	**DYNAMIC MICROPHONE INSTRUMENT**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5500	DYNAMIC MICROPHONE INSTRUMENT (Unit: Qty., Materials on construction site: 60%)	Qty	1	1.540,00	1.540,00	
		Total Excluding Profit (TRY)			1.540,00	
		Material and Installation w/o Profit (TRY)			1.540,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.925,00**	

Item No	Analysis Name					UoM
35.450.5600	**MICROPHONE STAND**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5600	MICROPHONE STAND (Unit: Qty., Materials on construction site: 60%)	Qty	1	586,08	586,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	586,08	150,00
				Material and Installation w/o Profit (TRY)	736,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**187,50**	
				Unit Price (TRY)	**920,10**	

Item No	Analysis Name					UoM
35.450.5701	**25 W / Amplifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5701	25 W	Qty	1	4.194,08	4.194,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.194,08	258,75
				Material and Installation w/o Profit (TRY)	4.452,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.566,04**	

Item No	Analysis Name					UoM
35.450.5702	**40 W / Amplifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5702	40 W	Qty	1	4.730,88	4.730,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.730,88	258,75
				Material and Installation w/o Profit (TRY)	4.989,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.237,04**	

Item No	Analysis Name					UoM
35.450.5703	**75 W / Amplifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5703	75 W	Qty	1	7.300,48	7.300,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	7.300,48	258,75
				Material and Installation w/o Profit (TRY)	7.559,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**9.449,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.450.5704	**100 W / Amplifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5704	100 W	Qty	1	7.300,48	7.300,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	7.300,48	408,75
				Material and Installation w/o Profit (TRY)	7.709,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**9.636,54**	

Item No	Analysis Name					UoM
35.450.5705	**200 W / Amplifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5705	200 W	Qty	1	10.244,08	10.244,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
				Total Excluding Profit (TRY)	10.244,08	408,75
				Material and Installation w/o Profit (TRY)	10.652,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**510,94**	
				Unit Price (TRY)	**13.316,04**	

Item No	Analysis Name					UoM
35.450.5706	**300 W / Amplifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.450.5706	300 W	Qty	1	10.238,80	10.238,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	10.238,80	517,50
				Material and Installation w/o Profit (TRY)	10.756,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**13.445,38**	

Item No	Analysis Name					UoM
35.460.1010	**24-channel Light Controller Mixer / Light Controller Mixer / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1010	24-channel Light Controller Mixer / Light Controller Mixer / Stage Lighting System (Market price)	Qty	1	10.137,60	10.137,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	10.137,60	3.835,00
				Material and Installation w/o Profit (TRY)	13.972,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.793,75**	
				Unit Price (TRY)	**17.465,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.460.1020	**48-channel Light Controller Mixer / Light Controller Mixer / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1020	48-channel Light Controller Mixer / Light Controller Mixer / Stage Lighting System (Market price)	Qty	1	16.051,20	16.051,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
		Total Excluding Profit (TRY)			16.051,20	5.235,00
		Material and Installation w/o Profit (TRY)			21.286,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**6.543,75**	
		Unit Price (TRY)			**26.607,75**	

Item No	Analysis Name					UoM
35.460.1110	**6-channel Digital Dimmer / Hall Light, Control Dimmer / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1110	6-channel Digital Dimmer / Hall Light, Control Dimmer / Stage Lighting System (Market price)	Qty	1	18.559,20	18.559,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
		Total Excluding Profit (TRY)			18.559,20	3.835,00
		Material and Installation w/o Profit (TRY)			22.394,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.793,75**	
		Unit Price (TRY)			**27.992,75**	

Item No	Analysis Name					UoM
35.460.1120	**12-channel Digital Dimmer / Hall Light, Control Dimmer / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1120	12-channel Digital Dimmer / Hall Light, Control Dimmer / Stage Lighting System (Market price)	Qty	1	39.142,40	39.142,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	39.142,40	5.235,00
				Material and Installation w/o Profit (TRY)	44.377,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**6.543,75**	
				Unit Price (TRY)	**55.471,75**	

Item No	Analysis Name					UoM
35.460.1210	**650 W Profile Spot / Profile Spot / Stage Lighting Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1210	650 W Profile Spot / Profile Spot / Stage Lighting Systems (Market price)	Qty	1	18.955,20	18.955,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	18.955,20	3.317,50
				Material and Installation w/o Profit (TRY)	22.272,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.146,88**	
				Unit Price (TRY)	**27.840,88**	

Item No	Analysis Name					UoM
35.460.1220	**1,000 W Profile Spot / Profile Spot / Stage Lighting Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1220	1000 W Profile Spot / Profile Spot / Stage Lighting Systems (Market price)	Qty	1	21.331,20	21.331,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
		Total Excluding Profit (TRY)			21.331,20	4.017,50
		Material and Installation w/o Profit (TRY)			25.348,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**5.021,88**	
		Unit Price (TRY)			**31.685,88**	

Item No	Analysis Name					UoM
35.460.1230	**2,000 W Profile Spot / Profile Spot / Stage Lighting Systems**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1230	2000 W Profile Spot / Profile Spot / Stage Lighting Systems (Market price)	Qty	1	22.756,80	22.756,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
		Total Excluding Profit (TRY)			22.756,80	4.717,50
		Material and Installation w/o Profit (TRY)			27.474,30	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**5.896,88**	
		Unit Price (TRY)			**34.342,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.460.1310	**300/500 W PC Spot, Barndoor, 500 W light bulb / PC Spot, Barndoor / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1310	300/500 W PC Spot, Barndoor, 500 W light bulb / PC Spot, Barndoor / Stage Lighting System (Market price)	Qty	1	6.547,20	6.547,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	6.547,20	3.317,50
				Material and Installation w/o Profit (TRY)	9.864,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.146,88**	
				Unit Price (TRY)	**12.330,88**	

Item No	Analysis Name					UoM
35.460.1320	**650/1,000 W PC Spot, Barndoor, 1,000 W light bulb / PC Spot, Barndoor / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1320	650/1,000 W PC Spot, Barndoor, 1,000 W light bulb / PC Spot, Barndoor / Stage Lighting System (Market price)	Qty	1	7.145,60	7.145,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
				Total Excluding Profit (TRY)	7.145,60	4.017,50
				Material and Installation w/o Profit (TRY)	11.163,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**5.021,88**	
				Unit Price (TRY)	**13.953,88**	

Item No	Analysis Name					UoM
35.460.1410	**300/500 W Fresnel Spotlight Barndoor, 500 W light bulb / Fresnel Spotlight, Barndoor / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1410	300/500 W Fresnel Spotlight Barndoor, 500 W light bulb / Fresnel Spotlight, Barndoor / Stage Lighting System (Market price)	Qty	1	6.547,20	6.547,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	6.547,20	3.317,50
				Material and Installation w/o Profit (TRY)	9.864,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.146,88**	
				Unit Price (TRY)	**12.330,88**	

Item No	Analysis Name					UoM
35.460.1420	**650/1,000 W Fresnel Spotlight Barndoor, 1,000 W light bulb / Fresnel Spotlight, Barndoor / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1420	650/1,000 W Fresnel Spotlight Barndoor, 1,000 W light bulb / Fresnel Spotlight, Barndoor / Stage Lighting System (Market price)	Qty	1	7.145,60	7.145,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
				Total Excluding Profit (TRY)	7.145,60	4.017,50
				Material and Installation w/o Profit (TRY)	11.163,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**5.021,88**	
				Unit Price (TRY)	**13.953,88**	

Item No	Analysis Name					UoM
35.460.1510	**PAR 56 Spotlight and light bulb / Par Spotlight and Light Bulb / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1510	PAR 56 Spotlight and light bulb / Par Spotlight and Light Bulb / Stage Lighting System (Market price)	Qty	1	4.895,44	4.895,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	4.895,44	1.917,50
				Material and Installation w/o Profit (TRY)	6.812,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.396,88**	
				Unit Price (TRY)	**8.516,17**	

Item No	Analysis Name					UoM
35.460.1520	**PAR 64 Spotlight and light bulb / Par Spotlight and Light Bulb / Stage Lighting System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.460.1520	PAR 64 Spotlight and light bulb / Par Spotlight and Light Bulb / Stage Lighting System (Market price)	Qty	1	6.092,24	6.092,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	6.092,24	1.917,50
				Material and Installation w/o Profit (TRY)	8.009,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.396,88**	
				Unit Price (TRY)	**10.012,17**	

Item No	Analysis Name					UoM
35.470.1001	**2,000 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1001	2,000 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	13.921,20	13.921,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	13.921,20	2.170,00
				Material and Installation w/o Profit (TRY)	16.091,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**20.114,00**	

Item No	Analysis Name					UoM
35.470.1002	**2,500 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1002	2,500 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	18.662,40	18.662,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	18.662,40	2.170,00
				Material and Installation w/o Profit (TRY)	20.832,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**26.040,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.470.1003	**3,000 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1003	3,000 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	23.392,80	23.392,80	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	23.392,80	2.170,00
				Material and Installation w/o Profit (TRY)	25.562,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**31.953,50**	

Item No	Analysis Name					UoM
35.470.1004	**3,500 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1004	3,500 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	28.177,20	28.177,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	28.177,20	2.170,00
				Material and Installation w/o Profit (TRY)	30.347,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**37.934,00**	

Item No	Analysis Name					UoM
35.470.1005	**4,000 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1005	4,000 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	32.799,60	32.799,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	32.799,60	2.170,00
				Material and Installation w/o Profit (TRY)	34.969,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**43.712,00**	

Item No	Analysis Name					UoM
35.470.1006	**4,500 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1006	4,500 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	37.476,00	37.476,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	37.476,00	2.170,00
				Material and Installation w/o Profit (TRY)	39.646,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**49.557,50**	

Item No	Analysis Name					UoM
35.470.1007	**5,000 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1007	5,000 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	42.314,40	42.314,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	42.314,40	2.170,00
				Material and Installation w/o Profit (TRY)	44.484,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**55.605,50**	

Item No	Analysis Name					UoM
35.470.1008	**6,500 ANSI lumens, 1024 x 768 projection / Projector / Hall Video Data Projection System**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.1008	6,500 ANSI lumens, 1024 x 768 projection / Projector / VIDEO DATA PROJECTION SYSTEMS (Market price)	Qty	1	47.552,40	47.552,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	47.552,40	2.170,00
				Material and Installation w/o Profit (TRY)	49.722,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.712,50**	
				Unit Price (TRY)	**62.153,00**	

Item No	Analysis Name					UoM
35.470.2001	**Lifting capacity: up to 5 tons / Hydraulic Stage Platform (Lift)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.2001	Lifting capacity: up to 5 tons / Hydraulic Stage Platform (Elevator) (Market price)	Qty	1	295.817,60	295.817,60	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	24	250,00		6.000,00
10.100.1083	Master electrician’s helper	h	24	185,00		4.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	295.817,60	15.220,00
				Material and Installation w/o Profit (TRY)	311.037,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**19.025,00**	
				Unit Price (TRY)	**388.797,00**	

Item No	Analysis Name					UoM
35.470.2002	**Lifting capacity: up to 10 tons / Hydraulic Stage Platform (Lift)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.2002	Lifting capacity: up to 10 tons / Hydraulic Stage Platform (Elevator) (Market price)	Qty	1	347.224,80	347.224,80	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	32	250,00		8.000,00
10.100.1083	Master electrician’s helper	h	32	185,00		5.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	347.224,80	20.760,00
				Material and Installation w/o Profit (TRY)	367.984,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**25.950,00**	
				Unit Price (TRY)	**459.981,00**	

Item No	Analysis Name					UoM
35.470.2003	**Lifting capacity: up to 20 tons / Hydraulic Stage Platform (Lift)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.2003	Lifting capacity: up to 20 tons / Hydraulic Stage Platform (Elevator) (Market price)	Qty	1	424.746,40	424.746,40	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	40	250,00		10.000,00
10.100.1083	Master electrician’s helper	h	40	185,00		7.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	424.746,40	26.300,00
				Material and Installation w/o Profit (TRY)	451.046,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**32.875,00**	
				Unit Price (TRY)	**563.808,00**	

Item No	Analysis Name					UoM
35.470.2004	**Lifting capacity: up to 30 tons / Hydraulic Stage Platform (Lift)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.2004	Lifting capacity: up to 30 tons / Hydraulic Stage Platform (Elevator) (Market price)	Qty	1	532.584,00	532.584,00	
	Installation Components					
10.100.1062	Unskilled worker	h	24	165,00		3.960,00
10.100.1081	Master electrician	h	48	250,00		12.000,00
10.100.1083	Master electrician’s helper	h	48	185,00		8.880,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	532.584,00	31.840,00
				Material and Installation w/o Profit (TRY)	564.424,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39.800,00**	
				Unit Price (TRY)	**705.530,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.470.2005	**Lifting capacity: up to 40 tons / Hydraulic Stage Platform (Lift)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.2005	Lifting capacity: up to 40 tons / Hydraulic Stage Platform (Elevator) (Market price)	Qty	1	663.208,00	663.208,00	
	Installation Components					
10.100.1062	Unskilled worker	h	28	165,00		4.620,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician’s helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
		Total Excluding Profit (TRY)			663.208,00	37.380,00
		Material and Installation w/o Profit (TRY)			700.588,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**46.725,00**	
		Unit Price (TRY)			**875.735,00**	

Item No	Analysis Name					UoM
35.470.3001	**200 x 150 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3001	200 x 150 Motorized screen / Motorized Screen (Market price)	Qty	1	3.270,96	3.270,96	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
		Total Excluding Profit (TRY)			3.270,96	1.200,00
		Material and Installation w/o Profit (TRY)			4.470,96	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.500,00**	
		Unit Price (TRY)			**5.588,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.470.3002	**250 x 190 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3002	250 x 190 Motorized screen / Motorized Screen (Market price)	Qty	1	4.442,24	4.442,24	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	4.442,24	1.500,00
				Material and Installation w/o Profit (TRY)	5.942,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.875,00**	
				Unit Price (TRY)	**7.427,80**	

Item No	Analysis Name					UoM
35.470.3003	**300 x 225 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3003	300 x 225 Motorized screen / Motorized Screen (Market price)	Qty	1	5.966,40	5.966,40	
	Installation Components					
10.100.1062	Unskilled worker	h	2,7	165,00		445,50
10.100.1081	Master electrician	h	2,7	250,00		675,00
10.100.1083	Master electrician’s helper	h	2,7	185,00		499,50
				Total Excluding Profit (TRY)	5.966,40	1.620,00
				Material and Installation w/o Profit (TRY)	7.586,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.025,00**	
				Unit Price (TRY)	**9.483,00**	

Item No	Analysis Name					UoM
35.470.3004	**350 x 265 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3004	350 x 265 Motorized screen / Motorized Screen (Market price)	Qty	1	7.075,20	7.075,20	
	Installation Components					
10.100.1062	Unskilled worker	h	2,9	165,00		478,50
10.100.1081	Master electrician	h	2,9	250,00		725,00
10.100.1083	Master electrician’s helper	h	2,9	185,00		536,50
				Total Excluding Profit (TRY)	7.075,20	1.740,00
				Material and Installation w/o Profit (TRY)	8.815,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.175,00**	
				Unit Price (TRY)	**11.019,00**	

Item No	Analysis Name					UoM
35.470.3005	**400 x 300 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3005	400 x 300 Motorized screen / Motorized Screen (Market price)	Qty	1	8.421,60	8.421,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3,2	165,00		528,00
10.100.1081	Master electrician	h	3,2	250,00		800,00
10.100.1083	Master electrician’s helper	h	3,2	185,00		592,00
				Total Excluding Profit (TRY)	8.421,60	1.920,00
				Material and Installation w/o Profit (TRY)	10.341,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.400,00**	
				Unit Price (TRY)	**12.927,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.470.3006	**450 x 340 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3006	450 x 340 Motorized screen / Motorized Screen (Market price)	Qty	1	9.794,40	9.794,40	
	Installation Components					
10.100.1062	Unskilled worker	h	3,5	165,00		577,50
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	9.794,40	2.100,00
				Material and Installation w/o Profit (TRY)	11.894,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.625,00**	
				Unit Price (TRY)	**14.868,00**	

Item No	Analysis Name					UoM
35.470.3007	**500 x 375 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3007	500 x 375 Motorized screen / Motorized Screen (Market price)	Qty	1	12.240,80	12.240,80	
	Installation Components					
10.100.1062	Unskilled worker	h	3,9	165,00		643,50
10.100.1081	Master electrician	h	3,9	250,00		975,00
10.100.1083	Master electrician’s helper	h	3,9	185,00		721,50
				Total Excluding Profit (TRY)	12.240,80	2.340,00
				Material and Installation w/o Profit (TRY)	14.580,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.925,00**	
				Unit Price (TRY)	**18.226,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.470.3008	**600 x 450 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3008	600 x 450 Motorized screen / Motorized Screen (Market price)	Qty	1	15.188,80	15.188,80	
	Installation Components					
10.100.1062	Unskilled worker	h	4,7	165,00		775,50
10.100.1081	Master electrician	h	4,7	250,00		1.175,00
10.100.1083	Master electrician’s helper	h	4,7	185,00		869,50
				Total Excluding Profit (TRY)	15.188,80	2.820,00
				Material and Installation w/o Profit (TRY)	18.008,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.525,00**	
				Unit Price (TRY)	**22.511,00**	

Item No	Analysis Name					UoM
35.470.3009	**700 x 575 Motorized screen / Motorized Screen**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.3009	700 x 575 Motorized screen / Motorized Screen (Market price)	Qty	1	16.825,60	16.825,60	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	16.825,60	3.600,00
				Material and Installation w/o Profit (TRY)	20.425,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.500,00**	
				Unit Price (TRY)	**25.532,00**	

Item No	Analysis Name					UoM
35.470.4001is	**2 x 100 W Power Amplifier / Power Amplifier**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.4001	2 x 100 W Power Amplifier	Qty	1	5.544,00	5.544,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	5.544,00	1.217,50
				Material and Installation w/o Profit (TRY)	6.761,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.521,88**	
				Unit Price (TRY)	**8.451,88**	

Item No	Analysis Name					UoM
35.470.4002is	**2 x 150 W Power Amplifier / Power Amplifier**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.4002	2 x 150 W Power Amplifier	Qty	1	7.867,20	7.867,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	7.867,20	1.217,50
				Material and Installation w/o Profit (TRY)	9.084,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.521,88**	
				Unit Price (TRY)	**11.355,88**	

Item No	Analysis Name					UoM
35.470.4003is	**2 x 250 W Power Amplifier / Power Amplifier**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.4003	2 x 250 W Power Amplifier	Qty	1	9.609,60	9.609,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	9.609,60	1.785,00
				Material and Installation w/o Profit (TRY)	11.394,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.231,25**	
				Unit Price (TRY)	**14.243,25**	

Item No	Analysis Name					UoM
35.470.4004is	**2 x 450 W Power Amplifier / Power Amplifier**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.4004	2 x 450 W Power Amplifier	Qty	1	14.977,60	14.977,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	14.977,60	1.785,00
				Material and Installation w/o Profit (TRY)	16.762,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.231,25**	
				Unit Price (TRY)	**20.953,25**	

Item No	Analysis Name					UoM
35.470.4005is	**2 x 800 W Power Amplifier / Power Amplifier**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.4005	2 x 800 W Power Amplifier	Qty	1	17.740,80	17.740,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,75	250,00		437,50
10.100.1083	Master electrician's helper	h	1,75	185,00		323,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	17.740,80	2.243,75
				Material and Installation w/o Profit (TRY)	19.984,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.804,69**	
				Unit Price (TRY)	**24.980,69**	

Item No	Analysis Name					UoM
35.470.4006is	**2 x 1,150 W Power Amplifier / Power Amplifier**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.470.4006	2 x 1,150 W Power Amplifier	Qty	1	21.428,00	21.428,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	21.428,00	2.352,50
				Material and Installation w/o Profit (TRY)	23.780,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.940,63**	
				Unit Price (TRY)	**29.725,63**	

Item No	Analysis Name					UoM
35.481.1150						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1150	10/8 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	1.635,12	1.635,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	1.635,12	1.083,75
				Material and Installation w/o Profit (TRY)	2.718,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.354,69**	
				Unit Price (TRY)	**3.398,59**	

Item No	Analysis Name					UoM
35.481.1154						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1154	10/12 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	1.879,62	1.879,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
				Total Excluding Profit (TRY)	1.879,62	1.083,75
				Material and Installation w/o Profit (TRY)	2.963,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.354,69**	
				Unit Price (TRY)	**3.704,21**	

Item No	Analysis Name					UoM
35.481.1156						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1156	10/16 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	2.013,83	2.013,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	2.013,83	1.605,00
				Material and Installation w/o Profit (TRY)	3.618,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.006,25**	
				Unit Price (TRY)	**4.523,54**	

Item No	Analysis Name					UoM
35.481.1158						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1158	10/20 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	2.342,26	2.342,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	2.342,26	1.605,00
				Material and Installation w/o Profit (TRY)	3.947,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.006,25**	
				Unit Price (TRY)	**4.934,08**	

Item No	Analysis Name					UoM
35.481.1160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1160	10/24 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	2.734,65	2.734,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	2.734,65	2.126,25
				Material and Installation w/o Profit (TRY)	4.860,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.657,81**	
				Unit Price (TRY)	**6.076,13**	

Item No	Analysis Name					UoM
35.481.1162						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1162	10/32 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	3.211,25	3.211,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
				Total Excluding Profit (TRY)	3.211,25	2.126,25
				Material and Installation w/o Profit (TRY)	5.337,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.657,81**	
				Unit Price (TRY)	**6.671,88**	

Item No	Analysis Name					UoM
35.481.1164						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1164	10/40 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	3.784,18	3.784,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	1,25	185,00		231,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,5	700,00		1.750,00
				Total Excluding Profit (TRY)	3.784,18	2.647,50
				Material and Installation w/o Profit (TRY)	6.431,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.309,38**	
				Unit Price (TRY)	**8.039,60**	

Item No	Analysis Name					UoM
35.481.1166						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1166	10/48 multiswitch / Multiswitch Satellite Exchange / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	4.917,65	4.917,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	1,25	185,00		231,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,5	700,00		1.750,00
				Total Excluding Profit (TRY)	4.917,65	2.647,50
				Material and Installation w/o Profit (TRY)	7.565,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.309,38**	
				Unit Price (TRY)	**9.456,44**	

Item No	Analysis Name					UoM
35.481.1210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1210	Min. 90 cm offset satellite dish / Offset satellite dish / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	739,87	739,87	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	739,87	1.035,00
				Material and Installation w/o Profit (TRY)	1.774,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**2.218,59**	

Item No	Analysis Name					UoM
35.481.1220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1220	Min. 100 cm offset satellite dish / Offset satellite dish / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	947,04	947,04	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	947,04	1.035,00
				Material and Installation w/o Profit (TRY)	1.982,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**2.477,55**	

Item No	Analysis Name					UoM
35.481.1230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1230	Min. 120 cm offset satellite dish / Offset satellite dish / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	1.469,21	1.469,21	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	1.469,21	1.035,00
				Material and Installation w/o Profit (TRY)	2.504,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**3.130,26**	

Item No	Analysis Name					UoM
35.481.1240						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1240	Min. 150 cm offset satellite dish / Offset satellite dish / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	4.520,63	4.520,63	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	4.520,63	1.035,00
				Material and Installation w/o Profit (TRY)	5.555,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**6.944,54**	

Item No	Analysis Name					UoM
35.481.1310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1310	1 output (single) LNB / LNB / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	139,17	139,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	139,17	106,75
				Material and Installation w/o Profit (TRY)	245,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**307,40**	

Item No	Analysis Name					UoM
35.481.1320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1320	2 output (twin) LNB / LNB / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	226,76	226,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	226,76	106,75
				Material and Installation w/o Profit (TRY)	333,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**416,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1330	4 output (quad) LNB / LNB / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	452,71	452,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
		Total Excluding Profit (TRY)			452,71	106,75
		Material and Installation w/o Profit (TRY)			559,46	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**133,44**	
		Unit Price (TRY)			**699,33**	

Item No	Analysis Name					UoM
35.481.1340						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1340	4 output (quatro) LNB / LNB / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	364,33	364,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
		Total Excluding Profit (TRY)			364,33	106,75
		Material and Installation w/o Profit (TRY)			471,08	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**133,44**	
		Unit Price (TRY)			**588,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1350						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1350	8 output (octo) LNB / LNB / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	1.003,80	1.003,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	1.003,80	106,75
				Material and Installation w/o Profit (TRY)	1.110,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**1.388,19**	

Item No	Analysis Name					UoM
35.481.1400						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1400	Satellite Socket / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	81,35	81,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician’s helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	81,35	133,50
				Material and Installation w/o Profit (TRY)	214,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**166,88**	
				Unit Price (TRY)	**268,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1510						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1510	8 way splitter (5-2400 MHz) / Splitter / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	133,51	133,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	133,51	106,75
				Material and Installation w/o Profit (TRY)	240,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**300,32**	

Item No	Analysis Name					UoM
35.481.1520						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1520	6 way splitter (5-2400 MHz) / Splitter / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	122,76	122,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	122,76	106,75
				Material and Installation w/o Profit (TRY)	229,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**286,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1530						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1530	4 way splitter (5-2400 MHz) / Splitter / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	68,78	68,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	68,78	106,75
				Material and Installation w/o Profit (TRY)	175,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**219,41**	

Item No	Analysis Name					UoM
35.481.1540						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1540	3 way splitter (5-2400 MHz) / Splitter / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	61,57	61,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	61,57	106,75
				Material and Installation w/o Profit (TRY)	168,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**210,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1550						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1550	2 way splitter (5-2400 MHz) / Splitter / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	36,78	36,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	36,78	106,75
				Material and Installation w/o Profit (TRY)	143,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**179,41**	

Item No	Analysis Name					UoM
35.481.1605						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1605	1 way tap off, 5-1000MHz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	65,82	65,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	65,82	106,75
				Material and Installation w/o Profit (TRY)	172,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**215,71**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1610						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1610	1 way tap off, 5-2400MHz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	69,12	69,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	69,12	106,75
				Material and Installation w/o Profit (TRY)	175,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**219,84**	

Item No	Analysis Name					UoM
35.481.1615						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1615	2 way tap off, 5-1000MHz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	79,44	79,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	79,44	106,75
				Material and Installation w/o Profit (TRY)	186,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**232,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1620						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1620	2 way tap off, 5-2400MHz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	83,42	83,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	83,42	106,75
				Material and Installation w/o Profit (TRY)	190,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**237,71**	

Item No	Analysis Name					UoM
35.481.1625						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1625	4 way tap off, 5-1000MHz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	135,60	135,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	135,60	106,75
				Material and Installation w/o Profit (TRY)	242,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**302,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1630						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1630	4 way tap off, 5-2400MHz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	142,38	142,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	142,38	106,75
				Material and Installation w/o Profit (TRY)	249,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**311,41**	

Item No	Analysis Name					UoM
35.481.1635						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1635	6 way tap off, 5-2400Mhz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	145,91	145,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	145,91	106,75
				Material and Installation w/o Profit (TRY)	252,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**315,82**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.481.1640						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.481.1640	8 way tap off, 5-2400Mhz / Tap Off / CENTRAL SATELLITE SYSTEM (Market price)	Qty	1	155,43	155,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,15	185,00		27,75
				Total Excluding Profit (TRY)	155,43	106,75
				Material and Installation w/o Profit (TRY)	262,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133,44**	
				Unit Price (TRY)	**327,73**	

Item No	Analysis Name					UoM
35.485.1001	**Up to 24 V, 20 A / Rectifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.485.1001	24 V. 20 A max. / Rectifier and Its Installation (Market price)	Qty	1	2.721,68	2.721,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.721,68	258,75
				Material and Installation w/o Profit (TRY)	2.980,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.725,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.485.1002	**Up to 24 V, 10 A / Rectifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.485.1002	24 V. 10 A max. / Rectifier and Its Installation (Market price)	Qty	1	2.139,28	2.139,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.139,28	258,75
				Material and Installation w/o Profit (TRY)	2.398,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.997,54**	

Item No	Analysis Name					UoM
35.485.1003	**Up to 24 V, 5 A / Rectifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.485.1003	24 V. 5 A max. / Rectifier and Its Installation (Market price)	Qty	1	1.983,28	1.983,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.983,28	258,75
				Material and Installation w/o Profit (TRY)	2.242,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.802,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.485.1004	**Up to 24 V, 2 A / Rectifier and Its Installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.485.1004	24 V. 2 A max. / Rectifier and Its Installation (Market price)	Qty	1	1.265,68	1.265,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.265,68	258,75
				Material and Installation w/o Profit (TRY)	1.524,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.905,54**	

Item No	Analysis Name					UoM
35.491.1101						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1101	4.3" video intercom (min. 480x270), with mechanical button / Video Intercoms / Video Intercom System (Market price)	Qty	1	1.114,66	1.114,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	1.114,66	608,75
				Material and Installation w/o Profit (TRY)	1.723,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**2.154,26**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.491.1102						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1102	7" video intercom (min. 800x480), with mechanical button / Video Intercoms / Video Intercom System (Market price)	Qty	1	1.665,95	1.665,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	1.665,95	608,75
				Material and Installation w/o Profit (TRY)	2.274,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**2.843,38**	

Item No	Analysis Name					UoM
35.491.1104						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1104	4.3" video intercom (min. 480x270), with touch button / Video Intercoms / Video Intercom System (Market price)	Qty	1	1.208,67	1.208,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	1.208,67	608,75
				Material and Installation w/o Profit (TRY)	1.817,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**2.271,78**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.491.1105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1105	7" video intercom (min. 800x480), with touch button / Video Intercoms / Video Intercom System (Market price)	Qty	1	1.767,94	1.767,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	1.767,94	717,50
				Material and Installation w/o Profit (TRY)	2.485,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**896,88**	
				Unit Price (TRY)	**3.106,80**	

Item No	Analysis Name					UoM
35.491.1108						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1108	7" video intercom (min. 800x480), with touch screen / Video Intercoms / Video Intercom System (Market price)	Qty	1	4.289,27	4.289,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	4.289,27	717,50
				Material and Installation w/o Profit (TRY)	5.006,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**896,88**	
				Unit Price (TRY)	**6.258,46**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.491.1109						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1109	10.1" video intercom (min. 1024x600), with touch screen / Video Intercoms / Video Intercom System (Market price)	Qty	1	5.156,25	5.156,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
		Total Excluding Profit (TRY)			5.156,25	717,50
		Material and Installation w/o Profit (TRY)			5.873,75	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**896,88**	
		Unit Price (TRY)			**7.342,19**	

Item No	Analysis Name					UoM
35.491.1201						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1201	Digital doorbell panel with mechanical keys (2-line display) / Doorbell Panels (with camera) / Video Intercom System (Market price)	Qty	1	3.386,81	3.386,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			3.386,81	258,75
		Material and Installation w/o Profit (TRY)			3.645,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**4.556,95**	

Item No	Analysis Name					UoM
35.491.1202						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1202	Digital doorbell panel with mechanical keys (2-line display) and card reader / Doorbell Panels (with camera) / Video Intercom System (Market price)	Qty	1	3.763,12	3.763,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.763,12	258,75
				Material and Installation w/o Profit (TRY)	4.021,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.027,34**	

Item No	Analysis Name					UoM
35.491.1203						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1203	Digital door panel with mechanical keys (4-line display) / Door Panels (with camera) / Video Intercom System (Market price)	Qty	1	3.554,06	3.554,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.554,06	258,75
				Material and Installation w/o Profit (TRY)	3.812,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**4.766,01**	

Item No	Analysis Name					UoM
35.491.1204						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1204	Digital doorbell panel with mechanical keys (4-line display) and card reader / Doorbell Panels (with camera) / Video Intercom System (Market price)	Qty	1	3.930,37	3.930,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.930,37	258,75
				Material and Installation w/o Profit (TRY)	4.189,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.236,40**	

Item No	Analysis Name					UoM
35.491.1205						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1205	Digital doorbell panel with touch keys, card reader, min. 4" color screen / Doorbell Panels (with camera) / Video Intercom System (Market price)	Qty	1	5.331,08	5.331,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.331,08	258,75
				Material and Installation w/o Profit (TRY)	5.589,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**6.987,29**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.491.1206						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1206	Digital doorbell panel with touch screen, card reader, min. 7" color screen / Doorbell Panels (with camera) / Video Intercom System (Market price)	Qty	1	10.725,00	10.725,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	10.725,00	258,75
				Material and Installation w/o Profit (TRY)	10.983,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**13.729,69**	

Item No	Analysis Name					UoM
35.491.1300						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1300	Surface-Mounted Doorbell Panel Base / Video Intercom System (Market price)	Qty	1	1.182,50	1.182,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.182,50	258,75
				Material and Installation w/o Profit (TRY)	1.441,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.801,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.491.1400						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.1400	Flush-Mounted Doorbell Panel Case / Video Intercom System (Market price)	Qty	1	103,47	103,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	103,47	258,75
				Material and Installation w/o Profit (TRY)	362,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**452,78**	

Item No	Analysis Name					UoM
35.491.2100						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.2100	Audio Intercom / Audio Intercom System / INTERCOM SYSTEMS (Market price)	Qty	1	489,60	489,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	489,60	608,75
				Material and Installation w/o Profit (TRY)	1.098,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**1.372,94**	

Item No	Analysis Name					UoM
35.491.2200						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.2200	Exchange / Audio Intercom System / INTERCOM SYSTEMS (Market price)	Qty	1	3.600,00	3.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	3.600,00	608,75
				Material and Installation w/o Profit (TRY)	4.208,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**5.260,94**	

Item No	Analysis Name					UoM
35.491.2310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.2310	Single-Button Voice Doorbell Panel / Voice Doorbell Panels / Voice Intercom System (Market price)	Qty	1	616,00	616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,2	165,00		33,00
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	616,00	207,00
				Material and Installation w/o Profit (TRY)	823,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258,75**	
				Unit Price (TRY)	**1.028,75**	

Item No	Analysis Name					UoM
35.491.2320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.2320	Additional key price difference for doorbell panel / Voice Doorbell Panels / Voice Intercom System (Market price)	Qty	1	66,00	66,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,02	165,00		3,30
10.100.1081	Master electrician	h	0,04	250,00		10,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	66,00	20,70
				Material and Installation w/o Profit (TRY)	86,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**25,88**	
				Unit Price (TRY)	**108,38**	

Item No	Analysis Name					UoM
35.491.4000						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.4000	DT-8 cable / INTERCOM SYSTEMS (Market price)	m	1	10,84	10,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,05	250,00		12,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	10,84	23,40
				Material and Installation w/o Profit (TRY)	34,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**29,25**	
				Unit Price (TRY)	**42,80**	

Item No	Analysis Name					UoM
35.491.5000						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.150.1461	1 x 1 mm² section / H07Z, H07Z1 type cable (min. 300/500 V) / Halogen-Free Cables (Market price)	m	5	4,70	23,50	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
30.185.1101	Flush-mounted regular switch (TS-4915 EN 60669-1) / Switches / Separate Installation Parts (Market price)	Qty	1	45,47	45,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,55	250,00		137,50
10.100.1083	Master electrician’s helper	h	0,55	185,00		101,75
				Total Excluding Profit (TRY)	89,97	288,75
				Material and Installation w/o Profit (TRY)	378,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**360,94**	
				Unit Price (TRY)	**473,40**	

Item No	Analysis Name					UoM
35.491.7110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.7110	Min. 7" screen, min. 800x480 pixels / IP Video Intercom / IP Intercom System (Market price)	Qty	1	4.200,00	4.200,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	4.200,00	717,50
				Material and Installation w/o Profit (TRY)	4.917,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**896,88**	
				Unit Price (TRY)	**6.146,88**	

Item No	Analysis Name					UoM
35.491.7120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.7120	Min. 10" screen, min. 1024x600 pixels / IP Video Intercom / IP Intercom System (Market price)	Qty	1	5.960,00	5.960,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,75	250,00		187,50
10.100.1083	Master electrician’s helper	h	0,75	185,00		138,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	5.960,00	717,50
				Material and Installation w/o Profit (TRY)	6.677,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**896,88**	
				Unit Price (TRY)	**8.346,88**	

Item No	Analysis Name					UoM
35.491.7210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.7210	Digital doorbell panel with touch keys, card reader, min. 4" color screen / IP Doorbell Panel / IP Intercom System (Market price)	Qty	1	11.040,00	11.040,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	11.040,00	608,75
				Material and Installation w/o Profit (TRY)	11.648,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**14.560,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.491.7220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.491.7220	Digital doorbell panel with touch screen, card reader, min. 7" color screen / IP Doorbell Panel / IP Intercom System (Market price)	Qty	1	17.820,00	17.820,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
				Total Excluding Profit (TRY)	17.820,00	608,75
				Material and Installation w/o Profit (TRY)	18.428,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**760,94**	
				Unit Price (TRY)	**23.035,94**	

Item No	Analysis Name					UoM
35.500.1001	**1 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1001	1 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	12,12	12,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	12,12	34,00
				Material and Installation w/o Profit (TRY)	46,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**57,65**	

Item No	Analysis Name					UoM
35.500.1002	**2 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1002	2 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	19,68	19,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,68	34,00
				Material and Installation w/o Profit (TRY)	53,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**67,10**	

Item No	Analysis Name					UoM
35.500.1003	**3 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1003	3 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	26,76	26,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	26,76	36,50
				Material and Installation w/o Profit (TRY)	63,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**79,08**	

Item No	Analysis Name					UoM
35.500.1004	**4 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1004	4 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	35,16	35,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	35,16	42,50
				Material and Installation w/o Profit (TRY)	77,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**97,07**	

Item No	Analysis Name					UoM
35.500.1005	**5 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1005	5 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	50,16	50,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	50,16	42,50
				Material and Installation w/o Profit (TRY)	92,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**115,82**	

Item No	Analysis Name					UoM
35.500.1006	**6 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1006	6 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	60,36	60,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	60,36	42,50
				Material and Installation w/o Profit (TRY)	102,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**128,57**	

Item No	Analysis Name					UoM
35.500.1007	**8 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1007	8 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	78,96	78,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	78,96	48,50
				Material and Installation w/o Profit (TRY)	127,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**159,32**	

Item No	Analysis Name					UoM
35.500.1008	**10 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1008	10 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	99,36	99,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
		Total Excluding Profit (TRY)			99,36	51,00
		Material and Installation w/o Profit (TRY)			150,36	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**63,75**	
		Unit Price (TRY)			**187,95**	

Item No	Analysis Name					UoM
35.500.1009	**1 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1009	1 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	18,60	18,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			18,60	34,00
		Material and Installation w/o Profit (TRY)			52,60	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**42,50**	
		Unit Price (TRY)			**65,75**	

Item No	Analysis Name					UoM
35.500.1010	**2 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1010	2 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	29,52	29,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,52	34,00
				Material and Installation w/o Profit (TRY)	63,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**79,40**	

Item No	Analysis Name					UoM
35.500.1011	**3 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1011	3 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	40,56	40,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	40,56	40,00
				Material and Installation w/o Profit (TRY)	80,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**100,70**	

Item No	Analysis Name					UoM
35.500.1012	**4 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1012	4 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	51,96	51,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			51,96	42,50
		Material and Installation w/o Profit (TRY)			94,46	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**53,13**	
		Unit Price (TRY)			**118,08**	

Item No	Analysis Name					UoM
35.500.1013	**5 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1013	5 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	74,16	74,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			74,16	45,00
		Material and Installation w/o Profit (TRY)			119,16	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,25**	
		Unit Price (TRY)			**148,95**	

Item No	Analysis Name					UoM
35.500.1014	**6 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1014	6 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	90,36	90,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
		Total Excluding Profit (TRY)			90,36	48,50
		Material and Installation w/o Profit (TRY)			138,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**60,63**	
		Unit Price (TRY)			**173,58**	

Item No	Analysis Name					UoM
35.500.1015	**8 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1015	8 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	103,56	103,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
		Total Excluding Profit (TRY)			103,56	51,00
		Material and Installation w/o Profit (TRY)			154,56	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**63,75**	
		Unit Price (TRY)			**193,20**	

Item No	Analysis Name					UoM
35.500.1016	**10 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1016	10 x 2 x 1 + 1 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	149,16	149,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
		Total Excluding Profit (TRY)			149,16	53,50
		Material and Installation w/o Profit (TRY)			202,66	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**66,88**	
		Unit Price (TRY)			**253,32**	

Item No	Analysis Name					UoM
35.500.1017	**1 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1017	1 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	31,08	31,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			31,08	36,50
		Material and Installation w/o Profit (TRY)			67,58	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**45,63**	
		Unit Price (TRY)			**84,47**	

Item No	Analysis Name					UoM
35.500.1018	**2 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1018	2 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	51,96	51,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	51,96	42,50
				Material and Installation w/o Profit (TRY)	94,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**118,08**	

Item No	Analysis Name					UoM
35.500.1019	**3 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1019	3 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	71,76	71,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	71,76	48,50
				Material and Installation w/o Profit (TRY)	120,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**150,33**	

Item No	Analysis Name					UoM
35.500.1020	**4 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1020	4 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	92,16	92,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	92,16	51,00
				Material and Installation w/o Profit (TRY)	143,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**178,95**	

Item No	Analysis Name					UoM
35.500.1021	**5 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1021	5 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	129,96	129,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	129,96	53,50
				Material and Installation w/o Profit (TRY)	183,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**229,33**	

Item No	Analysis Name					UoM
35.500.1022	**6 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1022	6 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	157,56	157,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			157,56	59,50
		Material and Installation w/o Profit (TRY)			217,06	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**74,38**	
		Unit Price (TRY)			**271,32**	

Item No	Analysis Name					UoM
35.500.1023	**8 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1023	8 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	205,56	205,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			205,56	62,00
		Material and Installation w/o Profit (TRY)			267,56	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**77,50**	
		Unit Price (TRY)			**334,45**	

Item No	Analysis Name					UoM
35.500.1024	**10 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1024	10 x 2 x 1.5 + 1.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	254,76	254,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	254,76	68,00
				Material and Installation w/o Profit (TRY)	322,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**403,45**	

Item No	Analysis Name					UoM
35.500.1025	**1 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1025	1 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	52,56	52,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,56	42,50
				Material and Installation w/o Profit (TRY)	95,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**118,83**	

Item No	Analysis Name					UoM
35.500.1026	**2 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1026	2 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	84,96	84,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
		Total Excluding Profit (TRY)			84,96	48,50
		Material and Installation w/o Profit (TRY)			133,46	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**60,63**	
		Unit Price (TRY)			**166,82**	

Item No	Analysis Name					UoM
35.500.1027	**3 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1027	3 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	119,16	119,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			119,16	57,00
		Material and Installation w/o Profit (TRY)			176,16	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**71,25**	
		Unit Price (TRY)			**220,20**	

Item No	Analysis Name					UoM
35.500.1028	**4 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1028	4 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	151,56	151,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	151,56	65,50
				Material and Installation w/o Profit (TRY)	217,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**271,32**	

Item No	Analysis Name					UoM
35.500.1029	**5 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1029	5 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	218,76	218,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	218,76	68,00
				Material and Installation w/o Profit (TRY)	286,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**358,45**	

Item No	Analysis Name					UoM
35.500.1030	**6 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1030	6 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	259,56	259,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			259,56	74,00
		Material and Installation w/o Profit (TRY)			333,56	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**92,50**	
		Unit Price (TRY)			**416,95**	

Item No	Analysis Name					UoM
35.500.1031	**8 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1031	8 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	338,76	338,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			338,76	76,50
		Material and Installation w/o Profit (TRY)			415,26	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**95,63**	
		Unit Price (TRY)			**519,08**	

Item No	Analysis Name					UoM
35.500.1032	**10 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.1032	10 x 2 x 2.5 + 2.5 mm² / J-Y (St) Fire Alarm Cables (Market price)	m	1	422,76	422,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	422,76	87,50
				Material and Installation w/o Profit (TRY)	510,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**109,38**	
				Unit Price (TRY)	**637,83**	

Item No	Analysis Name					UoM
35.500.2101	**2 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2101	2 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	7,80	7,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	7,80	25,50
				Material and Installation w/o Profit (TRY)	33,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**41,63**	

Item No	Analysis Name					UoM
35.500.2102	**12 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2102	12 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	23,10	23,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	23,10	31,50
				Material and Installation w/o Profit (TRY)	54,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**68,25**	

Item No	Analysis Name					UoM
35.500.2103	**14 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2103	14 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	28,20	28,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	28,20	31,50
				Material and Installation w/o Profit (TRY)	59,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**74,63**	

Item No	Analysis Name					UoM
35.500.2104	**16 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2104	16 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	30,00	30,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	30,00	31,50
				Material and Installation w/o Profit (TRY)	61,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**76,88**	

Item No	Analysis Name					UoM
35.500.2105	**18 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2105	18 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	32,20	32,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	32,20	34,00
				Material and Installation w/o Profit (TRY)	66,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**82,75**	

Item No	Analysis Name					UoM
35.500.2106	**20 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2106	20 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	36,20	36,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	36,20	34,00
				Material and Installation w/o Profit (TRY)	70,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**87,75**	

Item No	Analysis Name					UoM
35.500.2107	**25 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2107	25 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	41,60	41,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	41,60	34,00
				Material and Installation w/o Profit (TRY)	75,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**94,50**	

Item No	Analysis Name					UoM
35.500.2108	**3 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2108	3 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	9,20	9,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	9,20	25,50
				Material and Installation w/o Profit (TRY)	34,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**43,38**	

Item No	Analysis Name					UoM
35.500.2109	**4 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2109	4 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	12,00	12,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	12,00	25,50
				Material and Installation w/o Profit (TRY)	37,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**46,88**	

Item No	Analysis Name					UoM
35.500.2110	**5 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2110	5 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	13,00	13,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	13,00	25,50
				Material and Installation w/o Profit (TRY)	38,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**48,13**	

Item No	Analysis Name					UoM
35.500.2111	**6 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2111	6 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	15,90	15,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	15,90	25,50
				Material and Installation w/o Profit (TRY)	41,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**51,75**	

Item No	Analysis Name					UoM
35.500.2112	**7 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2112	7 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	16,80	16,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	16,80	28,00
				Material and Installation w/o Profit (TRY)	44,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**56,00**	

Item No	Analysis Name					UoM
35.500.2113	**8 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2113	8 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	18,10	18,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	18,10	28,00
				Material and Installation w/o Profit (TRY)	46,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**57,63**	

Item No	Analysis Name					UoM
35.500.2114	**9 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2114	9 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	20,70	20,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	20,70	28,00
				Material and Installation w/o Profit (TRY)	48,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**60,88**	

Item No	Analysis Name					UoM
35.500.2115	**10 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2115	10 x 0.14 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	22,00	22,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	22,00	31,50
				Material and Installation w/o Profit (TRY)	53,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**66,88**	

Item No	Analysis Name					UoM
35.500.2116	**2 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2116	2 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	10,60	10,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	10,60	28,00
				Material and Installation w/o Profit (TRY)	38,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**48,25**	

Item No	Analysis Name					UoM
35.500.2117	**14 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2117	14 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	36,60	36,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	36,60	36,50
				Material and Installation w/o Profit (TRY)	73,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**91,38**	

Item No	Analysis Name					UoM
35.500.2118	**16 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2118	16 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	41,80	41,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,80	40,00
				Material and Installation w/o Profit (TRY)	81,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**102,25**	

Item No	Analysis Name					UoM
35.500.2119	**18 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2119	18 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	45,40	45,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	45,40	40,00
				Material and Installation w/o Profit (TRY)	85,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**106,75**	

Item No	Analysis Name					UoM
35.500.2120	**20 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2120	20 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	48,90	48,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,90	40,00
				Material and Installation w/o Profit (TRY)	88,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**111,13**	

Item No	Analysis Name					UoM
35.500.2121	**25 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2121	25 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	61,90	61,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	61,90	40,00
				Material and Installation w/o Profit (TRY)	101,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**127,38**	

Item No	Analysis Name					UoM
35.500.2122	**3 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2122	3 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	12,40	12,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	12,40	28,00
				Material and Installation w/o Profit (TRY)	40,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**50,50**	

Item No	Analysis Name					UoM
35.500.2123	**4 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2123	4 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	14,10	14,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,10	31,50
				Material and Installation w/o Profit (TRY)	45,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**57,00**	

Item No	Analysis Name					UoM
35.500.2124	**5 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2124	5 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	17,50	17,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,50	31,50
				Material and Installation w/o Profit (TRY)	49,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**61,25**	

Item No	Analysis Name					UoM
35.500.2125	**6 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2125	6 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	19,50	19,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,50	34,00
				Material and Installation w/o Profit (TRY)	53,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**66,88**	

Item No	Analysis Name					UoM
35.500.2126	**7 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2126	7 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	20,80	20,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,80	34,00
				Material and Installation w/o Profit (TRY)	54,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**68,50**	

Item No	Analysis Name					UoM
35.500.2127	**8 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2127	8 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	24,30	24,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,30	34,00
				Material and Installation w/o Profit (TRY)	58,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**72,88**	

Item No	Analysis Name					UoM
35.500.2128	**10 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2128	10 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	29,80	29,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,80	34,00
				Material and Installation w/o Profit (TRY)	63,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**79,75**	

Item No	Analysis Name					UoM
35.500.2129	**12 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2129	12 x 0.25 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	33,20	33,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	33,20	36,50
				Material and Installation w/o Profit (TRY)	69,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**87,13**	

Item No	Analysis Name					UoM
35.500.2130	**2 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2130	2 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	13,90	13,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,90	31,50
				Material and Installation w/o Profit (TRY)	45,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**56,75**	

Item No	Analysis Name					UoM
35.500.2131	**14 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2131	14 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	50,20	50,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	50,20	40,00
				Material and Installation w/o Profit (TRY)	90,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**112,75**	

Item No	Analysis Name					UoM
35.500.2132	**16 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2132	16 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	57,20	57,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	57,20	42,50
				Material and Installation w/o Profit (TRY)	99,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**124,63**	

Item No	Analysis Name					UoM
35.500.2133	**18 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2133	18 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	64,70	64,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	64,70	42,50
				Material and Installation w/o Profit (TRY)	107,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**134,00**	

Item No	Analysis Name					UoM
35.500.2134	**20 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2134	20 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	69,70	69,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	69,70	42,50
				Material and Installation w/o Profit (TRY)	112,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**140,25**	

Item No	Analysis Name					UoM
35.500.2135	**25 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2135	25 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	85,70	85,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	85,70	42,50
				Material and Installation w/o Profit (TRY)	128,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**160,25**	

Item No	Analysis Name					UoM
35.500.2136	**3 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2136	3 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	16,40	16,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	16,40	31,50
				Material and Installation w/o Profit (TRY)	47,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**59,88**	

Item No	Analysis Name					UoM
35.500.2137	**4 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2137	4 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	18,60	18,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	18,60	31,50
				Material and Installation w/o Profit (TRY)	50,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**62,63**	

Item No	Analysis Name					UoM
35.500.2138	**5 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2138	5 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	22,60	22,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	22,60	34,00
				Material and Installation w/o Profit (TRY)	56,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**70,75**	

Item No	Analysis Name					UoM
35.500.2139	**6 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2139	6 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	25,60	25,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	25,60	34,00
				Material and Installation w/o Profit (TRY)	59,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**74,50**	

Item No	Analysis Name					UoM
35.500.2140	**7 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2140	7 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	27,60	27,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,60	34,00
				Material and Installation w/o Profit (TRY)	61,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**77,00**	

Item No	Analysis Name					UoM
35.500.2141	**8 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2141	8 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	31,80	31,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	31,80	34,00
				Material and Installation w/o Profit (TRY)	65,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**82,25**	

Item No	Analysis Name					UoM
35.500.2142	**10 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2142	10 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	34,20	34,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	34,20	36,50
				Material and Installation w/o Profit (TRY)	70,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**88,38**	

Item No	Analysis Name					UoM
35.500.2143	**12 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2143	12 x 0.34 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	39,70	39,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,70	40,00
				Material and Installation w/o Profit (TRY)	79,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**99,63**	

Item No	Analysis Name					UoM
35.500.2144	**2 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2144	2 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	15,00	15,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	15,00	34,00
				Material and Installation w/o Profit (TRY)	49,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**61,25**	

Item No	Analysis Name					UoM
35.500.2145	**3 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2145	3 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	17,60	17,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,60	34,00
				Material and Installation w/o Profit (TRY)	51,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**64,50**	

Item No	Analysis Name					UoM
35.500.2146	**4 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2146	4 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	22,10	22,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	22,10	34,00
				Material and Installation w/o Profit (TRY)	56,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**70,13**	

Item No	Analysis Name					UoM
35.500.2147	**5 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2147	5 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	25,20	25,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	25,20	36,50
				Material and Installation w/o Profit (TRY)	61,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**77,13**	

Item No	Analysis Name					UoM
35.500.2148	**6 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2148	6 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	30,20	30,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	30,20	36,50
				Material and Installation w/o Profit (TRY)	66,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**83,38**	

Item No	Analysis Name					UoM
35.500.2149	**7 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2149	7 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	33,00	33,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	33,00	36,50
				Material and Installation w/o Profit (TRY)	69,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**86,88**	

Item No	Analysis Name					UoM
35.500.2150	**8 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2150	8 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	37,60	37,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	37,60	40,00
				Material and Installation w/o Profit (TRY)	77,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**97,00**	

Item No	Analysis Name					UoM
35.500.2151	**9 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2151	9 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	40,70	40,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	40,70	42,50
				Material and Installation w/o Profit (TRY)	83,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**104,00**	

Item No	Analysis Name					UoM
35.500.2152	**10 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2152	10 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	43,70	43,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	43,70	42,50
				Material and Installation w/o Profit (TRY)	86,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**107,75**	

Item No	Analysis Name					UoM
35.500.2153	**12 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2153	12 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	52,20	52,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,20	42,50
				Material and Installation w/o Profit (TRY)	94,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**118,38**	

Item No	Analysis Name					UoM
35.500.2154	**14 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2154	14 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	59,20	59,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	59,20	45,00
				Material and Installation w/o Profit (TRY)	104,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**130,25**	

Item No	Analysis Name					UoM
35.500.2155	**16 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2155	16 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	66,70	66,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	66,70	45,00
				Material and Installation w/o Profit (TRY)	111,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**139,63**	

Item No	Analysis Name					UoM
35.500.2156	**18 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2156	18 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	73,70	73,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	73,70	48,50
				Material and Installation w/o Profit (TRY)	122,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**152,75**	

Item No	Analysis Name					UoM
35.500.2157	**20 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2157	20 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	82,70	82,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	82,70	48,50
				Material and Installation w/o Profit (TRY)	131,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**164,00**	

Item No	Analysis Name					UoM
35.500.2158	**25 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2158	25 x 0.50 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	100,70	100,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	100,70	51,00
				Material and Installation w/o Profit (TRY)	151,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**189,63**	

Item No	Analysis Name					UoM
35.500.2159	**2 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2159	2 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	17,50	17,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,50	34,00
				Material and Installation w/o Profit (TRY)	51,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**64,38**	

Item No	Analysis Name					UoM
35.500.2160	**3 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2160	3 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	23,40	23,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	23,40	34,00
				Material and Installation w/o Profit (TRY)	57,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**71,75**	

Item No	Analysis Name					UoM
35.500.2161	**4 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2161	4 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	27,50	27,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,50	34,00
				Material and Installation w/o Profit (TRY)	61,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**76,88**	

Item No	Analysis Name					UoM
35.500.2162	**5 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2162	5 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	33,10	33,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	33,10	36,50
				Material and Installation w/o Profit (TRY)	69,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**87,00**	

Item No	Analysis Name					UoM
35.500.2163	**6 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2163	6 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	39,60	39,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,60	40,00
				Material and Installation w/o Profit (TRY)	79,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**99,50**	

Item No	Analysis Name					UoM
35.500.2164	**7 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2164	7 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	43,70	43,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	43,70	40,00
				Material and Installation w/o Profit (TRY)	83,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**104,63**	

Item No	Analysis Name					UoM
35.500.2165	**8 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2165	8 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	48,20	48,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,20	40,00
				Material and Installation w/o Profit (TRY)	88,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**110,25**	

Item No	Analysis Name					UoM
35.500.2166	**9 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2166	9 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	54,20	54,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	54,20	42,50
				Material and Installation w/o Profit (TRY)	96,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**120,88**	

Item No	Analysis Name					UoM
35.500.2167	**10 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2167	10 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	58,70	58,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	58,70	45,00
				Material and Installation w/o Profit (TRY)	103,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**129,63**	

Item No	Analysis Name					UoM
35.500.2168	**12 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2168	12 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	68,70	68,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	68,70	45,00
				Material and Installation w/o Profit (TRY)	113,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**142,13**	

Item No	Analysis Name					UoM
35.500.2169	**14 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2169	14 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	78,20	78,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	78,20	48,50
				Material and Installation w/o Profit (TRY)	126,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**158,38**	

Item No	Analysis Name					UoM
35.500.2170	**16 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2170	16 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	89,70	89,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	89,70	48,50
				Material and Installation w/o Profit (TRY)	138,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**172,75**	

Item No	Analysis Name					UoM
35.500.2171	**18 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2171	18 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	98,70	98,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	98,70	51,00
				Material and Installation w/o Profit (TRY)	149,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**187,13**	

Item No	Analysis Name					UoM
35.500.2172	**20 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2172	20 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	110,70	110,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	110,70	51,00
				Material and Installation w/o Profit (TRY)	161,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**202,13**	

Item No	Analysis Name					UoM
35.500.2173	**25 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2173	25 x 0.75 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	137,70	137,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	137,70	51,00
				Material and Installation w/o Profit (TRY)	188,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**235,88**	

Item No	Analysis Name					UoM
35.500.2174	**2 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2174	2 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	22,00	22,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	22,00	34,00
				Material and Installation w/o Profit (TRY)	56,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**70,00**	

Item No	Analysis Name					UoM
35.500.2175	**3 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2175	3 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	29,10	29,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,10	34,00
				Material and Installation w/o Profit (TRY)	63,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**78,88**	

Item No	Analysis Name					UoM
35.500.2176	**4 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2176	4 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	34,80	34,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	34,80	36,50
				Material and Installation w/o Profit (TRY)	71,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**89,13**	

Item No	Analysis Name					UoM
35.500.2177	**5 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2177	5 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	42,30	42,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	42,30	40,00
				Material and Installation w/o Profit (TRY)	82,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**102,88**	

Item No	Analysis Name					UoM
35.500.2178	**6 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2178	6 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	50,30	50,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	50,30	42,50
				Material and Installation w/o Profit (TRY)	92,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**116,00**	

Item No	Analysis Name					UoM
35.500.2179	**7 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2179	7 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	56,30	56,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	56,30	42,50
				Material and Installation w/o Profit (TRY)	98,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**123,50**	

Item No	Analysis Name					UoM
35.500.2180	**8 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2180	8 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	61,30	61,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	61,30	42,50
				Material and Installation w/o Profit (TRY)	103,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**129,75**	

Item No	Analysis Name					UoM
35.500.2181	**9 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2181	9 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	69,30	69,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	69,30	45,00
				Material and Installation w/o Profit (TRY)	114,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**142,88**	

Item No	Analysis Name					UoM
35.500.2182	**10 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2182	10 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	74,30	74,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	74,30	48,50
				Material and Installation w/o Profit (TRY)	122,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**153,50**	

Item No	Analysis Name					UoM
35.500.2183	**12 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2183	12 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	89,80	89,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	89,80	48,50
				Material and Installation w/o Profit (TRY)	138,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**172,88**	

Item No	Analysis Name					UoM
35.500.2184	**14 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2184	14 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	99,80	99,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	99,80	51,00
				Material and Installation w/o Profit (TRY)	150,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**188,50**	

Item No	Analysis Name					UoM
35.500.2185	**16 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2185	16 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	115,80	115,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	115,80	51,00
				Material and Installation w/o Profit (TRY)	166,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**208,50**	

Item No	Analysis Name					UoM
35.500.2186	**18 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2186	18 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	128,80	128,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	128,80	53,50
				Material and Installation w/o Profit (TRY)	182,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**227,88**	

Item No	Analysis Name					UoM
35.500.2187	**20 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2187	20 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	143,80	143,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	143,80	53,50
				Material and Installation w/o Profit (TRY)	197,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**246,63**	

Item No	Analysis Name					UoM
35.500.2188	**25 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2188	25 x 1.0 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	177,80	177,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	177,80	57,00
				Material and Installation w/o Profit (TRY)	234,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**293,50**	

Item No	Analysis Name					UoM
35.500.2189	**2 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2189	2 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	27,30	27,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,30	34,00
				Material and Installation w/o Profit (TRY)	61,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**76,63**	

Item No	Analysis Name					UoM
35.500.2190	**3 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2190	3 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	34,40	34,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	34,40	36,50
				Material and Installation w/o Profit (TRY)	70,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**88,63**	

Item No	Analysis Name					UoM
35.500.2191	**4 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2191	4 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	43,80	43,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	43,80	40,00
				Material and Installation w/o Profit (TRY)	83,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**104,75**	

Item No	Analysis Name					UoM
35.500.2192	**5 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2192	5 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	53,30	53,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	53,30	42,50
				Material and Installation w/o Profit (TRY)	95,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**119,75**	

Item No	Analysis Name					UoM
35.500.2193	**6 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2193	6 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	63,30	63,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	63,30	42,50
				Material and Installation w/o Profit (TRY)	105,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**132,25**	

Item No	Analysis Name					UoM
35.500.2194	**7 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2194	7 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	71,80	71,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	71,80	42,50
				Material and Installation w/o Profit (TRY)	114,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**142,88**	

Item No	Analysis Name					UoM
35.500.2195	**8 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2195	8 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	80,80	80,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	80,80	42,50
				Material and Installation w/o Profit (TRY)	123,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**154,13**	

Item No	Analysis Name					UoM
35.500.2196	**9 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2196	9 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	90,80	90,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	90,80	48,50
				Material and Installation w/o Profit (TRY)	139,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**174,13**	

Item No	Analysis Name					UoM
35.500.2197	**10 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2197	10 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	99,80	99,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	99,80	51,00
				Material and Installation w/o Profit (TRY)	150,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**188,50**	

Item No	Analysis Name					UoM
35.500.2198	**12 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2198	12 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812) (Market price)	m	1	117,80	117,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	117,80	51,00
				Material and Installation w/o Profit (TRY)	168,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**211,00**	

Item No	Analysis Name					UoM
35.500.2199	**14 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2199	14 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	133,80	133,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	133,80	51,00
				Material and Installation w/o Profit (TRY)	184,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**231,00**	

Item No	Analysis Name					UoM
35.500.2200	**16 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2200	16 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	152,80	152,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	152,80	53,50
				Material and Installation w/o Profit (TRY)	206,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**257,88**	

Item No	Analysis Name					UoM
35.500.2201	**18 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2201	18 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	168,80	168,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	168,80	57,00
				Material and Installation w/o Profit (TRY)	225,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**282,25**	

Item No	Analysis Name					UoM
35.500.2202	**20 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2202	20 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	189,80	189,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	189,80	59,50
				Material and Installation w/o Profit (TRY)	249,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**311,63**	

Item No	Analysis Name					UoM
35.500.2203	**25 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2203	25 x 1.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	233,80	233,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	233,80	59,50
				Material and Installation w/o Profit (TRY)	293,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**366,63**	

Item No	Analysis Name					UoM
35.500.2204	**2 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2204	2 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	38,80	38,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	38,80	40,00
				Material and Installation w/o Profit (TRY)	78,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**98,50**	

Item No	Analysis Name					UoM
35.500.2205	**3 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2205	3 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	50,80	50,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	50,80	40,00
				Material and Installation w/o Profit (TRY)	90,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**113,50**	

Item No	Analysis Name					UoM
35.500.2206	**4 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2206	4 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	63,80	63,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	63,80	42,50
				Material and Installation w/o Profit (TRY)	106,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**132,88**	

Item No	Analysis Name					UoM
35.500.2207	**5 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2207	5 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	79,30	79,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	79,30	45,00
				Material and Installation w/o Profit (TRY)	124,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**155,38**	

Item No	Analysis Name					UoM
35.500.2208	**6 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2208	6 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	92,80	92,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	92,80	48,50
				Material and Installation w/o Profit (TRY)	141,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**176,63**	

Item No	Analysis Name					UoM
35.500.2209	**7 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2209	7 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	105,80	105,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	105,80	51,00
				Material and Installation w/o Profit (TRY)	156,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**196,00**	

Item No	Analysis Name					UoM
35.500.2210	**8 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2210	8 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	120,80	120,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	120,80	51,00
				Material and Installation w/o Profit (TRY)	171,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**214,75**	

Item No	Analysis Name					UoM
35.500.2211	**9 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2211	9 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	134,80	134,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	134,80	53,50
				Material and Installation w/o Profit (TRY)	188,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**235,38**	

Item No	Analysis Name					UoM
35.500.2212	**10 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2212	10 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	149,80	149,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	149,80	59,50
				Material and Installation w/o Profit (TRY)	209,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**261,63**	

Item No	Analysis Name					UoM
35.500.2213	**12 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2213	12 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	177,80	177,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	177,80	59,50
				Material and Installation w/o Profit (TRY)	237,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**296,63**	

Item No	Analysis Name					UoM
35.500.2214	**14 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2214	14 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	209,80	209,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	209,80	59,50
				Material and Installation w/o Profit (TRY)	269,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**336,63**	

Item No	Analysis Name					UoM
35.500.2215	**16 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2215	16 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	239,80	239,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	239,80	65,50
				Material and Installation w/o Profit (TRY)	305,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**381,63**	

Item No	Analysis Name					UoM
35.500.2216	**18 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2216	18 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	264,80	264,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	264,80	68,00
				Material and Installation w/o Profit (TRY)	332,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**416,00**	

Item No	Analysis Name					UoM
35.500.2217	**20 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2217	20 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	293,80	293,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	293,80	68,00
				Material and Installation w/o Profit (TRY)	361,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**452,25**	

Item No	Analysis Name					UoM
35.500.2218	**25 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2218	25 x 2.5 mm² / LIYCY, LIYC2Y Signal cables / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	363,80	363,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	363,80	68,00
				Material and Installation w/o Profit (TRY)	431,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**539,75**	

Item No	Analysis Name					UoM
35.500.2401	**2 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2401	2 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	14,60	14,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,60	34,00
				Material and Installation w/o Profit (TRY)	48,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**60,75**	

Item No	Analysis Name					UoM
35.500.2402	**3 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2402	3 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	20,10	20,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,10	34,00
				Material and Installation w/o Profit (TRY)	54,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**67,63**	

Item No	Analysis Name					UoM
35.500.2403	**4 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2403	4 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	25,20	25,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	25,20	34,00
				Material and Installation w/o Profit (TRY)	59,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**74,00**	

Item No	Analysis Name					UoM
35.500.2404	**5 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2404	5 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	28,30	28,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	28,30	36,50
				Material and Installation w/o Profit (TRY)	64,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**81,00**	

Item No	Analysis Name					UoM
35.500.2405	**6 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2405	6 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	34,20	34,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	34,20	40,00
				Material and Installation w/o Profit (TRY)	74,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**92,75**	

Item No	Analysis Name					UoM
35.500.2406	**7 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2406	7 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	37,30	37,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	37,30	42,50
				Material and Installation w/o Profit (TRY)	79,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**99,75**	

Item No	Analysis Name					UoM
35.500.2407	**8 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2407	8 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	42,80	42,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	42,80	42,50
				Material and Installation w/o Profit (TRY)	85,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**106,63**	

Item No	Analysis Name					UoM
35.500.2408	**10 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2408	10 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	51,90	51,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	51,90	45,00
				Material and Installation w/o Profit (TRY)	96,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**121,13**	

Item No	Analysis Name					UoM
35.500.2409	**12 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2409	12 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	59,90	59,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	59,90	45,00
				Material and Installation w/o Profit (TRY)	104,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**131,13**	

Item No	Analysis Name					UoM
35.500.2410	**15 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2410	15 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	84,40	84,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	84,40	48,50
				Material and Installation w/o Profit (TRY)	132,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**166,13**	

Item No	Analysis Name					UoM
35.500.2411	**18 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2411	18 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	109,40	109,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	109,40	51,00
				Material and Installation w/o Profit (TRY)	160,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**200,50**	

Item No	Analysis Name					UoM
35.500.2412	**20 x 2 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2412	20 x 2 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	126,40	126,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	126,40	53,50
				Material and Installation w/o Profit (TRY)	179,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**224,88**	

Item No	Analysis Name					UoM
35.500.2413	**2 x 25 x 0.22 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2413	2 x 25 x 0.22 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	138,40	138,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	138,40	53,50
				Material and Installation w/o Profit (TRY)	191,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**239,88**	

Item No	Analysis Name					UoM
35.500.2414	**2 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2414	2 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	21,60	21,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	21,60	34,00
				Material and Installation w/o Profit (TRY)	55,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**69,50**	

Item No	Analysis Name					UoM
35.500.2415	**3 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2415	3 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	29,30	29,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,30	36,50
				Material and Installation w/o Profit (TRY)	65,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**82,25**	

Item No	Analysis Name					UoM
35.500.2416	**4 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2416	4 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	36,80	36,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	36,80	36,50
				Material and Installation w/o Profit (TRY)	73,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**91,63**	

Item No	Analysis Name					UoM
35.500.2417	**5 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2417	5 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	44,30	44,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	44,30	42,50
				Material and Installation w/o Profit (TRY)	86,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**108,50**	

Item No	Analysis Name					UoM
35.500.2418	**6 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2418	6 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	50,30	50,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	50,30	42,50
				Material and Installation w/o Profit (TRY)	92,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**116,00**	

Item No	Analysis Name					UoM
35.500.2419	**7 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2419	7 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	58,30	58,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	58,30	42,50
				Material and Installation w/o Profit (TRY)	100,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**126,00**	

Item No	Analysis Name					UoM
35.500.2420	**8 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2420	8 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	64,30	64,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	64,30	45,00
				Material and Installation w/o Profit (TRY)	109,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**136,63**	

Item No	Analysis Name					UoM
35.500.2421	**10 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2421	10 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	78,40	78,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	78,40	48,50
				Material and Installation w/o Profit (TRY)	126,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**158,63**	

Item No	Analysis Name					UoM
35.500.2422	**12 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2422	12 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	95,40	95,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	95,40	48,50
				Material and Installation w/o Profit (TRY)	143,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**179,88**	

Item No	Analysis Name					UoM
35.500.2423	**15 x 2 x 0.34 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2423	15 x 2 x 0.34 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	126,40	126,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	126,40	51,00
				Material and Installation w/o Profit (TRY)	177,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**221,75**	

Item No	Analysis Name					UoM
35.500.2424	**2 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2424	2 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	25,10	25,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	25,10	40,00
				Material and Installation w/o Profit (TRY)	65,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**81,38**	

Item No	Analysis Name					UoM
35.500.2425	**3 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2425	3 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	33,70	33,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	33,70	42,50
				Material and Installation w/o Profit (TRY)	76,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**95,25**	

Item No	Analysis Name					UoM
35.500.2426	**4 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2426	4 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	42,30	42,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	42,30	42,50
				Material and Installation w/o Profit (TRY)	84,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**106,00**	

Item No	Analysis Name					UoM
35.500.2427	**5 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2427	5 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	48,80	48,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,80	45,00
				Material and Installation w/o Profit (TRY)	93,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**117,25**	

Item No	Analysis Name					UoM
35.500.2428	**6 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2428	6 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	57,30	57,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	57,30	48,50
				Material and Installation w/o Profit (TRY)	105,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**132,25**	

Item No	Analysis Name					UoM
35.500.2429	**7 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2429	7 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	64,80	64,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	64,80	51,00
				Material and Installation w/o Profit (TRY)	115,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**144,75**	

Item No	Analysis Name					UoM
35.500.2430	**8 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2430	8 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	73,80	73,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	73,80	51,00
				Material and Installation w/o Profit (TRY)	124,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**156,00**	

Item No	Analysis Name					UoM
35.500.2431	**9 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2431	9 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	80,40	80,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	80,40	53,50
				Material and Installation w/o Profit (TRY)	133,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**167,38**	

Item No	Analysis Name					UoM
35.500.2432	**10 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2432	10 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	89,40	89,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	89,40	57,00
				Material and Installation w/o Profit (TRY)	146,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**183,00**	

Item No	Analysis Name					UoM
35.500.2433	**12 x 2 x 0.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2433	12 x 2 x 0.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	109,40	109,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	109,40	57,00
				Material and Installation w/o Profit (TRY)	166,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**208,00**	

Item No	Analysis Name					UoM
35.500.2434	**2 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2434	2 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	29,40	29,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	29,40	42,50
				Material and Installation w/o Profit (TRY)	71,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**89,88**	

Item No	Analysis Name					UoM
35.500.2435	**3 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2435	3 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	42,80	42,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	42,80	42,50
				Material and Installation w/o Profit (TRY)	85,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**106,63**	

Item No	Analysis Name					UoM
35.500.2436	**4 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2436	4 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	52,30	52,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,30	45,00
				Material and Installation w/o Profit (TRY)	97,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**121,63**	

Item No	Analysis Name					UoM
35.500.2437	**5 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2437	5 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	62,80	62,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	62,80	48,50
				Material and Installation w/o Profit (TRY)	111,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**139,13**	

Item No	Analysis Name					UoM
35.500.2438	**6 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2438	6 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	74,80	74,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	74,80	51,00
				Material and Installation w/o Profit (TRY)	125,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**157,25**	

Item No	Analysis Name					UoM
35.500.2439	**7 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2439	7 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	83,30	83,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	83,30	53,50
				Material and Installation w/o Profit (TRY)	136,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**171,00**	

Item No	Analysis Name					UoM
35.500.2440	**8 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2440	8 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	96,30	96,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	96,30	53,50
				Material and Installation w/o Profit (TRY)	149,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**187,25**	

Item No	Analysis Name					UoM
35.500.2441	**10 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2441	10 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	115,40	115,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	115,40	59,50
				Material and Installation w/o Profit (TRY)	174,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**218,63**	

Item No	Analysis Name					UoM
35.500.2442	**12 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2442	12 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	142,40	142,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	142,40	59,50
				Material and Installation w/o Profit (TRY)	201,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**252,38**	

Item No	Analysis Name					UoM
35.500.2443	**14 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2443	14 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	147,40	147,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	147,40	62,00
				Material and Installation w/o Profit (TRY)	209,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**261,75**	

Item No	Analysis Name					UoM
35.500.2444	**16 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2444	16 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	158,40	158,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	158,40	68,00
				Material and Installation w/o Profit (TRY)	226,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**283,00**	

Item No	Analysis Name					UoM
35.500.2445	**18 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2445	18 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	184,40	184,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	184,40	68,00
				Material and Installation w/o Profit (TRY)	252,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**315,50**	

Item No	Analysis Name					UoM
35.500.2446	**20 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2446	20 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	212,40	212,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			212,40	74,00
		Material and Installation w/o Profit (TRY)			286,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**92,50**	
		Unit Price (TRY)			**358,00**	

Item No	Analysis Name					UoM
35.500.2447	**25 x 2 x 0.75 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2447	25 x 2 x 0.75 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	279,40	279,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			279,40	74,00
		Material and Installation w/o Profit (TRY)			353,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**92,50**	
		Unit Price (TRY)			**441,75**	

Item No	Analysis Name					UoM
35.500.2448	**2 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2448	2 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	36,30	36,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	36,30	42,50
				Material and Installation w/o Profit (TRY)	78,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**98,50**	

Item No	Analysis Name					UoM
35.500.2449	**3 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2449	3 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	52,30	52,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,30	45,00
				Material and Installation w/o Profit (TRY)	97,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**121,63**	

Item No	Analysis Name					UoM
35.500.2450	**4 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2450	4 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	64,30	64,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	64,30	48,50
				Material and Installation w/o Profit (TRY)	112,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**141,00**	

Item No	Analysis Name					UoM
35.500.2451	**5 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2451	5 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	77,80	77,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	77,80	51,00
				Material and Installation w/o Profit (TRY)	128,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**161,00**	

Item No	Analysis Name					UoM
35.500.2452	**6 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2452	6 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	93,30	93,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	93,30	53,50
				Material and Installation w/o Profit (TRY)	146,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**183,50**	

Item No	Analysis Name					UoM
35.500.2453	**7 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2453	7 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	104,30	104,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	104,30	57,00
				Material and Installation w/o Profit (TRY)	161,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**201,63**	

Item No	Analysis Name					UoM
35.500.2454	**8 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2454	8 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	118,30	118,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	118,30	59,50
				Material and Installation w/o Profit (TRY)	177,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**222,25**	

Item No	Analysis Name					UoM
35.500.2455	**10 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2455	10 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	134,40	134,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	134,40	62,00
				Material and Installation w/o Profit (TRY)	196,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**245,50**	

Item No	Analysis Name					UoM
35.500.2456	**12 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2456	12 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	177,40	177,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	177,40	65,50
				Material and Installation w/o Profit (TRY)	242,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**303,63**	

Item No	Analysis Name					UoM
35.500.2457	**14 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2457	14 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	193,40	193,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	193,40	68,00
				Material and Installation w/o Profit (TRY)	261,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**326,75**	

Item No	Analysis Name					UoM
35.500.2458	**16 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2458	16 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	207,40	207,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	207,40	70,50
				Material and Installation w/o Profit (TRY)	277,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**347,38**	

Item No	Analysis Name					UoM
35.500.2459	**18 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2459	18 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	234,40	234,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	234,40	74,00
				Material and Installation w/o Profit (TRY)	308,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**385,50**	

Item No	Analysis Name					UoM
35.500.2460	**20 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2460	20 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	295,40	295,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	295,40	76,50
				Material and Installation w/o Profit (TRY)	371,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**464,88**	

Item No	Analysis Name					UoM
35.500.2461	**25 x 2 x 1.00 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2461	25 x 2 x 1.00 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	400,40	400,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	400,40	79,00
				Material and Installation w/o Profit (TRY)	479,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**599,25**	

Item No	Analysis Name					UoM
35.500.2462	**2 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2462	2 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	46,30	46,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	46,30	45,00
				Material and Installation w/o Profit (TRY)	91,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**114,13**	

Item No	Analysis Name					UoM
35.500.2463	**3 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2463	3 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	65,30	65,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	65,30	48,50
				Material and Installation w/o Profit (TRY)	113,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**142,25**	

Item No	Analysis Name					UoM
35.500.2464	**4 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2464	4 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	83,30	83,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	83,30	51,00
				Material and Installation w/o Profit (TRY)	134,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**167,88**	

Item No	Analysis Name					UoM
35.500.2465	**5 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2465	5 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	103,30	103,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	103,30	53,50
				Material and Installation w/o Profit (TRY)	156,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**196,00**	

Item No	Analysis Name					UoM
35.500.2466	**6 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2466	6 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	122,30	122,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	122,30	57,00
				Material and Installation w/o Profit (TRY)	179,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**224,13**	

Item No	Analysis Name					UoM
35.500.2467	**7 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2467	7 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	137,30	137,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	137,30	59,50
				Material and Installation w/o Profit (TRY)	196,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**246,00**	

Item No	Analysis Name					UoM
35.500.2468	**8 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2468	8 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	156,30	156,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	156,30	59,50
				Material and Installation w/o Profit (TRY)	215,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**269,75**	

Item No	Analysis Name					UoM
35.500.2469	**10 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2469	10 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	199,40	199,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	199,40	68,00
				Material and Installation w/o Profit (TRY)	267,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**334,25**	

Item No	Analysis Name					UoM
35.500.2470	**12 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2470	12 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	240,40	240,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	240,40	68,00
				Material and Installation w/o Profit (TRY)	308,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**385,50**	

Item No	Analysis Name					UoM
35.500.2471	**14 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2471	14 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	249,40	249,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	249,40	70,50
				Material and Installation w/o Profit (TRY)	319,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**399,88**	

Item No	Analysis Name					UoM
35.500.2472	**16 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2472	16 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	288,40	288,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	288,40	76,50
				Material and Installation w/o Profit (TRY)	364,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**456,13**	

Item No	Analysis Name					UoM
35.500.2473	**18 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2473	18 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	325,40	325,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	325,40	79,00
				Material and Installation w/o Profit (TRY)	404,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**505,50**	

Item No	Analysis Name					UoM
35.500.2474	**20 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2474	20 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	392,40	392,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	392,40	82,50
				Material and Installation w/o Profit (TRY)	474,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**593,63**	

Item No	Analysis Name					UoM
35.500.2475	**25 x 2 x 1.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2475	25 x 2 x 1.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	595,40	595,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	595,40	85,00
				Material and Installation w/o Profit (TRY)	680,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**850,50**	

Item No	Analysis Name					UoM
35.500.2476	**2 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2476	2 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	67,30	67,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	67,30	51,00
				Material and Installation w/o Profit (TRY)	118,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**147,88**	

Item No	Analysis Name					UoM
35.500.2477	**3 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2477	3 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	98,30	98,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	98,30	53,50
				Material and Installation w/o Profit (TRY)	151,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**189,75**	

Item No	Analysis Name					UoM
35.500.2478	**4 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2478	4 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	129,30	129,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	129,30	59,50
				Material and Installation w/o Profit (TRY)	188,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**236,00**	

Item No	Analysis Name					UoM
35.500.2479	**5 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2479	5 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	156,30	156,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	156,30	62,00
				Material and Installation w/o Profit (TRY)	218,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**272,88**	

Item No	Analysis Name					UoM
35.500.2480	**6 x 2 x 2.50mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2480	6 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	186,30	186,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	186,30	68,00
				Material and Installation w/o Profit (TRY)	254,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**317,88**	

Item No	Analysis Name					UoM
35.500.2481	**7 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2481	7 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	212,30	212,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	212,30	68,00
				Material and Installation w/o Profit (TRY)	280,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**350,38**	

Item No	Analysis Name					UoM
35.500.2482	**8 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2482	8 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	244,30	244,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	244,30	70,50
				Material and Installation w/o Profit (TRY)	314,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**393,50**	

Item No	Analysis Name					UoM
35.500.2483	**10 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2483	10 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	298,40	298,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	298,40	76,50
				Material and Installation w/o Profit (TRY)	374,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**468,63**	

Item No	Analysis Name					UoM
35.500.2484	**12 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2484	12 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	372,40	372,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	372,40	82,50
				Material and Installation w/o Profit (TRY)	454,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**568,63**	

Item No	Analysis Name					UoM
35.500.2485	**14 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2485	14 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	394,40	394,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	394,40	85,00
				Material and Installation w/o Profit (TRY)	479,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**599,25**	

Item No	Analysis Name					UoM
35.500.2486	**16 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2486	16 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	466,40	466,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	466,40	91,00
				Material and Installation w/o Profit (TRY)	557,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**113,75**	
				Unit Price (TRY)	**696,75**	

Item No	Analysis Name					UoM
35.500.2487	**18 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2487	18 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	614,40	614,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	614,40	93,50
				Material and Installation w/o Profit (TRY)	707,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**884,88**	

Item No	Analysis Name					UoM
35.500.2488	**20 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2488	20 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	644,40	644,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	644,40	102,00
				Material and Installation w/o Profit (TRY)	746,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**933,00**	

Item No	Analysis Name					UoM
35.500.2489	**25 x 2 x 2.50 mm² / LIY(St)CY-TP signal cables / LIYCY, LIYC2Y or LIY(St)CY Type Instrumentation, signal and controller cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.500.2489	25 x 2 x 2.50 mm² / L LIY(St)CY-TP signal cable / LIYCY, LIYC2Y or LIY(St)CY-TP Type Instrumentation, signal and controller cables (Market price)	m	1	693,40	693,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	693,40	102,00
				Material and Installation w/o Profit (TRY)	795,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**127,50**	
				Unit Price (TRY)	**994,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1001	**RG 6AU 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1001	RG 6AU 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	40,93	40,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	40,93	36,50
				Material and Installation w/o Profit (TRY)	77,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**96,79**	

Item No	Analysis Name					UoM
35.505.1002	**RG 11 A/U 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1002	RG 11 A/U 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	33,37	33,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	33,37	42,50
				Material and Installation w/o Profit (TRY)	75,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**94,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1003	**RG 59 B/U 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1003	RG 59 B/U 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	14,36	14,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,36	36,50
				Material and Installation w/o Profit (TRY)	50,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**63,58**	

Item No	Analysis Name					UoM
35.505.1004	**RG 216 U 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1004	RG 216 U 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	47,95	47,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	47,95	25,50
				Material and Installation w/o Profit (TRY)	73,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**91,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1005	**RF 75-7-1 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1005	RF 75-7-1 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	29,59	29,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	29,59	25,50
				Material and Installation w/o Profit (TRY)	55,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**68,86**	

Item No	Analysis Name					UoM
35.505.1006	**RF 75-7-3 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1006	RF 75-7-3 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	47,95	47,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	47,95	25,50
				Material and Installation w/o Profit (TRY)	73,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**91,81**	

Item No	Analysis Name					UoM
35.505.1007	**RG 8A/U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1007	RG 8A/U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	38,23	38,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	38,23	36,50
				Material and Installation w/o Profit (TRY)	74,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**93,41**	

Item No	Analysis Name					UoM
35.505.1008	**RG 58 A/U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1008	RG 58 A/U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	9,94	9,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	9,94	31,50
				Material and Installation w/o Profit (TRY)	41,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**51,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1009	**RG 58 C/U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1009	RG 58 C/U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	15,01	15,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	15,01	31,50
				Material and Installation w/o Profit (TRY)	46,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**58,14**	

Item No	Analysis Name					UoM
35.505.1010	**RG 58-U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1010	RG 58-U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	13,50	13,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,50	31,50
				Material and Installation w/o Profit (TRY)	45,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**56,25**	

Item No	Analysis Name					UoM
35.505.1011	**RG 174-U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1011	RG 174-U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	9,94	9,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	9,94	25,50
				Material and Installation w/o Profit (TRY)	35,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**44,30**	

Item No	Analysis Name					UoM
35.505.1012	**RG 212 -U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1012	RG 212 -U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	94,39	94,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	94,39	25,50
				Material and Installation w/o Profit (TRY)	119,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**149,86**	

Item No	Analysis Name					UoM
35.505.1013	**RG 213-U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1013	RG 213-U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	55,51	55,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	55,51	45,00
				Material and Installation w/o Profit (TRY)	100,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**125,64**	

Item No	Analysis Name					UoM
35.505.1014	**RG 214-U 50 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1014	RG 214-U 50 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	159,19	159,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	159,19	25,50
				Material and Installation w/o Profit (TRY)	184,69	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**230,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1015	**RG 59-U-4 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1015	RG 59-U-4 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	13,18	13,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,18	34,00
				Material and Installation w/o Profit (TRY)	47,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**58,98**	

Item No	Analysis Name					UoM
35.505.1016	**RG 59-U-6 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1016	RG 59-U-6 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	14,36	14,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	14,36	25,50
				Material and Installation w/o Profit (TRY)	39,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**49,83**	

Item No	Analysis Name					UoM
35.505.1017	**RG 6/U-4 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1017	RG 6/U-4 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	14,36	14,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	14,36	25,50
				Material and Installation w/o Profit (TRY)	39,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**49,83**	

Item No	Analysis Name					UoM
35.505.1018	**RG 6/U-4P 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1018	RG 6/U-4P 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	16,96	16,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	16,96	25,50
				Material and Installation w/o Profit (TRY)	42,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**53,08**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1019	**RG 6/U-4A 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1019	RG 6/U-4A 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	26,35	26,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	26,35	25,50
				Material and Installation w/o Profit (TRY)	51,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**64,81**	

Item No	Analysis Name					UoM
35.505.1020	**RG 6/U-6 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1020	RG 6/U-6 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	18,14	18,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	18,14	34,00
				Material and Installation w/o Profit (TRY)	52,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**65,17**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1021	**RG 6/U-6P 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1021	RG 6/U-6P 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	18,14	18,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	18,14	25,50
				Material and Installation w/o Profit (TRY)	43,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**54,55**	

Item No	Analysis Name					UoM
35.505.1022	**RG 6/U-6A 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1022	RG 6/U-6A 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	33,37	33,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	33,37	25,50
				Material and Installation w/o Profit (TRY)	58,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**73,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.1023	**RG 11/U-4 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1023	RG 11/U-4 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	33,37	33,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	33,37	45,00
				Material and Installation w/o Profit (TRY)	78,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**97,96**	

Item No	Analysis Name					UoM
35.505.1024	**RG 11/U-4P 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1024	RG 11/U-4P 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	33,37	33,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	33,37	25,50
				Material and Installation w/o Profit (TRY)	58,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**73,59**	

Item No	Analysis Name					UoM
35.505.1025	**RG 11/U-4A 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1025	RG 11/U-4A 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	38,23	38,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	38,23	25,50
				Material and Installation w/o Profit (TRY)	63,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**79,66**	

Item No	Analysis Name					UoM
35.505.1026	**RG 11/U-6 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1026	RG 11/U-6 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	34,45	34,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	34,45	45,00
				Material and Installation w/o Profit (TRY)	79,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**99,31**	

Item No	Analysis Name					UoM
35.505.1027	**RG 11/U-6 A 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1027	RG 11/U-6 A 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	50,65	50,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	50,65	25,50
				Material and Installation w/o Profit (TRY)	76,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**95,19**	

Item No	Analysis Name					UoM
35.505.1028	**RG 11/U-6P 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1028	RG 11/U-6P 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	35,53	35,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	35,53	25,50
				Material and Installation w/o Profit (TRY)	61,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**76,29**	

Item No	Analysis Name					UoM
35.505.1029	**HF 7537 75 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1029	HF 7537 75 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	8,86	8,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	8,86	25,50
				Material and Installation w/o Profit (TRY)	34,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**42,95**	

Item No	Analysis Name					UoM
35.505.1030	**RG 62 A/U 93/105 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1030	RG 62 A/U 93/105 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	13,50	13,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,50	34,00
				Material and Installation w/o Profit (TRY)	47,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**59,38**	

Item No	Analysis Name					UoM
35.505.1031	**RG 62 A/U-1 93/105 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1031	RG 62 A/U-1 93/105 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	16,96	16,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	16,96	25,50
				Material and Installation w/o Profit (TRY)	42,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**53,08**	

Item No	Analysis Name					UoM
35.505.1032	**RG 62 A/U-2 93/105 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1032	RG 62 A/U-2 93/105 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	13,50	13,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	13,50	25,50
				Material and Installation w/o Profit (TRY)	39,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**48,75**	

Item No	Analysis Name					UoM
35.505.1033	**RG 71 B/U 93/105 / Coaxial Cables TSEK-certified**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.1033	RG 71 B/U 93/105 / Coaxial Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	24,41	24,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,41	34,00
				Material and Installation w/o Profit (TRY)	58,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**73,01**	

Item No	Analysis Name					UoM
35.505.2010	**UTP CAT 5e Cable / Copper Data Cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.2010	U/UTP Cat 5e Cable / Copper Data Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	13,34	13,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,34	34,00
				Material and Installation w/o Profit (TRY)	47,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**59,18**	

Item No	Analysis Name					UoM
35.505.2020	**FTP CAT 5e Cable / Copper Data Cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.2020	F/UTP Cat 5e Cable / Copper Data Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	15,66	15,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	15,66	34,00
				Material and Installation w/o Profit (TRY)	49,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**62,07**	

Item No	Analysis Name					UoM
35.505.2030	**UTP CAT 6 Cable / Copper Data Cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.2030	U/UTP Cat 6 Cable / Copper Data Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	16,12	16,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	16,12	34,00
				Material and Installation w/o Profit (TRY)	50,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**62,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.2040	**FTP CAT 6 Cable / Copper Data Cables**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.2040	F/UTP Cat 6 Cable / Copper Data Cables / COAXIAL AND COPPER DATA CABLES (Market price)	m	1	20,42	20,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			20,42	34,00
		Material and Installation w/o Profit (TRY)			54,42	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**42,50**	
		Unit Price (TRY)			**68,03**	

Item No	Analysis Name					UoM
35.505.2100	**FTP CAT 6 Cable / Copper Data Cables**					**Quantity**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.2100	Cat Patch Cord Price Difference / Copper Data Cables / COAXIAL AND COPPER DATA CABLES (Market price)	Quantity	1	144,00	144,00	
		Total Excluding Profit (TRY)			144,00	
		Material and Installation w/o Profit (TRY)			144,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**180,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.6100	**UTP CAT 5e Flush-mounted Single Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6100	UTP CAT 5e Flush-mounted Single Socket (Market price)	Qty	1	127,30	127,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	127,30	177,00
				Material and Installation w/o Profit (TRY)	304,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**380,38**	

Item No	Analysis Name					UoM
35.505.6110	**UTP CAT 5e Flush-mounted Double Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6110	UTP CAT 5e Flush-mounted Double Socket (Market price)	Qty	1	150,30	150,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	150,30	177,00
				Material and Installation w/o Profit (TRY)	327,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**409,13**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.6120	**UTP CAT 5e Surface-mounted Single Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6120	UTP CAT 5e Surface-mounted Single Socket (Market price)	Qty	1	171,30	171,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	171,30	177,00
				Material and Installation w/o Profit (TRY)	348,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**435,38**	

Item No	Analysis Name					UoM
35.505.6130	**UTP CAT 5e Surface-mounted Double Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6130	UTP CAT 5e Surface-mounted Double Socket (Market price)	Qty	1	171,30	171,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	171,30	177,00
				Material and Installation w/o Profit (TRY)	348,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**435,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.6140	**FTP CAT 5e Surface-mounted Single Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6140	FTP CAT 5e Surface-mounted Single Socket (Market price)	Qty	1	171,30	171,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	171,30	177,00
				Material and Installation w/o Profit (TRY)	348,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**435,38**	

Item No	Analysis Name					UoM
35.505.6150	**FTP CAT 5e Surface-mounted Double Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6150	FTP CAT 5e Surface-mounted Double Socket (Market price)	Qty	1	171,30	171,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	171,30	177,00
				Material and Installation w/o Profit (TRY)	348,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**435,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.6160	**FTP CAT 5e Flush-mounted Single Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6160	FTP CAT 5e Flush-mounted Single Socket (Market price)	Qty	1	130,30	130,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	130,30	177,00
				Material and Installation w/o Profit (TRY)	307,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**384,13**	

Item No	Analysis Name					UoM
35.505.6170	**FTP CAT 5e Flush-mounted Double Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6170	FTP CAT 5e Flush-mounted Double Socket (Market price)	Qty	1	231,30	231,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	231,30	177,00
				Material and Installation w/o Profit (TRY)	408,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**510,38**	

Item No	Analysis Name					UoM
35.505.6180	**UTP CAT 6 Surface-mounted Single Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6180	UTP CAT 6 Surface-mounted Single Socket (Market price)	Qty	1	171,30	171,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	171,30	177,00
				Material and Installation w/o Profit (TRY)	348,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**435,38**	

Item No	Analysis Name					UoM
35.505.6190	**UTP CAT 6 Surface-mounted Double Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6190	UTP CAT 6 Surface-mounted Double Socket (Market price)	Qty	1	261,30	261,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	261,30	177,00
				Material and Installation w/o Profit (TRY)	438,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**547,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.6200	**UTP CAT 6 Flush-mounted Single Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6200	UTP CAT 6 Flush-mounted Single Socket (Market price)	Qty	1	147,30	147,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	147,30	177,00
				Material and Installation w/o Profit (TRY)	324,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**405,38**	

Item No	Analysis Name					UoM
35.505.6210	**UTP CAT 6 Flush-mounted Double Socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.6210	UTP CAT 6 Flush-mounted Double Socket (Market price)	Qty	1	271,30	271,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
				Total Excluding Profit (TRY)	271,30	177,00
				Material and Installation w/o Profit (TRY)	448,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221,25**	
				Unit Price (TRY)	**560,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.7101	**24-port / UTP CAT 5E Patch Panel**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.7101	24-port / Utp Cat5e Patch Panel (Market price)	Qty	1	1.464,19	1.464,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			1.464,19	958,75
		Material and Installation w/o Profit (TRY)			2.422,94	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**3.028,68**	

Item No	Analysis Name					UoM
35.505.7102	**48-port / UTP CAT 5E Patch Panel**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.7102	48-port / Utp Cat5e Patch Panel (Market price)	Qty	1	2.775,52	2.775,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			2.775,52	958,75
		Material and Installation w/o Profit (TRY)			3.734,27	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**4.667,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.7201	**24-port / FTP CAT 5E Patch Panel**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.7201	24-port / Ftp Cat5e Patch Panel (Market price)	Qty	1	2.393,60	2.393,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			2.393,60	958,75
		Material and Installation w/o Profit (TRY)			3.352,35	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**4.190,44**	

Item No	Analysis Name					UoM
35.505.7202	**48-port / FTP CAT 5E Patch Panel**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.7202	48-port / Ftp Cat5e Patch Panel (Market price)	Qty	1	3.110,37	3.110,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			3.110,37	958,75
		Material and Installation w/o Profit (TRY)			4.069,12	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**5.086,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.505.7301	**24-port / UTP CAT 6 Patch Panel**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.7301	24-port / UTP CAT 6 Patch Panel (Market price)	Qty	1	2.898,72	2.898,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			2.898,72	958,75
		Material and Installation w/o Profit (TRY)			3.857,47	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**4.821,84**	

Item No	Analysis Name					UoM
35.505.7302	**48-port / UTP CAT 6 Patch Panel**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.505.7302	48-port / Utp Cat6 Patch Panel (Market price)	Qty	1	6.010,40	6.010,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician’s helper	h	0,5	185,00		92,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			6.010,40	958,75
		Material and Installation w/o Profit (TRY)			6.969,15	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.198,44**	
		Unit Price (TRY)			**8.711,44**	

Item No	Analysis Name					UoM
35.510.1101	**Up to 1 pair (with ground) P.14 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4105	1x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	5,11	5,11	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			13,12	52,20
		Material and Installation w/o Profit (TRY)			65,32	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**65,25**	
		Unit Price (TRY)			**81,65**	

Item No	Analysis Name					UoM
35.510.1102	**Up to 2 pair (with ground) P.14 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4110	2x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	7,82	7,82	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			15,83	54,70
		Material and Installation w/o Profit (TRY)			70,53	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**68,38**	
		Unit Price (TRY)			**88,16**	

Item No	Analysis Name					UoM
35.510.1103	**Up to 4 pair (with ground) P.14 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4120	4x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	14,52	14,52	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			22,53	56,55
		Material and Installation w/o Profit (TRY)			79,08	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**70,69**	
		Unit Price (TRY)			**98,85**	

Item No	Analysis Name					UoM
35.510.1104	**Up to 6 pairs (with ground) P.18 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4125	6x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	21,96	21,96	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			29,97	59,05
		Material and Installation w/o Profit (TRY)			89,02	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**73,81**	
		Unit Price (TRY)			**111,27**	

Item No	Analysis Name					UoM
35.510.1105	**Up to 10 pairs (with ground) P.18 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4130	10x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	33,14	33,14	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	8,01	8,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			41,15	61,55
		Material and Installation w/o Profit (TRY)			102,70	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**76,94**	
		Unit Price (TRY)			**128,38**	

Item No	Analysis Name					UoM
35.510.1107	**Up to 20 pairs (with ground) P.26 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4135	20x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	67,05	67,05	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
		Total Excluding Profit (TRY)			81,66	77,90
		Material and Installation w/o Profit (TRY)			159,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**97,38**	
		Unit Price (TRY)			**199,45**	

Item No	Analysis Name					UoM
35.510.1108	**Up to 30 pairs (with ground) P.26 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4140	30x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	93,08	93,08	
30.160.6102	25-32 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	14,61	14,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
		Total Excluding Profit (TRY)			107,69	82,05
		Material and Installation w/o Profit (TRY)			189,74	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**102,56**	
		Unit Price (TRY)			**237,18**	

Item No	Analysis Name					UoM
35.510.1109	**Up to 50 pairs (with ground) P.37 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4145	50x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	148,54	148,54	
30.160.6103	40-50 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	26,11	26,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,10	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician’s helper	h	0,14	185,00		25,90
		Total Excluding Profit (TRY)			174,65	94,90
		Material and Installation w/o Profit (TRY)			269,55	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**118,63**	
		Unit Price (TRY)			**336,94**	

Item No	Analysis Name					UoM
35.510.1110	**Up to 100 pairs (with ground) P.37 / Trunk line installation within the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4150	100x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	298,92	298,92	
30.160.6103	40-50 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	1	26,11	26,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,24	250,00		60,00
10.100.1083	Master electrician’s helper	h	0,16	185,00		29,60
		Total Excluding Profit (TRY)			325,03	109,40
		Material and Installation w/o Profit (TRY)			434,43	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**136,75**	
		Unit Price (TRY)			**543,04**	

Item No	Analysis Name					UoM
35.510.1201	**Up to 2 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1201	Up to 2 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	16,33	16,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			16,33	40,00
		Material and Installation w/o Profit (TRY)			56,33	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**50,00**	
		Unit Price (TRY)			**70,41**	

Item No	Analysis Name					UoM
35.510.1202	**Up to 6 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1202	Up to 6 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	28,18	28,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	28,18	42,50
				Material and Installation w/o Profit (TRY)	70,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**88,35**	

Item No	Analysis Name					UoM
35.510.1203	**Up to 10 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1203	Up to 10 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	39,21	39,21	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,21	45,00
				Material and Installation w/o Profit (TRY)	84,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**105,26**	

Item No	Analysis Name					UoM
35.510.1204	**Up to 20 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1204	Up to 20 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	69,26	69,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	69,26	51,00
				Material and Installation w/o Profit (TRY)	120,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**150,33**	

Item No	Analysis Name					UoM
35.510.1205	**Up to 30 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1205	Up to 30 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	107,64	107,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	107,64	57,00
				Material and Installation w/o Profit (TRY)	164,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**205,80**	

Item No	Analysis Name					UoM
35.510.1206	**Up to 50 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1206	Up to 50 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	166,40	166,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	166,40	62,00
				Material and Installation w/o Profit (TRY)	228,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**285,50**	

Item No	Analysis Name					UoM
35.510.1207	**Up to 100 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1207	Up to 100 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	321,67	321,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	321,67	76,50
				Material and Installation w/o Profit (TRY)	398,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**497,71**	

Item No	Analysis Name					UoM
35.510.1208	**Up to 150 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1208	Up to 150 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	512,72	512,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			512,72	85,00
		Material and Installation w/o Profit (TRY)			597,72	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**106,25**	
		Unit Price (TRY)			**747,15**	

Item No	Analysis Name					UoM
35.510.1209	**Up to 200 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1209	Up to 200 pairs (with ground) / Trunk line installation outside the building (TS-3930) / Trunk Line Installation (TS-3930) (Market price)	m	1	607,88	607,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
		Total Excluding Profit (TRY)			607,88	96,00
		Material and Installation w/o Profit (TRY)			703,88	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**120,00**	
		Unit Price (TRY)			**879,85**	

Item No	Analysis Name					UoM
35.510.1301	**Up to 10 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1301	Up to 10 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	48,78	48,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,78	42,50
				Material and Installation w/o Profit (TRY)	91,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**114,10**	

Item No	Analysis Name					UoM
35.510.1302	**Up to 20 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1302	Up to 20 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	80,81	80,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	80,81	48,50
				Material and Installation w/o Profit (TRY)	129,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**161,64**	

Item No	Analysis Name					UoM
35.510.1303	**Up to 30 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1303	Up to 30 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	111,90	111,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	111,90	51,00
				Material and Installation w/o Profit (TRY)	162,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**203,63**	

Item No	Analysis Name					UoM
35.510.1304	**Up to 50 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1304	Up to 50 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	172,12	172,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	172,12	57,00
				Material and Installation w/o Profit (TRY)	229,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**286,40**	

Item No	Analysis Name					UoM
35.510.1305	**Up to 100 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1305	Up to 100 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	325,00	325,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	325,00	68,00
				Material and Installation w/o Profit (TRY)	393,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**491,25**	

Item No	Analysis Name					UoM
35.510.1306	**Up to 150 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1306	Up to 150 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	471,12	471,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	471,12	79,00
				Material and Installation w/o Profit (TRY)	550,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**687,65**	

Item No	Analysis Name					UoM
35.510.1307	**Up to 200 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1307	Up to 200 pairs (with ground line) / Exterior-type telephone cable with suspension wires and 0.5 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	623,48	623,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	623,48	85,00
				Material and Installation w/o Profit (TRY)	708,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**885,60**	

Item No	Analysis Name					UoM
35.510.1401	**Up to 10 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1401	Up to 10 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	107,02	107,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	107,02	51,00
				Material and Installation w/o Profit (TRY)	158,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**197,52**	

Item No	Analysis Name					UoM
35.510.1402	**Up to 20 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1402	Up to 20 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	181,69	181,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			181,69	62,00
		Material and Installation w/o Profit (TRY)			243,69	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**77,50**	
		Unit Price (TRY)			**304,61**	

Item No	Analysis Name					UoM
35.510.1403	**Up to 30 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1403	Up to 30 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	258,54	258,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			258,54	68,00
		Material and Installation w/o Profit (TRY)			326,54	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**85,00**	
		Unit Price (TRY)			**408,18**	

Item No	Analysis Name					UoM
35.510.1404	**Up to 50 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1404	Up to 50 pairs (with ground) / Exterior-type telephone cable with suspension wires and 0.9 mm diameter / Trunk Line Installation (TS-3930) (Market price)	m	1	415,48	415,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	415,48	79,00
				Material and Installation w/o Profit (TRY)	494,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**618,10**	

Item No	Analysis Name					UoM
35.510.1501	**Up to 10 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1501	Up to 10 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930) (Market price)	m	1	105,77	105,77	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	105,77	53,50
				Material and Installation w/o Profit (TRY)	159,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**199,09**	

Item No	Analysis Name					UoM
35.510.1502	**Up to 20 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1502	Up to 20 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930) (Market price)	m	1	197,18	197,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	197,18	68,00
				Material and Installation w/o Profit (TRY)	265,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**331,48**	

Item No	Analysis Name					UoM
35.510.1503	**Up to 30 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1503	Up to 30 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930) (Market price)	m	1	275,08	275,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	275,08	74,00
				Material and Installation w/o Profit (TRY)	349,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**436,35**	

Item No	Analysis Name					UoM
35.510.1504	**Up to 50 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1504	Up to 50 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930) (Market price)	m	1	469,04	469,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	469,04	85,00
				Material and Installation w/o Profit (TRY)	554,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**692,55**	

Item No	Analysis Name					UoM
35.510.1505	**Up to 100 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1505	Up to 100 pairs (with ground) / Trunk line installation outside the building / Trunk Line Installation (TS-3930) (Market price)	m	1	963,35	963,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	963,35	104,50
				Material and Installation w/o Profit (TRY)	1.067,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**130,63**	
				Unit Price (TRY)	**1.334,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.1601	**Up to 10 pairs / Telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1601	Up to 10 pairs / Telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	213,20	213,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			213,20	517,50
		Material and Installation w/o Profit (TRY)			730,70	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**913,38**	

Item No	Analysis Name					UoM
35.510.1602	**Up to 30 pairs / Telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1602	Up to 30 pairs / Telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	413,92	413,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			413,92	517,50
		Material and Installation w/o Profit (TRY)			931,42	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**1.164,28**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.1603	**Up to 50 pairs / Telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1603	Up to 50 pairs / Telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	534,56	534,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
		Total Excluding Profit (TRY)			534,56	735,00
		Material and Installation w/o Profit (TRY)			1.269,56	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**918,75**	
		Unit Price (TRY)			**1.586,95**	

Item No	Analysis Name					UoM
35.510.1604	**Up to 100 pairs / Telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1604	Up to 100 pairs / Telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	927,68	927,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
		Total Excluding Profit (TRY)			927,68	952,50
		Material and Installation w/o Profit (TRY)			1.880,18	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.190,63**	
		Unit Price (TRY)			**2.350,22**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.1605	**Up to 150 pairs / Telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1605	Up to 150 pairs / Telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	1.196,00	1.196,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,75	165,00		123,75
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
		Total Excluding Profit (TRY)			1.196,00	1.211,25
		Material and Installation w/o Profit (TRY)			2.407,25	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.514,06**	
		Unit Price (TRY)			**3.009,06**	

Item No	Analysis Name					UoM
35.510.1606	**Up to 200 pairs / Telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1606	Up to 200 pairs / Telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	1.424,80	1.424,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,75	165,00		123,75
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
		Total Excluding Profit (TRY)			1.424,80	1.428,75
		Material and Installation w/o Profit (TRY)			2.853,55	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.785,94**	
		Unit Price (TRY)			**3.566,94**	

Item No	Analysis Name					UoM
35.510.1701	**Up to 20 Pairs / Self-extinguishing plastic telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1701	Up to 20 Pairs / Self-extinguishing plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	621,60	621,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			621,60	517,50
		Material and Installation w/o Profit (TRY)			1.139,10	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**1.423,88**	

Item No	Analysis Name					UoM
35.510.1702	**Up to 30 Pairs / Self-extinguishing plastic telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1702	Up to 30 Pairs / Self-extinguishing plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	735,84	735,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			735,84	517,50
		Material and Installation w/o Profit (TRY)			1.253,34	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**646,88**	
		Unit Price (TRY)			**1.566,68**	

Item No	Analysis Name					UoM
35.510.1703	**Up to 50 Pairs / Self-extinguishing plastic telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1703	Up to 50 Pairs / Self-extinguishing plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	1.046,64	1.046,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
		Total Excluding Profit (TRY)			1.046,64	735,00
		Material and Installation w/o Profit (TRY)			1.781,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**918,75**	
		Unit Price (TRY)			**2.227,05**	

Item No	Analysis Name					UoM
35.510.1704	**Up to 100 Pairs / Self-extinguishing plastic telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1704	Up to 100 Pairs / Self-extinguishing plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	2.002,56	2.002,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
		Total Excluding Profit (TRY)			2.002,56	952,50
		Material and Installation w/o Profit (TRY)			2.955,06	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.190,63**	
		Unit Price (TRY)			**3.693,82**	

Item No	Analysis Name					UoM
35.510.1705	**Up to 150 Pairs / Self-extinguishing plastic telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1705	Up to 150 Pairs / Self-extinguishing plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	2.923,20	2.923,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,75	165,00		123,75
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.923,20	1.211,25
				Material and Installation w/o Profit (TRY)	4.134,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.514,06**	
				Unit Price (TRY)	**5.168,06**	

Item No	Analysis Name					UoM
35.510.1706	**Up to 200 Pairs / Self-extinguishing plastic telephone distribution panels**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1706	Up to 200 Pairs / Self-extinguishing plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	3.696,00	3.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,75	165,00		123,75
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.696,00	1.428,75
				Material and Installation w/o Profit (TRY)	5.124,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.785,94**	
				Unit Price (TRY)	**6.405,94**	

Item No	Analysis Name					UoM
35.510.1801	**Up to 30 Pairs / Weather-proof plastic distribution panels (TSE Certificate of Quality)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1801	Up to 30 pairs / Weather-proof plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	1.186,08	1.186,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.186,08	517,50
				Material and Installation w/o Profit (TRY)	1.703,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**2.129,47**	

Item No	Analysis Name					UoM
35.510.1802	**Up to 50 Pairs / Weather-proof plastic distribution panels (TSE Certificate of Quality)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1802	Up to 50 pairs / Weather-proof plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	1.500,24	1.500,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.500,24	735,00
				Material and Installation w/o Profit (TRY)	2.235,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**918,75**	
				Unit Price (TRY)	**2.794,05**	

Item No	Analysis Name					UoM
35.510.1803	**Up to 80 Pairs / Weather-proof plastic distribution panels (TSE Certificate of Quality)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1803	Up to 80 pairs / Weather-proof plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	2.170,56	2.170,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.170,56	952,50
				Material and Installation w/o Profit (TRY)	3.123,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**3.903,82**	

Item No	Analysis Name					UoM
35.510.1804	**Up to 100 Pairs / Weather-proof plastic distribution panels (TSE Certificate of Quality)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1804	Up to 100 pairs / Weather-proof plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	2.271,36	2.271,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.271,36	1.170,00
				Material and Installation w/o Profit (TRY)	3.441,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.462,50**	
				Unit Price (TRY)	**4.301,70**	

Item No	Analysis Name					UoM
35.510.1805	**Up to 150 Pairs / Weather-proof plastic distribution panels (TSE Certificate of Quality)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1805	Up to 150 pairs / Weather-proof plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	3.175,20	3.175,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,75	165,00		123,75
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.175,20	1.428,75
				Material and Installation w/o Profit (TRY)	4.603,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.785,94**	
				Unit Price (TRY)	**5.754,94**	

Item No	Analysis Name					UoM
35.510.1806	**Up to 200 Pairs / Weather-proof plastic distribution panels (TSE Certificate of Quality)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.1806	Up to 200 pairs / Weather-proof plastic telephone distribution panels / Trunk Line Installation (Market price)	Qty	1	4.132,80	4.132,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,75	165,00		123,75
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	4.132,80	1.428,75
				Material and Installation w/o Profit (TRY)	5.561,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.785,94**	
				Unit Price (TRY)	**6.951,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.1901	**Service type / Telephone device and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.510.1901	**Material Components** Service type / Telephone device and its installation / TRUNK LINE INSTALLATION (Market price)	Qty	1	166,08	166,08	
		Total Excluding Profit (TRY)			166,08	
		Material and Installation w/o Profit (TRY)			166,08	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**207,60**	

Item No	Analysis Name					UoM
35.510.1902	**Push-button, automatic type / Telephone device and its installation**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.510.1902	**Material Components** Push-button, automatic type / Telephone device and its installation / TRUNK LINE INSTALLATION (Market price)	Qty	1	762,24	762,24	
		Total Excluding Profit (TRY)			762,24	
		Material and Installation w/o Profit (TRY)			762,24	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**952,80**	

Item No	Analysis Name					UoM
35.510.2000	**Telephone wiring outlet line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4110	2x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	10	7,82	78,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
30.510.2300	Telephone plug - socket / Trunk Line Installation (Market price)	Qty	1	95,86	95,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,89	165,00		146,85
10.100.1081	Master electrician	h	1,82	250,00		455,00
10.100.1083	Master electrician’s helper	h	1,49	185,00		275,65
		Total Excluding Profit (TRY)			274,17	877,50
		Material and Installation w/o Profit (TRY)			1.151,67	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.096,88**	
		Unit Price (TRY)			**1.439,59**	

Item No	Analysis Name					UoM
35.510.2100	**Parallel telephone outlet line**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4110	2x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	5	7,82	39,10	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	5	8,01	40,05	
30.185.1250	Flush-mounted junction box / Separate Installation Parts (Market price)	Qty	1	20,01	20,01	
30.510.2300	Telephone plug - socket / Trunk Line Installation (Market price)	Qty	1	95,86	95,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,59	165,00		97,35
10.100.1081	Master electrician	h	1,24	250,00		310,00
10.100.1083	Master electrician’s helper	h	1,07	185,00		197,95
		Total Excluding Profit (TRY)			195,02	605,30
		Material and Installation w/o Profit (TRY)			800,32	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**756,63**	
		Unit Price (TRY)			**1.000,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.2200	**Weather-proof telephone outlet line.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4110	2x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	10	7,82	78,20	
30.160.6101	16-20 mm PVC pipe / HOLLOW PIPE INSTALLATION / PIPES AND FITTINGS (Market price)	m	10	8,01	80,10	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
30.510.2300	Telephone plug - socket / Trunk Line Installation (Market price)	Qty	1	95,86	95,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,89	165,00		146,85
10.100.1081	Master electrician	h	1,82	250,00		455,00
10.100.1083	Master electrician's helper	h	1,49	185,00		275,65
		Total Excluding Profit (TRY)			325,68	877,50
		Material and Installation w/o Profit (TRY)			1.203,18	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**1.096,88**	
		Unit Price (TRY)			**1.503,98**	

Item No	Analysis Name					UoM
35.510.2300	**Telephone plug - socket**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.2300	Telephone plug - socket / Trunk Line Installation (Market price)	Qty	1	95,86	95,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,15	165,00		24,75
10.100.1081	Master electrician	h	0,35	250,00		87,50
10.100.1083	Master electrician's helper	h	0,35	185,00		64,75
		Total Excluding Profit (TRY)			95,86	177,00
		Material and Installation w/o Profit (TRY)			272,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**221,25**	
		Unit Price (TRY)			**341,08**	

Item No	Analysis Name					UoM
35.510.3100						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5221	2x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	10	8,64	86,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
30.510.2300	Telephone plug - socket / Trunk Line Installation (Market price)	Qty	1	95,86	95,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,88	165,00		145,20
10.100.1081	Master electrician	h	1,81	250,00		452,50
10.100.1083	Master electrician’s helper	h	1,48	185,00		273,80
		Total Excluding Profit (TRY)			285,06	871,50
		Material and Installation w/o Profit (TRY)			1.156,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.089,38**	
		Unit Price (TRY)			**1.445,70**	

Item No	Analysis Name					UoM
35.510.3200						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5221	2x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	5	8,64	43,20	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	5	8,18	40,90	
30.185.1350	Flush-mounted junction box (HF) / Separate Installation Parts (Market price)	Qty	1	21,00	21,00	
30.510.2300	Telephone plug - socket / Trunk Line Installation (Market price)	Qty	1	95,86	95,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,59	165,00		97,35
10.100.1081	Master electrician	h	1,23	250,00		307,50
10.100.1083	Master electrician’s helper	h	1,07	185,00		197,95
		Total Excluding Profit (TRY)			200,96	602,80
		Material and Installation w/o Profit (TRY)			803,76	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**753,50**	
		Unit Price (TRY)			**1.004,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.3300						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5221	2x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	10	8,64	86,40	
30.160.6201	16-20 mm PE HFFR pipe / HALOGEN-FREE FLAME-RETARDANT PIPES / PIPES AND FITTINGS (Market price)	m	10	8,18	81,80	
30.185.1252	Weather-proof junction box / Separate Installation Parts (Market price)	Qty	1	71,52	71,52	
30.510.2300	Telephone plug - socket / Trunk Line Installation (Market price)	Qty	1	95,86	95,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,88	165,00		145,20
10.100.1081	Master electrician	h	1,81	250,00		452,50
10.100.1083	Master electrician's helper	h	1,48	185,00		273,80
				Total Excluding Profit (TRY)	335,58	871,50
				Material and Installation w/o Profit (TRY)	1.207,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.089,38**	
				Unit Price (TRY)	**1.508,85**	

Item No	Analysis Name					UoM
35.510.4105						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4105	1x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	5,11	5,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	5,11	25,50
				Material and Installation w/o Profit (TRY)	30,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**38,26**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4110						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4110	2x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	7,82	7,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
		Total Excluding Profit (TRY)			7,82	28,00
		Material and Installation w/o Profit (TRY)			35,82	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**35,00**	
		Unit Price (TRY)			**44,77**	

Item No	Analysis Name					UoM
35.510.4115						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4115	3x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	10,03	10,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			10,03	31,50
		Material and Installation w/o Profit (TRY)			41,53	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**39,38**	
		Unit Price (TRY)			**51,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4120						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4120	4x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	14,52	14,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,52	31,50
				Material and Installation w/o Profit (TRY)	46,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**57,52**	

Item No	Analysis Name					UoM
35.510.4125						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4125	6x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	21,96	21,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	21,96	34,00
				Material and Installation w/o Profit (TRY)	55,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**69,95**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4130						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4130	10x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	33,14	33,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			33,14	36,50
		Material and Installation w/o Profit (TRY)			69,64	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**45,63**	
		Unit Price (TRY)			**87,05**	

Item No	Analysis Name					UoM
35.510.4135						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4135	20x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	67,05	67,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			67,05	42,50
		Material and Installation w/o Profit (TRY)			109,55	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**53,13**	
		Unit Price (TRY)			**136,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4140						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4140	30x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	93,08	93,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	93,08	45,00
				Material and Installation w/o Profit (TRY)	138,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**172,60**	

Item No	Analysis Name					UoM
35.510.4145						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4145	50x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	148,54	148,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	148,54	51,00
				Material and Installation w/o Profit (TRY)	199,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**249,42**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4150						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4150	100x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	298,92	298,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	298,92	68,00
				Material and Installation w/o Profit (TRY)	366,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**458,65**	

Item No	Analysis Name					UoM
35.510.4155						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4155	200x2x0.5+0.5 / VBV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	593,07	593,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	593,07	85,00
				Material and Installation w/o Profit (TRY)	678,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**847,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4205						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4205	1x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	5,38	5,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	5,38	25,50
				Material and Installation w/o Profit (TRY)	30,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**38,60**	

Item No	Analysis Name					UoM
35.510.4210						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4210	2x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	8,16	8,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	8,16	28,00
				Material and Installation w/o Profit (TRY)	36,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**45,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4215						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4215	3x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	11,47	11,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			11,47	31,50
		Material and Installation w/o Profit (TRY)			42,97	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**39,38**	
		Unit Price (TRY)			**53,71**	

Item No	Analysis Name					UoM
35.510.4220						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4220	4x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	14,52	14,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			14,52	31,50
		Material and Installation w/o Profit (TRY)			46,02	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**39,38**	
		Unit Price (TRY)			**57,52**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4225						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4225	6x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	21,29	21,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	21,29	34,00
				Material and Installation w/o Profit (TRY)	55,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**69,11**	

Item No	Analysis Name					UoM
35.510.4230						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4230	10x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	34,22	34,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	34,22	36,50
				Material and Installation w/o Profit (TRY)	70,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**88,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4235						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4235	20x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	64,15	64,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	64,15	42,50
				Material and Installation w/o Profit (TRY)	106,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**133,31**	

Item No	Analysis Name					UoM
35.510.4240						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4240	30x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	93,71	93,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	93,71	45,00
				Material and Installation w/o Profit (TRY)	138,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**173,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.510.4245						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4245	50x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	155,05	155,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	155,05	51,00
				Material and Installation w/o Profit (TRY)	206,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**257,56**	

Item No	Analysis Name					UoM
35.510.4250						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4250	100x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	302,71	302,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	302,71	68,00
				Material and Installation w/o Profit (TRY)	370,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**463,39**	

Item No	Analysis Name					UoM
35.510.4255						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.510.4255	200x2x0.5+0.5 / PDV Internal Telephone Cable / TRUNK LINE INSTALLATION (Market price)	m	1	593,07	593,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	593,07	85,00
				Material and Installation w/o Profit (TRY)	678,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**847,59**	

Item No	Analysis Name					UoM
35.515.1001	**1 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1001	1 x 2 x 0.8 + 0.8 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	13,06	13,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,06	34,00
				Material and Installation w/o Profit (TRY)	47,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**58,83**	

Item No	Analysis Name					UoM
35.515.1002	**2 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1002	2 x 2 x 0.8 + 0.8 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	20,54	20,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,54	34,00
				Material and Installation w/o Profit (TRY)	54,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**68,17**	

Item No	Analysis Name					UoM
35.515.1003	**3 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1003	3 x 2 x 0.8 + 0.8 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	27,74	27,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	27,74	40,00
				Material and Installation w/o Profit (TRY)	67,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**84,67**	

Item No	Analysis Name					UoM
35.515.1004	**4 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1004	4 x 2 x 0.8 + 0.8 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	37,67	37,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	37,67	40,00
				Material and Installation w/o Profit (TRY)	77,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**97,09**	

Item No	Analysis Name					UoM
35.515.1005 ae	**5 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1005	5 x 2 x 0.8 + 0.8 mm²	m	1	54,81	54,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	54,81	42,50
				Material and Installation w/o Profit (TRY)	97,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**121,64**	

Item No	Analysis Name					UoM
35.515.1006 ae	**6 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1006	6 x 2 x 0.8 + 0.8 mm²	m	1	67,73	67,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	67,73	42,50
				Material and Installation w/o Profit (TRY)	110,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**137,79**	

Item No	Analysis Name					UoM
35.515.1007 ae	**8 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1007	8 x 2 x 0.8 + 0.8 mm²	m	1	87,45	87,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	87,45	45,00
				Material and Installation w/o Profit (TRY)	132,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**165,56**	

Item No	Analysis Name					UoM
35.515.1008 ae	**10 x 2 x 0.8 + 0.8 mm² / J-Y (St) Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1008	10 x 2 x 0.8 + 0.8 mm²	m	1	118,73	118,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	118,73	51,00
				Material and Installation w/o Profit (TRY)	169,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**212,16**	

Item No	Analysis Name					UoM
35.515.1009	**1 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1009	1 x 2 x 1 + 1 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	19,04	19,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,04	34,00
				Material and Installation w/o Profit (TRY)	53,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**66,30**	

Item No	Analysis Name					UoM
35.515.1010	**2 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1010	2 x 2 x 1 + 1 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	30,19	30,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	30,19	40,00
				Material and Installation w/o Profit (TRY)	70,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**87,74**	

Item No	Analysis Name					UoM
35.515.1011	**3 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1011	3 x 2 x 1 + 1 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	41,75	41,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,75	42,50
				Material and Installation w/o Profit (TRY)	84,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**105,31**	

Item No	Analysis Name					UoM
35.515.1012	**4 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1012	4 x 2 x 1 + 1 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	53,45	53,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	53,45	48,50
				Material and Installation w/o Profit (TRY)	101,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**127,44**	

Item No	Analysis Name					UoM
35.515.1013 ae	**5 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1013	5 x 2 x 1 + 1 mm²	m	1	68,41	68,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	68,41	51,00
				Material and Installation w/o Profit (TRY)	119,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**149,26**	

Item No	Analysis Name					UoM
35.515.1014 ae	**6 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1014	6 x 2 x 1 + 1 mm²	m	1	99,69	99,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
		Total Excluding Profit (TRY)			99,69	51,00
		Material and Installation w/o Profit (TRY)			150,69	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**63,75**	
		Unit Price (TRY)			**188,36**	

Item No	Analysis Name					UoM
35.515.1015 ae	**8 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1015	8 x 2 x 1 + 1 mm²	m	1	132,33	132,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			132,33	57,00
		Material and Installation w/o Profit (TRY)			189,33	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**71,25**	
		Unit Price (TRY)			**236,66**	

Item No	Analysis Name					UoM
35.515.1016 ae	**10 x 2 x 1 + 1 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1016	10 x 2 x 1 + 1 mm²	m	1	167,69	167,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			167,69	59,50
		Material and Installation w/o Profit (TRY)			227,19	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**74,38**	
		Unit Price (TRY)			**283,99**	

Item No	Analysis Name					UoM
35.515.1017	**1 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1017	1 x 2 x 1.5 + 1.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	31,96	31,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			31,96	40,00
		Material and Installation w/o Profit (TRY)			71,96	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**50,00**	
		Unit Price (TRY)			**89,95**	

Item No	Analysis Name					UoM
35.515.1018	**2 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1018	2 x 2 x 1.5 + 1.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	52,09	52,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	52,09	34,00
				Material and Installation w/o Profit (TRY)	86,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**107,61**	

Item No	Analysis Name					UoM
35.515.1019	**3 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1019	3 x 2 x 1.5 + 1.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	71,81	71,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	71,81	51,00
				Material and Installation w/o Profit (TRY)	122,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**153,51**	

Item No	Analysis Name					UoM
35.515.1020	**4 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1020	4 x 2 x 1.5 + 1.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	91,53	91,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	91,53	53,50
				Material and Installation w/o Profit (TRY)	145,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**181,29**	

Item No	Analysis Name					UoM
35.515.1021 ae	**5 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1021	5 x 2 x 1.5 + 1.5 mm².	m	1	133,69	133,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	133,69	57,00
				Material and Installation w/o Profit (TRY)	190,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**238,36**	

Item No	Analysis Name					UoM
35.515.1022 ae	**6 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1022	6 x 2 x 1.5 + 1.5 mm²	m	1	163,61	163,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			163,61	59,50
		Material and Installation w/o Profit (TRY)			223,11	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**74,38**	
		Unit Price (TRY)			**278,89**	

Item No	Analysis Name					UoM
35.515.1023 ae	**8 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1023	8 x 2 x 1.5 + 1.5 mm²	m	1	209,85	209,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			209,85	68,00
		Material and Installation w/o Profit (TRY)			277,85	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**85,00**	
		Unit Price (TRY)			**347,31**	

Item No	Analysis Name					UoM
35.515.1024 ae	**10 x 2 x 1.5 + 1.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1024	10 x 2 x 1.5 + 1.5 mm²	m	1	262,89	262,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			262,89	70,50
		Material and Installation w/o Profit (TRY)			333,39	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**88,13**	
		Unit Price (TRY)			**416,74**	

Item No	Analysis Name					UoM
35.515.1025	**1 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1025	1 x 2 x 2.5 + 2.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	52,09	52,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
		Total Excluding Profit (TRY)			52,09	42,50
		Material and Installation w/o Profit (TRY)			94,59	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**53,13**	
		Unit Price (TRY)			**118,24**	

Item No	Analysis Name					UoM
35.515.1026	**2 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1026	2 x 2 x 2.5 + 2.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	84,05	84,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	84,05	34,00
				Material and Installation w/o Profit (TRY)	118,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**147,56**	

Item No	Analysis Name					UoM
35.515.1027	**3 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1027	3 x 2 x 2.5 + 2.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	117,37	117,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	117,37	59,50
				Material and Installation w/o Profit (TRY)	176,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**221,09**	

Item No	Analysis Name					UoM
35.515.1028	**4 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1028	4 x 2 x 2.5 + 2.5 mm² / JH(St)H HALOGEN-FREE FIRE ALARM CABLES / HALOGEN-FREE CABLES (Market price)	m	1	154,09	154,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
		Total Excluding Profit (TRY)			154,09	59,50
		Material and Installation w/o Profit (TRY)			213,59	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**74,38**	
		Unit Price (TRY)			**266,99**	

Item No	Analysis Name					UoM
35.515.1029 ae	**5 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1029	5 x 2 x 2.5 + 2.5 mm²	m	1	222,09	222,09	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			222,09	65,50
		Material and Installation w/o Profit (TRY)			287,59	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**81,88**	
		Unit Price (TRY)			**359,49**	

Item No	Analysis Name					UoM
35.515.1030 ae	**6 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1030	6 x 2 x 2.5 + 2.5 mm²	m	1	268,33	268,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			268,33	70,50
		Material and Installation w/o Profit (TRY)			338,83	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**88,13**	
		Unit Price (TRY)			**423,54**	

Item No	Analysis Name					UoM
35.515.1031 ae	**8 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1031	8 x 2 x 2.5 + 2.5 mm²	m	1	400,25	400,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			400,25	82,50
		Material and Installation w/o Profit (TRY)			482,75	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**103,13**	
		Unit Price (TRY)			**603,44**	

Item No	Analysis Name					UoM
35.515.1032 ae	**10 x 2 x 2.5 + 2.5 mm² / Jh(St)H Halogen-free Fire Alarm Cables (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.1032	10 x 2 x 2.5 + 2.5 mm²	m	1	434,25	434,25	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	434,25	85,00
				Material and Installation w/o Profit (TRY)	519,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**649,06**	

Item No	Analysis Name					UoM
35.515.2001 ae	**2 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2001 ae	2 x 0.14 mm²	m	1	4,43	4,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician's helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	4,43	25,50
				Material and Installation w/o Profit (TRY)	29,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**37,41**	

Item No	Analysis Name					UoM
35.515.2002 ae	**3 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2002 ae	3 x 0.14 mm²	m	1	6,70	6,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	6,70	25,50
				Material and Installation w/o Profit (TRY)	32,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**40,25**	

Item No	Analysis Name					UoM
35.515.2003 ae	**4 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2003 ae	4 x 0.14 mm²	m	1	8,53	8,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	8,53	25,50
				Material and Installation w/o Profit (TRY)	34,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**42,54**	

Item No	Analysis Name					UoM
35.515.2004 ae	**5 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2004 ae	5 x 0.14 mm²	m	1	9,94	9,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	9,94	25,50
				Material and Installation w/o Profit (TRY)	35,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**44,30**	

Item No	Analysis Name					UoM
35.515.2005 ae	**6 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2005 ae	6 x 0.14 mm²	m	1	11,88	11,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	11,88	25,50
				Material and Installation w/o Profit (TRY)	37,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**46,73**	

Item No	Analysis Name					UoM
35.515.2006 ae	**7 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2006 ae	7 x 0.14 mm²	m	1	13,28	13,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	13,28	25,50
				Material and Installation w/o Profit (TRY)	38,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**48,48**	

Item No	Analysis Name					UoM
35.515.2007 ae	**8 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2007 ae	8 x 0.14 mm²	m	1	14,80	14,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	14,80	25,50
				Material and Installation w/o Profit (TRY)	40,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**50,38**	

Item No	Analysis Name					UoM
35.515.2008 ae	**9 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2008 ae	9 x 0.14 mm²	m	1	16,52	16,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	16,52	28,00
				Material and Installation w/o Profit (TRY)	44,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**55,65**	

Item No	Analysis Name					UoM
35.515.2009 ae	**10 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2009 ae	10 x 0.14 mm²	m	1	17,82	17,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	17,82	28,00
				Material and Installation w/o Profit (TRY)	45,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**57,27**	

Item No	Analysis Name					UoM
35.515.2010 ae	**12 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2010 ae	12 x 0.14 mm²	m	1	20,74	20,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,74	31,50
				Material and Installation w/o Profit (TRY)	52,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**65,30**	

Item No	Analysis Name					UoM
35.515.2011 ae	**14 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2011 ae	14 x 0.14 mm²	m	1	24,08	24,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,08	31,50
				Material and Installation w/o Profit (TRY)	55,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**69,47**	

Item No	Analysis Name					UoM
35.515.2012 ae	**16 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2012 ae	16 x 0.14 mm²	m	1	27,00	27,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,00	31,50
				Material and Installation w/o Profit (TRY)	58,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**73,13**	

Item No	Analysis Name					UoM
35.515.2013 ae	**18 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2013 ae	18 x 0.14 mm²	m	1	30,13	30,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	30,13	31,50
				Material and Installation w/o Profit (TRY)	61,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**77,04**	

Item No	Analysis Name					UoM
35.515.2014 ae	**20 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2014 ae	20 x 0.14 mm²	m	1	33,05	33,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	33,05	34,00
				Material and Installation w/o Profit (TRY)	67,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**83,81**	

Item No	Analysis Name					UoM
35.515.2015 ae	**25 x 0.14 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2015 ae	25 x 0.14 mm²	m	1	41,36	41,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	41,36	34,00
				Material and Installation w/o Profit (TRY)	75,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**94,20**	

Item No	Analysis Name					UoM
35.515.2016 ae	**2 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2016 ae	2 x 0.25 mm²	m	1	7,67	7,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	7,67	28,00
				Material and Installation w/o Profit (TRY)	35,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**44,59**	

Item No	Analysis Name					UoM
35.515.2017 ae	**3 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2017 ae	3 x 0.25 mm²	m	1	10,15	10,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	10,15	28,00
				Material and Installation w/o Profit (TRY)	38,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**47,69**	

Item No	Analysis Name					UoM
35.515.2018 ae	**4 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2018 ae	4 x 0.25 mm²	m	1	12,42	12,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	12,42	31,50
				Material and Installation w/o Profit (TRY)	43,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**54,90**	

Item No	Analysis Name					UoM
35.515.2019 ae	**5 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2019 ae	5 x 0.25 mm²	m	1	15,23	15,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	15,23	31,50
				Material and Installation w/o Profit (TRY)	46,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**58,41**	

Item No	Analysis Name					UoM
35.515.2020 ae	**6 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2020 ae	6 x 0.25 mm²	m	1	18,36	18,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	18,36	31,50
				Material and Installation w/o Profit (TRY)	49,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**62,33**	

Item No	Analysis Name					UoM
35.515.2021 ae	**7 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2021 ae	7 x 0.25 mm²	m	1	20,41	20,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,41	34,00
				Material and Installation w/o Profit (TRY)	54,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**68,01**	

Item No	Analysis Name					UoM
35.515.2022 ae	**8 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2022 ae	8 x 0.25 mm²	m	1	23,00	23,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	23,00	34,00
				Material and Installation w/o Profit (TRY)	57,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**71,25**	

Item No	Analysis Name					UoM
35.515.2023 ae	**10 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2023 ae	10 x 0.25 mm²	m	1	27,76	27,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,76	34,00
				Material and Installation w/o Profit (TRY)	61,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**77,20**	

Item No	Analysis Name					UoM
35.515.2024 ae	**12 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2024 ae	12 x 0.25 mm²	m	1	32,94	32,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	32,94	34,00
				Material and Installation w/o Profit (TRY)	66,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**83,67**	

Item No	Analysis Name					UoM
35.515.2025 ae	**14 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2025 ae	14 x 0.25 mm²	m	1	38,02	38,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	38,02	36,50
				Material and Installation w/o Profit (TRY)	74,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**93,15**	

Item No	Analysis Name					UoM
35.515.2026 ae	**16 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2026 ae	16 x 0.25 mm²	m	1	42,98	42,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	42,98	36,50
				Material and Installation w/o Profit (TRY)	79,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**99,35**	

Item No	Analysis Name					UoM
35.515.2027 ae	**18 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2027 ae	18 x 0.25 mm²	m	1	48,38	48,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	48,38	36,50
				Material and Installation w/o Profit (TRY)	84,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**106,10**	

Item No	Analysis Name					UoM
35.515.2028 ae	**20 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2028 ae	20 x 0.25 mm²	m	1	53,78	53,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	53,78	40,00
				Material and Installation w/o Profit (TRY)	93,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**117,22**	

Item No	Analysis Name					UoM
35.515.2029 ae	**25 x 0.25 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2029 ae	25 x 0.25 mm²	m	1	66,74	66,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	66,74	40,00
				Material and Installation w/o Profit (TRY)	106,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**133,42**	

Item No	Analysis Name					UoM
35.515.2030 ae	**2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2030 ae	2 x 0 34 mm²	m	1	10,37	10,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	10,37	28,00
				Material and Installation w/o Profit (TRY)	38,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**47,96**	

Item No	Analysis Name					UoM
35.515.2031 ae	**3 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2031 ae	3 x 0.34 mm²	m	1	13,61	13,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,61	31,50
				Material and Installation w/o Profit (TRY)	45,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**56,39**	

Item No	Analysis Name					UoM
35.515.2032 ae	**4 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2032 ae	4 x 0.34 mm²	m	1	17,06	17,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,06	31,50
				Material and Installation w/o Profit (TRY)	48,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**60,70**	

Item No	Analysis Name					UoM
35.515.2033 ae	**5 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2033 ae	5 x 0.34 mm²	m	1	20,74	20,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,74	34,00
				Material and Installation w/o Profit (TRY)	54,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**68,42**	

Item No	Analysis Name					UoM
35.515.2034 ae	**6 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2034 ae	6 x 0.34 mm²	m	1	24,84	24,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,84	34,00
				Material and Installation w/o Profit (TRY)	58,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**73,55**	

Item No	Analysis Name					UoM
35.515.2035 ae	**7 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2035 ae	7 x 0.34 mm²	m	1	27,76	27,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,76	34,00
				Material and Installation w/o Profit (TRY)	61,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**77,20**	

Item No	Analysis Name					UoM
35.515.2036 ae	**8 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2036 ae	8 x 0.34 mm²	m	1	31,43	31,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	31,43	34,00
				Material and Installation w/o Profit (TRY)	65,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**81,79**	

Item No	Analysis Name					UoM
35.515.2037 ae	**10 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2037 ae	10 x 0.34 mm²	m	1	38,66	38,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	38,66	36,50
				Material and Installation w/o Profit (TRY)	75,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**93,95**	

Item No	Analysis Name					UoM
35.515.2038 ae	**12 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2038 ae	12 x 0.34 mm²	m	1	45,68	45,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	45,68	40,00
				Material and Installation w/o Profit (TRY)	85,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**107,10**	

Item No	Analysis Name					UoM
35.515.2039 ae	**14 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2039 ae	14 x 0.34 mm²	m	1	52,70	52,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,70	40,00
				Material and Installation w/o Profit (TRY)	92,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**115,88**	

Item No	Analysis Name					UoM
35.515.2040 ae	**16 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2040 ae	16 x 0.34 mm²	m	1	59,72	59,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	59,72	42,50
				Material and Installation w/o Profit (TRY)	102,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**127,78**	

Item No	Analysis Name					UoM
35.515.2041 ae	**18 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2041 ae	18 x 0.34 mm²	m	1	67,82	67,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	67,82	42,50
				Material and Installation w/o Profit (TRY)	110,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**137,90**	

Item No	Analysis Name					UoM
35.515.2042 ae	**20 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2042 ae	20 x 0.34 mm²	m	1	74,84	74,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	74,84	42,50
				Material and Installation w/o Profit (TRY)	117,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**146,68**	

Item No	Analysis Name					UoM
35.515.2043 ae	**25 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2043 ae	25 x 0.34 mm²	m	1	94,28	94,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	94,28	42,50
				Material and Installation w/o Profit (TRY)	136,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**170,97**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2044	**2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2044	2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	11,66	11,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	11,66	31,50
				Material and Installation w/o Profit (TRY)	43,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**53,95**	

Item No	Analysis Name					UoM
35.515.2045	**3 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2045	3 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	15,88	15,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	15,88	34,00
				Material and Installation w/o Profit (TRY)	49,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**62,35**	

Item No	Analysis Name					UoM
35.515.2046	**4 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2046	4 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	19,87	19,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,87	34,00
				Material and Installation w/o Profit (TRY)	53,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**67,34**	

Item No	Analysis Name					UoM
35.515.2047	**5 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2047	5 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	24,08	24,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,08	34,00
				Material and Installation w/o Profit (TRY)	58,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**72,60**	

Item No	Analysis Name					UoM
35.515.2048	**6 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2048	6 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	30,13	30,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	30,13	34,00
				Material and Installation w/o Profit (TRY)	64,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**80,16**	

Item No	Analysis Name					UoM
35.515.2049	**7 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2049	7 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	32,94	32,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	32,94	34,00
				Material and Installation w/o Profit (TRY)	66,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**83,67**	

Item No	Analysis Name					UoM
35.515.2050	**8 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2050	8 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	37,15	37,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	37,15	36,50
				Material and Installation w/o Profit (TRY)	73,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**92,06**	

Item No	Analysis Name					UoM
35.515.2051	**9 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2051	9 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	41,36	41,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,36	40,00
				Material and Installation w/o Profit (TRY)	81,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**101,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2052	**10 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2052	10 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	44,06	44,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	44,06	42,50
				Material and Installation w/o Profit (TRY)	86,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**108,20**	

Item No	Analysis Name					UoM
35.515.2053	**12 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2053	12 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	54,32	54,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	54,32	42,50
				Material and Installation w/o Profit (TRY)	96,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**121,02**	

Item No	Analysis Name					UoM
35.515.2054	**14 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2054	14 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	62,96	62,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	62,96	42,50
				Material and Installation w/o Profit (TRY)	105,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**131,83**	

Item No	Analysis Name					UoM
35.515.2055	**16 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2055	16 x 0.50 mm² / Lih(St)H Halogen-free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	71,60	71,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	71,60	42,50
				Material and Installation w/o Profit (TRY)	114,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**142,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2056	**18 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2056	18 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	79,70	79,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	79,70	45,00
				Material and Installation w/o Profit (TRY)	124,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**155,88**	

Item No	Analysis Name					UoM
35.515.2057	**20 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2057	20 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	88,88	88,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	88,88	45,00
				Material and Installation w/o Profit (TRY)	133,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**167,35**	

Item No	Analysis Name					UoM
35.515.2058	**25 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2058	25 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	112,64	112,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	112,64	48,50
				Material and Installation w/o Profit (TRY)	161,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**201,42**	

Item No	Analysis Name					UoM
35.515.2059	**2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2059	2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	14,90	14,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,90	34,00
				Material and Installation w/o Profit (TRY)	48,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**61,13**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2060	**3 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2060	3 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	20,63	20,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,63	34,00
				Material and Installation w/o Profit (TRY)	54,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**68,29**	

Item No	Analysis Name					UoM
35.515.2061	**4 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2061	4 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	26,14	26,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	26,14	34,00
				Material and Installation w/o Profit (TRY)	60,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**75,17**	

Item No	Analysis Name					UoM
35.515.2062	**5 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2062	5 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	31,86	31,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	31,86	34,00
				Material and Installation w/o Profit (TRY)	65,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**82,33**	

Item No	Analysis Name					UoM
35.515.2063	**6 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2063	6 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	38,66	38,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	38,66	36,50
				Material and Installation w/o Profit (TRY)	75,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**93,95**	

Item No	Analysis Name					UoM
35.515.2064	**7 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2064	7 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	44,06	44,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	44,06	36,50
				Material and Installation w/o Profit (TRY)	80,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**100,70**	

Item No	Analysis Name					UoM
35.515.2065	**8 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2065	8 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	50,00	50,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	50,00	42,50
				Material and Installation w/o Profit (TRY)	92,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**115,63**	

Item No	Analysis Name					UoM
35.515.2066	**9 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2066	9 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	55,40	55,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	55,40	42,50
				Material and Installation w/o Profit (TRY)	97,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**122,38**	

Item No	Analysis Name					UoM
35.515.2067	**10 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2067	10 x 0.75 mm² / Lih(St)H Halogen-free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	60,80	60,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	60,80	42,50
				Material and Installation w/o Profit (TRY)	103,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**129,13**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2068	**12 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2068	12 x 0.75 mm² / Lih(St)H Halogen-free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	72,14	72,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	72,14	42,50
				Material and Installation w/o Profit (TRY)	114,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**143,30**	

Item No	Analysis Name					UoM
35.515.2069	**14 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2069	14 x 0.75 mm² / Lih(St)H Halogen-free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	85,64	85,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	85,64	45,00
				Material and Installation w/o Profit (TRY)	130,64	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**163,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2070	**16 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2070	16 x 0.75 mm² / Lih(St)H Halogen-free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	97,52	97,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	97,52	48,50
				Material and Installation w/o Profit (TRY)	146,02	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**182,52**	

Item No	Analysis Name					UoM
35.515.2071	**18 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2071	18 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	109,40	109,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	109,40	51,00
				Material and Installation w/o Profit (TRY)	160,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**200,50**	

Item No	Analysis Name					UoM
35.515.2072	**20 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2072	20 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	121,28	121,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	121,28	51,00
				Material and Installation w/o Profit (TRY)	172,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**215,35**	

Item No	Analysis Name					UoM
35.515.2073	**25 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2073	25 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	151,52	151,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	151,52	51,00
				Material and Installation w/o Profit (TRY)	202,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**253,15**	

Item No	Analysis Name					UoM
35.515.2074	**2 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2074	2 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	21,92	21,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	21,92	34,00
				Material and Installation w/o Profit (TRY)	55,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**69,90**	

Item No	Analysis Name					UoM
35.515.2075	**3 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2075	3 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	29,05	29,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,05	34,00
				Material and Installation w/o Profit (TRY)	63,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**78,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2076	**4 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2076	4 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	36,61	36,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	36,61	34,00
				Material and Installation w/o Profit (TRY)	70,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**88,26**	

Item No	Analysis Name					UoM
35.515.2077	**5 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2077	5 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	44,71	44,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	44,71	36,50
				Material and Installation w/o Profit (TRY)	81,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**101,51**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2078	**6 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2078	6 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	53,89	53,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	53,89	40,00
				Material and Installation w/o Profit (TRY)	93,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**117,36**	

Item No	Analysis Name					UoM
35.515.2079	**7 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2079	7 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)) (Market price)	m	1	60,91	60,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	60,91	40,00
				Material and Installation w/o Profit (TRY)	100,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**126,14**	

Item No	Analysis Name					UoM
35.515.2080	**8 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2080	8 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	68,47	68,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	68,47	42,50
				Material and Installation w/o Profit (TRY)	110,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**138,71**	

Item No	Analysis Name					UoM
35.515.2081	**9 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2081	9 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	76,03	76,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	76,03	42,50
				Material and Installation w/o Profit (TRY)	118,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**148,16**	

Item No	Analysis Name					UoM
35.515.2082	**10 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2082	10 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	80,89	80,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	80,89	45,00
				Material and Installation w/o Profit (TRY)	125,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**157,36**	

Item No	Analysis Name					UoM
35.515.2083	**12 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2083	12 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	99,79	99,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	99,79	45,00
				Material and Installation w/o Profit (TRY)	144,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**180,99**	

Item No	Analysis Name					UoM
35.515.2084	**14 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2084	14 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	115,99	115,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	115,99	48,50
				Material and Installation w/o Profit (TRY)	164,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**205,61**	

Item No	Analysis Name					UoM
35.515.2085	**16 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2085	16 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	133,27	133,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	133,27	51,00
				Material and Installation w/o Profit (TRY)	184,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**230,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2086	**18 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2086	18 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	147,31	147,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	147,31	51,00
				Material and Installation w/o Profit (TRY)	198,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**247,89**	

Item No	Analysis Name					UoM
35.515.2087	**20 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2087	20 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	162,43	162,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	162,43	53,50
				Material and Installation w/o Profit (TRY)	215,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**269,91**	

Item No	Analysis Name					UoM
35.515.2088	**25 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2088	25 x 1.0 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	203,47	203,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	203,47	53,50
				Material and Installation w/o Profit (TRY)	256,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**321,21**	

Item No	Analysis Name					UoM
35.515.2089	**2 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2089	2 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	28,51	28,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	28,51	34,00
				Material and Installation w/o Profit (TRY)	62,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**78,14**	

Item No	Analysis Name					UoM
35.515.2090	**3 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2090	3 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	38,23	38,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	38,23	34,00
				Material and Installation w/o Profit (TRY)	72,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**90,29**	

Item No	Analysis Name					UoM
35.515.2091	**4 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2091	4 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	49,03	49,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	49,03	36,50
				Material and Installation w/o Profit (TRY)	85,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**106,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2092	**5 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2092	5 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	59,83	59,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	59,83	40,00
				Material and Installation w/o Profit (TRY)	99,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**124,79**	

Item No	Analysis Name					UoM
35.515.2093	**6 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2093	6 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	71,71	71,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	71,71	42,50
				Material and Installation w/o Profit (TRY)	114,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**142,76**	

Item No	Analysis Name					UoM
35.515.2094	**7 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2094	7 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	81,97	81,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	81,97	42,50
				Material and Installation w/o Profit (TRY)	124,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**155,59**	

Item No	Analysis Name					UoM
35.515.2095	**8 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2095	8 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	93,31	93,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	93,31	42,50
				Material and Installation w/o Profit (TRY)	135,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**169,76**	

Item No	Analysis Name					UoM
35.515.2096	**9 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2096	9 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	105,19	105,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	105,19	45,00
				Material and Installation w/o Profit (TRY)	150,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**187,74**	

Item No	Analysis Name					UoM
35.515.2097	**10 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2097	10 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	114,91	114,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	114,91	48,50
				Material and Installation w/o Profit (TRY)	163,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**204,26**	

Item No	Analysis Name					UoM
35.515.2098	**12 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2098	12 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	136,51	136,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	136,51	51,00
				Material and Installation w/o Profit (TRY)	187,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**234,39**	

Item No	Analysis Name					UoM
35.515.2099	**14 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2099	14 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	160,27	160,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	160,27	51,00
				Material and Installation w/o Profit (TRY)	211,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**264,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2100	**16 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2100	16 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	182,95	182,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	182,95	51,00
				Material and Installation w/o Profit (TRY)	233,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**292,44**	

Item No	Analysis Name					UoM
35.515.2101	**18 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2101	18 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	202,39	202,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	202,39	53,50
				Material and Installation w/o Profit (TRY)	255,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**319,86**	

Item No	Analysis Name					UoM
35.515.2102	**20 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2102	20 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	226,15	226,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	226,15	57,00
				Material and Installation w/o Profit (TRY)	283,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**353,94**	

Item No	Analysis Name					UoM
35.515.2103	**25 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2103	25 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	283,39	283,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	283,39	59,50
				Material and Installation w/o Profit (TRY)	342,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**428,61**	

Item No	Analysis Name					UoM
35.515.2104	**2 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2104	2 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	41,47	41,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,47	40,00
				Material and Installation w/o Profit (TRY)	81,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**101,84**	

Item No	Analysis Name					UoM
35.515.2105	**3 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2105	3 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	58,75	58,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	58,75	42,50
				Material and Installation w/o Profit (TRY)	101,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**126,56**	

Item No	Analysis Name					UoM
35.515.2106	**4 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2106	4 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	74,95	74,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	74,95	42,50
				Material and Installation w/o Profit (TRY)	117,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**146,81**	

Item No	Analysis Name					UoM
35.515.2107	**5 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2107	5 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	90,07	90,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	90,07	45,00
				Material and Installation w/o Profit (TRY)	135,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**168,84**	

Item No	Analysis Name					UoM
35.515.2108	**6 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2108	6 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	108,43	108,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	108,43	48,50
				Material and Installation w/o Profit (TRY)	156,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**196,16**	

Item No	Analysis Name					UoM
35.515.2109	**7 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2109	7 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	124,63	124,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	124,63	48,50
				Material and Installation w/o Profit (TRY)	173,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**216,41**	

Item No	Analysis Name					UoM
35.515.2110	**8 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2110	8 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	141,91	141,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	141,91	51,00
				Material and Installation w/o Profit (TRY)	192,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**241,14**	

Item No	Analysis Name					UoM
35.515.2111	**9 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2111	9 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	158,11	158,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	158,11	57,00
				Material and Installation w/o Profit (TRY)	215,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**268,89**	

Item No	Analysis Name					UoM
35.515.2112	**10 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2112	10 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	174,31	174,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	174,31	57,00
				Material and Installation w/o Profit (TRY)	231,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**289,14**	

Item No	Analysis Name					UoM
35.515.2113	**12 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2113	12 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	207,79	207,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	207,79	59,50
				Material and Installation w/o Profit (TRY)	267,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**334,11**	

Item No	Analysis Name					UoM
35.515.2114	**14 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2114	14 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	241,27	241,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	241,27	59,50
				Material and Installation w/o Profit (TRY)	300,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**375,96**	

Item No	Analysis Name					UoM
35.515.2115	**16 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2115	16 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	274,75	274,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	274,75	62,00
				Material and Installation w/o Profit (TRY)	336,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**420,94**	

Item No	Analysis Name					UoM
35.515.2116	**18 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2116	18 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	309,31	309,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	309,31	65,50
				Material and Installation w/o Profit (TRY)	374,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81,88**	
				Unit Price (TRY)	**468,51**	

Item No	Analysis Name					UoM
35.515.2117	**20 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2117	20 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	354,67	354,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	354,67	68,00
				Material and Installation w/o Profit (TRY)	422,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**528,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.2118	**25 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.2118	25 x 2.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815) (Market price)	m	1	441,07	441,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	441,07	74,00
				Material and Installation w/o Profit (TRY)	515,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**643,84**	

Item No	Analysis Name					UoM
35.515.3001	**2 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3001	2 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	11,66	11,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	11,66	34,00
				Material and Installation w/o Profit (TRY)	45,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**57,07**	

Item No	Analysis Name					UoM
35.515.3002	**3 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3002	3 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	16,85	16,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			16,85	34,00
		Material and Installation w/o Profit (TRY)			50,85	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**42,50**	
		Unit Price (TRY)			**63,56**	

Item No	Analysis Name					UoM
35.515.3003	**4 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3003	4 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	21,06	21,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
		Total Excluding Profit (TRY)			21,06	34,00
		Material and Installation w/o Profit (TRY)			55,06	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**42,50**	
		Unit Price (TRY)			**68,83**	

Item No	Analysis Name					UoM
35.515.3004	**5 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3004	5 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	25,27	25,27	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	25,27	36,50
				Material and Installation w/o Profit (TRY)	61,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**77,21**	

Item No	Analysis Name					UoM
35.515.3005	**6 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3005	6 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	29,59	29,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	29,59	40,00
				Material and Installation w/o Profit (TRY)	69,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**86,99**	

Item No	Analysis Name					UoM
35.515.3006	**7 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3006	7 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	34,34	34,34	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	34,34	40,00
				Material and Installation w/o Profit (TRY)	74,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**92,93**	

Item No	Analysis Name					UoM
35.515.3007	**8 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3007	8 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	39,20	39,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,20	42,50
				Material and Installation w/o Profit (TRY)	81,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**102,13**	

Item No	Analysis Name					UoM
35.515.3008	**10 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3008	10 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	48,38	48,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,38	42,50
				Material and Installation w/o Profit (TRY)	90,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**113,60**	

Item No	Analysis Name					UoM
35.515.3009	**12 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3009	12 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	60,26	60,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	60,26	45,00
				Material and Installation w/o Profit (TRY)	105,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**131,57**	

Item No	Analysis Name					UoM
35.515.3010	**15 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3010	15 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	79,16	79,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	79,16	48,50
				Material and Installation w/o Profit (TRY)	127,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**159,57**	

Item No	Analysis Name					UoM
35.515.3011	**18 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3011	18 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	100,76	100,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	100,76	51,00
				Material and Installation w/o Profit (TRY)	151,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**189,70**	

Item No	Analysis Name					UoM
35.515.3012	**20 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3012	20 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	115,88	115,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	115,88	51,00
				Material and Installation w/o Profit (TRY)	166,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**208,60**	

Item No	Analysis Name					UoM
35.515.3013	**25 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3013	25 x 2 x 0.22 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	145,04	145,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	145,04	57,00
				Material and Installation w/o Profit (TRY)	202,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**252,55**	

Item No	Analysis Name					UoM
35.515.3014 ae	**2 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3014 ae	2x2x0.34 mm²	m	1	18,68	18,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	18,68	34,00
				Material and Installation w/o Profit (TRY)	52,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**65,85**	

Item No	Analysis Name					UoM
35.515.3015 ae	**3 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3015 ae	3x2x0.34 mm²	m	1	26,35	26,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	26,35	34,00
				Material and Installation w/o Profit (TRY)	60,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**75,44**	

Item No	Analysis Name					UoM
35.515.3016 ae	**4 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3016 ae	4x2x0.34 mm²	m	1	34,13	34,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	34,13	36,50
				Material and Installation w/o Profit (TRY)	70,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**88,29**	

Item No	Analysis Name					UoM
35.515.3017 ae	**5 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3017 ae	5x2x0.34 mm²	m	1	41,36	41,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,36	40,00
				Material and Installation w/o Profit (TRY)	81,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**101,70**	

Item No	Analysis Name					UoM
35.515.3018 ae	**6 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3018 ae	6x2x0.34 mm²	m	1	48,38	48,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,38	42,50
				Material and Installation w/o Profit (TRY)	90,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**113,60**	

Item No	Analysis Name					UoM
35.515.3019 ae	**7 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3019 ae	7x2x0.34 mm²	m	1	57,02	57,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	57,02	42,50
				Material and Installation w/o Profit (TRY)	99,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**124,40**	

Item No	Analysis Name					UoM
35.515.3020 ae	**8 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3020 ae	8x2x0.34 mm²	m	1	64,15	64,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	64,15	42,50
				Material and Installation w/o Profit (TRY)	106,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**133,31**	

Item No	Analysis Name					UoM
35.515.3021 ae	**10 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3021 ae	10x2x0.34 mm²	m	1	81,97	81,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	81,97	48,50
				Material and Installation w/o Profit (TRY)	130,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**163,09**	

Item No	Analysis Name					UoM
35.515.3022 ae	**12 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3022 ae	12x2x0.34 mm²	m	1	99,79	99,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	99,79	48,50
				Material and Installation w/o Profit (TRY)	148,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**185,36**	

Item No	Analysis Name					UoM
35.515.3023 ae	**15 x 2 x 0.34 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3023 ae	15x2x0.34 mm²	m	1	137,59	137,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	137,59	51,00
				Material and Installation w/o Profit (TRY)	188,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**235,74**	

Item No	Analysis Name					UoM
35.515.3024	**2 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3024	2 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	22,03	22,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	22,03	36,50
				Material and Installation w/o Profit (TRY)	58,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**73,16**	

Item No	Analysis Name					UoM
35.515.3025	**3 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3025	3 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	32,29	32,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	32,29	40,00
				Material and Installation w/o Profit (TRY)	72,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**90,36**	

Item No	Analysis Name					UoM
35.515.3026	**4 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3026	4 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	41,36	41,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,36	42,50
				Material and Installation w/o Profit (TRY)	83,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**104,83**	

Item No	Analysis Name					UoM
35.515.3027	**5 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3027	5 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	50,54	50,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	50,54	45,00
				Material and Installation w/o Profit (TRY)	95,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**119,42**	

Item No	Analysis Name					UoM
35.515.3028	**6 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3028	6 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	60,26	60,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	60,26	48,50
				Material and Installation w/o Profit (TRY)	108,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**135,95**	

Item No	Analysis Name					UoM
35.515.3029	**7 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3029	7 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	69,98	69,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	69,98	51,00
				Material and Installation w/o Profit (TRY)	120,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**151,22**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.3030	**8 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3030	8 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	78,73	78,73	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	78,73	51,00
				Material and Installation w/o Profit (TRY)	129,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**162,16**	

Item No	Analysis Name					UoM
35.515.3031	**9 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3031	9 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	90,07	90,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	90,07	51,00
				Material and Installation w/o Profit (TRY)	141,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**176,34**	

Item No	Analysis Name					UoM
35.515.3032	**10 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3032	10 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	99,79	99,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	99,79	53,50
				Material and Installation w/o Profit (TRY)	153,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**191,61**	

Item No	Analysis Name					UoM
35.515.3033	**12 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3033	12 x 2 x 0.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	124,63	124,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	124,63	57,00
				Material and Installation w/o Profit (TRY)	181,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**227,04**	

Item No	Analysis Name					UoM
35.515.3034	**2 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3034	2 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	27,22	27,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	27,22	40,00
				Material and Installation w/o Profit (TRY)	67,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**84,03**	

Item No	Analysis Name					UoM
35.515.3035	**3 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3035	3 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	39,74	39,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,74	42,50
				Material and Installation w/o Profit (TRY)	82,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**102,80**	

Item No	Analysis Name					UoM
35.515.3036	**4 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3036	4 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	51,62	51,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	51,62	45,00
				Material and Installation w/o Profit (TRY)	96,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**120,78**	

Item No	Analysis Name					UoM
35.515.3037	**5 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3037	5 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	64,04	64,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	64,04	48,50
				Material and Installation w/o Profit (TRY)	112,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**140,68**	

Item No	Analysis Name					UoM
35.515.3038	**6 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3038	6 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	74,84	74,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	74,84	51,00
				Material and Installation w/o Profit (TRY)	125,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**157,30**	

Item No	Analysis Name					UoM
35.515.3039	**7 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3039	7 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	88,88	88,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	88,88	51,00
				Material and Installation w/o Profit (TRY)	139,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**174,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.3040	**8 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3040	8 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	100,76	100,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	100,76	53,50
				Material and Installation w/o Profit (TRY)	154,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**192,82**	

Item No	Analysis Name					UoM
35.515.3041	**10 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3041	10 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	130,03	130,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	130,03	59,50
				Material and Installation w/o Profit (TRY)	189,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**236,91**	

Item No	Analysis Name					UoM
35.515.3042	**12 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3042	12 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	162,43	162,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	162,43	59,50
				Material and Installation w/o Profit (TRY)	221,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**277,41**	

Item No	Analysis Name					UoM
35.515.3043	**14 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3043	14 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	184,03	184,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	184,03	62,00
				Material and Installation w/o Profit (TRY)	246,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**307,54**	

Item No	Analysis Name					UoM
35.515.3044	**16 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3044	16 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	213,19	213,19	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	213,19	68,00
				Material and Installation w/o Profit (TRY)	281,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**351,49**	

Item No	Analysis Name					UoM
35.515.3045	**18 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3045	18 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	236,95	236,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	236,95	68,00
				Material and Installation w/o Profit (TRY)	304,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**381,19**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.3046	**20 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3046	20 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	296,35	296,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	296,35	70,50
				Material and Installation w/o Profit (TRY)	366,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**458,56**	

Item No	Analysis Name					UoM
35.515.3047	**25 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3047	25 x 2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	408,67	408,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	408,67	76,50
				Material and Installation w/o Profit (TRY)	485,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**606,46**	

Item No	Analysis Name					UoM
35.515.3048	**2 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3048	2 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	38,66	38,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	38,66	42,50
				Material and Installation w/o Profit (TRY)	81,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**101,45**	

Item No	Analysis Name					UoM
35.515.3049	**3 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3049	3 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	55,40	55,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	55,40	42,50
				Material and Installation w/o Profit (TRY)	97,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**122,38**	

Item No	Analysis Name					UoM
35.515.3050	**4 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3050	4 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	71,06	71,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	71,06	48,50
				Material and Installation w/o Profit (TRY)	119,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**149,45**	

Item No	Analysis Name					UoM
35.515.3051	**5 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3051	5 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	87,80	87,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	87,80	51,00
				Material and Installation w/o Profit (TRY)	138,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**173,50**	

Item No	Analysis Name					UoM
35.515.3052	**6 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3052	6 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	104,00	104,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	104,00	53,50
				Material and Installation w/o Profit (TRY)	157,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,88**	
				Unit Price (TRY)	**196,88**	

Item No	Analysis Name					UoM
35.515.3053	**7 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3053	7 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	122,36	122,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	122,36	57,00
				Material and Installation w/o Profit (TRY)	179,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**224,20**	

Item No	Analysis Name					UoM
35.515.3054	**8 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3054	8 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	137,59	137,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	137,59	57,00
				Material and Installation w/o Profit (TRY)	194,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**243,24**	

Item No	Analysis Name					UoM
35.515.3055	**10 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3055	10 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	176,47	176,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	176,47	62,00
				Material and Installation w/o Profit (TRY)	238,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**298,09**	

Item No	Analysis Name					UoM
35.515.3056	**12 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3056	12 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	218,59	218,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	218,59	62,00
				Material and Installation w/o Profit (TRY)	280,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**350,74**	

Item No	Analysis Name					UoM
35.515.3057	**14 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3057	14 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	250,99	250,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	250,99	68,00
				Material and Installation w/o Profit (TRY)	318,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**398,74**	

Item No	Analysis Name					UoM
35.515.3058	**16 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3058	16 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	284,47	284,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
		Total Excluding Profit (TRY)			284,47	68,00
		Material and Installation w/o Profit (TRY)			352,47	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**85,00**	
		Unit Price (TRY)			**440,59**	

Item No	Analysis Name					UoM
35.515.3059	**18 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3059	18 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	320,11	320,11	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			320,11	74,00
		Material and Installation w/o Profit (TRY)			394,11	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**92,50**	
		Unit Price (TRY)			**492,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.3060	**20 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3060	20 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	405,43	405,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	405,43	76,50
				Material and Installation w/o Profit (TRY)	481,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**602,41**	

Item No	Analysis Name					UoM
35.515.3061	**25 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3061	25 x 2 x 1.00 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	547,99	547,99	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	547,99	82,50
				Material and Installation w/o Profit (TRY)	630,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**788,11**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.3062	**2 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3062	2 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	48,92	48,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,92	42,50
				Material and Installation w/o Profit (TRY)	91,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**114,28**	

Item No	Analysis Name					UoM
35.515.3063	**3 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3063	3 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	71,60	71,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	71,60	45,00
				Material and Installation w/o Profit (TRY)	116,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**145,75**	

Item No	Analysis Name					UoM
35.515.3064	**4 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3064	4 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	93,20	93,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	93,20	48,50
				Material and Installation w/o Profit (TRY)	141,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**177,13**	

Item No	Analysis Name					UoM
35.515.3065	**5 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3065	5 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	114,80	114,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	114,80	51,00
				Material and Installation w/o Profit (TRY)	165,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**207,25**	

Item No	Analysis Name					UoM
35.515.3066	**6 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3066	6 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	137,48	137,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	137,48	57,00
				Material and Installation w/o Profit (TRY)	194,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**243,10**	

Item No	Analysis Name					UoM
35.515.3067	**7 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3067	7 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	165,56	165,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	165,56	59,50
				Material and Installation w/o Profit (TRY)	225,06	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**281,32**	

Item No	Analysis Name					UoM
35.515.3068	**8 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3068	8x2x1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (Vde 0812) (Market price)	m	1	188,35	188,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	188,35	59,50
				Material and Installation w/o Profit (TRY)	247,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**309,81**	

Item No	Analysis Name					UoM
35.515.3069	**10 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3069	10 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	235,87	235,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	235,87	68,00
				Material and Installation w/o Profit (TRY)	303,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**379,84**	

Item No	Analysis Name					UoM
35.515.3070	**12 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3070	12 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	296,35	296,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	296,35	68,00
				Material and Installation w/o Profit (TRY)	364,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**455,44**	

Item No	Analysis Name					UoM
35.515.3071	**14 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3071	14 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	333,07	333,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	333,07	70,50
				Material and Installation w/o Profit (TRY)	403,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**504,46**	

Item No	Analysis Name					UoM
35.515.3072	**16 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3072	16 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	380,59	380,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	380,59	76,50
				Material and Installation w/o Profit (TRY)	457,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**571,36**	

Item No	Analysis Name					UoM
35.515.3073	**18 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3073	18 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	427,03	427,03	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	427,03	76,50
				Material and Installation w/o Profit (TRY)	503,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**629,41**	

Item No	Analysis Name					UoM
35.515.3074	**20 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3074	20 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	539,35	539,35	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	539,35	82,50
				Material and Installation w/o Profit (TRY)	621,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**103,13**	
				Unit Price (TRY)	**777,31**	

Item No	Analysis Name					UoM
35.515.3075	**25 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3075	25 x 2 x 1.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	702,43	702,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	702,43	85,00
				Material and Installation w/o Profit (TRY)	787,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**984,29**	

Item No	Analysis Name					UoM
35.515.3076	**2 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3076	2 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	75,92	75,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	75,92	45,00
				Material and Installation w/o Profit (TRY)	120,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**151,15**	

Item No	Analysis Name					UoM
35.515.3077	**3 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3077	3 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	113,72	113,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	113,72	51,00
				Material and Installation w/o Profit (TRY)	164,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**205,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.3078	**4 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3078	4 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	147,20	147,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	147,20	59,50
				Material and Installation w/o Profit (TRY)	206,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**258,38**	

Item No	Analysis Name					UoM
35.515.3079	**5 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3079	5 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	181,76	181,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	181,76	59,50
				Material and Installation w/o Profit (TRY)	241,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**301,57**	

Item No	Analysis Name					UoM
35.515.3080	**6 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3080	6 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	217,40	217,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,15	250,00		37,50
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	217,40	62,00
				Material and Installation w/o Profit (TRY)	279,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,50**	
				Unit Price (TRY)	**349,25**	

Item No	Analysis Name					UoM
35.515.3081	**7 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3081	7 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	249,80	249,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	249,80	68,00
				Material and Installation w/o Profit (TRY)	317,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**397,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.3082	**8 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3082	8 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	284,47	284,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	284,47	68,00
				Material and Installation w/o Profit (TRY)	352,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**440,59**	

Item No	Analysis Name					UoM
35.515.3083	**10 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3083	10 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	354,67	354,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	354,67	74,00
				Material and Installation w/o Profit (TRY)	428,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92,50**	
				Unit Price (TRY)	**535,84**	

Item No	Analysis Name					UoM
35.515.3084	**12 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3084	12 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	441,07	441,07	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,18	250,00		45,00
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	441,07	76,50
				Material and Installation w/o Profit (TRY)	517,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95,63**	
				Unit Price (TRY)	**646,96**	

Item No	Analysis Name					UoM
35.515.3085	**14 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3085	14 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	497,23	497,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,09	165,00		14,85
10.100.1081	Master electrician	h	0,19	250,00		47,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	497,23	79,00
				Material and Installation w/o Profit (TRY)	576,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**98,75**	
				Unit Price (TRY)	**720,29**	

Item No	Analysis Name					UoM
35.515.3086	**16 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3086	16 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	586,87	586,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			586,87	85,00
		Material and Installation w/o Profit (TRY)			671,87	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**106,25**	
		Unit Price (TRY)			**839,84**	

Item No	Analysis Name					UoM
35.515.3087	**18 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3087	18 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	665,71	665,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,21	250,00		52,50
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			665,71	87,50
		Material and Installation w/o Profit (TRY)			753,21	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**109,38**	
		Unit Price (TRY)			**941,51**	

Item No	Analysis Name					UoM
35.515.3088	**20 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3088	20 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	730,51	730,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,22	250,00		55,00
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	730,51	93,50
				Material and Installation w/o Profit (TRY)	824,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**116,88**	
				Unit Price (TRY)	**1.030,01**	

Item No	Analysis Name					UoM
35.515.3089	**25 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.3089	25 x 2 x 2.50 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0812) (Market price)	m	1	789,91	789,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,11	165,00		18,15
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	789,91	96,00
				Material and Installation w/o Profit (TRY)	885,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**120,00**	
				Unit Price (TRY)	**1.107,39**	

Item No	Analysis Name					UoM
35.515.4001						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4001	2 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	11,00	11,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	11,00	28,00
				Material and Installation w/o Profit (TRY)	39,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**48,75**	

Item No	Analysis Name					UoM
35.515.4002						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4002	3 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	12,40	12,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	12,40	31,50
				Material and Installation w/o Profit (TRY)	43,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**54,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4003						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4003	4 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	14,10	14,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,10	31,50
				Material and Installation w/o Profit (TRY)	45,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**57,00**	

Item No	Analysis Name					UoM
35.515.4004						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4004	5 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	17,90	17,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,90	31,50
				Material and Installation w/o Profit (TRY)	49,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**61,75**	

Item No	Analysis Name					UoM
35.515.4005						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4005	6 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	20,40	20,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,40	34,00
				Material and Installation w/o Profit (TRY)	54,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**68,00**	

Item No	Analysis Name					UoM
35.515.4006						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4006	7 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	21,90	21,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	21,90	34,00
				Material and Installation w/o Profit (TRY)	55,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**69,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4007						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4007	8 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	25,30	25,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	25,30	34,00
				Material and Installation w/o Profit (TRY)	59,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**74,13**	

Item No	Analysis Name					UoM
35.515.4008						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4008	10 x 0.22 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	27,30	27,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,30	34,00
				Material and Installation w/o Profit (TRY)	61,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**76,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4009						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4009	2 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	16,50	16,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	16,50	34,00
				Material and Installation w/o Profit (TRY)	50,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**63,13**	

Item No	Analysis Name					UoM
35.515.4010						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4010	3 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	20,00	20,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,00	34,00
				Material and Installation w/o Profit (TRY)	54,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**67,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4011						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4011	4 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	24,60	24,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,60	34,00
				Material and Installation w/o Profit (TRY)	58,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**73,25**	

Item No	Analysis Name					UoM
35.515.4012						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4012	5 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	28,90	28,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	28,90	36,50
				Material and Installation w/o Profit (TRY)	65,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**81,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4013						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4013	6 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	34,80	34,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	34,80	40,00
				Material and Installation w/o Profit (TRY)	74,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**93,50**	

Item No	Analysis Name					UoM
35.515.4014						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4014	7 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	38,50	38,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	38,50	40,00
				Material and Installation w/o Profit (TRY)	78,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**98,13**	

Item No	Analysis Name					UoM
35.515.4015						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4015	8 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	42,70	42,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	42,70	40,00
				Material and Installation w/o Profit (TRY)	82,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**103,38**	

Item No	Analysis Name					UoM
35.515.4016						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4016	10 x 0.50 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	47,70	47,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	47,70	42,50
				Material and Installation w/o Profit (TRY)	90,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**112,75**	

Item No	Analysis Name					UoM
35.515.4017						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4017	2 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	19,60	19,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,60	34,00
				Material and Installation w/o Profit (TRY)	53,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**67,00**	

Item No	Analysis Name					UoM
35.515.4018						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4018	3 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	24,30	24,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,30	34,00
				Material and Installation w/o Profit (TRY)	58,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**72,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4019						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4019	4 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	29,40	29,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,40	34,00
				Material and Installation w/o Profit (TRY)	63,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**79,25**	

Item No	Analysis Name					UoM
35.515.4020						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4020	5 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	35,40	35,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	35,40	40,00
				Material and Installation w/o Profit (TRY)	75,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**94,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4021						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4021	6 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	41,70	41,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,70	40,00
				Material and Installation w/o Profit (TRY)	81,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**102,13**	

Item No	Analysis Name					UoM
35.515.4022						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4022	7 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	46,20	46,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	46,20	40,00
				Material and Installation w/o Profit (TRY)	86,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**107,75**	

Item No	Analysis Name					UoM
35.515.4023						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4023	8 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	52,70	52,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,70	42,50
				Material and Installation w/o Profit (TRY)	95,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**119,00**	

Item No	Analysis Name					UoM
35.515.4024						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4024	10 x 0.75 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	63,20	63,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	63,20	45,00
				Material and Installation w/o Profit (TRY)	108,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**135,25**	

Item No	Analysis Name					UoM
35.515.4025						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4025	2 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	23,50	23,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	23,50	34,00
				Material and Installation w/o Profit (TRY)	57,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**71,88**	

Item No	Analysis Name					UoM
35.515.4026						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4026	3 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	29,90	29,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,90	34,00
				Material and Installation w/o Profit (TRY)	63,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**79,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4027						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4027	4 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	37,80	37,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	37,80	36,50
				Material and Installation w/o Profit (TRY)	74,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**92,88**	

Item No	Analysis Name					UoM
35.515.4028						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4028	5 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	44,80	44,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	44,80	40,00
				Material and Installation w/o Profit (TRY)	84,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**106,00**	

Item No	Analysis Name					UoM
35.515.4029						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4029	6 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	53,80	53,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	53,80	42,50
				Material and Installation w/o Profit (TRY)	96,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**120,38**	

Item No	Analysis Name					UoM
35.515.4030						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4030	7 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	60,30	60,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	60,30	42,50
				Material and Installation w/o Profit (TRY)	102,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**128,50**	

Item No	Analysis Name					UoM
35.515.4031						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4031	8 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	67,80	67,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	67,80	42,50
				Material and Installation w/o Profit (TRY)	110,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**137,88**	

Item No	Analysis Name					UoM
35.515.4032						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4032	10 x 1.0 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	80,80	80,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	80,80	48,50
				Material and Installation w/o Profit (TRY)	129,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**161,63**	

Item No	Analysis Name					UoM
35.515.4033						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4033	2 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	31,30	31,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	31,30	36,50
				Material and Installation w/o Profit (TRY)	67,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**84,75**	

Item No	Analysis Name					UoM
35.515.4034						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4034	3 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	40,30	40,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	40,30	36,50
				Material and Installation w/o Profit (TRY)	76,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**96,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4035						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4035	4 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	51,80	51,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	51,80	40,00
				Material and Installation w/o Profit (TRY)	91,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**114,75**	

Item No	Analysis Name					UoM
35.515.4036						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4036	5 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	62,80	62,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	62,80	42,50
				Material and Installation w/o Profit (TRY)	105,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**131,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4037						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4037	6 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	73,80	73,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	73,80	42,50
				Material and Installation w/o Profit (TRY)	116,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**145,38**	

Item No	Analysis Name					UoM
35.515.4038						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4038	7 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	84,30	84,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	84,30	42,50
				Material and Installation w/o Profit (TRY)	126,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**158,50**	

Item No	Analysis Name					UoM
35.515.4039						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4039	8 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	93,80	93,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	93,80	45,00
				Material and Installation w/o Profit (TRY)	138,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**173,50**	

Item No	Analysis Name					UoM
35.515.4040						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4040	10 x 1.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	114,80	114,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	114,80	51,00
				Material and Installation w/o Profit (TRY)	165,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**207,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.4041						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4041	2 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	44,30	44,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	44,30	42,50
				Material and Installation w/o Profit (TRY)	86,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**108,50**	

Item No	Analysis Name					UoM
35.515.4042						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4042	3 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	58,30	58,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	58,30	42,50
				Material and Installation w/o Profit (TRY)	100,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**126,00**	

Item No	Analysis Name					UoM
35.515.4043						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4043	4 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	72,30	72,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	72,30	45,00
				Material and Installation w/o Profit (TRY)	117,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**146,63**	

Item No	Analysis Name					UoM
35.515.4044						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4044	5 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	89,80	89,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	89,80	48,50
				Material and Installation w/o Profit (TRY)	138,30	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**172,88**	

Item No	Analysis Name					UoM
35.515.4045						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4045	6 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	105,80	105,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	105,80	48,50
				Material and Installation w/o Profit (TRY)	154,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**192,88**	

Item No	Analysis Name					UoM
35.515.4046						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4046	7 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	119,80	119,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	119,80	51,00
				Material and Installation w/o Profit (TRY)	170,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**213,50**	

Item No	Analysis Name					UoM
35.515.4047						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4047	8 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	136,80	136,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	136,80	51,00
				Material and Installation w/o Profit (TRY)	187,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**234,75**	

Item No	Analysis Name					UoM
35.515.4048						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.4048	10 x 2.5 mm² / LIH(St)CH HALOGEN-FREE SIGNAL and CONTROLLER CABLE / HALOGEN-FREE CABLES (Market price)	m	1	154,80	154,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	154,80	57,00
				Material and Installation w/o Profit (TRY)	211,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**264,75**	

Item No	Analysis Name					UoM
35.515.5120						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5120	1x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	5,17	5,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	5,17	25,50
				Material and Installation w/o Profit (TRY)	30,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**38,34**	

Item No	Analysis Name					UoM
35.515.5121						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5121	2x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	8,14	8,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	8,14	28,00
				Material and Installation w/o Profit (TRY)	36,14	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**45,17**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.5122						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5122	3x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	10,81	10,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	10,81	31,50
				Material and Installation w/o Profit (TRY)	42,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**52,89**	

Item No	Analysis Name					UoM
35.515.5123						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5123	4x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	13,95	13,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,95	31,50
				Material and Installation w/o Profit (TRY)	45,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**56,81**	

Item No	Analysis Name					UoM
35.515.5126						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5126	6x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	19,66	19,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,66	34,00
				Material and Installation w/o Profit (TRY)	53,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**67,07**	

Item No	Analysis Name					UoM
35.515.5130						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5130	10x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	31,53	31,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	31,53	36,50
				Material and Installation w/o Profit (TRY)	68,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**85,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.5135						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5135	20x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	61,86	61,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	61,86	42,50
				Material and Installation w/o Profit (TRY)	104,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**130,45**	

Item No	Analysis Name					UoM
35.515.5140						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5140	30x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	90,61	90,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	90,61	45,00
				Material and Installation w/o Profit (TRY)	135,61	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**169,51**	

Item No	Analysis Name					UoM
35.515.5145						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5145	50x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	151,47	151,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	151,47	51,00
				Material and Installation w/o Profit (TRY)	202,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**253,09**	

Item No	Analysis Name					UoM
35.515.5150						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5150	100x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	283,55	283,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	283,55	68,00
				Material and Installation w/o Profit (TRY)	351,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**439,44**	

Item No	Analysis Name					UoM
35.515.5155						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5155	150x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	414,24	414,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	414,24	85,00
				Material and Installation w/o Profit (TRY)	499,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**624,05**	

Item No	Analysis Name					UoM
35.515.5160						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5160	200x2x0.5+0.5 / PDH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	544,81	544,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,12	165,00		19,80
10.100.1081	Master electrician	h	0,23	250,00		57,50
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	544,81	99,50
				Material and Installation w/o Profit (TRY)	644,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**124,38**	
				Unit Price (TRY)	**805,39**	

Item No	Analysis Name					UoM
35.515.5220						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5220	1x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	5,58	5,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,06	250,00		15,00
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	5,58	25,50
				Material and Installation w/o Profit (TRY)	31,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**31,88**	
				Unit Price (TRY)	**38,85**	

Item No	Analysis Name					UoM
35.515.5221						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5221	2x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	8,64	8,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,03	185,00		5,55
				Total Excluding Profit (TRY)	8,64	28,00
				Material and Installation w/o Profit (TRY)	36,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35,00**	
				Unit Price (TRY)	**45,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.5222						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5222	3x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	11,55	11,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	11,55	31,50
				Material and Installation w/o Profit (TRY)	43,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**53,81**	

Item No	Analysis Name					UoM
35.515.5223						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5223	4x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	14,82	14,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,82	31,50
				Material and Installation w/o Profit (TRY)	46,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**57,90**	

Item No	Analysis Name					UoM
35.515.5226						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5226	6x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	20,06	20,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	20,06	34,00
				Material and Installation w/o Profit (TRY)	54,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**67,58**	

Item No	Analysis Name					UoM
35.515.5230						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5230	10x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	33,55	33,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	33,55	36,50
				Material and Installation w/o Profit (TRY)	70,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**87,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.5235						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5235	20x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	65,12	65,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	65,12	42,50
				Material and Installation w/o Profit (TRY)	107,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**134,53**	

Item No	Analysis Name					UoM
35.515.5240						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5240	30x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	94,83	94,83	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	94,83	45,00
				Material and Installation w/o Profit (TRY)	139,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**174,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.5245						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5245	50x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	158,78	158,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	158,78	51,00
				Material and Installation w/o Profit (TRY)	209,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**262,23**	

Item No	Analysis Name					UoM
35.515.5250						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5250	100x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	293,65	293,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,16	250,00		40,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	293,65	68,00
				Material and Installation w/o Profit (TRY)	361,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85,00**	
				Unit Price (TRY)	**452,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.5255						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.5255	200x2x0.5+0.5 / HBH Halogen-Free Internal Telephone Cable / HALOGEN-FREE INTERNAL TELEPHONE CABLES (Market price)	m	1	580,67	580,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,2	250,00		50,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	580,67	85,00
				Material and Installation w/o Profit (TRY)	665,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106,25**	
				Unit Price (TRY)	**832,09**	

Item No	Analysis Name					UoM
35.515.7010	**UTP CAT 5H HALOGEN-FREE 4 x 2 x 24 AWG / Copper Data Wires**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.7010	U/UTP Cat 5e HALOGEN-FREE 4X2X24 AWG / HALOGEN-FREE COPPER DATA CABLES / HALOGEN-FREE CABLES (Market price)	m	1	13,61	13,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,61	31,50
				Material and Installation w/o Profit (TRY)	45,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**56,39**	

Item No	Analysis Name					UoM
35.515.7020	**FTP CAT 5H HALOGEN-FREE 4 x 2 x 24 AWG / Copper Data Wires**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.7020	F/UTP Cat 5e HALOGEN-FREE 4X2X24 AWG / HALOGEN-FREE COPPER DATA CABLES / HALOGEN-FREE CABLES (Market price)	m	1	15,98	15,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	15,98	34,00
				Material and Installation w/o Profit (TRY)	49,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**62,48**	

Item No	Analysis Name					UoM
35.515.7030	**UTP CAT 6H HALOGEN-FREE 4 x 2 x 23 AWG / Copper Data Wires**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.7030	U/UTP Cat 6 HALOGEN-FREE 4X2X23 AWG / HALOGEN-FREE COPPER DATA CABLES / HALOGEN-FREE CABLES (Market price)	m	1	17,28	17,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,28	34,00
				Material and Installation w/o Profit (TRY)	51,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**64,10**	

Item No	Analysis Name					UoM
35.515.7040	**FTP CAT 6H HALOGEN-FREE 4 x 2 x 23 AWG / Copper Data Wires**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.7040	F/UTP Cat 6 HALOGEN-FREE 4X2X23 AWG / HALOGEN-FREE COPPER DATA CABLES / HALOGEN-FREE CABLES (Market price)	m	1	23,98	23,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	23,98	34,00
				Material and Installation w/o Profit (TRY)	57,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**72,48**	

Item No	Analysis Name					UoM
35.515.7100						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.7100	F/FTP Cat 6a HF / HALOGEN-FREE COPPER DATA CABLES / HALOGEN-FREE CABLES (Market price)	m	1	27,32	27,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,32	36,50
				Material and Installation w/o Profit (TRY)	63,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**79,78**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.7200						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.7200	F/FTP Cat 6a HF / HALOGEN-FREE COPPER DATA CABLES / HALOGEN-FREE CABLES (Market price)	m	1	31,97	31,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	31,97	36,50
				Material and Installation w/o Profit (TRY)	68,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**85,59**	

Item No	Analysis Name					UoM
35.515.8001						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8001	RG 59 U-4 (Cu/Al) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	10,37	10,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	10,37	34,00
				Material and Installation w/o Profit (TRY)	44,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**55,46**	

Item No	Analysis Name					UoM
35.515.8002						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8002	RG 59 U-4 (Cu/CuSn) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	8,53	8,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	8,53	34,00
				Material and Installation w/o Profit (TRY)	42,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**53,16**	

Item No	Analysis Name					UoM
35.515.8003						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8003	RG 59 U-6 (Cu/Cu) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	14,36	14,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	14,36	34,00
				Material and Installation w/o Profit (TRY)	48,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**60,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.8010						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8010	RG 6/U-4 (Cu/Al) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	12,74	12,74	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	12,74	34,00
				Material and Installation w/o Profit (TRY)	46,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**58,43**	

Item No	Analysis Name					UoM
35.515.8011						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8011	RG 6/U-4 (Trishield Cu/Al) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	13,61	13,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	13,61	36,50
				Material and Installation w/o Profit (TRY)	50,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**62,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.8012						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8012	RG 6/U-4 (Cu/CuSn) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	17,60	17,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,60	34,00
				Material and Installation w/o Profit (TRY)	51,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**64,50**	

Item No	Analysis Name					UoM
35.515.8013						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8013	RG 6/U-4 (Trishield Cu/CuSn) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	34,45	34,45	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	34,45	36,50
				Material and Installation w/o Profit (TRY)	70,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**88,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.8014						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8014	RG 6/U-6 (Cu/Cu) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	19,01	19,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,01	36,50
				Material and Installation w/o Profit (TRY)	55,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**69,39**	

Item No	Analysis Name					UoM
35.515.8015						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8015	RG 6/U-6 (Trishield Cu/Cu) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	23,33	23,33	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	23,33	36,50
				Material and Installation w/o Profit (TRY)	59,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**74,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.8020						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8020	RG 11/U-4 (Cu/Al) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	27,22	27,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	27,22	45,00
				Material and Installation w/o Profit (TRY)	72,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**90,28**	

Item No	Analysis Name					UoM
35.515.8021						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8021	RG 11/U-4 (Cu/CuSn) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	33,91	33,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	33,91	45,00
				Material and Installation w/o Profit (TRY)	78,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**98,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.8022						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8022	RG 11/U-4 (Trishield Cu/CuSn) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	59,29	59,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	59,29	45,00
				Material and Installation w/o Profit (TRY)	104,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**130,36**	

Item No	Analysis Name					UoM
35.515.8023						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8023	RG 11/U-6 (Cu/Cu) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	39,31	39,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	39,31	45,00
				Material and Installation w/o Profit (TRY)	84,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**105,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.515.8024						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8024	RG 11/U-6 (Trishield Cu/Cu) HFFR / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	29,05	29,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	29,05	45,00
				Material and Installation w/o Profit (TRY)	74,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**92,56**	

Item No	Analysis Name					UoM
35.515.8030						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8030	RG 58 C/U HFFR (50 ohm) / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	19,76	19,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	19,76	31,50
				Material and Installation w/o Profit (TRY)	51,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39,38**	
				Unit Price (TRY)	**64,08**	

Item No	Analysis Name					UoM
35.515.8031						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.515.8031	RG 213 U HFFR (50 ohm) / Halogen-free Coaxial Cables (LS HFFR) / HALOGEN-FREE CABLES (Market price)	m	1	70,63	70,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	70,63	45,00
				Material and Installation w/o Profit (TRY)	115,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**144,54**	

Item No	Analysis Name					UoM
35.520.5001	**1 x 2 x 0.8 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5001	1x2x0.8+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	17,47	17,47	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	17,47	34,00
				Material and Installation w/o Profit (TRY)	51,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**64,34**	

Item No	Analysis Name					UoM
35.520.5002	**2 x 2 x 0.8 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5002	2x2x0.8+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	26,94	26,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	26,94	34,00
				Material and Installation w/o Profit (TRY)	60,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**76,17**	

Item No	Analysis Name					UoM
35.520.5003	**3 x 2 x 0.8 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5003	3x2x0.8+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	38,06	38,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	38,06	40,00
				Material and Installation w/o Profit (TRY)	78,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**97,58**	

Item No	Analysis Name					UoM
35.520.5004	**4 x 2 x 0.8 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5004	4x2x0.8+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	47,42	47,42	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	47,42	42,50
				Material and Installation w/o Profit (TRY)	89,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**112,40**	

Item No	Analysis Name					UoM
35.520.5005	**10 x 2 x 0.8 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5005	10x2x0.8+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	113,98	113,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	113,98	51,00
				Material and Installation w/o Profit (TRY)	164,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**206,23**	

Item No	Analysis Name					UoM
35.520.5006	**1 x 2 x 1 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5006	1x2x1+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	21,94	21,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	21,94	34,00
				Material and Installation w/o Profit (TRY)	55,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**69,92**	

Item No	Analysis Name					UoM
35.520.5007	**2 x 2 x 1 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5007	2x2x1+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	35,15	35,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	35,15	40,00
				Material and Installation w/o Profit (TRY)	75,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**93,94**	

Item No	Analysis Name					UoM
35.520.5008	**3 x 2 x 1 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5008	3x2x1+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	56,26	56,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	56,26	42,50
				Material and Installation w/o Profit (TRY)	98,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**123,45**	

Item No	Analysis Name					UoM
35.520.5009	**4 x 2 x 1 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5009	4x2x1+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	70,30	70,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	70,30	45,00
				Material and Installation w/o Profit (TRY)	115,30	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**144,13**	

Item No	Analysis Name					UoM
35.520.5010	**10 x 2 x 1 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5010	10x2x1+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	178,46	178,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	178,46	57,00
				Material and Installation w/o Profit (TRY)	235,46	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,25**	
				Unit Price (TRY)	**294,32**	

Item No	Analysis Name					UoM
35.520.5011	**1 x 2 x 1.5 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5011	1x2x1.5+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	33,38	33,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	33,38	40,00
				Material and Installation w/o Profit (TRY)	73,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**91,72**	

Item No	Analysis Name					UoM
35.520.5012	**2 x 2 x 1.5 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5012	2x2x1.5+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	57,82	57,82	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	57,82	42,50
				Material and Installation w/o Profit (TRY)	100,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**125,40**	

Item No	Analysis Name					UoM
35.520.5013	**3 x 2 x 1.5 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5013	3x2x1.5+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	90,06	90,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	90,06	48,50
				Material and Installation w/o Profit (TRY)	138,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**173,20**	

Item No	Analysis Name					UoM
35.520.5014	**4 x 2 x 1.5 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5014	4x2x1.5+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	119,18	119,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	119,18	51,00
				Material and Installation w/o Profit (TRY)	170,18	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**212,73**	

Item No	Analysis Name					UoM
35.520.5015	**10 x 2 x 1.5 + 0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE FIRE ALARM CABLES (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.5015	10x2x1.5+0.8 mm² / JE-H(St)H FE180 PH120 FIRE-PF, HALOGEN-FREE FIRE ALARM CABLES / FIRE-RESISTANT CABLES (Market price)	m	1	282,46	282,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,08	165,00		13,20
10.100.1081	Master electrician	h	0,17	250,00		42,50
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	282,46	70,50
				Material and Installation w/o Profit (TRY)	352,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**88,13**	
				Unit Price (TRY)	**441,20**	

Item No	Analysis Name					UoM
35.520.6001	**2 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6001	2x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	21,17	21,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	21,17	36,50
				Material and Installation w/o Profit (TRY)	57,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**72,09**	

Item No	Analysis Name					UoM
35.520.6002	**3 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6002	3x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	27,89	27,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	27,89	36,50
				Material and Installation w/o Profit (TRY)	64,39	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**80,49**	

Item No	Analysis Name					UoM
35.520.6003	**4 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6003	4x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	34,22	34,22	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	34,22	40,00
				Material and Installation w/o Profit (TRY)	74,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**92,78**	

Item No	Analysis Name					UoM
35.520.6004	**5 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6004	5x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	40,96	40,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	40,96	42,50
				Material and Installation w/o Profit (TRY)	83,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**104,33**	

Item No	Analysis Name					UoM
35.520.6005	**6 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6005	6x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	48,69	48,69	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	48,69	42,50
				Material and Installation w/o Profit (TRY)	91,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**113,99**	

Item No	Analysis Name					UoM
35.520.6006	**7 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6006	7x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	55,31	55,31	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	55,31	42,50
				Material and Installation w/o Profit (TRY)	97,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**122,26**	

Item No	Analysis Name					UoM
35.520.6007	**8 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6007	8x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	61,93	61,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	61,93	45,00
				Material and Installation w/o Profit (TRY)	106,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**133,66**	

Item No	Analysis Name					UoM
35.520.6008	**10 x 0.75 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6008	10x0.75 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	76,29	76,29	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	76,29	51,00
				Material and Installation w/o Profit (TRY)	127,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**159,11**	

Item No	Analysis Name					UoM
35.520.6009	**2 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6009	2x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	28,70	28,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	28,70	36,50
				Material and Installation w/o Profit (TRY)	65,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**81,50**	

Item No	Analysis Name					UoM
35.520.6010	**3 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6010	3x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	37,43	37,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	37,43	40,00
				Material and Installation w/o Profit (TRY)	77,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**96,79**	

Item No	Analysis Name					UoM
35.520.6011	**4 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6011	4x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	41,84	41,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	41,84	42,50
				Material and Installation w/o Profit (TRY)	84,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**105,43**	

Item No	Analysis Name					UoM
35.520.6012	**5 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6012	5x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	55,64	55,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	55,64	42,50
				Material and Installation w/o Profit (TRY)	98,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**122,67**	

Item No	Analysis Name					UoM
35.520.6013	**6 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6013	6x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	66,13	66,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	66,13	45,00
				Material and Installation w/o Profit (TRY)	111,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**138,91**	

Item No	Analysis Name					UoM
35.520.6014	**7 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6014	7x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	74,41	74,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	74,41	45,00
				Material and Installation w/o Profit (TRY)	119,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**149,26**	

Item No	Analysis Name					UoM
35.520.6015	**8 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6015	8x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	83,79	83,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	83,79	48,50
				Material and Installation w/o Profit (TRY)	132,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**165,36**	

Item No	Analysis Name					UoM
35.520.6016	**10 x 1 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6016	10x1 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	102,01	102,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	102,01	51,00
				Material and Installation w/o Profit (TRY)	153,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**191,26**	

Item No	Analysis Name					UoM
35.520.6017	**2 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6017	2x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	35,77	35,77	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	35,77	40,00
				Material and Installation w/o Profit (TRY)	75,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**94,71**	

Item No	Analysis Name					UoM
35.520.6018	**3 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6018	3x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	47,36	47,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	47,36	42,50
				Material and Installation w/o Profit (TRY)	89,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**112,33**	

Item No	Analysis Name					UoM
35.520.6019	**4 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6019	4x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	60,61	60,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	60,61	42,50
				Material and Installation w/o Profit (TRY)	103,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**128,89**	

Item No	Analysis Name					UoM
35.520.6020	**5 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6020	5x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	72,75	72,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	72,75	45,00
				Material and Installation w/o Profit (TRY)	117,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**147,19**	

Item No	Analysis Name					UoM
35.520.6021	**6 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6021	6x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	87,66	87,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	87,66	51,00
				Material and Installation w/o Profit (TRY)	138,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**173,32**	

Item No	Analysis Name					UoM
35.520.6022	**7 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6022	7x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	98,70	98,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	98,70	51,00
				Material and Installation w/o Profit (TRY)	149,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**187,13**	

Item No	Analysis Name					UoM
35.520.6023	**8 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6023	8x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	108,63	108,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	108,63	51,00
				Material and Installation w/o Profit (TRY)	159,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**199,54**	

Item No	Analysis Name					UoM
35.520.6024	**10 x 1.5 mm² / Lih(St)H Halogen-Free Signal and Controller Cable (VDE 0815)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.6024	10x1.5 mm² / LIH(St)H FE180 PH120 FIRE-PROOF, HALOGEN-FREE SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	135,13	135,13	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	135,13	59,50
				Material and Installation w/o Profit (TRY)	194,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**243,29**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7001						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7001	2x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	24,24	24,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	24,24	34,00
				Material and Installation w/o Profit (TRY)	58,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**72,80**	

Item No	Analysis Name					UoM
35.520.7002						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7002	3x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	29,58	29,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	29,58	34,00
				Material and Installation w/o Profit (TRY)	63,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**79,47**	

Item No	Analysis Name					UoM
35.520.7003						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7003	4x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	33,80	33,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	33,80	34,00
				Material and Installation w/o Profit (TRY)	67,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**84,75**	

Item No	Analysis Name					UoM
35.520.7004						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7004	5x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	43,62	43,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	43,62	36,50
				Material and Installation w/o Profit (TRY)	80,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**100,15**	

Item No	Analysis Name					UoM
35.520.7005						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7005	6x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	52,51	52,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	52,51	36,50
				Material and Installation w/o Profit (TRY)	89,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**111,26**	

Item No	Analysis Name					UoM
35.520.7006						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7006	7x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	58,59	58,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	58,59	40,00
				Material and Installation w/o Profit (TRY)	98,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**123,24**	

Item No	Analysis Name					UoM
35.520.7007						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7007	8x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	65,61	65,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	65,61	42,50
				Material and Installation w/o Profit (TRY)	108,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**135,14**	

Item No	Analysis Name					UoM
35.520.7008						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7008	10x0.75 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	81,06	81,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	81,06	42,50
				Material and Installation w/o Profit (TRY)	123,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**154,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7009						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7009	2x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	28,92	28,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	28,92	34,00
				Material and Installation w/o Profit (TRY)	62,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**78,65**	

Item No	Analysis Name					UoM
35.520.7010						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7010	3x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	37,81	37,81	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	37,81	34,00
				Material and Installation w/o Profit (TRY)	71,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**89,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7011						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7011	4x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	46,71	46,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	46,71	34,00
				Material and Installation w/o Profit (TRY)	80,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42,50**	
				Unit Price (TRY)	**100,89**	

Item No	Analysis Name					UoM
35.520.7012						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7012	5x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	55,60	55,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	55,60	36,50
				Material and Installation w/o Profit (TRY)	92,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**115,13**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7013						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7013	6x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	65,43	65,43	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	65,43	40,00
				Material and Installation w/o Profit (TRY)	105,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**131,79**	

Item No	Analysis Name					UoM
35.520.7014						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7014	7x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	73,38	73,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	73,38	40,00
				Material and Installation w/o Profit (TRY)	113,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**141,72**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7015						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7015	8x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	83,68	83,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	83,68	42,50
				Material and Installation w/o Profit (TRY)	126,18	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**157,73**	

Item No	Analysis Name					UoM
35.520.7016						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7016	10x1.0 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	101,95	101,95	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	101,95	45,00
				Material and Installation w/o Profit (TRY)	146,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**183,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7017						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7017	2x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	36,88	36,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	36,88	36,50
				Material and Installation w/o Profit (TRY)	73,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**91,72**	

Item No	Analysis Name					UoM
35.520.7018						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7018	3x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	47,17	47,17	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,04	185,00		7,40
				Total Excluding Profit (TRY)	47,17	36,50
				Material and Installation w/o Profit (TRY)	83,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**45,63**	
				Unit Price (TRY)	**104,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7019						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7019	4x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	52,79	52,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,79	40,00
				Material and Installation w/o Profit (TRY)	92,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**50,00**	
				Unit Price (TRY)	**115,99**	

Item No	Analysis Name					UoM
35.520.7020						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7020	5x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	73,38	73,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	73,38	42,50
				Material and Installation w/o Profit (TRY)	115,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**144,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7021						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7021	6x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	86,49	86,49	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	86,49	42,50
				Material and Installation w/o Profit (TRY)	128,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**161,24**	

Item No	Analysis Name					UoM
35.520.7022						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7022	7x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	96,78	96,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	96,78	42,50
				Material and Installation w/o Profit (TRY)	139,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**174,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7023						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7023	8x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	111,76	111,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	111,76	48,50
				Material and Installation w/o Profit (TRY)	160,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**200,32**	

Item No	Analysis Name					UoM
35.520.7024						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7024	10x1.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	133,40	133,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	133,40	51,00
				Material and Installation w/o Profit (TRY)	184,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63,75**	
				Unit Price (TRY)	**230,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.520.7025						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7025	2x2.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	52,79	52,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	52,79	42,50
				Material and Installation w/o Profit (TRY)	95,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**119,11**	

Item No	Analysis Name					UoM
35.520.7026						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7026	3x2.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	71,04	71,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	71,04	42,50
				Material and Installation w/o Profit (TRY)	113,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**141,93**	

Item No	Analysis Name					UoM
35.520.7027						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7027	4x2.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	78,06	78,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	78,06	45,00
				Material and Installation w/o Profit (TRY)	123,06	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**56,25**	
				Unit Price (TRY)	**153,82**	

Item No	Analysis Name					UoM
35.520.7028						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7028	5x2.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	109,89	109,89	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	109,89	48,50
				Material and Installation w/o Profit (TRY)	158,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**197,99**	

Item No	Analysis Name					UoM
35.520.7029						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.520.7029	6x2.5 mm² / LIHCH FE180 PH120 FIRE-PROOF SIGNAL AND CONTROLLER CABLE / FIRE-RESISTANT CABLES (Market price)	m	1	127,67	127,67	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	127,67	48,50
				Material and Installation w/o Profit (TRY)	176,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**220,21**	

Item No	Analysis Name					UoM
35.540.1001	**Central Single Loose Tube with 2 fibers 1x2 62.5/125 OM1 MM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1001	Central Single Loose Tube with 2 fibers 1x2 62.5/125 OM1 MM Armored F/O Cable	m	1	16,00	16,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	16,00	39,75
				Material and Installation w/o Profit (TRY)	55,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**69,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1002	**Central Single Loose Tube with 4 fibers 1x4 62.5/125 OM1 MM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1002	Central Single Loose Tube with 4 fibers 1x4 62.5/125 OM1 MM Armored F/O Cable	m	1	18,24	18,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	18,24	44,10
				Material and Installation w/o Profit (TRY)	62,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**77,93**	

Item No	Analysis Name					UoM
35.540.1003	**Central Single Loose Tube with 6 fibers 1x6 62.5/125 OM1 MM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1003	Central Single Loose Tube with 6 fibers 1x6 62.5/125 OM1 MM Armored F/O Cable	m	1	21,84	21,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	21,84	44,10
				Material and Installation w/o Profit (TRY)	65,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**82,42**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1004	**Central Single Loose Tube with 8 fibers 1x8 62.5/125 OM1 MM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1004	Central Single Loose Tube with 8 fibers 1x8 62.5/125 OM1 MM Armored F/O Cable	m	1	25,68	25,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	25,68	48,45
				Material and Installation w/o Profit (TRY)	74,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**92,66**	

Item No	Analysis Name					UoM
35.540.1005	**Central Single Loose Tube with 12 fibers 1x12 62.5/125 OM1 MM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1005	Central Single Loose Tube with 12 fibers 1x12 62.5/125 OM1 MM Armored F/O Cable	m	1	34,00	34,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	34,00	52,80
				Material and Installation w/o Profit (TRY)	86,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**108,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1006	**Central Single Loose Tube with 24 fibers 1x24 62.5/125 OM1 MM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1006	Central Single Loose Tube with 24 fibers 1x24 62.5/125 OM1 MM Armored F/O Cable	m	1	60,65	60,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	60,65	61,50
				Material and Installation w/o Profit (TRY)	122,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**152,69**	

Item No	Analysis Name					UoM
35.540.1007						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1007	Central Multi Loose Tube with 24 fibers 2x12 62.5/125 OM1 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	72,72	72,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	72,72	61,50
				Material and Installation w/o Profit (TRY)	134,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**167,78**	

Item No	Analysis Name					UoM
35.540.1008	**Central Single Loose Tube with 2 fibers 1x2 62.5/125 OM1 MM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1008	Central Single Loose Tube with 2 fibers 1x2 62.5/125 OM1 MM Non-Armored F/O Cable	m	1	12,96	12,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	12,96	39,75
				Material and Installation w/o Profit (TRY)	52,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**65,89**	

Item No	Analysis Name					UoM
35.540.1009	**Central Single Loose Tube with 4 fibers 1x4 62.5/125 OM1 MM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1009	Central Single Loose Tube with 4 fibers 1x4 62.5/125 OM1 MM Non-Armored F/O Cable	m	1	15,36	15,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	15,36	39,75
				Material and Installation w/o Profit (TRY)	55,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**68,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1010	**Central Single Loose Tube with 6 fibers 1x6 62.5/125 OM1 MM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1010	Central Single Loose Tube with 6 fibers 1x6 62.5/125 OM1 MM Non-Armored F/O Cable	m	1	19,44	19,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	19,44	44,10
				Material and Installation w/o Profit (TRY)	63,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**79,43**	

Item No	Analysis Name					UoM
35.540.1011	**Central Single Loose Tube with 8 fibers 1x8 62.5/125 OM1 MM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1011	Central Single Loose Tube with 8 fibers 1x8 62.5/125 OM1 MM Non-Armored F/O Cable	m	1	22,88	22,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	22,88	44,10
				Material and Installation w/o Profit (TRY)	66,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**83,73**	

Item No	Analysis Name					UoM
35.540.1012	**Central Single Loose Tube with 12 fibers 1x12 62.5/125 OM1 MM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1012	Central Single Loose Tube with 12 fibers 1x12 62.5/125 OM1 MM Non-Armored F/O Cable	m	1	30,80	30,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	30,80	48,45
				Material and Installation w/o Profit (TRY)	79,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**99,06**	

Item No	Analysis Name					UoM
35.540.1013	**Central Single Loose Tube with 24 fibers 1x24 62.5/125 OM1 MM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1013	Central Single Loose Tube with 24 fibers 1x24 62.5/125 OM1 MM Non-Armored F/O Cable	m	1	55,92	55,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	55,92	57,15
				Material and Installation w/o Profit (TRY)	113,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**141,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1014						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1014	Central Multi Loose Tube with 24 fibers 2x12 62.5/125 OM1 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	66,32	66,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	66,32	57,15
				Material and Installation w/o Profit (TRY)	123,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**154,34**	

Item No	Analysis Name					UoM
35.540.1015						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1015	Central Single Loose Tube with 2 fibers 1x2 50/125 OM2 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	14,48	14,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	14,48	39,75
				Material and Installation w/o Profit (TRY)	54,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**67,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1016						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1016	Central Single Loose Tube with 4 fibers 1x4 50/125 OM2 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	15,36	15,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	15,36	44,10
				Material and Installation w/o Profit (TRY)	59,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**74,33**	

Item No	Analysis Name					UoM
35.540.1017						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1017	Central Single Loose Tube with 6 fibers 1x6 50/125 OM2 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	17,60	17,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	17,60	44,10
				Material and Installation w/o Profit (TRY)	61,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**77,13**	

Item No	Analysis Name					UoM
35.540.1018						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1018	Central Single Loose Tube with 8 fibers 1x8 50/125 OM2 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	19,68	19,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	19,68	48,45
				Material and Installation w/o Profit (TRY)	68,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**85,16**	

Item No	Analysis Name					UoM
35.540.1019						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1019	Central Single Loose Tube with 12 fibers 1x12 50/125 OM2 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	24,40	24,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	24,40	52,80
				Material and Installation w/o Profit (TRY)	77,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**96,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1020						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1020	Central Single Loose Tube with 24 fibers 1x24 50/125 OM2 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	41,92	41,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	41,92	61,50
				Material and Installation w/o Profit (TRY)	103,42	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**129,28**	

Item No	Analysis Name					UoM
35.540.1021						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1021	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM2 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	54,32	54,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	54,32	61,50
				Material and Installation w/o Profit (TRY)	115,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**144,77**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1022						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1022	Central Single Loose Tube with 2 fibers 1x2 50/125 OM2 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	11,44	11,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	11,44	39,75
				Material and Installation w/o Profit (TRY)	51,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**63,99**	

Item No	Analysis Name					UoM
35.540.1023						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1023	Central Single Loose Tube with 4 fibers 1x4 50/125 OM2 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	12,72	12,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	12,72	39,75
				Material and Installation w/o Profit (TRY)	52,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**65,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1024						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1024	Central Single Loose Tube with 6 fibers 1x6 50/125 OM2 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	14,88	14,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	14,88	44,10
				Material and Installation w/o Profit (TRY)	58,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**73,73**	

Item No	Analysis Name					UoM
35.540.1025						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1025	Central Single Loose Tube with 8 fibers 1x8 50/125 OM2 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	16,88	16,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	16,88	44,10
				Material and Installation w/o Profit (TRY)	60,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**76,23**	

Item No	Analysis Name					UoM
35.540.1026						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1026	Central Single Loose Tube with 12 fibers 1x12 50/125 OM2 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	21,20	21,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	21,20	48,45
				Material and Installation w/o Profit (TRY)	69,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**87,06**	

Item No	Analysis Name					UoM
35.540.1027						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1027	Central Single Loose Tube with 24 fibers 1x24 50/125 OM2 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	38,32	38,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	38,32	57,15
				Material and Installation w/o Profit (TRY)	95,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**119,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1028						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1028	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM2 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	47,92	47,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	47,92	57,15
				Material and Installation w/o Profit (TRY)	105,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**131,34**	

Item No	Analysis Name					UoM
35.540.1029						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1029	Central Single Loose Tube with 2 fibers 1x2 50/125 OM3 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	18,64	18,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	18,64	39,75
				Material and Installation w/o Profit (TRY)	58,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**72,99**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1030						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1030	Central Single Loose Tube with 4 fibers 1x4 50/125 OM3 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	21,04	21,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	21,04	44,10
				Material and Installation w/o Profit (TRY)	65,14	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**81,42**	

Item No	Analysis Name					UoM
35.540.1031						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1031	Central Single Loose Tube with 6 fibers 1x6 50/125 OM3 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	26,24	26,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	26,24	44,10
				Material and Installation w/o Profit (TRY)	70,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**87,93**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1032						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1032	Central Single Loose Tube with 8 fibers 1x8 50/125 OM3 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	32,08	32,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	32,08	48,45
				Material and Installation w/o Profit (TRY)	80,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**100,66**	

Item No	Analysis Name					UoM
35.540.1033						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1033	Central Single Loose Tube with 12 fibers 1x12 50/125 OM3 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	42,00	42,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	42,00	52,80
				Material and Installation w/o Profit (TRY)	94,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**118,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1034						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1034	Central Single Loose Tube with 24 fibers 1x24 50/125 OM3 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	76,72	76,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	76,72	61,50
				Material and Installation w/o Profit (TRY)	138,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**172,78**	

Item No	Analysis Name					UoM
35.540.1035						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1035	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM3 MM Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	91,12	91,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	91,12	61,50
				Material and Installation w/o Profit (TRY)	152,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**190,78**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1036						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1036	Central Single Loose Tube with 2 fibers 1x2 50/125 OM3 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	15,68	15,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	15,68	39,75
				Material and Installation w/o Profit (TRY)	55,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**69,29**	

Item No	Analysis Name					UoM
35.540.1037						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1037	Central Single Loose Tube with 4 fibers 1x4 50/125 OM3 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	18,24	18,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	18,24	39,75
				Material and Installation w/o Profit (TRY)	57,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**72,49**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1038						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1038	Central Single Loose Tube with 6 fibers 1x6 50/125 OM3 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	23,44	23,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	23,44	44,10
				Material and Installation w/o Profit (TRY)	67,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**84,43**	

Item No	Analysis Name					UoM
35.540.1039						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1039	Central Single Loose Tube with 8 fibers 1x8 50/125 OM3 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	28,88	28,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	28,88	44,10
				Material and Installation w/o Profit (TRY)	72,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**91,23**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.1040						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1040	Central Single Loose Tube with 12 fibers 1x12 50/125 OM3 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	39,60	39,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	39,60	48,45
				Material and Installation w/o Profit (TRY)	88,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**110,06**	

Item No	Analysis Name					UoM
35.540.1041						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1041	Central Single Loose Tube with 24 fibers 1x24 50/125 OM3 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	72,72	72,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	72,72	57,15
				Material and Installation w/o Profit (TRY)	129,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**162,34**	

Item No	Analysis Name					UoM
35.540.1042						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.1042	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM3 MM Non-Armored F/O Cable / MULTI-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	85,52	85,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	85,52	57,15
				Material and Installation w/o Profit (TRY)	142,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**178,34**	

Item No	Analysis Name					UoM
35.540.2001	**Central Single Loose Tube with 2 fibers 1x2 9/125 SM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2001	Central Single Loose Tube with 2 fibers 1x2 9/125 SM Armored F/O Cable	m	1	12,72	12,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	12,72	39,75
				Material and Installation w/o Profit (TRY)	52,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**65,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.2002	**Central Single Loose Tube with 4 fibers 1x4 9/125 SM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2002	Central Single Loose Tube with 4 fibers 1x4 9/125 SM Armored F/O Cable	m	1	13,44	13,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	13,44	44,10
				Material and Installation w/o Profit (TRY)	57,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**71,92**	

Item No	Analysis Name					UoM
35.540.2003	**Central Single Loose Tube with 6 fibers 1x6 9/125 SM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2003	Central Single Loose Tube with 6 fibers 1x6 9/125 SM Armored F/O Cable	m	1	14,48	14,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	14,48	44,10
				Material and Installation w/o Profit (TRY)	58,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**73,22**	

Item No	Analysis Name					UoM
35.540.2004	**Central Single Loose Tube with 8 fibers 1x8 9/125 SM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2004	Central Single Loose Tube with 8 fibers 1x8 9/125 SM Armored F/O Cable	m	1	15,28	15,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	15,28	48,45
				Material and Installation w/o Profit (TRY)	63,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**79,66**	

Item No	Analysis Name					UoM
35.540.2005	**Central Single Loose Tube with 12 fibers 1x12 9/125 SM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2005	Central Single Loose Tube with 12 fibers 1x12 9/125 SM Armored F/O Cable	m	1	18,00	18,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	18,00	52,80
				Material and Installation w/o Profit (TRY)	70,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**88,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.2006	**Central Single Loose Tube with 24 fibers 1x24 9/125 SM Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2006	Central Single Loose Tube with 24 fibers 1x24 9/125 SM Armored F/O Cable	m	1	28,72	28,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	28,72	61,50
				Material and Installation w/o Profit (TRY)	90,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**112,78**	

Item No	Analysis Name					UoM
35.540.2007						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2007	Central Multi Loose Tube with 24 fibers 2x12 9/125 SM Armored F/O Cable / SINGLE-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	38,72	38,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	38,72	61,50
				Material and Installation w/o Profit (TRY)	100,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**125,28**	

Item No	Analysis Name					UoM
35.540.2008	**Central Single Loose Tube with 2 fibers 1x2 9/125 SM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2008	Central Single Loose Tube with 2 fibers 1x2 9/125 SM Non-Armored F/O Cable	m	1	10,00	10,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	10,00	39,75
				Material and Installation w/o Profit (TRY)	49,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**62,19**	

Item No	Analysis Name					UoM
35.540.2009	**Central Single Loose Tube with 4 fibers 1x4 9/125 SM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2009	Central Single Loose Tube with 4 fibers 1x4 9/125 SM Non-Armored F/O Cable	m	1	10,40	10,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician's helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	10,40	39,75
				Material and Installation w/o Profit (TRY)	50,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**62,69**	

Item No	Analysis Name					UoM
35.540.2010	**Central Single Loose Tube with 6 fibers 1x6 9/125 SM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2010	Central Single Loose Tube with 6 fibers 1x6 9/125 SM Non-Armored F/O Cable	m	1	11,44	11,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			11,44	44,10
		Material and Installation w/o Profit (TRY)			55,54	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**55,13**	
		Unit Price (TRY)			**69,42**	

Item No	Analysis Name					UoM
35.540.2011	**Central Single Loose Tube with 8 fibers 1x8 9/125 SM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2011	Central Single Loose Tube with 8 fibers 1x8 9/125 SM Non-Armored F/O Cable	m	1	12,72	12,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
		Total Excluding Profit (TRY)			12,72	44,10
		Material and Installation w/o Profit (TRY)			56,82	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**55,13**	
		Unit Price (TRY)			**71,03**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.2012	**Central Single Loose Tube with 12 fibers 1x12 9/125 SM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2012	Central Single Loose Tube with 12 fibers 1x12 9/125 SM Non-Armored F/O Cable	m	1	15,60	15,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	15,60	48,45
				Material and Installation w/o Profit (TRY)	64,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**80,06**	

Item No	Analysis Name					UoM
35.540.2013	**Central Single Loose Tube with 24 fibers 1x24 9/125 SM Non-Armored F/O Cable**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2013	Central Single Loose Tube with 24 fibers 1x24 9/125 SM Non-Armored F/O Cable	m	1	25,12	25,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	25,12	57,15
				Material and Installation w/o Profit (TRY)	82,27	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**102,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.2014						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.2014	Central Multi Loose Tube with 24 fibers 2x12 9/125 SM Non-Armored F/O Cable / SINGLE-MODE FIBER OPTIC CABLE / FIBER OPTIC CABLES (Market price)	m	1	33,92	33,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	33,92	57,15
				Material and Installation w/o Profit (TRY)	91,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**113,84**	

Item No	Analysis Name					UoM
35.540.3001						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3001	Central Single Loose Tube with 2 fibers 1x2 62.5/125 OM1 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	19,44	19,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	19,44	39,75
				Material and Installation w/o Profit (TRY)	59,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**73,99**	

Item No	Analysis Name					UoM
35.540.3002						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3002	Central Single Loose Tube with 4 fibers 1x4 62.5/125 OM1 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	21,44	21,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	21,44	44,10
				Material and Installation w/o Profit (TRY)	65,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**81,93**	

Item No	Analysis Name					UoM
35.540.3003						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3003	Central Single Loose Tube with 6 fibers 1x6 62.5/125 OM1 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	24,64	24,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	24,64	44,10
				Material and Installation w/o Profit (TRY)	68,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**85,93**	

Item No	Analysis Name					UoM
35.540.3004						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3004	Central Single Loose Tube with 8 fibers 1x8 62.5/125 OM1 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	28,88	28,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	28,88	48,45
				Material and Installation w/o Profit (TRY)	77,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**96,66**	

Item No	Analysis Name					UoM
35.540.3005						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3005	Central Single Loose Tube with 12 fibers 1x12 62.5/125 OM1 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	36,40	36,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	36,40	52,80
				Material and Installation w/o Profit (TRY)	89,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**111,50**	

Item No	Analysis Name					UoM
35.540.3006						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3006	Central Single Loose Tube with 24 fibers 1x24 62.5/125 OM1 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	63,12	63,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	63,12	61,50
				Material and Installation w/o Profit (TRY)	124,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**155,78**	

Item No	Analysis Name					UoM
35.540.3007						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3007	Central Multi Loose Tube with 24 fibers 2x12 62.5/125 OM1 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	76,72	76,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician's helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	76,72	61,50
				Material and Installation w/o Profit (TRY)	138,22	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**172,78**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3008						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3008	Central Single Loose Tube with 2 fibers 1x2 62.5/125 OM1 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	15,36	15,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	15,36	39,75
				Material and Installation w/o Profit (TRY)	55,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**68,89**	

Item No	Analysis Name					UoM
35.540.3009						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3009	Central Single Loose Tube with 4 fibers 1x4 62.5/125 OM1 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	17,04	17,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	17,04	39,75
				Material and Installation w/o Profit (TRY)	56,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**70,99**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3010						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3010	Central Single Loose Tube with 6 fibers 1x6 62.5/125 OM1 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	21,04	21,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	21,04	44,10
				Material and Installation w/o Profit (TRY)	65,14	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**81,42**	

Item No	Analysis Name					UoM
35.540.3011						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3011	Central Single Loose Tube with 8 fibers 1x8 62.5/125 OM1 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	24,88	24,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	24,88	44,10
				Material and Installation w/o Profit (TRY)	68,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**86,23**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3012						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3012	Central Single Loose Tube with 12 fibers 1x12 62.5/125 OM1 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	32,40	32,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	32,40	48,45
				Material and Installation w/o Profit (TRY)	80,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**101,06**	

Item No	Analysis Name					UoM
35.540.3013						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3013	Central Single Loose Tube with 24 fibers 1x24 62.5/125 OM1 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	57,52	57,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	57,52	57,15
				Material and Installation w/o Profit (TRY)	114,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**143,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3014						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3014	Central Multi Loose Tube with 24 fibers 2x12 62.5/125 OM1 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	69,52	69,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	69,52	57,15
				Material and Installation w/o Profit (TRY)	126,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**158,34**	

Item No	Analysis Name					UoM
35.540.3015						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3015	Central Single Loose Tube with 2 fibers 1x2 50/125 OM2 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	17,60	17,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	17,60	39,75
				Material and Installation w/o Profit (TRY)	57,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**71,69**	

Item No	Analysis Name					UoM
35.540.3016						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3016	Central Single Loose Tube with 4 fibers 1x4 50/125 OM2 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	18,24	18,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	18,24	44,10
				Material and Installation w/o Profit (TRY)	62,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**77,93**	

Item No	Analysis Name					UoM
35.540.3017						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3017	Central Single Loose Tube with 6 fibers 1x6 50/125 OM2 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	20,64	20,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	20,64	44,10
				Material and Installation w/o Profit (TRY)	64,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**80,93**	

Item No	Analysis Name					UoM
35.540.3018						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3018	Central Single Loose Tube with 8 fibers 1x8 50/125 OM2 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	22,88	22,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	22,88	48,45
				Material and Installation w/o Profit (TRY)	71,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**89,16**	

Item No	Analysis Name					UoM
35.540.3019						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3019	Central Single Loose Tube with 12 fibers 1x12 50/125 OM2 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	27,60	27,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	27,60	52,80
				Material and Installation w/o Profit (TRY)	80,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**100,50**	

Item No	Analysis Name					UoM
35.540.3020						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3020	Central Single Loose Tube with 24 fibers 1x24 50/125 OM2 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	44,72	44,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	44,72	61,50
				Material and Installation w/o Profit (TRY)	106,22	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**132,78**	

Item No	Analysis Name					UoM
35.540.3021						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3021	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM2 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	58,32	58,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	58,32	61,50
				Material and Installation w/o Profit (TRY)	119,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**149,77**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3022						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3022	Central Single Loose Tube with 2 fibers 1x2 50/125 OM2 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	13,44	13,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	13,44	39,75
				Material and Installation w/o Profit (TRY)	53,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**66,49**	

Item No	Analysis Name					UoM
35.540.3023						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3023	Central Single Loose Tube with 4 fibers 1x4 50/125 OM2 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	14,00	14,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	14,00	39,75
				Material and Installation w/o Profit (TRY)	53,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**67,19**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3024						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3024	Central Single Loose Tube with 6 fibers 1x6 50/125 OM2 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	16,64	16,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	16,64	44,10
				Material and Installation w/o Profit (TRY)	60,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**75,92**	

Item No	Analysis Name					UoM
35.540.3025						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3025	Central Single Loose Tube with 8 fibers 1x8 50/125 OM2 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	18,88	18,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	18,88	44,10
				Material and Installation w/o Profit (TRY)	62,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**78,73**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3026						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3026	Central Single Loose Tube with 12 fibers 1x12 50/125 OM2 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	23,20	23,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	23,20	48,45
				Material and Installation w/o Profit (TRY)	71,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**89,56**	

Item No	Analysis Name					UoM
35.540.3027						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3027	Central Single Loose Tube with 24 fibers 1x24 50/125 OM2 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	40,32	40,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	40,32	57,15
				Material and Installation w/o Profit (TRY)	97,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**121,84**	

Item No	Analysis Name					UoM
35.540.3028						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3028	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM2 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	51,92	51,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	51,92	57,15
				Material and Installation w/o Profit (TRY)	109,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**136,34**	

Item No	Analysis Name					UoM
35.540.3029						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3029	Central Single Loose Tube with 2 fibers 1x2 50/125 OM3 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	21,84	21,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	21,84	39,75
				Material and Installation w/o Profit (TRY)	61,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**76,99**	

Item No	Analysis Name					UoM
35.540.3030						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3030	Central Single Loose Tube with 4 fibers 1x4 50/125 OM3 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	24,24	24,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	24,24	44,10
				Material and Installation w/o Profit (TRY)	68,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**85,43**	

Item No	Analysis Name					UoM
35.540.3031						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3031	Central Single Loose Tube with 6 fibers 1x6 50/125 OM3 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	29,44	29,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	29,44	44,10
				Material and Installation w/o Profit (TRY)	73,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**91,93**	

Item No	Analysis Name					UoM
35.540.3032						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3032	Central Single Loose Tube with 8 fibers 1x8 50/125 OM3 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	34,48	34,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	34,48	48,45
				Material and Installation w/o Profit (TRY)	82,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**103,66**	

Item No	Analysis Name					UoM
35.540.3033						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3033	Central Single Loose Tube with 12 fibers 1x12 50/125 OM3 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	44,80	44,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	44,80	52,80
				Material and Installation w/o Profit (TRY)	97,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**122,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3034						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3034	Central Single Loose Tube with 24 fibers 1x24 50/125 OM3 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	79,92	79,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	79,92	61,50
				Material and Installation w/o Profit (TRY)	141,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**176,78**	

Item No	Analysis Name					UoM
35.540.3035						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3035	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM3 MM Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	95,92	95,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	95,92	61,50
				Material and Installation w/o Profit (TRY)	157,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**196,78**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3036						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3036	Central Single Loose Tube with 2 fibers 1x2 50/125 OM3 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	17,60	17,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	17,60	39,75
				Material and Installation w/o Profit (TRY)	57,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**71,69**	

Item No	Analysis Name					UoM
35.540.3037						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3037	Central Single Loose Tube with 4 fibers 1x4 50/125 OM3 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	20,24	20,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	20,24	39,75
				Material and Installation w/o Profit (TRY)	59,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**74,99**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3038						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3038	Central Single Loose Tube with 6 fibers 1x6 50/125 OM3 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	25,84	25,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	25,84	44,10
				Material and Installation w/o Profit (TRY)	69,94	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**87,42**	

Item No	Analysis Name					UoM
35.540.3039						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3039	Central Single Loose Tube with 8 fibers 1x8 50/125 OM3 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	30,48	30,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician's helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	30,48	44,10
				Material and Installation w/o Profit (TRY)	74,58	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**93,22**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3040						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3040	Central Single Loose Tube with 12 fibers 1x12 50/125 OM3 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	41,60	41,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	41,60	48,45
				Material and Installation w/o Profit (TRY)	90,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**112,56**	

Item No	Analysis Name					UoM
35.540.3041						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3041	Central Single Loose Tube with 24 fibers 1x24 50/125 OM3 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	75,12	75,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	75,12	57,15
				Material and Installation w/o Profit (TRY)	132,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**165,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.3042						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.3042	Central Multi Loose Tube with 24 fibers 2x12 50/125 OM3 MM Non-Armored LSOH F/O Cable / MULTI-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	89,52	89,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	89,52	57,15
				Material and Installation w/o Profit (TRY)	146,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**183,34**	

Item No	Analysis Name					UoM
35.540.4001						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4001	Central Single Loose Tube with 2 fibers 1x2 9/125 SM Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	15,52	15,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	15,52	39,75
				Material and Installation w/o Profit (TRY)	55,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**69,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.4002						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4002	Central Single Loose Tube with 4 fibers 1x4 9/125 SM Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	16,00	16,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	16,00	44,10
				Material and Installation w/o Profit (TRY)	60,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**75,13**	

Item No	Analysis Name					UoM
35.540.4003						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4003	Central Single Loose Tube with 6 fibers 1x6 9/125 SM Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	17,04	17,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	17,04	44,10
				Material and Installation w/o Profit (TRY)	61,14	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**76,42**	

Item No	Analysis Name					UoM
35.540.4004						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4004	Central Single Loose Tube with 8 fibers 1x8 9/125 SM Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	18,88	18,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	18,88	48,45
				Material and Installation w/o Profit (TRY)	67,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**84,16**	

Item No	Analysis Name					UoM
35.540.4005						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4005	Central Single Loose Tube with 12 fibers 1x12 9/125 SM Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	21,20	21,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,11	185,00		20,35
				Total Excluding Profit (TRY)	21,20	52,80
				Material and Installation w/o Profit (TRY)	74,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**66,00**	
				Unit Price (TRY)	**92,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.4006						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4006	Central Single Loose Tube with 24 fibers 1x24 9/125 SM Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	32,32	32,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	32,32	61,50
				Material and Installation w/o Profit (TRY)	93,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**117,27**	

Item No	Analysis Name					UoM
35.540.4007						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4007	Central Multi Loose Tube with 24 fibers 2x12 9/125 SM Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	43,92	43,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,13	250,00		32,50
10.100.1083	Master electrician’s helper	h	0,13	185,00		24,05
				Total Excluding Profit (TRY)	43,92	61,50
				Material and Installation w/o Profit (TRY)	105,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**76,88**	
				Unit Price (TRY)	**131,78**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.4008						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4008	Central Single Loose Tube with 2 fibers 1x2 9/125 SM Non-Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	11,44	11,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	11,44	39,75
				Material and Installation w/o Profit (TRY)	51,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**63,99**	

Item No	Analysis Name					UoM
35.540.4009						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4009	Central Single Loose Tube with 4 fibers 1x4 9/125 SM Non-Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	12,16	12,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	12,16	39,75
				Material and Installation w/o Profit (TRY)	51,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49,69**	
				Unit Price (TRY)	**64,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.4010						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4010	Central Single Loose Tube with 6 fibers 1x6 9/125 SM Non-Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	13,44	13,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	13,44	44,10
				Material and Installation w/o Profit (TRY)	57,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**71,92**	

Item No	Analysis Name					UoM
35.540.4011						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4011	Central Single Loose Tube with 8 fibers 1x8 9/125 SM Non-Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	14,24	14,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,09	250,00		22,50
10.100.1083	Master electrician’s helper	h	0,09	185,00		16,65
				Total Excluding Profit (TRY)	14,24	44,10
				Material and Installation w/o Profit (TRY)	58,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55,13**	
				Unit Price (TRY)	**72,93**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.4012						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4012	Central Single Loose Tube with 12 fibers 1x12 9/125 SM Non-Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	16,80	16,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	16,80	48,45
				Material and Installation w/o Profit (TRY)	65,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,56**	
				Unit Price (TRY)	**81,56**	

Item No	Analysis Name					UoM
35.540.4013						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4013	Central Single Loose Tube with 24 fibers 1x24 9/125 SM Non-Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	27,52	27,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician’s helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	27,52	57,15
				Material and Installation w/o Profit (TRY)	84,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**105,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.540.4014						**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.540.4014	Central Multi Loose Tube with 24 fibers 2x12 9/125 SM Non-Armored LSOH F/O Cable / SINGLE-MODE FIBER OPTIC CABLE - LSOH / FIBER OPTIC CABLES (Market price)	m	1	37,52	37,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,03	165,00		4,95
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	37,52	57,15
				Material and Installation w/o Profit (TRY)	94,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**71,44**	
				Unit Price (TRY)	**118,34**	

Item No	Analysis Name					UoM
35.545.1001	**SM LC pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1001	SM LC pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	106,80	106,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	106,80	45,15
				Material and Installation w/o Profit (TRY)	151,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**189,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.1002	**SM SC pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1002	SM SC pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	124,40	124,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	124,40	45,15
				Material and Installation w/o Profit (TRY)	169,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**211,94**	

Item No	Analysis Name					UoM
35.545.1003	**SM FC pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1003	SM FC pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	126,00	126,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	126,00	45,15
				Material and Installation w/o Profit (TRY)	171,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**213,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.1004	**SM MTRJ pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1004	SM MTRJ pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	153,60	153,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	153,60	45,15
				Material and Installation w/o Profit (TRY)	198,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**248,44**	

Item No	Analysis Name					UoM
35.545.1005	**SM ST pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1005	SM ST pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	102,00	102,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	102,00	45,15
				Material and Installation w/o Profit (TRY)	147,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**183,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.1006	**MM LC pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1006	MM LC pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	70,16	70,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	70,16	45,15
				Material and Installation w/o Profit (TRY)	115,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**144,14**	

Item No	Analysis Name					UoM
35.545.1007	**MM SC pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1007	MM SC pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	66,56	66,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	66,56	45,15
				Material and Installation w/o Profit (TRY)	111,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**139,64**	

Item No	Analysis Name					UoM
35.545.1008	**MM FC pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1008	MM FC pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	136,56	136,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	136,56	45,15
				Material and Installation w/o Profit (TRY)	181,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**227,14**	

Item No	Analysis Name					UoM
35.545.1009	**MM MTRJ pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1009	MM MTRJ pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	148,64	148,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	148,64	45,15
				Material and Installation w/o Profit (TRY)	193,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**242,24**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.1010	**MM ST pigtail / Pigtail**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.1010	MM ST pigtail / PIGTAIL / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	85,20	85,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	85,20	45,15
				Material and Installation w/o Profit (TRY)	130,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**162,94**	

Item No	Analysis Name					UoM
35.545.2101	**SM LC-LC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2101	SM LC-LC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	174,68	174,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	174,68	45,15
				Material and Installation w/o Profit (TRY)	219,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**274,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2102	**SM LC-ST patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2102	SM LC-ST patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	147,40	147,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	147,40	45,15
				Material and Installation w/o Profit (TRY)	192,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**240,69**	

Item No	Analysis Name					UoM
35.545.2103	**SM LC-SC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2103	SM LC-SC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	147,40	147,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	147,40	45,15
				Material and Installation w/o Profit (TRY)	192,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**240,69**	

Item No	Analysis Name					UoM
35.545.2104	**SM LC-FC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2104	SM LC-FC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	161,39	161,39	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			161,39	45,15
		Material and Installation w/o Profit (TRY)			206,54	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**258,18**	

Item No	Analysis Name					UoM
35.545.2105	**SM ST-ST patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2105	SM ST-ST patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	78,06	78,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			78,06	45,15
		Material and Installation w/o Profit (TRY)			123,21	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**154,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2106	**SM ST-SC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2106	SM ST-SC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	90,38	90,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			90,38	45,15
		Material and Installation w/o Profit (TRY)			135,53	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**169,41**	

Item No	Analysis Name					UoM
35.545.2107	**SM ST-FC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2107	SM ST-FC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	111,50	111,50	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			111,50	45,15
		Material and Installation w/o Profit (TRY)			156,65	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**195,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2108	**SM SC-SC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2108	SM SC-SC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	97,68	97,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			97,68	45,15
		Material and Installation w/o Profit (TRY)			142,83	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**178,54**	

Item No	Analysis Name					UoM
35.545.2109	**SM SC-FC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2109	SM SC-FC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	121,62	121,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			121,62	45,15
		Material and Installation w/o Profit (TRY)			166,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**208,46**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2110	**SM FC-FC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2110	SM FC-FC patch cord / 3 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	135,26	135,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			135,26	45,15
		Material and Installation w/o Profit (TRY)			180,41	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**225,51**	

Item No	Analysis Name					UoM
35.545.2111	**SM MTRJ-MTRJ patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2111	SM MTRJ-MTRJ patch cord / 3 M SM PATCH CORDs / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2112	**SM MTRJ-ST patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2112	SM MTRJ-ST patch cord / 3 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Item No	Analysis Name					UoM
35.545.2113	**SM MTRJ-SC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2113	SM MTRJ-SC patch cord / 3 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Item No	Analysis Name					UoM
35.545.2114	**SM MTRJ-LC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2114	SM MTRJ-LC patch cords / 3 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Item No	Analysis Name					UoM
35.545.2115	**SM MTRJ-FC patch cord / 3 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2115	SM MTRJ-FC patch cords / 3 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Item No	Analysis Name					UoM
35.545.2201	**SM LC-LC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2201	SM LC-LC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	188,06	188,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			188,06	45,15
		Material and Installation w/o Profit (TRY)			233,21	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**291,51**	

Item No	Analysis Name					UoM
35.545.2202	**SM LC-ST patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2202	SM LC-ST patch cord / 6 M SM PATCH CORDS / Patch cord (Market price)	Qty	1	155,94	155,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			155,94	45,15
		Material and Installation w/o Profit (TRY)			201,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**251,36**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2203	**SM LC-SC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2203	SM LC-SC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	155,94	155,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			155,94	45,15
		Material and Installation w/o Profit (TRY)			201,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**251,36**	

Item No	Analysis Name					UoM
35.545.2204	**SM LC-FC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2204	SM LC-FC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	169,05	169,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			169,05	45,15
		Material and Installation w/o Profit (TRY)			214,20	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**267,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2205	**SM ST-ST patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2205	SM ST-ST patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	88,62	88,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			88,62	45,15
		Material and Installation w/o Profit (TRY)			133,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**167,21**	

Item No	Analysis Name					UoM
35.545.2206	**SM ST-SC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2206	SM ST-SC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	101,20	101,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			101,20	45,15
		Material and Installation w/o Profit (TRY)			146,35	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**182,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2207	**SM ST-FC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2207	SM ST-FC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	124,26	124,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			124,26	45,15
		Material and Installation w/o Profit (TRY)			169,41	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**211,76**	

Item No	Analysis Name					UoM
35.545.2208	**SM SC-SC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2208	SM SC-SC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	107,71	107,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			107,71	45,15
		Material and Installation w/o Profit (TRY)			152,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**191,07**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2209	**SM SC-FC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2209	SM SC-FC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	130,68	130,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			130,68	45,15
		Material and Installation w/o Profit (TRY)			175,83	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**219,79**	

Item No	Analysis Name					UoM
35.545.2210	**SM FC-FC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2210	SM FC-FC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	147,75	147,75	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			147,75	45,15
		Material and Installation w/o Profit (TRY)			192,90	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**241,13**	

Item No	Analysis Name					UoM
35.545.2211	**SM MTRJ-MTRJ patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2211	SM MTRJ-MTRJ patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	177,94	177,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			177,94	45,15
		Material and Installation w/o Profit (TRY)			223,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**278,86**	

Item No	Analysis Name					UoM
35.545.2212	**SM MTRJ-ST patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2212	SM MTRJ-ST patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	177,94	177,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			177,94	45,15
		Material and Installation w/o Profit (TRY)			223,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**278,86**	

Item No	Analysis Name					UoM
35.545.2213	**SM MTRJ-SC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2213	SM MTRJ-SC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	177,94	177,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			177,94	45,15
		Material and Installation w/o Profit (TRY)			223,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**278,86**	

Item No	Analysis Name					UoM
35.545.2214	**SM MTRJ-LC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2214	SM MTRJ-LC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	177,94	177,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			177,94	45,15
		Material and Installation w/o Profit (TRY)			223,09	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**278,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2215	**SM MTRJ-FC patch cord / 6 M SM PATCH CORDS / Patch cord**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2215	SM MTRJ-FC patch cords / 6 M SM PATCH CORDS / Patch cords (Market price)	Qty	1	177,94	177,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	177,94	45,15
				Material and Installation w/o Profit (TRY)	223,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**278,86**	

Item No	Analysis Name					UoM
35.545.2301	**MM LC-LC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2301	MM LC-LC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	214,72	214,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	214,72	45,15
				Material and Installation w/o Profit (TRY)	259,87	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**56,44**	
				Unit Price (TRY)	**324,84**	

Item No	Analysis Name					UoM
35.545.2302	**MM LC-ST patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2302	MM LC-ST patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	159,46	159,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			159,46	45,15
		Material and Installation w/o Profit (TRY)			204,61	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**255,76**	

Item No	Analysis Name					UoM
35.545.2303	**MM LC-SC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2303	MM LC-SC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	166,41	166,41	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			166,41	45,15
		Material and Installation w/o Profit (TRY)			211,56	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**264,45**	

Item No	Analysis Name					UoM
35.545.2304	**MM LC-FC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2304	MM LC-FC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	180,84	180,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			180,84	45,15
		Material and Installation w/o Profit (TRY)			225,99	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**282,49**	

Item No	Analysis Name					UoM
35.545.2305	**MM ST-ST patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2305	MM ST-ST patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	63,80	63,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			63,80	45,15
		Material and Installation w/o Profit (TRY)			108,95	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**136,19**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2306	**MM ST-SC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2306	MM ST-SC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	71,54	71,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			71,54	45,15
		Material and Installation w/o Profit (TRY)			116,69	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**145,86**	

Item No	Analysis Name					UoM
35.545.2307	**MM ST-FC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2307	MM ST-FC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	155,23	155,23	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			155,23	45,15
		Material and Installation w/o Profit (TRY)			200,38	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**250,47**	

Item No	Analysis Name					UoM
35.545.2308	**MM SC-SC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2308	MM SC-SC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	73,66	73,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			73,66	45,15
		Material and Installation w/o Profit (TRY)			118,81	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**148,51**	

Item No	Analysis Name					UoM
35.545.2309	**MM SC-FC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2309	MM SC-FC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	155,94	155,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician’s helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			155,94	45,15
		Material and Installation w/o Profit (TRY)			201,09	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**251,36**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2310	**MM FC-FC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2310	MM FC-FC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	164,91	164,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			164,91	45,15
		Material and Installation w/o Profit (TRY)			210,06	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**262,57**	

Item No	Analysis Name					UoM
35.545.2311	**MM MTRJ-MTRJ patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2311	MM MTRJ-MTRJ patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2312	**MM MTRJ-ST patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2312	MM MTRJ-ST patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Item No	Analysis Name					UoM
35.545.2313	**MM MTRJ-SC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2313	MM MTRJ-SC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Item No	Analysis Name					UoM
35.545.2314	**MM MTRJ-LC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2314	MM MTRJ-LC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Item No	Analysis Name					UoM
35.545.2315	**MM MTRJ-FC patch cords / 3 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2315	MM MTRJ-FC patch cords / 3 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	165,79	165,79	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			165,79	45,15
		Material and Installation w/o Profit (TRY)			210,94	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**263,68**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2401	**MM LC-LC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2401	MM LC-LC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	227,92	227,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			227,92	45,15
		Material and Installation w/o Profit (TRY)			273,07	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**341,34**	

Item No	Analysis Name					UoM
35.545.2402	**MM LC-ST patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2402	MM LC-ST patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	173,10	173,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			173,10	45,15
		Material and Installation w/o Profit (TRY)			218,25	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**272,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2403	**MM LC-SC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2403	MM LC-SC Patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	180,84	180,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			180,84	45,15
		Material and Installation w/o Profit (TRY)			225,99	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**282,49**	

Item No	Analysis Name					UoM
35.545.2404	**MM LC-FC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2404	MM LC-FC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	188,06	188,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			188,06	45,15
		Material and Installation w/o Profit (TRY)			233,21	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**291,51**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2405	**MM ST-ST patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2405	MM ST-ST patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	74,18	74,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			74,18	45,15
		Material and Installation w/o Profit (TRY)			119,33	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**149,16**	

Item No	Analysis Name					UoM
35.545.2406	**MM ST-SC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2406	MM ST-SC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	82,46	82,46	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			82,46	45,15
		Material and Installation w/o Profit (TRY)			127,61	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**159,51**	

Item No	Analysis Name					UoM
35.545.2407	**MM ST-FC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2407	MM ST-FC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	169,05	169,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			169,05	45,15
		Material and Installation w/o Profit (TRY)			214,20	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**267,75**	

Item No	Analysis Name					UoM
35.545.2408	**MM SC-SC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2408	MM SC-SC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	88,62	88,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			88,62	45,15
		Material and Installation w/o Profit (TRY)			133,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**167,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2409	**MM SC-FC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2409	MM SC-FC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	169,05	169,05	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			169,05	45,15
		Material and Installation w/o Profit (TRY)			214,20	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**267,75**	

Item No	Analysis Name					UoM
35.545.2410	**MM FC-FC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2410	MM FC-FC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	174,68	174,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			174,68	45,15
		Material and Installation w/o Profit (TRY)			219,83	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**274,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2411	**MM MTRJ-MTRJ patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2411	MM MTRJ-MTRJ patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	173,71	173,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			173,71	45,15
		Material and Installation w/o Profit (TRY)			218,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**273,58**	

Item No	Analysis Name					UoM
35.545.2412	**MM MTRJ-ST patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2412	MM MTRJ-ST patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	173,71	173,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			173,71	45,15
		Material and Installation w/o Profit (TRY)			218,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**273,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2413	**MM MTRJ-SC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2413	MM MTRJ-SC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	173,71	173,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			173,71	45,15
		Material and Installation w/o Profit (TRY)			218,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**273,58**	

Item No	Analysis Name					UoM
35.545.2414	**MM MTRJ-LC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2414	MM MTRJ-LC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	173,71	173,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			173,71	45,15
		Material and Installation w/o Profit (TRY)			218,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**273,58**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.2415	**MM MTRJ-FC patch cords / 6 M MM PATCH CORDS / Patch cords**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.2415	MM MTRJ-FC patch cords / 6 M MM PATCH CORDS / Patch cords (Market price)	Qty	1	173,71	173,71	
	Installation Components					
10.100.1062	Unskilled worker	h	0,01	165,00		1,65
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
		Total Excluding Profit (TRY)			173,71	45,15
		Material and Installation w/o Profit (TRY)			218,86	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**56,44**	
		Unit Price (TRY)			**273,58**	

Item No	Analysis Name					UoM
35.545.3001	**ST / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3001	ST / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.071,20	1.071,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
		Total Excluding Profit (TRY)			1.071,20	476,25
		Material and Installation w/o Profit (TRY)			1.547,45	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**595,31**	
		Unit Price (TRY)			**1.934,31**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3002	**ST / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3002	ST / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.158,56	1.158,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.158,56	519,75
				Material and Installation w/o Profit (TRY)	1.678,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.097,89**	

Item No	Analysis Name					UoM
35.545.3003	**ST / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3003	ST / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.239,68	1.239,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.239,68	606,75
				Material and Installation w/o Profit (TRY)	1.846,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.308,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3004	**ST / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3004	ST / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.369,68	1.369,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.369,68	693,75
				Material and Installation w/o Profit (TRY)	2.063,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.579,29**	

Item No	Analysis Name					UoM
35.545.3005	**ST / MM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3005	ST / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.222,48	2.222,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.222,48	911,25
				Material and Installation w/o Profit (TRY)	3.133,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.917,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3006	**SC / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3006	SC / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.081,60	1.081,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.081,60	476,25
				Material and Installation w/o Profit (TRY)	1.557,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**1.947,31**	

Item No	Analysis Name					UoM
35.545.3007	**SC / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3007	SC / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.134,64	1.134,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.134,64	519,75
				Material and Installation w/o Profit (TRY)	1.654,39	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.067,99**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3008	**SC / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3008	SC / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.219,92	1.219,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.219,92	606,75
				Material and Installation w/o Profit (TRY)	1.826,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.283,34**	

Item No	Analysis Name					UoM
35.545.3009	**SC / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3009	SC / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.350,96	1.350,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.350,96	693,75
				Material and Installation w/o Profit (TRY)	2.044,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.555,89**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3010	**SC / MM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3010	SC / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.013,44	2.013,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.013,44	911,25
				Material and Installation w/o Profit (TRY)	2.924,69	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.655,86**	

Item No	Analysis Name					UoM
35.545.3011	**FC / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3011	FC / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.157,52	1.157,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.157,52	476,25
				Material and Installation w/o Profit (TRY)	1.633,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.042,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3012	**FC / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3012	FC / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.243,84	1.243,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.243,84	519,75
				Material and Installation w/o Profit (TRY)	1.763,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.204,49**	

Item No	Analysis Name					UoM
35.545.3013	**FC / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3013	FC / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.329,12	1.329,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.329,12	606,75
				Material and Installation w/o Profit (TRY)	1.935,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.419,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3014	**FC / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3014	FC / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.577,68	1.577,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.577,68	693,75
				Material and Installation w/o Profit (TRY)	2.271,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.839,29**	

Item No	Analysis Name					UoM
35.545.3015	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3015	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.060,80	1.060,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.060,80	476,25
				Material and Installation w/o Profit (TRY)	1.537,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**1.921,31**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3016	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3016	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.137,76	1.137,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.137,76	519,75
				Material and Installation w/o Profit (TRY)	1.657,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.071,89**	

Item No	Analysis Name					UoM
35.545.3017	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3017	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.178,32	1.178,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.178,32	606,75
				Material and Installation w/o Profit (TRY)	1.785,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.231,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3018	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3018	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.322,88	1.322,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.322,88	693,75
				Material and Installation w/o Profit (TRY)	2.016,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.520,79**	

Item No	Analysis Name					UoM
35.545.3019	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3019	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	1.885,52	1.885,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	1.885,52	911,25
				Material and Installation w/o Profit (TRY)	2.796,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.495,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3020	**LC / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3020	LC / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.157,52	1.157,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.157,52	476,25
				Material and Installation w/o Profit (TRY)	1.633,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.042,21**	

Item No	Analysis Name					UoM
35.545.3021	**LC / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3021	LC / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.226,16	1.226,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.226,16	519,75
				Material and Installation w/o Profit (TRY)	1.745,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.182,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3022	**LC / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3022	LC / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.302,08	1.302,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.302,08	606,75
				Material and Installation w/o Profit (TRY)	1.908,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.386,04**	

Item No	Analysis Name					UoM
35.545.3023	**LC / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3023	LC / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.516,32	1.516,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.516,32	693,75
				Material and Installation w/o Profit (TRY)	2.210,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.762,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3024	**LC / MM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3024	LC / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.300,48	2.300,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.300,48	911,25
				Material and Installation w/o Profit (TRY)	3.211,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.014,66**	

Item No	Analysis Name					UoM
35.545.3025	**ST / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3025	ST / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.105,52	1.105,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.105,52	476,25
				Material and Installation w/o Profit (TRY)	1.581,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**1.977,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3026	**ST / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3026	ST / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.157,52	1.157,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.157,52	519,75
				Material and Installation w/o Profit (TRY)	1.677,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.096,59**	

Item No	Analysis Name					UoM
35.545.3027	**ST / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3027	ST / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.268,80	1.268,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.268,80	606,75
				Material and Installation w/o Profit (TRY)	1.875,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.344,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3028	**ST / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3028	ST / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.447,68	1.447,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.447,68	693,75
				Material and Installation w/o Profit (TRY)	2.141,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.676,79**	

Item No	Analysis Name					UoM
35.545.3029	**ST / SM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3029	ST / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.288,00	2.288,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.288,00	911,25
				Material and Installation w/o Profit (TRY)	3.199,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.999,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3030	**SC / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3030	SC / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.150,24	1.150,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.150,24	476,25
				Material and Installation w/o Profit (TRY)	1.626,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.033,11**	

Item No	Analysis Name					UoM
35.545.3031	**SC / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3031	SC / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.200,16	1.200,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.200,16	519,75
				Material and Installation w/o Profit (TRY)	1.719,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.149,89**	

Item No	Analysis Name					UoM
35.545.3032	**SC / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3032	SC / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.306,24	1.306,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.306,24	606,75
				Material and Installation w/o Profit (TRY)	1.912,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.391,24**	

Item No	Analysis Name					UoM
35.545.3033	**SC / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3033	SC / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.557,92	1.557,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.557,92	693,75
				Material and Installation w/o Profit (TRY)	2.251,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.814,59**	

Item No	Analysis Name					UoM
35.545.3034	**SC / SM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3034	SC / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.113,28	2.113,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.113,28	911,25
				Material and Installation w/o Profit (TRY)	3.024,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.780,66**	

Item No	Analysis Name					UoM
35.545.3035	**FC / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3035	FC / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.157,52	1.157,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.157,52	476,25
				Material and Installation w/o Profit (TRY)	1.633,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.042,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3036	**FC / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3036	FC / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.243,84	1.243,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.243,84	519,75
				Material and Installation w/o Profit (TRY)	1.763,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.204,49**	

Item No	Analysis Name					UoM
35.545.3037	**FC / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3037	FC / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.329,12	1.329,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.329,12	606,75
				Material and Installation w/o Profit (TRY)	1.935,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.419,84**	

Item No	Analysis Name					UoM
35.545.3038	**FC / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3038	FC / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.577,68	1.577,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.577,68	693,75
				Material and Installation w/o Profit (TRY)	2.271,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.839,29**	

Item No	Analysis Name					UoM
35.545.3039	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3039	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.071,20	1.071,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.071,20	476,25
				Material and Installation w/o Profit (TRY)	1.547,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**1.934,31**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3040	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3040	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.096,16	1.096,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician's helper	h	1,1	185,00		203,50
		Total Excluding Profit (TRY)			1.096,16	519,75
		Material and Installation w/o Profit (TRY)			1.615,91	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**649,69**	
		Unit Price (TRY)			**2.019,89**	

Item No	Analysis Name					UoM
35.545.3041	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3041	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.178,32	1.178,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
		Total Excluding Profit (TRY)			1.178,32	606,75
		Material and Installation w/o Profit (TRY)			1.785,07	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**758,44**	
		Unit Price (TRY)			**2.231,34**	

Item No	Analysis Name					UoM
35.545.3042	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3042	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.327,04	1.327,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician's helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.327,04	693,75
				Material and Installation w/o Profit (TRY)	2.020,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.525,99**	

Item No	Analysis Name					UoM
35.545.3043	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3043	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	1.925,04	1.925,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	1.925,04	911,25
				Material and Installation w/o Profit (TRY)	2.836,29	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.545,36**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3044	**LC / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3044	LC / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.182,48	1.182,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.182,48	476,25
				Material and Installation w/o Profit (TRY)	1.658,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.073,41**	

Item No	Analysis Name					UoM
35.545.3045	**LC / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3045	LC / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	1.266,72	1.266,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,1	250,00		275,00
10.100.1083	Master electrician’s helper	h	1,1	185,00		203,50
				Total Excluding Profit (TRY)	1.266,72	519,75
				Material and Installation w/o Profit (TRY)	1.786,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**649,69**	
				Unit Price (TRY)	**2.233,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.3046	**LC / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3046	LC / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	1.344,72	1.344,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.344,72	606,75
				Material and Installation w/o Profit (TRY)	1.951,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.439,34**	

Item No	Analysis Name					UoM
35.545.3047	**LC / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3047	LC / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	1.592,24	1.592,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.592,24	693,75
				Material and Installation w/o Profit (TRY)	2.285,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.857,49**	

Item No	Analysis Name					UoM
35.545.3048	**LC / SM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.3048	LC / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.371,20	2.371,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.371,20	911,25
				Material and Installation w/o Profit (TRY)	3.282,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.103,06**	

Item No	Analysis Name					UoM
35.545.4001	**ST / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4001	ST / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.012,40	2.012,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.012,40	911,25
				Material and Installation w/o Profit (TRY)	2.923,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.654,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4002	**ST / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4002	ST / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.075,84	2.075,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.075,84	1.041,75
				Material and Installation w/o Profit (TRY)	3.117,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.896,99**	

Item No	Analysis Name					UoM
35.545.4003	**ST / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4003	ST / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.092,48	2.092,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.092,48	1.041,75
				Material and Installation w/o Profit (TRY)	3.134,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.917,79**	

Item No	Analysis Name					UoM
35.545.4004	**ST / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4004	ST / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.142,40	2.142,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.142,40	1.128,75
				Material and Installation w/o Profit (TRY)	3.271,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.088,94**	

Item No	Analysis Name					UoM
35.545.4005	**ST / MM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4005	ST / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.681,12	2.681,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	2.681,12	1.346,25
				Material and Installation w/o Profit (TRY)	4.027,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.034,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4006	**ST / MM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4006	ST / MM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	3.411,20	3.411,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	3.411,20	1.563,75
				Material and Installation w/o Profit (TRY)	4.974,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**6.218,69**	

Item No	Analysis Name					UoM
35.545.4007	**ST / MM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4007	ST / MM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	3.910,40	3.910,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	3.910,40	1.781,25
				Material and Installation w/o Profit (TRY)	5.691,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**7.114,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4008	**SC / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4008	SC / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.017,60	2.017,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.017,60	911,25
				Material and Installation w/o Profit (TRY)	2.928,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.661,06**	

Item No	Analysis Name					UoM
35.545.4009	**SC / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4009	SC / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.050,88	2.050,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.050,88	1.041,75
				Material and Installation w/o Profit (TRY)	3.092,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.865,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4010	**SC / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4010	SC / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.113,28	2.113,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.113,28	1.041,75
				Material and Installation w/o Profit (TRY)	3.155,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.943,79**	

Item No	Analysis Name					UoM
35.545.4011	**SC / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4011	SC / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.218,32	2.218,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.218,32	1.128,75
				Material and Installation w/o Profit (TRY)	3.347,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.183,84**	

Item No	Analysis Name					UoM
35.545.4012	**SC / MM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4012	SC / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.799,68	2.799,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	2.799,68	1.346,25
				Material and Installation w/o Profit (TRY)	4.145,93	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.182,41**	

Item No	Analysis Name					UoM
35.545.4013	**SC / MM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4013	SC / MM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	3.473,60	3.473,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	3.473,60	1.563,75
				Material and Installation w/o Profit (TRY)	5.037,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**6.296,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4014	**SC / MM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4014	SC / MM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.160,00	4.160,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.160,00	1.781,25
				Material and Installation w/o Profit (TRY)	5.941,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**7.426,56**	

Item No	Analysis Name					UoM
35.545.4015	**FC / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4015	FC / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.155,92	2.155,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.155,92	911,25
				Material and Installation w/o Profit (TRY)	3.067,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.833,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4016	**FC / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4016	FC / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.216,24	2.216,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.216,24	1.041,75
				Material and Installation w/o Profit (TRY)	3.257,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.072,49**	

Item No	Analysis Name					UoM
35.545.4017	**FC / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4017	FC / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.283,84	2.283,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.283,84	1.041,75
				Material and Installation w/o Profit (TRY)	3.325,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.156,99**	

Item No	Analysis Name					UoM
35.545.4018	**FC / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4018	FC / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.473,12	2.473,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.473,12	1.128,75
				Material and Installation w/o Profit (TRY)	3.601,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.502,34**	

Item No	Analysis Name					UoM
35.545.4019	**FC / MM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4019	FC / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.615,60	2.615,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	2.615,60	1.346,25
				Material and Installation w/o Profit (TRY)	3.961,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**4.952,31**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4020	**FC / MM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4020	FC / MM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	4.118,40	4.118,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	4.118,40	1.563,75
				Material and Installation w/o Profit (TRY)	5.682,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**7.102,69**	

Item No	Analysis Name					UoM
35.545.4021	**FC / MM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4021	FC / MM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.825,60	4.825,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.825,60	1.781,25
				Material and Installation w/o Profit (TRY)	6.606,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**8.258,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4022	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4022	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	1.970,80	1.970,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	1.970,80	911,25
				Material and Installation w/o Profit (TRY)	2.882,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.602,56**	

Item No	Analysis Name					UoM
35.545.4023	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4023	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.050,88	2.050,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.050,88	1.041,75
				Material and Installation w/o Profit (TRY)	3.092,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.865,79**	

Item No	Analysis Name					UoM
35.545.4024	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4024	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.155,92	2.155,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.155,92	1.041,75
				Material and Installation w/o Profit (TRY)	3.197,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.997,09**	

Item No	Analysis Name					UoM
35.545.4025	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4025	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.246,40	2.246,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.246,40	1.128,75
				Material and Installation w/o Profit (TRY)	3.375,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.218,94**	

Item No	Analysis Name					UoM
35.545.4026	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4026	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.863,12	2.863,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	2.863,12	1.346,25
				Material and Installation w/o Profit (TRY)	4.209,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.261,71**	

Item No	Analysis Name					UoM
35.545.4027	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4027	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	3.839,68	3.839,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	3.839,68	1.563,75
				Material and Installation w/o Profit (TRY)	5.403,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**6.754,29**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4028	**MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4028	MTRJ / MM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.513,60	4.513,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.513,60	1.781,25
				Material and Installation w/o Profit (TRY)	6.294,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**7.868,56**	

Item No	Analysis Name					UoM
35.545.4029	**LC / MM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4029	LC / MM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.155,92	2.155,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.155,92	911,25
				Material and Installation w/o Profit (TRY)	3.067,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.833,96**	

Item No	Analysis Name					UoM
35.545.4030	**LC / MM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4030	LC / MM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.218,32	2.218,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.218,32	1.041,75
				Material and Installation w/o Profit (TRY)	3.260,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.075,09**	

Item No	Analysis Name					UoM
35.545.4031	**LC / MM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4031	LC / MM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.301,52	2.301,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.301,52	1.041,75
				Material and Installation w/o Profit (TRY)	3.343,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.179,09**	

Item No	Analysis Name					UoM
35.545.4032	**LC / MM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4032	LC / MM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.390,96	2.390,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.390,96	1.128,75
				Material and Installation w/o Profit (TRY)	3.519,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.399,64**	

Item No	Analysis Name					UoM
35.545.4033	**LC / MM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4033	LC / MM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	3.244,80	3.244,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.244,80	1.346,25
				Material and Installation w/o Profit (TRY)	4.591,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.738,81**	

Item No	Analysis Name					UoM
35.545.4034	**LC / MM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4034	LC / MM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	3.910,40	3.910,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	3.910,40	1.563,75
				Material and Installation w/o Profit (TRY)	5.474,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**6.842,69**	

Item No	Analysis Name					UoM
35.545.4035	**LC / MM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4035	LC / MM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.659,20	4.659,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.659,20	1.781,25
				Material and Installation w/o Profit (TRY)	6.440,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**8.050,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4036	**ST / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4036	ST / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.075,84	2.075,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.075,84	911,25
				Material and Installation w/o Profit (TRY)	2.987,09	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.733,86**	

Item No	Analysis Name					UoM
35.545.4037	**ST / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4037	ST / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.118,48	2.118,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.118,48	1.041,75
				Material and Installation w/o Profit (TRY)	3.160,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.950,29**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4038	**ST / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4038	ST / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.142,40	2.142,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.142,40	1.041,75
				Material and Installation w/o Profit (TRY)	3.184,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.980,19**	

Item No	Analysis Name					UoM
35.545.4039	**ST / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4039	ST / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.246,40	2.246,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.246,40	1.128,75
				Material and Installation w/o Profit (TRY)	3.375,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.218,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4040	**ST / SM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4040	ST / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.905,76	2.905,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	2.905,76	1.346,25
				Material and Installation w/o Profit (TRY)	4.252,01	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.315,01**	

Item No	Analysis Name					UoM
35.545.4041	**ST / SM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4041	ST / SM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	3.640,00	3.640,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	3.640,00	1.563,75
				Material and Installation w/o Profit (TRY)	5.203,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**6.504,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4042	**ST / SM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4042	ST / SM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.451,20	4.451,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.451,20	1.781,25
				Material and Installation w/o Profit (TRY)	6.232,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**7.790,56**	

Item No	Analysis Name					UoM
35.545.4043	**SC / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4043	SC / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.119,52	2.119,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.119,52	911,25
				Material and Installation w/o Profit (TRY)	3.030,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.788,46**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4044	**SC / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4044	SC / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.159,04	2.159,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.159,04	1.041,75
				Material and Installation w/o Profit (TRY)	3.200,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.000,99**	

Item No	Analysis Name					UoM
35.545.4045	**SC / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4045	SC / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.217,28	2.217,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.217,28	1.041,75
				Material and Installation w/o Profit (TRY)	3.259,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.073,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4046	**SC / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4046	SC / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.387,84	2.387,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.387,84	1.128,75
				Material and Installation w/o Profit (TRY)	3.516,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.395,74**	

Item No	Analysis Name					UoM
35.545.4047	**SC / SM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4047	SC / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	3.161,60	3.161,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.161,60	1.346,25
				Material and Installation w/o Profit (TRY)	4.507,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.634,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4048	**SC / SM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4048	SC / SM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	3.827,20	3.827,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	3.827,20	1.563,75
				Material and Installation w/o Profit (TRY)	5.390,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**6.738,69**	

Item No	Analysis Name					UoM
35.545.4049	**SC / SM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4049	SC / SM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.659,20	4.659,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.659,20	1.781,25
				Material and Installation w/o Profit (TRY)	6.440,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**8.050,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4050	**FC / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4050	FC / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.155,92	2.155,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.155,92	911,25
				Material and Installation w/o Profit (TRY)	3.067,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.833,96**	

Item No	Analysis Name					UoM
35.545.4051	**FC / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4051	FC / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.216,24	2.216,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.216,24	1.041,75
				Material and Installation w/o Profit (TRY)	3.257,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.072,49**	

Item No	Analysis Name					UoM
35.545.4052	**FC / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4052	FC / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.283,84	2.283,84	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.283,84	1.041,75
				Material and Installation w/o Profit (TRY)	3.325,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.156,99**	

Item No	Analysis Name					UoM
35.545.4053	**FC / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4053	FC / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.473,12	2.473,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.473,12	1.128,75
				Material and Installation w/o Profit (TRY)	3.601,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.502,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4054	**FC / SM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4054	FC / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.594,80	2.594,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	2.594,80	1.346,25
				Material and Installation w/o Profit (TRY)	3.941,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**4.926,31**	

Item No	Analysis Name					UoM
35.545.4055	**FC / SM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4055	FC / SM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	4.118,40	4.118,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	4.118,40	1.563,75
				Material and Installation w/o Profit (TRY)	5.682,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**7.102,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4056	**FC / SM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4056	FC / SM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.825,60	4.825,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.825,60	1.781,25
				Material and Installation w/o Profit (TRY)	6.606,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**8.258,56**	

Item No	Analysis Name					UoM
35.545.4057	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4057	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.012,40	2.012,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.012,40	911,25
				Material and Installation w/o Profit (TRY)	2.923,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.654,56**	

Item No	Analysis Name					UoM
35.545.4058	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4058	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.092,48	2.092,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician's helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.092,48	1.041,75
				Material and Installation w/o Profit (TRY)	3.134,23	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.917,79**	

Item No	Analysis Name					UoM
35.545.4059	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4059	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.155,92	2.155,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician's helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.155,92	1.041,75
				Material and Installation w/o Profit (TRY)	3.197,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**3.997,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4060	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4060	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.301,52	2.301,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.301,52	1.128,75
				Material and Installation w/o Profit (TRY)	3.430,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.287,84**	

Item No	Analysis Name					UoM
35.545.4061	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4061	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	2.930,72	2.930,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	2.930,72	1.346,25
				Material and Installation w/o Profit (TRY)	4.276,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.346,21**	

Item No	Analysis Name					UoM
35.545.4062	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4062	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	3.577,60	3.577,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	3.577,60	1.563,75
				Material and Installation w/o Profit (TRY)	5.141,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**6.426,69**	

Item No	Analysis Name					UoM
35.545.4063	**MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4063	MTRJ / SM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.680,00	4.680,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.680,00	1.781,25
				Material and Installation w/o Profit (TRY)	6.461,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**8.076,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4064	**LC / SM / Rack Mount Fiber Optic Termination with 4 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4064	LC / SM / Rack Mount Fiber Optic Termination Unit with 4 Fiber Capacity (Market price)	Qty	1	2.142,40	2.142,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.142,40	911,25
				Material and Installation w/o Profit (TRY)	3.053,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.817,06**	

Item No	Analysis Name					UoM
35.545.4065	**LC / SM / Rack Mount Fiber Optic Termination with 6 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4065	LC / SM / Rack Mount Fiber Optic Termination Unit with 6 Fiber Capacity (Market price)	Qty	1	2.217,28	2.217,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.217,28	1.041,75
				Material and Installation w/o Profit (TRY)	3.259,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.073,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4066	**LC / SM / Rack Mount Fiber Optic Termination with 8 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4066	LC / SM / Rack Mount Fiber Optic Termination Unit with 8 Fiber Capacity (Market price)	Qty	1	2.288,00	2.288,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,3	250,00		575,00
10.100.1083	Master electrician’s helper	h	2,3	185,00		425,50
				Total Excluding Profit (TRY)	2.288,00	1.041,75
				Material and Installation w/o Profit (TRY)	3.329,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.302,19**	
				Unit Price (TRY)	**4.162,19**	

Item No	Analysis Name					UoM
35.545.4067	**LC / SM / Rack Mount Fiber Optic Termination with 12 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4067	LC / SM / Rack Mount Fiber Optic Termination Unit with 12 Fiber Capacity (Market price)	Qty	1	2.490,80	2.490,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.490,80	1.128,75
				Material and Installation w/o Profit (TRY)	3.619,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.524,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4068	**LC / SM / Rack Mount Fiber Optic Termination with 24 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4068	LC / SM / Rack Mount Fiber Optic Termination Unit with 24 Fiber Capacity (Market price)	Qty	1	3.307,20	3.307,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.307,20	1.346,25
				Material and Installation w/o Profit (TRY)	4.653,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.816,81**	

Item No	Analysis Name					UoM
35.545.4069	**LC / SM / Rack Mount Fiber Optic Termination with 36 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4069	LC / SM / Rack Mount Fiber Optic Termination Unit with 36 Fiber Capacity (Market price)	Qty	1	4.180,80	4.180,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician’s helper	h	3,5	185,00		647,50
				Total Excluding Profit (TRY)	4.180,80	1.563,75
				Material and Installation w/o Profit (TRY)	5.744,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.954,69**	
				Unit Price (TRY)	**7.180,69**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.4070	**LC / SM / Rack Mount Fiber Optic Termination with 48 Fiber Capacity**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.4070	LC / SM / Rack Mount Fiber Optic Termination Unit with 48 Fiber Capacity (Market price)	Qty	1	4.825,60	4.825,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
				Total Excluding Profit (TRY)	4.825,60	1.781,25
				Material and Installation w/o Profit (TRY)	6.606,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.226,56**	
				Unit Price (TRY)	**8.258,56**	

Item No	Analysis Name					UoM
35.545.5001	**4 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5001	4 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	919,36	919,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	919,36	258,75
				Material and Installation w/o Profit (TRY)	1.178,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.472,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5002	**6 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5002	6 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	975,52	975,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	975,52	389,25
				Material and Installation w/o Profit (TRY)	1.364,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.705,96**	

Item No	Analysis Name					UoM
35.545.5003	**8 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5003	8 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.054,56	1.054,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.054,56	389,25
				Material and Installation w/o Profit (TRY)	1.443,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.804,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5004	**12 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5004	12 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.168,96	1.168,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.168,96	476,25
				Material and Installation w/o Profit (TRY)	1.645,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.056,51**	

Item No	Analysis Name					UoM
35.545.5005	**4 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5005	4 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	920,40	920,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	920,40	258,75
				Material and Installation w/o Profit (TRY)	1.179,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.473,94**	

Item No	Analysis Name					UoM
35.545.5006	**6 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5006	6 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.002,56	1.002,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.002,56	389,25
				Material and Installation w/o Profit (TRY)	1.391,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.739,76**	

Item No	Analysis Name					UoM
35.545.5007	**8 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5007	8 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.088,88	1.088,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.088,88	389,25
				Material and Installation w/o Profit (TRY)	1.478,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.847,66**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5008	**12 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5008	12 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.222,00	1.222,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.222,00	476,25
				Material and Installation w/o Profit (TRY)	1.698,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.122,81**	

Item No	Analysis Name					UoM
35.545.5009	**4 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5009	4 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	984,88	984,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	984,88	258,75
				Material and Installation w/o Profit (TRY)	1.243,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.554,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5010	**6 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5010	6 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.082,64	1.082,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.082,64	389,25
				Material and Installation w/o Profit (TRY)	1.471,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.839,86**	

Item No	Analysis Name					UoM
35.545.5011	**4 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5011	4 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	919,36	919,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	919,36	258,75
				Material and Installation w/o Profit (TRY)	1.178,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.472,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5012	**6 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5012	6 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	976,56	976,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	976,56	389,25
				Material and Installation w/o Profit (TRY)	1.365,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.707,26**	

Item No	Analysis Name					UoM
35.545.5013	**8 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5013	8 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.054,56	1.054,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.054,56	389,25
				Material and Installation w/o Profit (TRY)	1.443,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.804,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5014	**12 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5014	12 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.149,20	1.149,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.149,20	476,25
				Material and Installation w/o Profit (TRY)	1.625,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.031,81**	

Item No	Analysis Name					UoM
35.545.5015	**4 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5015	4 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	984,88	984,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	984,88	258,75
				Material and Installation w/o Profit (TRY)	1.243,63	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.554,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5016	**6 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5016	6 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.053,52	1.053,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
		Total Excluding Profit (TRY)			1.053,52	389,25
		Material and Installation w/o Profit (TRY)			1.442,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**486,56**	
		Unit Price (TRY)			**1.803,46**	

Item No	Analysis Name					UoM
35.545.5017	**8 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5017	8 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.133,60	1.133,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
		Total Excluding Profit (TRY)			1.133,60	389,25
		Material and Installation w/o Profit (TRY)			1.522,85	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**486,56**	
		Unit Price (TRY)			**1.903,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5018	**12 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5018	12 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.350,96	1.350,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.350,96	476,25
				Material and Installation w/o Profit (TRY)	1.827,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.284,01**	

Item No	Analysis Name					UoM
35.545.5019	**4 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5019	4 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	954,72	954,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	954,72	258,75
				Material and Installation w/o Profit (TRY)	1.213,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.516,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5020	**6 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5020	6 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.036,88	1.036,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.036,88	389,25
				Material and Installation w/o Profit (TRY)	1.426,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.782,66**	

Item No	Analysis Name					UoM
35.545.5021	**8 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5021	8 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.086,80	1.086,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.086,80	389,25
				Material and Installation w/o Profit (TRY)	1.476,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.845,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5022	**4 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5022	4 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	981,76	981,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			981,76	258,75
		Material and Installation w/o Profit (TRY)			1.240,51	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.550,64**	

Item No	Analysis Name					UoM
35.545.5023	**6 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5023	6 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.045,20	1.045,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
		Total Excluding Profit (TRY)			1.045,20	389,25
		Material and Installation w/o Profit (TRY)			1.434,45	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**486,56**	
		Unit Price (TRY)			**1.793,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5024	**8 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5024	8 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.164,80	1.164,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
				Total Excluding Profit (TRY)	1.164,80	389,25
				Material and Installation w/o Profit (TRY)	1.554,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**486,56**	
				Unit Price (TRY)	**1.942,56**	

Item No	Analysis Name					UoM
35.545.5025	**12 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5025	12 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.344,72	1.344,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.344,72	476,25
				Material and Installation w/o Profit (TRY)	1.820,97	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.276,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5026	**4 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5026	4 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	995,28	995,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			995,28	258,75
		Material and Installation w/o Profit (TRY)			1.254,03	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.567,54**	

Item No	Analysis Name					UoM
35.545.5027	**6 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5027	6 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.082,64	1.082,64	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
		Total Excluding Profit (TRY)			1.082,64	389,25
		Material and Installation w/o Profit (TRY)			1.471,89	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**486,56**	
		Unit Price (TRY)			**1.839,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5028	**12 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5028	12 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.168,96	1.168,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.168,96	476,25
				Material and Installation w/o Profit (TRY)	1.645,21	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.056,51**	

Item No	Analysis Name					UoM
35.545.5029	**4 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5029	4 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.023,36	1.023,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.023,36	258,75
				Material and Installation w/o Profit (TRY)	1.282,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.602,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5030	**6 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5030	6 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.112,80	1.112,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
		Total Excluding Profit (TRY)			1.112,80	389,25
		Material and Installation w/o Profit (TRY)			1.502,05	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**486,56**	
		Unit Price (TRY)			**1.877,56**	

Item No	Analysis Name					UoM
35.545.5031	**8 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5031	8 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.198,08	1.198,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,8	250,00		200,00
10.100.1083	Master electrician's helper	h	0,8	185,00		148,00
		Total Excluding Profit (TRY)			1.198,08	389,25
		Material and Installation w/o Profit (TRY)			1.587,33	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**486,56**	
		Unit Price (TRY)			**1.984,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.5032	**12 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.5032	12 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.447,68	1.447,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.447,68	476,25
				Material and Installation w/o Profit (TRY)	1.923,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.404,91**	

Item No	Analysis Name					UoM
35.545.6001	**4 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6001	4 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.178,32	1.178,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.178,32	476,25
				Material and Installation w/o Profit (TRY)	1.654,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.068,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6002	**6 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6002	6 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.189,76	1.189,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.189,76	606,75
				Material and Installation w/o Profit (TRY)	1.796,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.245,64**	

Item No	Analysis Name					UoM
35.545.6003	**8 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6003	8 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.306,24	1.306,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.306,24	606,75
				Material and Installation w/o Profit (TRY)	1.912,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.391,24**	

Item No	Analysis Name					UoM
35.545.6004	**12 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6004	12 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.413,36	1.413,36	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.413,36	693,75
				Material and Installation w/o Profit (TRY)	2.107,11	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.633,89**	

Item No	Analysis Name					UoM
35.545.6005	**24 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6005	24 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.133,04	2.133,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.133,04	911,25
				Material and Installation w/o Profit (TRY)	3.044,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.805,36**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6006	**36 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6006	36 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.724,80	2.724,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.724,80	1.128,75
				Material and Installation w/o Profit (TRY)	3.853,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.816,94**	

Item No	Analysis Name					UoM
35.545.6007	**48 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6007	48 Fiber Capacity ST / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.411,20	3.411,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.411,20	1.346,25
				Material and Installation w/o Profit (TRY)	4.757,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.946,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6008	**4 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6008	4 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.175,20	1.175,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.175,20	476,25
				Material and Installation w/o Profit (TRY)	1.651,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.064,31**	

Item No	Analysis Name					UoM
35.545.6009	**6 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6009	6 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.182,48	1.182,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.182,48	606,75
				Material and Installation w/o Profit (TRY)	1.789,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.236,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6010	**8 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6010	8 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.308,32	1.308,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.308,32	606,75
				Material and Installation w/o Profit (TRY)	1.915,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.393,84**	

Item No	Analysis Name					UoM
35.545.6011	**12 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6011	12 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.469,52	1.469,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.469,52	693,75
				Material and Installation w/o Profit (TRY)	2.163,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.704,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6012	**24 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6012	24 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.222,48	2.222,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.222,48	911,25
				Material and Installation w/o Profit (TRY)	3.133,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.917,16**	

Item No	Analysis Name					UoM
35.545.6013	**36 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6013	36 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.865,20	2.865,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.865,20	1.128,75
				Material and Installation w/o Profit (TRY)	3.993,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.992,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6014	**48 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6014	48 Fiber Capacity SC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.598,40	3.598,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.598,40	1.346,25
				Material and Installation w/o Profit (TRY)	4.944,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**6.180,81**	

Item No	Analysis Name					UoM
35.545.6015	**4 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6015	4 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.285,44	1.285,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.285,44	476,25
				Material and Installation w/o Profit (TRY)	1.761,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.202,11**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6016	**6 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6016	6 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.349,92	1.349,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.349,92	606,75
				Material and Installation w/o Profit (TRY)	1.956,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.445,84**	

Item No	Analysis Name					UoM
35.545.6017	**8 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6017	8 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.450,80	1.450,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.450,80	606,75
				Material and Installation w/o Profit (TRY)	2.057,55	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.571,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6018	**12 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6018	12 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.636,96	1.636,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.636,96	693,75
				Material and Installation w/o Profit (TRY)	2.330,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.913,39**	

Item No	Analysis Name					UoM
35.545.6019	**24 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6019	24 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.532,40	2.532,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.532,40	911,25
				Material and Installation w/o Profit (TRY)	3.443,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.304,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6020	**36 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6020	36 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.432,00	3.432,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	3.432,00	1.128,75
				Material and Installation w/o Profit (TRY)	4.560,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**5.700,94**	

Item No	Analysis Name					UoM
35.545.6021	**48 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6021	48 Fiber Capacity FC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	4.264,00	4.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	4.264,00	1.346,25
				Material and Installation w/o Profit (TRY)	5.610,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**7.012,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6022	**4 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6022	4 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.167,92	1.167,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.167,92	476,25
				Material and Installation w/o Profit (TRY)	1.644,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.055,21**	

Item No	Analysis Name					UoM
35.545.6023	**6 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6023	6 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.196,00	1.196,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.196,00	606,75
				Material and Installation w/o Profit (TRY)	1.802,75	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.253,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6024	**8 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6024	8 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.288,56	1.288,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.288,56	606,75
				Material and Installation w/o Profit (TRY)	1.895,31	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.369,14**	

Item No	Analysis Name					UoM
35.545.6025	**12 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6025	12 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.448,72	1.448,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.448,72	693,75
				Material and Installation w/o Profit (TRY)	2.142,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.678,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6026	**24 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6026	24 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.184,00	2.184,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.184,00	911,25
				Material and Installation w/o Profit (TRY)	3.095,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.869,06**	

Item No	Analysis Name					UoM
35.545.6027	**36 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6027	36 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.744,56	2.744,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.744,56	1.128,75
				Material and Installation w/o Profit (TRY)	3.873,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.841,64**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6028	**48 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6028	48 Fiber Capacity MTRJ / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.409,12	3.409,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.409,12	1.346,25
				Material and Installation w/o Profit (TRY)	4.755,37	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.944,21**	

Item No	Analysis Name					UoM
35.545.6029	**4 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6029	4 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.266,72	1.266,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.266,72	476,25
				Material and Installation w/o Profit (TRY)	1.742,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.178,71**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6030	**6 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6030	6 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.344,72	1.344,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.344,72	606,75
				Material and Installation w/o Profit (TRY)	1.951,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.439,34**	

Item No	Analysis Name					UoM
35.545.6031	**8 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6031	8 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.453,92	1.453,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.453,92	606,75
				Material and Installation w/o Profit (TRY)	2.060,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.575,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6032	**12 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6032	12 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.634,88	1.634,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.634,88	693,75
				Material and Installation w/o Profit (TRY)	2.328,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.910,79**	

Item No	Analysis Name					UoM
35.545.6033	**24 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6033	24 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.494,96	2.494,96	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.494,96	911,25
				Material and Installation w/o Profit (TRY)	3.406,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.257,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6034	**36 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6034	36 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.348,80	3.348,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	3.348,80	1.128,75
				Material and Installation w/o Profit (TRY)	4.477,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**5.596,94**	

Item No	Analysis Name					UoM
35.545.6035	**48 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6035	48 Fiber Capacity LC / MM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	4.139,20	4.139,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	4.139,20	1.346,25
				Material and Installation w/o Profit (TRY)	5.485,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**6.856,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6036	**4 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6036	4 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.200,16	1.200,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.200,16	476,25
				Material and Installation w/o Profit (TRY)	1.676,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.095,51**	

Item No	Analysis Name					UoM
35.545.6037	**6 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6037	6 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.266,72	1.266,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician's helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.266,72	606,75
				Material and Installation w/o Profit (TRY)	1.873,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.341,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6038	**8 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6038	8 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.371,76	1.371,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.371,76	606,75
				Material and Installation w/o Profit (TRY)	1.978,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.473,14**	

Item No	Analysis Name					UoM
35.545.6039	**12 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6039	12 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.516,32	1.516,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.516,32	693,75
				Material and Installation w/o Profit (TRY)	2.210,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.762,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6040	**24 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6040	24 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.300,48	2.300,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.300,48	911,25
				Material and Installation w/o Profit (TRY)	3.211,73	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.014,66**	

Item No	Analysis Name					UoM
35.545.6041	**36 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6041	36 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.097,12	3.097,12	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	3.097,12	1.128,75
				Material and Installation w/o Profit (TRY)	4.225,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**5.282,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6042	**48 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6042	48 Fiber Capacity ST / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.848,00	3.848,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.848,00	1.346,25
				Material and Installation w/o Profit (TRY)	5.194,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**6.492,81**	

Item No	Analysis Name					UoM
35.545.6043	**4 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6043	4 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.285,44	1.285,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.285,44	476,25
				Material and Installation w/o Profit (TRY)	1.761,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.202,11**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6044	**6 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6044	6 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.285,44	1.285,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.285,44	606,75
				Material and Installation w/o Profit (TRY)	1.892,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.365,24**	

Item No	Analysis Name					UoM
35.545.6045	**8 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6045	8 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.390,48	1.390,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.390,48	606,75
				Material and Installation w/o Profit (TRY)	1.997,23	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.496,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6046	**12 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6046	12 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.599,52	1.599,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.599,52	693,75
				Material and Installation w/o Profit (TRY)	2.293,27	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.866,59**	

Item No	Analysis Name					UoM
35.545.6047	**24 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6047	24 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.454,40	2.454,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.454,40	911,25
				Material and Installation w/o Profit (TRY)	3.365,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.207,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6048	**36 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6048	36 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.286,40	3.286,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	3.286,40	1.128,75
				Material and Installation w/o Profit (TRY)	4.415,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**5.518,94**	

Item No	Analysis Name					UoM
35.545.6049	**48 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6049	48 Fiber Capacity SC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	4.118,40	4.118,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	4.118,40	1.346,25
				Material and Installation w/o Profit (TRY)	5.464,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**6.830,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6050	**4 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6050	4 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.285,44	1.285,44	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.285,44	476,25
				Material and Installation w/o Profit (TRY)	1.761,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.202,11**	

Item No	Analysis Name					UoM
35.545.6051	**6 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6051	6 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.349,92	1.349,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.349,92	606,75
				Material and Installation w/o Profit (TRY)	1.956,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.445,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6052	**8 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6052	8 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.450,80	1.450,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.450,80	606,75
				Material and Installation w/o Profit (TRY)	2.057,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.571,94**	

Item No	Analysis Name					UoM
35.545.6053	**12 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6053	12 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.657,76	1.657,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.657,76	693,75
				Material and Installation w/o Profit (TRY)	2.351,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.939,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6054	**24 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6054	24 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.532,40	2.532,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.532,40	911,25
				Material and Installation w/o Profit (TRY)	3.443,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.304,56**	

Item No	Analysis Name					UoM
35.545.6055	**36 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6055	36 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.432,00	3.432,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	3.432,00	1.128,75
				Material and Installation w/o Profit (TRY)	4.560,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**5.700,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6056	**48 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6056	48 Fiber Capacity FC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	4.305,60	4.305,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	4.305,60	1.346,25
				Material and Installation w/o Profit (TRY)	5.651,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**7.064,81**	

Item No	Analysis Name					UoM
35.545.6057	**4 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6057	4 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.178,32	1.178,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.178,32	476,25
				Material and Installation w/o Profit (TRY)	1.654,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.068,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6058	**6 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6058	6 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.189,76	1.189,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.189,76	606,75
				Material and Installation w/o Profit (TRY)	1.796,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.245,64**	

Item No	Analysis Name					UoM
35.545.6059	**8 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6059	8 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.306,24	1.306,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.306,24	606,75
				Material and Installation w/o Profit (TRY)	1.912,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.391,24**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6060	**12 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6060	12 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.453,92	1.453,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.453,92	693,75
				Material and Installation w/o Profit (TRY)	2.147,67	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.684,59**	

Item No	Analysis Name					UoM
35.545.6061	**24 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6061	24 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.267,20	2.267,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.267,20	911,25
				Material and Installation w/o Profit (TRY)	3.178,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**3.973,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6062	**36 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6062	36 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.786,16	2.786,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	2.786,16	1.128,75
				Material and Installation w/o Profit (TRY)	3.914,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**4.893,64**	

Item No	Analysis Name					UoM
35.545.6063	**48 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6063	48 Fiber Capacity MTRJ / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.428,88	3.428,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.428,88	1.346,25
				Material and Installation w/o Profit (TRY)	4.775,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**5.968,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6064	**4 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6064	4 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.302,08	1.302,08	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	1.302,08	476,25
				Material and Installation w/o Profit (TRY)	1.778,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**595,31**	
				Unit Price (TRY)	**2.222,91**	

Item No	Analysis Name					UoM
35.545.6065	**6 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6065	6 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.369,68	1.369,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.369,68	606,75
				Material and Installation w/o Profit (TRY)	1.976,43	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.470,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6066	**8 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6066	8 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.474,72	1.474,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,3	250,00		325,00
10.100.1083	Master electrician’s helper	h	1,3	185,00		240,50
				Total Excluding Profit (TRY)	1.474,72	606,75
				Material and Installation w/o Profit (TRY)	2.081,47	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**758,44**	
				Unit Price (TRY)	**2.601,84**	

Item No	Analysis Name					UoM
35.545.6067	**12 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6067	12 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	1.622,40	1.622,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
				Total Excluding Profit (TRY)	1.622,40	693,75
				Material and Installation w/o Profit (TRY)	2.316,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**867,19**	
				Unit Price (TRY)	**2.895,19**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6068	**24 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6068	24 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	2.534,48	2.534,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.534,48	911,25
				Material and Installation w/o Profit (TRY)	3.445,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.139,06**	
				Unit Price (TRY)	**4.307,16**	

Item No	Analysis Name					UoM
35.545.6069	**36 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6069	36 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	3.473,60	3.473,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	3.473,60	1.128,75
				Material and Installation w/o Profit (TRY)	4.602,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.410,94**	
				Unit Price (TRY)	**5.752,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.6070	**48 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.6070	48 Fiber Capacity LC / SM / Wall Mount Fiber Optical Termination Unit (Market price)	Qty	1	4.305,60	4.305,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	4.305,60	1.346,25
				Material and Installation w/o Profit (TRY)	5.651,85	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.682,81**	
				Unit Price (TRY)	**7.064,81**	

Item No	Analysis Name					UoM
35.545.7001	**single pipe, Ø32 mm / PE Optical Fiber Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.7001	single pipe, Ø32 mm / PE Optical Fiber Cable Protection Pipes (Market price)	m	1	19,91	19,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,07	250,00		17,50
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	19,91	37,05
				Material and Installation w/o Profit (TRY)	56,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**46,31**	
				Unit Price (TRY)	**71,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.7002	**single pipe, Ø40 mm / PE Optical Fiber Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.7002	single pipe, Ø40 mm / PE Optical Fiber Cable Protection Pipes (Market price)	m	1	29,57	29,57	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	29,57	41,40
				Material and Installation w/o Profit (TRY)	70,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**51,75**	
				Unit Price (TRY)	**88,71**	

Item No	Analysis Name					UoM
35.545.7003	**dual multiplexer pipe, Ø2 x 32 mm / PE Optical Fiber Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.7003	dual multiplexer pipe, Ø2 x 32 mm / PE Optical Fiber Cable Protection Pipes (Market price)	m	1	40,15	40,15	
	Installation Components					
10.100.1062	Unskilled worker	h	0,04	165,00		6,60
10.100.1081	Master electrician	h	0,08	250,00		20,00
10.100.1083	Master electrician’s helper	h	0,08	185,00		14,80
				Total Excluding Profit (TRY)	40,15	41,40
				Material and Installation w/o Profit (TRY)	81,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**51,75**	
				Unit Price (TRY)	**101,94**	

Item No	Analysis Name					UoM
35.545.7004	**dual multiplexer pipe, Ø2 x 40 mm / PE Optical Fiber Cable Protection Pipes**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.7004	dual multiplexer pipe, Ø2 x 40 mm / PE Optical Fiber Cable Protection Pipes (Market price)	m	1	58,63	58,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,1	185,00		18,50
				Total Excluding Profit (TRY)	58,63	51,75
				Material and Installation w/o Profit (TRY)	110,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**64,69**	
				Unit Price (TRY)	**137,97**	

Item No	Analysis Name					UoM
35.545.7005	**triple multiplexer pipe, Ø40 x 32 x 32 mm**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.7005	triple multiplexer pipe, Ø40 x 32 x 32 mm / PE Optical Fiber Cable Protection Pipes (Market price)	m	1	69,55	69,55	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,12	250,00		30,00
10.100.1083	Master electrician's helper	h	0,12	185,00		22,20
				Total Excluding Profit (TRY)	69,55	62,10
				Material and Installation w/o Profit (TRY)	131,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**77,63**	
				Unit Price (TRY)	**164,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.8105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.8105	Surface-mounted single fiber optic socket / Fiber Optic Socket / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	266,91	266,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	266,91	190,50
				Material and Installation w/o Profit (TRY)	457,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**238,13**	
				Unit Price (TRY)	**571,76**	

Item No	Analysis Name					UoM
35.545.8110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.8110	Surface-mounted double fiber optic socket / Fiber Optic Socket / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	371,91	371,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	371,91	277,50
				Material and Installation w/o Profit (TRY)	649,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**346,88**	
				Unit Price (TRY)	**811,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.545.8115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.8115	Flush-mounted single fiber optic socket / Fiber Optic Socket / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	266,91	266,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,4	250,00		100,00
10.100.1083	Master electrician’s helper	h	0,4	185,00		74,00
				Total Excluding Profit (TRY)	266,91	190,50
				Material and Installation w/o Profit (TRY)	457,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**238,13**	
				Unit Price (TRY)	**571,76**	

Item No	Analysis Name					UoM
35.545.8120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.545.8120	Flush-mounted double fiber optic socket / Fiber Optic Socket / FIBER OPTIC CONNECTION COMPONENTS (Market price)	Qty	1	371,91	371,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician’s helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	371,91	277,50
				Material and Installation w/o Profit (TRY)	649,41	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**346,88**	
				Unit Price (TRY)	**811,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.1105	**7U 600 mm x 500 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1105	7U 600 mm x 450 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	6.546,10	6.546,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	6.546,10	586,30
				Material and Installation w/o Profit (TRY)	7.132,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**8.915,50**	

Item No	Analysis Name					UoM
35.550.1110	**9U 600 mm x 500 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1110	9U 600 mm x 450 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	6.887,04	6.887,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	6.887,04	586,30
				Material and Installation w/o Profit (TRY)	7.473,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**9.341,67**	

Item No	Analysis Name					UoM
35.550.1115	**12U 600 mm x 500 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1115	12U 600 mm x 450 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	7.691,52	7.691,52	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	7.691,52	586,30
				Material and Installation w/o Profit (TRY)	8.277,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**10.347,27**	

Item No	Analysis Name					UoM
35.550.1120	**12U 600 mm x 500 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1120	16U 600 mm x 450 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	8.780,58	8.780,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	8.780,58	586,30
				Material and Installation w/o Profit (TRY)	9.366,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**11.708,60**	

Item No	Analysis Name					UoM
35.550.1160	**7U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1160	7U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	6.585,60	6.585,60	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	6.585,60	586,30
				Material and Installation w/o Profit (TRY)	7.171,90	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**8.964,88**	

Item No	Analysis Name					UoM
35.550.1165	**9U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1165	9U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	7.954,56	7.954,56	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	7.954,56	586,30
				Material and Installation w/o Profit (TRY)	8.540,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**10.676,08**	

Item No	Analysis Name					UoM
35.550.1170	**12U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1170	12U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	8.778,24	8.778,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	8.778,24	586,30
				Material and Installation w/o Profit (TRY)	9.364,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**11.705,67**	

Item No	Analysis Name					UoM
35.550.1175	**12U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.1175	16U 600 mm x 600 mm 19″ cabinet / Wall-mounted cabinets / Rack Cabinets (Market price)	Qty	1	9.924,48	9.924,48	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	9.924,48	586,30
				Material and Installation w/o Profit (TRY)	10.510,78	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**13.138,47**	

Item No	Analysis Name					UoM
35.550.2105	**15U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2105	12U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	10.654,90	10.654,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	10.654,90	586,30
				Material and Installation w/o Profit (TRY)	11.241,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**14.051,50**	

Item No	Analysis Name					UoM
35.550.2110	**15U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2110	16U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	14.207,04	14.207,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	14.207,04	586,30
				Material and Installation w/o Profit (TRY)	14.793,34	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**732,88**	
				Unit Price (TRY)	**18.491,67**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2115	20U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	15.982,58	15.982,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			15.982,58	695,05
		Material and Installation w/o Profit (TRY)			16.677,63	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**20.847,04**	

Item No	Analysis Name					UoM
35.550.2120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2120	22U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	16.782,91	16.782,91	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			16.782,91	695,05
		Material and Installation w/o Profit (TRY)			17.477,96	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**21.847,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2125	26U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	18.003,00	18.003,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	18.003,00	695,05
				Material and Installation w/o Profit (TRY)	18.698,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**23.372,56**	

Item No	Analysis Name					UoM
35.550.2130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2130	32U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	20.084,98	20.084,98	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	20.084,98	695,05
				Material and Installation w/o Profit (TRY)	20.780,03	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**25.975,04**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2135						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2135	34U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	20.672,40	20.672,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			20.672,40	695,05
		Material and Installation w/o Profit (TRY)			21.367,45	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**26.709,31**	

Item No	Analysis Name					UoM
35.550.2140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2140	36U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	21.192,20	21.192,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			21.192,20	695,05
		Material and Installation w/o Profit (TRY)			21.887,25	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**27.359,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2145						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2145	39U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	22.254,78	22.254,78	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	22.254,78	763,84
				Material and Installation w/o Profit (TRY)	23.018,62	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**954,80**	
				Unit Price (TRY)	**28.773,27**	

Item No	Analysis Name					UoM
35.550.2150						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2150	42U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	23.196,98	23.196,98	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	23.196,98	955,09
				Material and Installation w/o Profit (TRY)	24.152,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**30.190,09**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2155						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2155	45U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	24.854,12	24.854,12	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	24.854,12	955,09
				Material and Installation w/o Profit (TRY)	25.809,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**32.261,51**	

Item No	Analysis Name					UoM
35.550.2160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2160	47U 600 mm x 600 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	25.737,60	25.737,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	25.737,60	955,09
				Material and Installation w/o Profit (TRY)	26.692,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**33.365,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2205						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2205	12U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	10.840,51	10.840,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			10.840,51	695,05
		Material and Installation w/o Profit (TRY)			11.535,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**14.419,45**	

Item No	Analysis Name					UoM
35.550.2210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2210	16U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	14.454,53	14.454,53	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			14.454,53	695,05
		Material and Installation w/o Profit (TRY)			15.149,58	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**18.936,97**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2215						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2215	20U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	17.322,04	17.322,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	17.322,04	695,05
				Material and Installation w/o Profit (TRY)	18.017,09	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**22.521,36**	

Item No	Analysis Name					UoM
35.550.2220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2220	22U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	18.907,97	18.907,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	18.907,97	695,05
				Material and Installation w/o Profit (TRY)	19.603,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**24.503,78**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2225						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2225	26U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	19.814,20	19.814,20	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			19.814,20	695,05
		Material and Installation w/o Profit (TRY)			20.509,25	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**25.636,56**	

Item No	Analysis Name					UoM
35.550.2230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2230	32U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	21.994,37	21.994,37	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,2	687,95		137,59
		Total Excluding Profit (TRY)			21.994,37	763,84
		Material and Installation w/o Profit (TRY)			22.758,21	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**954,80**	
		Unit Price (TRY)			**28.447,76**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2235						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2235	34U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	22.636,70	22.636,70	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	22.636,70	763,84
				Material and Installation w/o Profit (TRY)	23.400,54	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**954,80**	
				Unit Price (TRY)	**29.250,68**	

Item No	Analysis Name					UoM
35.550.2240						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2240	36U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	23.310,80	23.310,80	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	23.310,80	763,84
				Material and Installation w/o Profit (TRY)	24.074,64	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**954,80**	
				Unit Price (TRY)	**30.093,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2245						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2245	39U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	24.493,26	24.493,26	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	24.493,26	955,09
				Material and Installation w/o Profit (TRY)	25.448,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**31.810,44**	

Item No	Analysis Name					UoM
35.550.2250						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2250	42U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	25.534,43	25.534,43	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	25.534,43	955,09
				Material and Installation w/o Profit (TRY)	26.489,52	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**33.111,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2255						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2255	45U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	27.359,16	27.359,16	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	27.359,16	955,09
				Material and Installation w/o Profit (TRY)	28.314,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**35.392,81**	

Item No	Analysis Name					UoM
35.550.2260						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2260	47U 600 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	28.343,04	28.343,04	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	28.343,04	955,09
				Material and Installation w/o Profit (TRY)	29.298,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**36.622,66**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2305						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2305	12U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	12.062,54	12.062,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	12.062,54	695,05
				Material and Installation w/o Profit (TRY)	12.757,59	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**15.946,99**	

Item No	Analysis Name					UoM
35.550.2310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2310	16U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	16.083,65	16.083,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	16.083,65	695,05
				Material and Installation w/o Profit (TRY)	16.778,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**20.973,38**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2315	20U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	19.166,58	19.166,58	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	19.166,58	695,05
				Material and Installation w/o Profit (TRY)	19.861,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**24.827,04**	

Item No	Analysis Name					UoM
35.550.2320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2320	22U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	21.082,94	21.082,94	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	21.082,94	695,05
				Material and Installation w/o Profit (TRY)	21.777,99	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**27.222,49**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2325						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2325	26U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	22.611,65	22.611,65	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	22.611,65	695,05
				Material and Installation w/o Profit (TRY)	23.306,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**868,81**	
				Unit Price (TRY)	**29.133,38**	

Item No	Analysis Name					UoM
35.550.2330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2330	32U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	25.171,20	25.171,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	25.171,20	955,09
				Material and Installation w/o Profit (TRY)	26.126,29	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**32.657,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2335						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2335	34U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	25.804,89	25.804,89	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	25.804,89	955,09
				Material and Installation w/o Profit (TRY)	26.759,98	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**33.449,97**	

Item No	Analysis Name					UoM
35.550.2340						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2340	36U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	26.451,42	26.451,42	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	26.451,42	955,09
				Material and Installation w/o Profit (TRY)	27.406,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**34.258,14**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2345						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2345	39U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	27.745,47	27.745,47	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	27.745,47	955,09
				Material and Installation w/o Profit (TRY)	28.700,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**35.875,70**	

Item No	Analysis Name					UoM
35.550.2350						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2350	42U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	28.892,60	28.892,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	28.892,60	955,09
				Material and Installation w/o Profit (TRY)	29.847,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**37.309,61**	

Item No	Analysis Name					UoM
35.550.2355						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2355	45U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	30.956,33	30.956,33	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	30.956,33	955,09
				Material and Installation w/o Profit (TRY)	31.911,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**39.889,28**	

Item No	Analysis Name					UoM
35.550.2360						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2360	47U 600 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	32.078,78	32.078,78	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	32.078,78	955,09
				Material and Installation w/o Profit (TRY)	33.033,87	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**41.292,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2450						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2450	42U 600 mm x 1200 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	39.483,46	39.483,46	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	39.483,46	955,09
				Material and Installation w/o Profit (TRY)	40.438,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**50.548,19**	

Item No	Analysis Name					UoM
35.550.2460						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2460	47U 600 mm x 1200 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	44.049,79	44.049,79	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	44.049,79	955,09
				Material and Installation w/o Profit (TRY)	45.004,88	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**56.256,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2505						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2505	12U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	11.994,04	11.994,04	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			11.994,04	695,05
		Material and Installation w/o Profit (TRY)			12.689,09	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**15.861,36**	

Item No	Analysis Name					UoM
35.550.2510						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2510	16U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	15.448,32	15.448,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			15.448,32	695,05
		Material and Installation w/o Profit (TRY)			16.143,37	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**20.179,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2515						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2515	20U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	18.284,97	18.284,97	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			18.284,97	695,05
		Material and Installation w/o Profit (TRY)			18.980,02	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**23.725,03**	

Item No	Analysis Name					UoM
35.550.2520						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2520	22U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	20.113,54	20.113,54	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			20.113,54	695,05
		Material and Installation w/o Profit (TRY)			20.808,59	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**868,81**	
		Unit Price (TRY)			**26.010,74**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2525						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2525	26U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	23.321,66	23.321,66	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1,25	250,00		312,50
10.100.1083	Master electrician’s helper	h	1,25	185,00		231,25
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	23.321,66	763,84
				Material and Installation w/o Profit (TRY)	24.085,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**954,80**	
				Unit Price (TRY)	**30.106,88**	

Item No	Analysis Name					UoM
35.550.2530						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2530	32U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	25.901,11	25.901,11	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	25.901,11	955,09
				Material and Installation w/o Profit (TRY)	26.856,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**33.570,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2535						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2535	34U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	26.435,74	26.435,74	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	26.435,74	955,09
				Material and Installation w/o Profit (TRY)	27.390,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**34.238,54**	

Item No	Analysis Name					UoM
35.550.2540						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2540	36U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	27.017,82	27.017,82	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	27.017,82	955,09
				Material and Installation w/o Profit (TRY)	27.972,91	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**34.966,14**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2545						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2545	39U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	28.332,10	28.332,10	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	28.332,10	955,09
				Material and Installation w/o Profit (TRY)	29.287,19	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**36.608,99**	

Item No	Analysis Name					UoM
35.550.2550						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2550	42U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	29.616,23	29.616,23	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	29.616,23	955,09
				Material and Installation w/o Profit (TRY)	30.571,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**38.214,15**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2555						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2555	45U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	31.731,62	31.731,62	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	31.731,62	955,09
				Material and Installation w/o Profit (TRY)	32.686,71	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**40.858,39**	

Item No	Analysis Name					UoM
35.550.2560						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2560	47U 800 mm x 800 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	32.864,26	32.864,26	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	32.864,26	955,09
				Material and Installation w/o Profit (TRY)	33.819,35	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**42.274,19**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2640						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2640	26U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	26.501,48	26.501,48	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	26.501,48	955,09
				Material and Installation w/o Profit (TRY)	27.456,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**34.320,71**	

Item No	Analysis Name					UoM
35.550.2645						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2645	32U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	28.737,98	28.737,98	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	28.737,98	955,09
				Material and Installation w/o Profit (TRY)	29.693,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**37.116,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2650						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2650	34U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	29.610,60	29.610,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	29.610,60	955,09
				Material and Installation w/o Profit (TRY)	30.565,69	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**38.207,11**	

Item No	Analysis Name					UoM
35.550.2655						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2655	36U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	30.449,86	30.449,86	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	30.449,86	955,09
				Material and Installation w/o Profit (TRY)	31.404,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**39.256,19**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2660						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2660	39U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	31.666,56	31.666,56	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	31.666,56	955,09
				Material and Installation w/o Profit (TRY)	32.621,65	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**40.777,06**	

Item No	Analysis Name					UoM
35.550.2665						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2665	42U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	32.977,73	32.977,73	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,2	687,95		137,59
				Total Excluding Profit (TRY)	32.977,73	955,09
				Material and Installation w/o Profit (TRY)	33.932,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.193,86**	
				Unit Price (TRY)	**42.416,03**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2670						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2670	45U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	35.333,07	35.333,07	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	35.333,07	1.023,89
				Material and Installation w/o Profit (TRY)	36.356,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.279,86**	
				Unit Price (TRY)	**45.446,20**	

Item No	Analysis Name					UoM
35.550.2675						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2675	47U 800 mm x 1000 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	36.629,18	36.629,18	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	36.629,18	1.023,89
				Material and Installation w/o Profit (TRY)	37.653,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.279,86**	
				Unit Price (TRY)	**47.066,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.2750						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2750	42U 800 mm x 1200 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	40.435,97	40.435,97	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	40.435,97	1.023,89
				Material and Installation w/o Profit (TRY)	41.459,86	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.279,86**	
				Unit Price (TRY)	**51.824,82**	

Item No	Analysis Name					UoM
35.550.2760						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.2760	47U 800 mm x 1200 mm 19″ Floor-standing cabinet / Floor-standing cabinets / Rack Cabinets (Market price)	Qty	1	45.332,74	45.332,74	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
19.100.1112	Forklift	h	0,3	687,95		206,39
				Total Excluding Profit (TRY)	45.332,74	1.023,89
				Material and Installation w/o Profit (TRY)	46.356,63	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.279,86**	
				Unit Price (TRY)	**57.945,79**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4001	**Fixed shelf for 500 mm depth / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.550.4001	**Material Components** Fixed shelf for 450 mm depth / Product Accessories / Rack Cabinets (Market price)	Qty	1	525,79	525,79	
				Total Excluding Profit (TRY)	525,79	
				Material and Installation w/o Profit (TRY)	525,79	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**657,24**	

Item No	Analysis Name					UoM
35.550.4002	**Fixed shelf for 600 mm depth / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.550.4002	**Material Components** Fixed shelf for 600 mm depth / Product Accessories / Rack Cabinets (Market price)	Qty	1	565,45	565,45	
				Total Excluding Profit (TRY)	565,45	
				Material and Installation w/o Profit (TRY)	565,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**706,81**	

Item No	Analysis Name					UoM
35.550.4003	**Fixed shelf for 800 mm depth / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.550.4003	**Material Components** Fixed shelf for 800 mm depth / Product Accessories / Rack Cabinets (Market price)	Qty	1	680,88	680,88	
				Total Excluding Profit (TRY)	680,88	
				Material and Installation w/o Profit (TRY)	680,88	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**851,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4004	**Fixed shelf for 1000 mm depth / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.550.4004	**Material Components** Fixed shelf for 1000 mm depth / Product Accessories / Rack Cabinets (Market price)	Qty	1	982,84	982,84	
		Total Excluding Profit (TRY)			982,84	
		Material and Installation w/o Profit (TRY)			982,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.228,55**	

Item No	Analysis Name					UoM
35.550.4005	**Adjustable shelf for 600 mm depth / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.550.4005	**Material Components** Adjustable shelf for 600 mm depth / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.345,16	1.345,16	
		Total Excluding Profit (TRY)			1.345,16	
		Material and Installation w/o Profit (TRY)			1.345,16	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.681,45**	

Item No	Analysis Name					UoM
35.550.4006	**Adjustable shelf for 800 mm depth / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.550.4006	**Material Components** Adjustable shelf for 800 mm depth / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.575,40	1.575,40	
		Total Excluding Profit (TRY)			1.575,40	
		Material and Installation w/o Profit (TRY)			1.575,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**1.969,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4007	**Adjustable shelf for 1000 mm depth / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4007	Adjustable shelf for 1000 mm depth / Product Accessories / Rack Cabinets (Market price)	Qty	1	2.435,58	2.435,58	
		Total Excluding Profit (TRY)			2.435,58	
		Material and Installation w/o Profit (TRY)			2.435,58	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**3.044,47**	

Item No	Analysis Name					UoM
35.550.4008	**Brake castor group (Front wheels with brakes) / Product Accessories / Rack Cabinets**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4008	Brake castor group (Front wheels with brakes) / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.327,16	1.327,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			1.327,16	258,75
		Material and Installation w/o Profit (TRY)			1.585,91	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.982,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4050						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4050	Thermostatic fan module (1 fans) / Product Accessories / Rack Cabinets (Market price)	Qty	1	2.163,38	2.163,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.163,38	258,75
				Material and Installation w/o Profit (TRY)	2.422,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.027,66**	

Item No	Analysis Name					UoM
35.550.4055						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4055	Thermostatic fan module (1 fan), analog thermostat / Product Accessories / Rack Cabinets (Market price)	Qty	1	2.477,30	2.477,30	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.477,30	258,75
				Material and Installation w/o Profit (TRY)	2.736,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.420,06**	

Item No	Analysis Name					UoM
35.550.4060						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4060	Thermostatic fan module (2 fans) / Product Accessories / Rack Cabinets (Market price)	Qty	1	3.028,01	3.028,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.028,01	258,75
				Material and Installation w/o Profit (TRY)	3.286,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**4.108,45**	

Item No	Analysis Name					UoM
35.550.4065						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4065	Thermostatic fan module (2 fan), analog thermostat / Product Accessories / Rack Cabinets (Market price)	Qty	1	3.348,01	3.348,01	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	3.348,01	258,75
				Material and Installation w/o Profit (TRY)	3.606,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**4.508,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4070						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4070	Thermostatic fan module (2 fan), digital thermostat / Product Accessories / Rack Cabinets (Market price)	Qty	1	5.547,61	5.547,61	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	5.547,61	258,75
				Material and Installation w/o Profit (TRY)	5.806,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**7.257,95**	

Item No	Analysis Name					UoM
35.550.4080						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4080	Thermostatic fan module (4 fans) / Product Accessories / Rack Cabinets (Market price)	Qty	1	4.303,18	4.303,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.303,18	258,75
				Material and Installation w/o Profit (TRY)	4.561,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.702,41**	

Item No	Analysis Name					UoM
35.550.4085						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4085	Thermostatic fan module (4 fan), analog thermostat / Product Accessories / Rack Cabinets (Market price)	Qty	1	4.463,18	4.463,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	4.463,18	258,75
				Material and Installation w/o Profit (TRY)	4.721,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**5.902,41**	

Item No	Analysis Name					UoM
35.550.4090						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4090	Thermostatic fan module (4 fan), digital thermostat / Product Accessories / Rack Cabinets (Market price)	Qty	1	6.923,93	6.923,93	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	6.923,93	258,75
				Material and Installation w/o Profit (TRY)	7.182,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**8.978,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4110	19″ rack-type 3-outlet socket with switch / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.290,00	1.290,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.290,00	258,75
				Material and Installation w/o Profit (TRY)	1.548,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.935,94**	

Item No	Analysis Name					UoM
35.550.4115						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4115	19″ rack-type 4-outlet socket with switch / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.430,85	1.430,85	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.430,85	258,75
				Material and Installation w/o Profit (TRY)	1.689,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.112,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4120	19″ rack-type 6-outlet socket with switch / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.567,87	1.567,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.567,87	258,75
				Material and Installation w/o Profit (TRY)	1.826,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.283,27**	

Item No	Analysis Name					UoM
35.550.4125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4125	19″ rack-type 8-outlet socket with switch / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.737,51	1.737,51	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.737,51	258,75
				Material and Installation w/o Profit (TRY)	1.996,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.495,32**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4160	19″ rack-type 4-outlet socket with fuse / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.987,76	1.987,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.987,76	258,75
				Material and Installation w/o Profit (TRY)	2.246,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**2.808,14**	

Item No	Analysis Name					UoM
35.550.4165						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4165	19″ rack-type 6-outlet socket with fuse / Product Accessories / Rack Cabinets (Market price)	Qty	1	2.195,38	2.195,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.195,38	258,75
				Material and Installation w/o Profit (TRY)	2.454,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.067,66**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4170						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4170	19″ rack-type 8-outlet socket with fuse / Product Accessories / Rack Cabinets (Market price)	Qty	1	2.589,68	2.589,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.589,68	258,75
				Material and Installation w/o Profit (TRY)	2.848,43	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**3.560,54**	

Item No	Analysis Name					UoM
35.550.4210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4210	19″ 1U horizontal cable organizer / Product Accessories / Rack Cabinets (Market price)	Qty	1	489,18	489,18	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	489,18	258,75
				Material and Installation w/o Profit (TRY)	747,93	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**934,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4220	19″ 2U horizontal cable organizer / Product Accessories / Rack Cabinets (Market price)	Qty	1	644,72	644,72	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	644,72	258,75
				Material and Installation w/o Profit (TRY)	903,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.129,34**	

Item No	Analysis Name					UoM
35.550.4310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4310	7U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	272,10	272,10	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	272,10	258,75
				Material and Installation w/o Profit (TRY)	530,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**663,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4315	9U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	306,02	306,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	306,02	258,75
				Material and Installation w/o Profit (TRY)	564,77	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**705,96**	

Item No	Analysis Name					UoM
35.550.4320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4320	12U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	330,32	330,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	330,32	258,75
				Material and Installation w/o Profit (TRY)	589,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**736,34**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4325						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4325	16U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	426,14	426,14	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			426,14	258,75
		Material and Installation w/o Profit (TRY)			684,89	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**856,11**	

Item No	Analysis Name					UoM
35.550.4330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4330	20U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	553,02	553,02	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
		Total Excluding Profit (TRY)			553,02	258,75
		Material and Installation w/o Profit (TRY)			811,77	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**323,44**	
		Unit Price (TRY)			**1.014,71**	

Item No	Analysis Name					UoM
35.550.4335						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4335	22U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	638,26	638,26	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	638,26	258,75
				Material and Installation w/o Profit (TRY)	897,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.121,26**	

Item No	Analysis Name					UoM
35.550.4340						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4340	26U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	740,40	740,40	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	740,40	258,75
				Material and Installation w/o Profit (TRY)	999,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.248,94**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4345						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4345	32U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	821,87	821,87	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	821,87	258,75
				Material and Installation w/o Profit (TRY)	1.080,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.350,77**	

Item No	Analysis Name					UoM
35.550.4350						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4350	34U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	862,86	862,86	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	862,86	258,75
				Material and Installation w/o Profit (TRY)	1.121,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.402,01**	

Item No	Analysis Name					UoM
35.550.4355						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4355	36U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	913,62	913,62	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	913,62	258,75
				Material and Installation w/o Profit (TRY)	1.172,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.465,46**	

Item No	Analysis Name					UoM
35.550.4360						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4360	39U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	976,38	976,38	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	976,38	258,75
				Material and Installation w/o Profit (TRY)	1.235,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.543,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4365						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4365	42U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.033,90	1.033,90	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.033,90	258,75
				Material and Installation w/o Profit (TRY)	1.292,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.615,81**	

Item No	Analysis Name					UoM
35.550.4370						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4370	45U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.096,59	1.096,59	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.096,59	258,75
				Material and Installation w/o Profit (TRY)	1.355,34	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.694,17**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.4375						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.4375	47U vertical cable organizer (single side) / Product Accessories / Rack Cabinets (Market price)	Qty	1	1.140,06	1.140,06	
	Installation Components					
10.100.1062	Unskilled worker	h	0,25	165,00		41,25
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	1.140,06	258,75
				Material and Installation w/o Profit (TRY)	1.398,81	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**323,44**	
				Unit Price (TRY)	**1.748,51**	

Item No	Analysis Name					UoM
35.550.7101						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7101	600x1000mm / Single-cabinet Data Center (min. 10-kW cooling) / Data Center Cabinets (Market price)	Qty	1	862.356,00	862.356,00	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	28	250,00		7.000,00
10.100.1083	Master electrician's helper	h	28	185,00		5.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	2	687,95		1.375,90
				Total Excluding Profit (TRY)	862.356,00	26.735,90
				Material and Installation w/o Profit (TRY)	889.091,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**33.419,88**	
				Unit Price (TRY)	**1.111.364,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.7102						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7102	600x1200mm / Single-cabinet Data Center (min. 10-kW cooling) / Data Center Cabinets (Market price)	Qty	1	866.228,00	866.228,00	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	28	250,00		7.000,00
10.100.1083	Master electrician's helper	h	28	185,00		5.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	2	687,95		1.375,90
				Total Excluding Profit (TRY)	866.228,00	26.735,90
				Material and Installation w/o Profit (TRY)	892.963,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**33.419,88**	
				Unit Price (TRY)	**1.116.204,88**	

Item No	Analysis Name					UoM
35.550.7103						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7103	800x1000mm / Single-cabinet Data Center (min. 10-kW cooling) / Data Center Cabinets (Market price)	Qty	1	871.508,00	871.508,00	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	28	250,00		7.000,00
10.100.1083	Master electrician's helper	h	28	185,00		5.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	2	687,95		1.375,90
				Total Excluding Profit (TRY)	871.508,00	26.735,90
				Material and Installation w/o Profit (TRY)	898.243,90	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**33.419,88**	
				Unit Price (TRY)	**1.122.804,88**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.7104						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7104	800x1200mm / Single-cabinet Data Center (min. 10-kW cooling) / Data Center Cabinets (Market price)	Qty	1	888.844,00	888.844,00	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	28	250,00		7.000,00
10.100.1083	Master electrician’s helper	h	28	185,00		5.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1112	Forklift	h	2	687,95		1.375,90
		Total Excluding Profit (TRY)			888.844,00	26.735,90
		Material and Installation w/o Profit (TRY)			915.579,90	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**33.419,88**	
		Unit Price (TRY)			**1.144.474,88**	

Item No	Analysis Name					UoM
35.550.7201						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7201	600x1000mm / Dual-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.009.377,60	1.009.377,60	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician’s helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	3	687,95		2.063,85
		Total Excluding Profit (TRY)			1.009.377,60	31.423,85
		Material and Installation w/o Profit (TRY)			1.040.801,45	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**39.279,81**	
		Unit Price (TRY)			**1.301.001,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.7202						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7202	600x1200mm / Dual-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.028.385,60	1.028.385,60	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician’s helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	1.028.385,60	31.423,85
				Material and Installation w/o Profit (TRY)	1.059.809,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39.279,81**	
				Unit Price (TRY)	**1.324.761,81**	

Item No	Analysis Name					UoM
35.550.7203						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7203	800x1000mm / Dual-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.028.033,60	1.028.033,60	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician’s helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	1.028.033,60	31.423,85
				Material and Installation w/o Profit (TRY)	1.059.457,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39.279,81**	
				Unit Price (TRY)	**1.324.321,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.7204						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7204	800x1200mm / Dual-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.046.513,60	1.046.513,60	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician’s helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	1.046.513,60	31.423,85
				Material and Installation w/o Profit (TRY)	1.077.937,45	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**39.279,81**	
				Unit Price (TRY)	**1.347.421,81**	

Item No	Analysis Name					UoM
35.550.7301						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7301	600x1000mm / 3-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.245.543,20	1.245.543,20	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	32	250,00		8.000,00
10.100.1083	Master electrician’s helper	h	32	185,00		5.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	1.245.543,20	35.423,85
				Material and Installation w/o Profit (TRY)	1.280.967,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**44.279,81**	
				Unit Price (TRY)	**1.601.208,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.7302						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7302	600x1200mm / 3-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.258.215,20	1.258.215,20	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	32	250,00		8.000,00
10.100.1083	Master electrician’s helper	h	32	185,00		5.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	1.258.215,20	35.423,85
				Material and Installation w/o Profit (TRY)	1.293.639,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**44.279,81**	
				Unit Price (TRY)	**1.617.048,81**	

Item No	Analysis Name					UoM
35.550.7303						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7303	800x1000mm / 3-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.262.967,20	1.262.967,20	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	32	250,00		8.000,00
10.100.1083	Master electrician’s helper	h	32	185,00		5.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	1.262.967,20	35.423,85
				Material and Installation w/o Profit (TRY)	1.298.391,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**44.279,81**	
				Unit Price (TRY)	**1.622.988,81**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.7304						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7304	800x1200mm / 3-cabinet Data Center / Data Center Cabinets (Market price)	Qty	1	1.270.095,20	1.270.095,20	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	32	250,00		8.000,00
10.100.1083	Master electrician’s helper	h	32	185,00		5.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	3	687,95		2.063,85
				Total Excluding Profit (TRY)	1.270.095,20	35.423,85
				Material and Installation w/o Profit (TRY)	1.305.519,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**44.279,81**	
				Unit Price (TRY)	**1.631.898,81**	

Item No	Analysis Name					UoM
35.550.7501						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7501	36U / Data Center Cabinet (min. 3.7-kW cooling) / Data Center Cabinets (Market price)	Qty	1	435.204,00	435.204,00	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1112	Forklift	h	1	687,95		687,95
				Total Excluding Profit (TRY)	435.204,00	9.557,95
				Material and Installation w/o Profit (TRY)	444.761,95	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.947,44**	
				Unit Price (TRY)	**555.952,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.550.7502						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.550.7502	42U / Data Center Cabinet (min. 3.7-kW cooling) / Data Center Cabinets (Market price)	Qty	1	441.012,00	441.012,00	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1112	Forklift	h	1	687,95		687,95
				Total Excluding Profit (TRY)	441.012,00	9.557,95
				Material and Installation w/o Profit (TRY)	450.569,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**11.947,44**	
				Unit Price (TRY)	**563.212,44**	

Item No	Analysis Name					UoM
35.701.1102						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1102	4 / 6 / 2 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	29.783,51	29.783,51	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	29.783,51	6.940,00
				Material and Installation w/o Profit (TRY)	36.723,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.675,00**	
				Unit Price (TRY)	**45.904,39**	

Item No	Analysis Name					UoM
35.701.1104						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1104	4 / 14 / 2 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	42.923,61	42.923,61	
	Installation Components					
10.100.1062	Unskilled worker	h	4,5	165,00		742,50
10.100.1081	Master electrician	h	9	250,00		2.250,00
10.100.1083	Master electrician's helper	h	9	185,00		1.665,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
				Total Excluding Profit (TRY)	42.923,61	10.957,50
				Material and Installation w/o Profit (TRY)	53.881,11	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.696,88**	
				Unit Price (TRY)	**67.351,39**	

Item No	Analysis Name					UoM
35.701.1106						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1106	4 / 22 / 2 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	48.533,59	48.533,59	
	Installation Components					
10.100.1062	Unskilled worker	h	4,5	165,00		742,50
10.100.1081	Master electrician	h	9	250,00		2.250,00
10.100.1083	Master electrician's helper	h	9	185,00		1.665,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
				Total Excluding Profit (TRY)	48.533,59	10.957,50
				Material and Installation w/o Profit (TRY)	59.491,09	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.696,88**	
				Unit Price (TRY)	**74.363,86**	

Item No	Analysis Name					UoM
35.701.1108						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1108	8 / 32 / 4 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	75.704,49	75.704,49	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician's helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	75.704,49	12.175,00
				Material and Installation w/o Profit (TRY)	87.879,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.218,75**	
				Unit Price (TRY)	**109.849,36**	

Item No	Analysis Name					UoM
35.701.1110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1110	12 / 48 / 6 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	107.655,25	107.655,25	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	107.655,25	14.610,00
				Material and Installation w/o Profit (TRY)	122.265,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**18.262,50**	
				Unit Price (TRY)	**152.831,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1112						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1112	16 / 64 / 6 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	129.064,15	129.064,15	
	Installation Components					
10.100.1062	Unskilled worker	h	6,5	165,00		1.072,50
10.100.1081	Master electrician	h	13	250,00		3.250,00
10.100.1083	Master electrician's helper	h	13	185,00		2.405,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	13	700,00		9.100,00
				Total Excluding Profit (TRY)	129.064,15	15.827,50
				Material and Installation w/o Profit (TRY)	144.891,65	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**19.784,38**	
				Unit Price (TRY)	**181.114,56**	

Item No	Analysis Name					UoM
35.701.1114						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1114	16 / 80 / 6 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	183.719,05	183.719,05	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
				Total Excluding Profit (TRY)	183.719,05	17.045,00
				Material and Installation w/o Profit (TRY)	200.764,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**21.306,25**	
				Unit Price (TRY)	**250.955,06**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1116						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1116	20 / 112 / 8 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	273.496,07	273.496,07	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
				Total Excluding Profit (TRY)	273.496,07	18.262,50
				Material and Installation w/o Profit (TRY)	291.758,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**22.828,13**	
				Unit Price (TRY)	**364.698,21**	

Item No	Analysis Name					UoM
35.701.1118						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1118	20 / 128 / 8 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	293.177,62	293.177,62	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
				Total Excluding Profit (TRY)	293.177,62	19.480,00
				Material and Installation w/o Profit (TRY)	312.657,62	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**24.350,00**	
				Unit Price (TRY)	**390.822,03**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1120	24 / 160 / 8 / _ / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	332.821,89	332.821,89	
	Installation Components					
10.100.1062	Unskilled worker	h	9	165,00		1.485,00
10.100.1081	Master electrician	h	18	250,00		4.500,00
10.100.1083	Master electrician's helper	h	18	185,00		3.330,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
				Total Excluding Profit (TRY)	332.821,89	21.915,00
				Material and Installation w/o Profit (TRY)	354.736,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**27.393,75**	
				Unit Price (TRY)	**443.421,11**	

Item No	Analysis Name					UoM
35.701.1122						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1122	16 / 112 / 8 / 1 / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	292.705,49	292.705,49	
	Installation Components					
10.100.1062	Unskilled worker	h	10	165,00		1.650,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	20	185,00		3.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
				Total Excluding Profit (TRY)	292.705,49	24.350,00
				Material and Installation w/o Profit (TRY)	317.055,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**30.437,50**	
				Unit Price (TRY)	**396.319,36**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1124						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1124	20 / 128 / 8 / 1 / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	321.699,39	321.699,39	
	Installation Components					
10.100.1062	Unskilled worker	h	10,5	165,00		1.732,50
10.100.1081	Master electrician	h	21	250,00		5.250,00
10.100.1083	Master electrician's helper	h	21	185,00		3.885,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
				Total Excluding Profit (TRY)	321.699,39	25.567,50
				Material and Installation w/o Profit (TRY)	347.266,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.959,38**	
				Unit Price (TRY)	**434.083,61**	

Item No	Analysis Name					UoM
35.701.1126						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1126	24 / 160 / 8 / 1 / _ / _ / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	359.124,66	359.124,66	
	Installation Components					
10.100.1062	Unskilled worker	h	11	165,00		1.815,00
10.100.1081	Master electrician	h	22	250,00		5.500,00
10.100.1083	Master electrician's helper	h	22	185,00		4.070,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	22	700,00		15.400,00
				Total Excluding Profit (TRY)	359.124,66	26.785,00
				Material and Installation w/o Profit (TRY)	385.909,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**33.481,25**	
				Unit Price (TRY)	**482.387,07**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1128						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1128	32 / 192 / 8 / _ / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	437.198,41	437.198,41	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	24	250,00		6.000,00
10.100.1083	Master electrician's helper	h	24	185,00		4.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
		Total Excluding Profit (TRY)			437.198,41	43.920,00
		Material and Installation w/o Profit (TRY)			481.118,41	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**54.900,00**	
		Unit Price (TRY)			**601.398,01**	

Item No	Analysis Name					UoM
35.701.1130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1130	16 / 224 / 15 / 1 / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	482.381,81	482.381,81	
	Installation Components					
10.100.1062	Unskilled worker	h	13	165,00		2.145,00
10.100.1081	Master electrician	h	26	250,00		6.500,00
10.100.1083	Master electrician's helper	h	26	185,00		4.810,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
		Total Excluding Profit (TRY)			482.381,81	51.255,00
		Material and Installation w/o Profit (TRY)			533.636,81	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**64.068,75**	
		Unit Price (TRY)			**667.046,01**	

Item No	Analysis Name					UoM
35.701.1132						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1132	24 / 288 / 15 / _ / _ / _ / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	549.402,00	549.402,00	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	28	250,00		7.000,00
10.100.1083	Master electrician’s helper	h	28	185,00		5.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	65	700,00		45.500,00
		Total Excluding Profit (TRY)			549.402,00	59.990,00
		Material and Installation w/o Profit (TRY)			609.392,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**74.987,50**	
		Unit Price (TRY)			**761.740,00**	

Item No	Analysis Name					UoM
35.701.1134						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1134	16 / 288 / 15 / 1 /_ / _ / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	565.915,85	565.915,85	
	Installation Components					
10.100.1062	Unskilled worker	h	14,5	165,00		2.392,50
10.100.1081	Master electrician	h	29	250,00		7.250,00
10.100.1083	Master electrician’s helper	h	29	185,00		5.365,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
		Total Excluding Profit (TRY)			565.915,85	62.607,50
		Material and Installation w/o Profit (TRY)			628.523,35	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**78.259,38**	
		Unit Price (TRY)			**785.654,19**	

Item No	Analysis Name					UoM
35.701.1136						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1136	48 / 352 / 15 / _ /_ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	630.051,57	630.051,57	
	Installation Components					
10.100.1062	Unskilled worker	h	15,5	165,00		2.557,50
10.100.1081	Master electrician	h	31	250,00		7.750,00
10.100.1083	Master electrician’s helper	h	31	185,00		5.735,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	75	700,00		52.500,00
		Total Excluding Profit (TRY)			630.051,57	68.542,50
		Material and Installation w/o Profit (TRY)			698.594,07	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**85.678,13**	
		Unit Price (TRY)			**873.242,59**	

Item No	Analysis Name					UoM
35.701.1138						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1138	24 / 352 / 15 / 1 /_ / _ / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	648.456,28	648.456,28	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	32	250,00		8.000,00
10.100.1083	Master electrician’s helper	h	32	185,00		5.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	77	700,00		53.900,00
		Total Excluding Profit (TRY)			648.456,28	70.460,00
		Material and Installation w/o Profit (TRY)			718.916,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**88.075,00**	
		Unit Price (TRY)			**898.645,35**	

Item No	Analysis Name					UoM
35.701.1140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1140	16 / 448 / 15 / 2 /_ / _ / With at least 2 processors and 50% expandable / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	755.177,10	755.177,10	
	Installation Components					
10.100.1062	Unskilled worker	h	16,5	165,00		2.722,50
10.100.1081	Master electrician	h	33	250,00		8.250,00
10.100.1083	Master electrician’s helper	h	33	185,00		6.105,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	81	700,00		56.700,00
		Total Excluding Profit (TRY)			755.177,10	73.777,50
		Material and Installation w/o Profit (TRY)			828.954,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**92.221,88**	
		Unit Price (TRY)			**1.036.193,25**	

Item No	Analysis Name					UoM
35.701.1142						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1142	24 / 464 / 15 / 1 /_ / _ / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	747.155,42	747.155,42	
	Installation Components					
10.100.1062	Unskilled worker	h	17	165,00		2.805,00
10.100.1081	Master electrician	h	34	250,00		8.500,00
10.100.1083	Master electrician’s helper	h	34	185,00		6.290,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	90	700,00		63.000,00
		Total Excluding Profit (TRY)			747.155,42	80.595,00
		Material and Installation w/o Profit (TRY)			827.750,42	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**100.743,75**	
		Unit Price (TRY)			**1.034.688,03**	

Item No	Analysis Name					UoM
35.701.1144						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1144	16 / 544 / 30 / 2 / _ / _ / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	975.634,42	975.634,42	
	Installation Components					
10.100.1062	Unskilled worker	h	18	165,00		2.970,00
10.100.1081	Master electrician	h	36	250,00		9.000,00
10.100.1083	Master electrician's helper	h	36	185,00		6.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	99	700,00		69.300,00
		Total Excluding Profit (TRY)			975.634,42	87.930,00
		Material and Installation w/o Profit (TRY)			1.063.564,42	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**109.912,50**	
		Unit Price (TRY)			**1.329.455,52**	

Item No	Analysis Name					UoM
35.701.1146						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1146	24 / 640 / 30 / 2 / _ / _ / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	995.932,83	995.932,83	
	Installation Components					
10.100.1062	Unskilled worker	h	18,5	165,00		3.052,50
10.100.1081	Master electrician	h	37	250,00		9.250,00
10.100.1083	Master electrician's helper	h	37	185,00		6.845,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	108	700,00		75.600,00
		Total Excluding Profit (TRY)			995.932,83	94.747,50
		Material and Installation w/o Profit (TRY)			1.090.680,33	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**118.434,38**	
		Unit Price (TRY)			**1.363.350,41**	

Item No	Analysis Name					UoM
35.701.1148						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1148	80 / 704 / 30 / _ / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.203.726,92	1.203.726,92	
	Installation Components					
10.100.1062	Unskilled worker	h	19,5	165,00		3.217,50
10.100.1081	Master electrician	h	39	250,00		9.750,00
10.100.1083	Master electrician’s helper	h	39	185,00		7.215,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	117	700,00		81.900,00
				Total Excluding Profit (TRY)	1.203.726,92	102.082,50
				Material and Installation w/o Profit (TRY)	1.305.809,42	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**127.603,13**	
				Unit Price (TRY)	**1.632.261,77**	

Item No	Analysis Name					UoM
35.701.1150						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1150	24 / 736 / 30 / 2 / _ / _ / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.139.605,84	1.139.605,84	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	40	250,00		10.000,00
10.100.1083	Master electrician’s helper	h	40	185,00		7.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	120	700,00		84.000,00
				Total Excluding Profit (TRY)	1.139.605,84	104.700,00
				Material and Installation w/o Profit (TRY)	1.244.305,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**130.875,00**	
				Unit Price (TRY)	**1.555.382,30**	

Item No	Analysis Name					UoM
35.701.1152						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1152	32 / 816 / 40 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.331.417,77	1.331.417,77	
	Installation Components					
10.100.1062	Unskilled worker	h	21	165,00		3.465,00
10.100.1081	Master electrician	h	42	250,00		10.500,00
10.100.1083	Master electrician’s helper	h	42	185,00		7.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	126	700,00		88.200,00
				Total Excluding Profit (TRY)	1.331.417,77	109.935,00
				Material and Installation w/o Profit (TRY)	1.441.352,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**137.418,75**	
				Unit Price (TRY)	**1.801.690,96**	

Item No	Analysis Name					UoM
35.701.1154						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1154	32 / 912 / 40 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.345.641,24	1.345.641,24	
	Installation Components					
10.100.1062	Unskilled worker	h	22	165,00		3.630,00
10.100.1081	Master electrician	h	44	250,00		11.000,00
10.100.1083	Master electrician’s helper	h	44	185,00		8.140,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	144	700,00		100.800,00
				Total Excluding Profit (TRY)	1.345.641,24	123.570,00
				Material and Installation w/o Profit (TRY)	1.469.211,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**154.462,50**	
				Unit Price (TRY)	**1.836.514,05**	

Item No	Analysis Name					UoM
35.701.1156						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1156	40 / 1.104 / 50 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.676.158,15	1.676.158,15	
	Installation Components					
10.100.1062	Unskilled worker	h	23	165,00		3.795,00
10.100.1081	Master electrician	h	46	250,00		11.500,00
10.100.1083	Master electrician’s helper	h	46	185,00		8.510,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	162	700,00		113.400,00
				Total Excluding Profit (TRY)	1.676.158,15	137.205,00
				Material and Installation w/o Profit (TRY)	1.813.363,15	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**171.506,25**	
				Unit Price (TRY)	**2.266.703,94**	

Item No	Analysis Name					UoM
35.701.1158						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1158	32 / 1,376 / 60 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.978.907,21	1.978.907,21	
	Installation Components					
10.100.1062	Unskilled worker	h	24	165,00		3.960,00
10.100.1081	Master electrician	h	48	250,00		12.000,00
10.100.1083	Master electrician’s helper	h	48	185,00		8.880,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	180	700,00		126.000,00
				Total Excluding Profit (TRY)	1.978.907,21	150.840,00
				Material and Installation w/o Profit (TRY)	2.129.747,21	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**188.550,00**	
				Unit Price (TRY)	**2.662.184,01**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1160	56 / 1,680 / 80 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.245.356,51	2.245.356,51	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	50	250,00		12.500,00
10.100.1083	Master electrician's helper	h	50	185,00		9.250,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	198	700,00		138.600,00
				Total Excluding Profit (TRY)	2.245.356,51	164.475,00
				Material and Installation w/o Profit (TRY)	2.409.831,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**205.593,75**	
				Unit Price (TRY)	**3.012.289,39**	

Item No	Analysis Name					UoM
35.701.1162						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1162	56 / 1,760 / 80 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.311.593,40	2.311.593,40	
	Installation Components					
10.100.1062	Unskilled worker	h	26	165,00		4.290,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician's helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	216	700,00		151.200,00
				Total Excluding Profit (TRY)	2.311.593,40	178.110,00
				Material and Installation w/o Profit (TRY)	2.489.703,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**222.637,50**	
				Unit Price (TRY)	**3.112.129,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1164						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1164	72 / 2,192 / 112 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.869.038,86	2.869.038,86	
	Installation Components					
10.100.1062	Unskilled worker	h	27	165,00		4.455,00
10.100.1081	Master electrician	h	54	250,00		13.500,00
10.100.1083	Master electrician's helper	h	54	185,00		9.990,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	234	700,00		163.800,00
				Total Excluding Profit (TRY)	2.869.038,86	191.745,00
				Material and Installation w/o Profit (TRY)	3.060.783,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**239.681,25**	
				Unit Price (TRY)	**3.825.979,82**	

Item No	Analysis Name					UoM
35.701.1166						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1166	96 / 2.496 / 128 / 2 / _ / _ / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	3.097.810,76	3.097.810,76	
	Installation Components					
10.100.1062	Unskilled worker	h	28	165,00		4.620,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician's helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	252	700,00		176.400,00
				Total Excluding Profit (TRY)	3.097.810,76	205.380,00
				Material and Installation w/o Profit (TRY)	3.303.190,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**256.725,00**	
				Unit Price (TRY)	**4.128.988,45**	

Item No	Analysis Name					UoM
35.701.1168						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1168	108 / 3,504 / 176 / _ / _ / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	4.540.906,04	4.540.906,04	
	Installation Components					
10.100.1062	Unskilled worker	h	29	165,00		4.785,00
10.100.1081	Master electrician	h	58	250,00		14.500,00
10.100.1083	Master electrician’s helper	h	58	185,00		10.730,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	288	700,00		201.600,00
				Total Excluding Profit (TRY)	4.540.906,04	231.615,00
				Material and Installation w/o Profit (TRY)	4.772.521,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**289.518,75**	
				Unit Price (TRY)	**5.965.651,30**	

Item No	Analysis Name					UoM
35.701.1170						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1170	128 / 3.904 / 214 / 6 / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	5.192.365,20	5.192.365,20	
	Installation Components					
10.100.1062	Unskilled worker	h	32	165,00		5.280,00
10.100.1081	Master electrician	h	64	250,00		16.000,00
10.100.1083	Master electrician’s helper	h	64	185,00		11.840,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	342	700,00		239.400,00
				Total Excluding Profit (TRY)	5.192.365,20	272.520,00
				Material and Installation w/o Profit (TRY)	5.464.885,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**340.650,00**	
				Unit Price (TRY)	**6.831.106,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1172						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1172	176 / 4.992 / 256 / 8 / _ / _ / With minimum 2 processors and 50% expansion capacity / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	6.532.446,35	6.532.446,35	
	Installation Components					
10.100.1062	Unskilled worker	h	36	165,00		5.940,00
10.100.1081	Master electrician	h	72	250,00		18.000,00
10.100.1083	Master electrician's helper	h	72	185,00		13.320,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	432	700,00		302.400,00
				Total Excluding Profit (TRY)	6.532.446,35	339.660,00
				Material and Installation w/o Profit (TRY)	6.872.106,35	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**424.575,00**	
				Unit Price (TRY)	**8.590.132,94**	

Item No	Analysis Name					UoM
35.701.1200						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1200	4 / 14 / 2 / _ / 2 / 10 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	34.009,71	34.009,71	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	34.009,71	6.940,00
				Material and Installation w/o Profit (TRY)	40.949,71	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.675,00**	
				Unit Price (TRY)	**51.187,14**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1201						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1201	4 / 22 / 2 / _ / 4 / 20 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	42.599,95	42.599,95	
	Installation Components					
10.100.1062	Unskilled worker	h	4,5	165,00		742,50
10.100.1081	Master electrician	h	9	250,00		2.250,00
10.100.1083	Master electrician's helper	h	9	185,00		1.665,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4,5	700,00		3.150,00
				Total Excluding Profit (TRY)	42.599,95	7.807,50
				Material and Installation w/o Profit (TRY)	50.407,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**9.759,38**	
				Unit Price (TRY)	**63.009,31**	

Item No	Analysis Name					UoM
35.701.1202						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1202	4 / 22 / 2 / _ / 8 / 40 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	50.593,86	50.593,86	
	Installation Components					
10.100.1062	Unskilled worker	h	4,5	165,00		742,50
10.100.1081	Master electrician	h	9	250,00		2.250,00
10.100.1083	Master electrician's helper	h	9	185,00		1.665,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4,5	700,00		3.150,00
				Total Excluding Profit (TRY)	50.593,86	7.807,50
				Material and Installation w/o Profit (TRY)	58.401,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**9.759,38**	
				Unit Price (TRY)	**73.001,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1203						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1203	4 / 22 / 2 /_ / 10 / 50 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	54.992,80	54.992,80	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician's helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
				Total Excluding Profit (TRY)	54.992,80	8.675,00
				Material and Installation w/o Profit (TRY)	63.667,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**10.843,75**	
				Unit Price (TRY)	**79.584,75**	

Item No	Analysis Name					UoM
35.701.1204						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1204	4 / 22 / 2 /_ / 16 / 80 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	98.138,08	98.138,08	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	98.138,08	10.410,00
				Material and Installation w/o Profit (TRY)	108.548,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.012,50**	
				Unit Price (TRY)	**135.685,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1205						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1205	4 / 22 / 2 /_ / 20 / 100 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	105.328,01	105.328,01	
	Installation Components					
10.100.1062	Unskilled worker	h	6,5	165,00		1.072,50
10.100.1081	Master electrician	h	13	250,00		3.250,00
10.100.1083	Master electrician's helper	h	13	185,00		2.405,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6,5	700,00		4.550,00
				Total Excluding Profit (TRY)	105.328,01	11.277,50
				Material and Installation w/o Profit (TRY)	116.605,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.096,88**	
				Unit Price (TRY)	**145.756,89**	

Item No	Analysis Name					UoM
35.701.1206						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1206	4 / 22 / 2 /_ / 24 / 120 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	110.410,11	110.410,11	
	Installation Components					
10.100.1062	Unskilled worker	h	6,5	165,00		1.072,50
10.100.1081	Master electrician	h	13	250,00		3.250,00
10.100.1083	Master electrician's helper	h	13	185,00		2.405,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6,5	700,00		4.550,00
				Total Excluding Profit (TRY)	110.410,11	11.277,50
				Material and Installation w/o Profit (TRY)	121.687,61	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.096,88**	
				Unit Price (TRY)	**152.109,51**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1208						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1208	4 / 22 / 2 /_ / 24 / 150 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	118.817,50	118.817,50	
	Installation Components					
10.100.1062	Unskilled worker	h	6,5	165,00		1.072,50
10.100.1081	Master electrician	h	13	250,00		3.250,00
10.100.1083	Master electrician's helper	h	13	185,00		2.405,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6,5	700,00		4.550,00
				Total Excluding Profit (TRY)	118.817,50	11.277,50
				Material and Installation w/o Profit (TRY)	130.095,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.096,88**	
				Unit Price (TRY)	**162.618,75**	

Item No	Analysis Name					UoM
35.701.1209						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1209	4 / 22 / 2 /_ / 36 / 180 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	135.184,33	135.184,33	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
				Total Excluding Profit (TRY)	135.184,33	12.145,00
				Material and Installation w/o Profit (TRY)	147.329,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.181,25**	
				Unit Price (TRY)	**184.161,66**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1210	4 / 22 / 2 /_ / 36 / 200 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	141.822,95	141.822,95	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7,5	700,00		5.250,00
				Total Excluding Profit (TRY)	141.822,95	13.012,50
				Material and Installation w/o Profit (TRY)	154.835,45	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**16.265,63**	
				Unit Price (TRY)	**193.544,31**	

Item No	Analysis Name					UoM
35.701.1211						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1211	4 / 22 / 2 /_ / 40 / 220 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	148.920,99	148.920,99	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7,5	700,00		5.250,00
				Total Excluding Profit (TRY)	148.920,99	13.012,50
				Material and Installation w/o Profit (TRY)	161.933,49	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**16.265,63**	
				Unit Price (TRY)	**202.416,86**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1212						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1212	8 / 32 / 4 / _ / 6 / 30 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	89.107,95	89.107,95	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	89.107,95	10.410,00
				Material and Installation w/o Profit (TRY)	99.517,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.012,50**	
				Unit Price (TRY)	**124.397,44**	

Item No	Analysis Name					UoM
35.701.1213						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1213	8 / 32 / 4 / _ / 10 / 50 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	110.850,01	110.850,01	
	Installation Components					
10.100.1062	Unskilled worker	h	6,5	165,00		1.072,50
10.100.1081	Master electrician	h	13	250,00		3.250,00
10.100.1083	Master electrician's helper	h	13	185,00		2.405,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6,5	700,00		4.550,00
				Total Excluding Profit (TRY)	110.850,01	11.277,50
				Material and Installation w/o Profit (TRY)	122.127,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.096,88**	
				Unit Price (TRY)	**152.659,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1214						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1214	8 / 32 / 4 / _ / 16 / 80 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	117.557,54	117.557,54	
	Installation Components					
10.100.1062	Unskilled worker	h	6,5	165,00		1.072,50
10.100.1081	Master electrician	h	13	250,00		3.250,00
10.100.1083	Master electrician's helper	h	13	185,00		2.405,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6,5	700,00		4.550,00
				Total Excluding Profit (TRY)	117.557,54	11.277,50
				Material and Installation w/o Profit (TRY)	128.835,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.096,88**	
				Unit Price (TRY)	**161.043,80**	

Item No	Analysis Name					UoM
35.701.1215						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1215	8 / 32 / 4 / _ / 20 / 100 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	125.450,37	125.450,37	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
				Total Excluding Profit (TRY)	125.450,37	12.145,00
				Material and Installation w/o Profit (TRY)	137.595,37	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.181,25**	
				Unit Price (TRY)	**171.994,21**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1216						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1216	8 / 32 / 4 / _ / 24 / 120 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	133.340,91	133.340,91	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
				Total Excluding Profit (TRY)	133.340,91	12.145,00
				Material and Installation w/o Profit (TRY)	145.485,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.181,25**	
				Unit Price (TRY)	**181.857,39**	

Item No	Analysis Name					UoM
35.701.1217						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1217	8 / 32 / 4 / _ / 30 / 150 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	143.528,55	143.528,55	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7,5	700,00		5.250,00
				Total Excluding Profit (TRY)	143.528,55	13.012,50
				Material and Installation w/o Profit (TRY)	156.541,05	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**16.265,63**	
				Unit Price (TRY)	**195.676,31**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1218						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1218	8 / 32 / 4 / _ / 36 / 180 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	151.981,88	151.981,88	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7,5	700,00		5.250,00
				Total Excluding Profit (TRY)	151.981,88	13.012,50
				Material and Installation w/o Profit (TRY)	164.994,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**16.265,63**	
				Unit Price (TRY)	**206.242,98**	

Item No	Analysis Name					UoM
35.701.1219						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1219	8 / 32 / 4 / _ / 40 / 200 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	164.133,54	164.133,54	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	164.133,54	13.880,00
				Material and Installation w/o Profit (TRY)	178.013,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.350,00**	
				Unit Price (TRY)	**222.516,93**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1220	12 / 48 / 4 /_ / 6 / 50 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	104.217,36	104.217,36	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	104.217,36	10.410,00
				Material and Installation w/o Profit (TRY)	114.627,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.012,50**	
				Unit Price (TRY)	**143.284,20**	

Item No	Analysis Name					UoM
35.701.1221						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1221	12 / 48 / 4 /_ / 16 / 80 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	130.254,99	130.254,99	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
				Total Excluding Profit (TRY)	130.254,99	12.145,00
				Material and Installation w/o Profit (TRY)	142.399,99	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.181,25**	
				Unit Price (TRY)	**177.999,99**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1222						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1222	12 / 48 / 4 /_ / 20 / 100 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	138.141,85	138.141,85	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
		Total Excluding Profit (TRY)			138.141,85	12.145,00
		Material and Installation w/o Profit (TRY)			150.286,85	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**15.181,25**	
		Unit Price (TRY)			**187.858,56**	

Item No	Analysis Name					UoM
35.701.1223						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1223	12 / 48 / 4 /_ / 24 / 120 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	146.032,39	146.032,39	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7,5	700,00		5.250,00
		Total Excluding Profit (TRY)			146.032,39	13.012,50
		Material and Installation w/o Profit (TRY)			159.044,89	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**16.265,63**	
		Unit Price (TRY)			**198.806,11**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1224						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1224	12 / 48 / 4 /_ / 30 / 150 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	158.149,59	158.149,59	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	158.149,59	13.880,00
				Material and Installation w/o Profit (TRY)	172.029,59	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.350,00**	
				Unit Price (TRY)	**215.036,99**	

Item No	Analysis Name					UoM
35.701.1225						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1225	12 / 48 / 4 /_ / 36 / 180 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	167.452,85	167.452,85	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	167.452,85	13.880,00
				Material and Installation w/o Profit (TRY)	181.332,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.350,00**	
				Unit Price (TRY)	**226.666,06**	

Item No	Analysis Name					UoM
35.701.1226						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1226	16 / 64 / 8 / _ / 6 / 50 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	141.058,48	141.058,48	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7,5	700,00		5.250,00
				Total Excluding Profit (TRY)	141.058,48	13.012,50
				Material and Installation w/o Profit (TRY)	154.070,98	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**16.265,63**	
				Unit Price (TRY)	**192.588,73**	

Item No	Analysis Name					UoM
35.701.1227						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1227	16 / 64 / 8 / _ / 10 / 80 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	166.016,47	166.016,47	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	166.016,47	13.880,00
				Material and Installation w/o Profit (TRY)	179.896,47	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.350,00**	
				Unit Price (TRY)	**224.870,59**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1228						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1228	16 / 64 / 8 / _ / 10 / 100 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	169.571,92	169.571,92	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	169.571,92	13.880,00
				Material and Installation w/o Profit (TRY)	183.451,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.350,00**	
				Unit Price (TRY)	**229.314,90**	

Item No	Analysis Name					UoM
35.701.1229						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1229	16 / 64 / 8 / _ / 12 / 120 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	175.165,36	175.165,36	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	175.165,36	13.880,00
				Material and Installation w/o Profit (TRY)	189.045,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.350,00**	
				Unit Price (TRY)	**236.306,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1230	16 / 64 / 8 / _ / 15 / 150 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	182.171,52	182.171,52	
	Installation Components					
10.100.1062	Unskilled worker	h	8,5	165,00		1.402,50
10.100.1081	Master electrician	h	17	250,00		4.250,00
10.100.1083	Master electrician’s helper	h	17	185,00		3.145,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8,5	700,00		5.950,00
				Total Excluding Profit (TRY)	182.171,52	14.747,50
				Material and Installation w/o Profit (TRY)	196.919,02	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**18.434,38**	
				Unit Price (TRY)	**246.148,77**	

Item No	Analysis Name					UoM
35.701.1231						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1231	16 / 80 / 8 / _ / 10 / 80 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	183.221,75	183.221,75	
	Installation Components					
10.100.1062	Unskilled worker	h	8,5	165,00		1.402,50
10.100.1081	Master electrician	h	17	250,00		4.250,00
10.100.1083	Master electrician’s helper	h	17	185,00		3.145,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8,5	700,00		5.950,00
				Total Excluding Profit (TRY)	183.221,75	14.747,50
				Material and Installation w/o Profit (TRY)	197.969,25	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**18.434,38**	
				Unit Price (TRY)	**247.461,56**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1232						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1232	20 / 112 / 8 / _ / 10 / 100 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	239.983,41	239.983,41	
	Installation Components					
10.100.1062	Unskilled worker	h	10	165,00		1.650,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	20	185,00		3.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	239.983,41	17.350,00
				Material and Installation w/o Profit (TRY)	257.333,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**21.687,50**	
				Unit Price (TRY)	**321.666,76**	

Item No	Analysis Name					UoM
35.701.1233						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1233	20 / 128 / 8 / _ / 10 / 120 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	260.485,03	260.485,03	
	Installation Components					
10.100.1062	Unskilled worker	h	10,5	165,00		1.732,50
10.100.1081	Master electrician	h	21	250,00		5.250,00
10.100.1083	Master electrician's helper	h	21	185,00		3.885,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10,5	700,00		7.350,00
				Total Excluding Profit (TRY)	260.485,03	18.217,50
				Material and Installation w/o Profit (TRY)	278.702,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**22.771,88**	
				Unit Price (TRY)	**348.378,16**	

Item No	Analysis Name					UoM
35.701.1234						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1234	16 / 80 / 8 / 1 / 10 / 80 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	205.360,28	205.360,28	
	Installation Components					
10.100.1062	Unskilled worker	h	9	165,00		1.485,00
10.100.1081	Master electrician	h	18	250,00		4.500,00
10.100.1083	Master electrician's helper	h	18	185,00		3.330,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
		Total Excluding Profit (TRY)			205.360,28	15.615,00
		Material and Installation w/o Profit (TRY)			220.975,28	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**19.518,75**	
		Unit Price (TRY)			**276.219,10**	

Item No	Analysis Name					UoM
35.701.1235						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1235	16 / 112 / 8 / 1 / 10 / 100 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	258.788,53	258.788,53	
	Installation Components					
10.100.1062	Unskilled worker	h	10,5	165,00		1.732,50
10.100.1081	Master electrician	h	21	250,00		5.250,00
10.100.1083	Master electrician's helper	h	21	185,00		3.885,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10,5	700,00		7.350,00
		Total Excluding Profit (TRY)			258.788,53	18.217,50
		Material and Installation w/o Profit (TRY)			277.006,03	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**22.771,88**	
		Unit Price (TRY)			**346.257,54**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1236						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1236	20 / 128 / 8 / 1 / 10 / 120 / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	281.201,10	281.201,10	
	Installation Components					
10.100.1062	Unskilled worker	h	11	165,00		1.815,00
10.100.1081	Master electrician	h	22	250,00		5.500,00
10.100.1083	Master electrician's helper	h	22	185,00		4.070,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	11	700,00		7.700,00
				Total Excluding Profit (TRY)	281.201,10	19.085,00
				Material and Installation w/o Profit (TRY)	300.286,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**23.856,25**	
				Unit Price (TRY)	**375.357,63**	

Item No	Analysis Name					UoM
35.701.1237						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1237	32 / 192 / 8 / _ / 10 / 200 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	494.729,28	494.729,28	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	24	250,00		6.000,00
10.100.1083	Master electrician's helper	h	24	185,00		4.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
				Total Excluding Profit (TRY)	494.729,28	47.420,00
				Material and Installation w/o Profit (TRY)	542.149,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**59.275,00**	
				Unit Price (TRY)	**677.686,60**	

Item No	Analysis Name					UoM
35.701.1238						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1238	16 / 224 / 15 / 1 / 14 / 220 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	503.307,19	503.307,19	
	Installation Components					
10.100.1062	Unskilled worker	h	13	165,00		2.145,00
10.100.1081	Master electrician	h	26	250,00		6.500,00
10.100.1083	Master electrician's helper	h	26	185,00		4.810,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
				Total Excluding Profit (TRY)	503.307,19	55.455,00
				Material and Installation w/o Profit (TRY)	558.762,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**69.318,75**	
				Unit Price (TRY)	**698.452,74**	

Item No	Analysis Name					UoM
35.701.1239						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1239	24 / 288 / 15 / _ / 14 / 280 / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	559.258,19	559.258,19	
	Installation Components					
10.100.1062	Unskilled worker	h	14	165,00		2.310,00
10.100.1081	Master electrician	h	28	250,00		7.000,00
10.100.1083	Master electrician's helper	h	28	185,00		5.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
				Total Excluding Profit (TRY)	559.258,19	64.890,00
				Material and Installation w/o Profit (TRY)	624.148,19	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81.112,50**	
				Unit Price (TRY)	**780.185,24**	

Item No	Analysis Name					UoM
35.701.1240						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1240	16 / 288 / 15 / 1 / 18 / 280 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	590.852,32	590.852,32	
	Installation Components					
10.100.1062	Unskilled worker	h	14,5	165,00		2.392,50
10.100.1081	Master electrician	h	29	250,00		7.250,00
10.100.1083	Master electrician's helper	h	29	185,00		5.365,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	75	700,00		52.500,00
				Total Excluding Profit (TRY)	590.852,32	67.507,50
				Material and Installation w/o Profit (TRY)	658.359,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**84.384,38**	
				Unit Price (TRY)	**822.949,77**	

Item No	Analysis Name					UoM
35.701.1241						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1241	48 / 352 / 15 / _ / 22 / 350 / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	851.887,53	851.887,53	
	Installation Components					
10.100.1062	Unskilled worker	h	15,5	165,00		2.557,50
10.100.1081	Master electrician	h	31	250,00		7.750,00
10.100.1083	Master electrician's helper	h	31	185,00		5.735,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	83	700,00		58.100,00
				Total Excluding Profit (TRY)	851.887,53	74.142,50
				Material and Installation w/o Profit (TRY)	926.030,03	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**92.678,13**	
				Unit Price (TRY)	**1.157.537,54**	

Item No	Analysis Name					UoM
35.701.1242						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1242	24 / 352 / 15 / 1 / 22 / 350 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	836.498,82	836.498,82	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	32	250,00		8.000,00
10.100.1083	Master electrician's helper	h	32	185,00		5.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	85	700,00		59.500,00
				Total Excluding Profit (TRY)	836.498,82	76.060,00
				Material and Installation w/o Profit (TRY)	912.558,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**95.075,00**	
				Unit Price (TRY)	**1.140.698,52**	

Item No	Analysis Name					UoM
35.701.1243						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1243	24 / 464 / 15 / 1 / 26 / 460 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	997.828,33	997.828,33	
	Installation Components					
10.100.1062	Unskilled worker	h	17	165,00		2.805,00
10.100.1081	Master electrician	h	34	250,00		8.500,00
10.100.1083	Master electrician's helper	h	34	185,00		6.290,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	100	700,00		70.000,00
				Total Excluding Profit (TRY)	997.828,33	87.595,00
				Material and Installation w/o Profit (TRY)	1.085.423,33	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**109.493,75**	
				Unit Price (TRY)	**1.356.779,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1244						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1244	64 / 512 / 15 / _ / 30 / 500 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.094.479,03	1.094.479,03	
	Installation Components					
10.100.1062	Unskilled worker	h	17,5	165,00		2.887,50
10.100.1081	Master electrician	h	35	250,00		8.750,00
10.100.1083	Master electrician's helper	h	35	185,00		6.475,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	108	700,00		75.600,00
				Total Excluding Profit (TRY)	1.094.479,03	93.712,50
				Material and Installation w/o Profit (TRY)	1.188.191,53	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**117.140,63**	
				Unit Price (TRY)	**1.485.239,41**	

Item No	Analysis Name					UoM
35.701.1245						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1245	16 / 544 / 30 / 2 / 30 / 540 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.125.398,80	1.125.398,80	
	Installation Components					
10.100.1062	Unskilled worker	h	18	165,00		2.970,00
10.100.1081	Master electrician	h	36	250,00		9.000,00
10.100.1083	Master electrician's helper	h	36	185,00		6.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	110	700,00		77.000,00
				Total Excluding Profit (TRY)	1.125.398,80	95.630,00
				Material and Installation w/o Profit (TRY)	1.221.028,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**119.537,50**	
				Unit Price (TRY)	**1.526.286,00**	

Item No	Analysis Name					UoM
35.701.1246						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1246	24 / 640 / 30 / 2 / 38 / 640 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.296.736,32	1.296.736,32	
	Installation Components					
10.100.1062	Unskilled worker	h	18,5	165,00		3.052,50
10.100.1081	Master electrician	h	37	250,00		9.250,00
10.100.1083	Master electrician's helper	h	37	185,00		6.845,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	120	700,00		84.000,00
				Total Excluding Profit (TRY)	1.296.736,32	103.147,50
				Material and Installation w/o Profit (TRY)	1.399.883,82	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**128.934,38**	
				Unit Price (TRY)	**1.749.854,78**	

Item No	Analysis Name					UoM
35.701.1247						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1247	80 / 704 / 30 / _ / 42 / 700 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.431.063,60	1.431.063,60	
	Installation Components					
10.100.1062	Unskilled worker	h	19,5	165,00		3.217,50
10.100.1081	Master electrician	h	39	250,00		9.750,00
10.100.1083	Master electrician's helper	h	39	185,00		7.215,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	130	700,00		91.000,00
				Total Excluding Profit (TRY)	1.431.063,60	111.182,50
				Material and Installation w/o Profit (TRY)	1.542.246,10	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**138.978,13**	
				Unit Price (TRY)	**1.927.807,63**	

Item No	Analysis Name					UoM
35.701.1248						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1248	96 / 784 / 30 / _ / 46 / 780 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.554.334,57	1.554.334,57	
	Installation Components					
10.100.1062	Unskilled worker	h	20,5	165,00		3.382,50
10.100.1081	Master electrician	h	41	250,00		10.250,00
10.100.1083	Master electrician’s helper	h	41	185,00		7.585,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	138	700,00		96.600,00
				Total Excluding Profit (TRY)	1.554.334,57	117.817,50
				Material and Installation w/o Profit (TRY)	1.672.152,07	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**147.271,88**	
				Unit Price (TRY)	**2.090.190,09**	

Item No	Analysis Name					UoM
35.701.1249						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1249	32 / 816 / 30 / 2 / 46 / 800 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.555.737,48	1.555.737,48	
	Installation Components					
10.100.1062	Unskilled worker	h	21	165,00		3.465,00
10.100.1081	Master electrician	h	42	250,00		10.500,00
10.100.1083	Master electrician’s helper	h	42	185,00		7.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	140	700,00		98.000,00
				Total Excluding Profit (TRY)	1.555.737,48	119.735,00
				Material and Installation w/o Profit (TRY)	1.675.472,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**149.668,75**	
				Unit Price (TRY)	**2.094.340,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1250						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1250	32 / 912 / 30 / 3 / 50 / 900 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.754.697,26	1.754.697,26	
	Installation Components					
10.100.1062	Unskilled worker	h	22	165,00		3.630,00
10.100.1081	Master electrician	h	44	250,00		11.000,00
10.100.1083	Master electrician's helper	h	44	185,00		8.140,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	160	700,00		112.000,00
				Total Excluding Profit (TRY)	1.754.697,26	134.770,00
				Material and Installation w/o Profit (TRY)	1.889.467,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**168.462,50**	
				Unit Price (TRY)	**2.361.834,08**	

Item No	Analysis Name					UoM
35.701.1251						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1251	120 / 1.056 / 30 / _ / 54 / 1000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.917.232,81	1.917.232,81	
	Installation Components					
10.100.1062	Unskilled worker	h	22,5	165,00		3.712,50
10.100.1081	Master electrician	h	45	250,00		11.250,00
10.100.1083	Master electrician's helper	h	45	185,00		8.325,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	175	700,00		122.500,00
				Total Excluding Profit (TRY)	1.917.232,81	145.787,50
				Material and Installation w/o Profit (TRY)	2.063.020,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**182.234,38**	
				Unit Price (TRY)	**2.578.775,39**	

Item No	Analysis Name					UoM
35.701.1252						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1252	40 / 1.104 / 30 / 3 / 54 / 1100 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.988.078,12	1.988.078,12	
	Installation Components					
10.100.1062	Unskilled worker	h	23	165,00		3.795,00
10.100.1081	Master electrician	h	46	250,00		11.500,00
10.100.1083	Master electrician's helper	h	46	185,00		8.510,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	180	700,00		126.000,00
				Total Excluding Profit (TRY)	1.988.078,12	149.805,00
				Material and Installation w/o Profit (TRY)	2.137.883,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**187.256,25**	
				Unit Price (TRY)	**2.672.353,90**	

Item No	Analysis Name					UoM
35.701.1253						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1253	32 / 1.376 / 30 / 4 / 58 / 1350 / With at least 2 processors and 50% expandable. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.340.871,51	2.340.871,51	
	Installation Components					
10.100.1062	Unskilled worker	h	24	165,00		3.960,00
10.100.1081	Master electrician	h	48	250,00		12.000,00
10.100.1083	Master electrician's helper	h	48	185,00		8.880,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	200	700,00		140.000,00
				Total Excluding Profit (TRY)	2.340.871,51	164.840,00
				Material and Installation w/o Profit (TRY)	2.505.711,51	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**206.050,00**	
				Unit Price (TRY)	**3.132.139,39**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1254						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1254	56 / 1.680 / 30 / 4 / 62 / 1680 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.727.046,00	2.727.046,00	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	50	250,00		12.500,00
10.100.1083	Master electrician's helper	h	50	185,00		9.250,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	220	700,00		154.000,00
				Total Excluding Profit (TRY)	2.727.046,00	179.875,00
				Material and Installation w/o Profit (TRY)	2.906.921,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**224.843,75**	
				Unit Price (TRY)	**3.633.651,25**	

Item No	Analysis Name					UoM
35.701.1255						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1255	200 / 1,760 / 30 / _ / 70 / 1,760 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	3.140.736,83	3.140.736,83	
	Installation Components					
10.100.1062	Unskilled worker	h	26	165,00		4.290,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician's helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	240	700,00		168.000,00
				Total Excluding Profit (TRY)	3.140.736,83	194.910,00
				Material and Installation w/o Profit (TRY)	3.335.646,83	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**243.637,50**	
				Unit Price (TRY)	**4.169.558,54**	

Item No	Analysis Name					UoM
35.701.1256						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1256	256 / 2.192 / 30 / _ / 90 / 2,000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	3.584.491,14	3.584.491,14	
	Installation Components					
10.100.1062	Unskilled worker	h	27	165,00		4.455,00
10.100.1081	Master electrician	h	54	250,00		13.500,00
10.100.1083	Master electrician’s helper	h	54	185,00		9.990,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	260	700,00		182.000,00
				Total Excluding Profit (TRY)	3.584.491,14	209.945,00
				Material and Installation w/o Profit (TRY)	3.794.436,14	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**262.431,25**	
				Unit Price (TRY)	**4.743.045,17**	

Item No	Analysis Name					UoM
35.701.1257						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1257	96 / 2.496 / 45 / 6 / 100 / 2500 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	3.874.330,83	3.874.330,83	
	Installation Components					
10.100.1062	Unskilled worker	h	28	165,00		4.620,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician’s helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	280	700,00		196.000,00
				Total Excluding Profit (TRY)	3.874.330,83	224.980,00
				Material and Installation w/o Profit (TRY)	4.099.310,83	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**281.225,00**	
				Unit Price (TRY)	**5.124.138,54**	

Item No	Analysis Name					UoM
35.701.1258						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1258	304 / 2.800 / 45 / _ / 120 / 2800 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	4.766.151,10	4.766.151,10	
	Installation Components					
10.100.1062	Unskilled worker	h	29	165,00		4.785,00
10.100.1081	Master electrician	h	58	250,00		14.500,00
10.100.1083	Master electrician’s helper	h	58	185,00		10.730,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	300	700,00		210.000,00
				Total Excluding Profit (TRY)	4.766.151,10	240.015,00
				Material and Installation w/o Profit (TRY)	5.006.166,10	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**300.018,75**	
				Unit Price (TRY)	**6.257.707,63**	

Item No	Analysis Name					UoM
35.701.1259						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1259	112 / 3.104 / 45 / 7 / 150 / 3100 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	5.163.157,66	5.163.157,66	
	Installation Components					
10.100.1062	Unskilled worker	h	30	165,00		4.950,00
10.100.1081	Master electrician	h	60	250,00		15.000,00
10.100.1083	Master electrician’s helper	h	60	185,00		11.100,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	320	700,00		224.000,00
				Total Excluding Profit (TRY)	5.163.157,66	255.050,00
				Material and Installation w/o Profit (TRY)	5.418.207,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**318.812,50**	
				Unit Price (TRY)	**6.772.759,58**	

Item No	Analysis Name					UoM
35.701.1260						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1260	128 / 3.904 / 45 / 9 / 250 / 3900 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	6.536.507,25	6.536.507,25	
	Installation Components					
10.100.1062	Unskilled worker	h	32	165,00		5.280,00
10.100.1081	Master electrician	h	64	250,00		16.000,00
10.100.1083	Master electrician's helper	h	64	185,00		11.840,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	380	700,00		266.000,00
				Total Excluding Profit (TRY)	6.536.507,25	299.120,00
				Material and Installation w/o Profit (TRY)	6.835.627,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**373.900,00**	
				Unit Price (TRY)	**8.544.534,06**	

Item No	Analysis Name					UoM
35.701.1261						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1261	176 / 4,992 / 45 / 11 / 350 / 5000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	8.238.191,07	8.238.191,07	
	Installation Components					
10.100.1062	Unskilled worker	h	36	165,00		5.940,00
10.100.1081	Master electrician	h	72	250,00		18.000,00
10.100.1083	Master electrician's helper	h	72	185,00		13.320,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	480	700,00		336.000,00
				Total Excluding Profit (TRY)	8.238.191,07	373.260,00
				Material and Installation w/o Profit (TRY)	8.611.451,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**466.575,00**	
				Unit Price (TRY)	**10.764.313,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1300						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1300	12 / 24 / 8 / _ / 25 / 300 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	503.284,89	503.284,89	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
				Total Excluding Profit (TRY)	503.284,89	34.210,00
				Material and Installation w/o Profit (TRY)	537.494,89	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42.762,50**	
				Unit Price (TRY)	**671.868,61**	

Item No	Analysis Name					UoM
35.701.1303						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1303	12 / 24 / 8 / _ / 25 / 350 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	510.000,00	510.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
				Total Excluding Profit (TRY)	510.000,00	34.210,00
				Material and Installation w/o Profit (TRY)	544.210,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42.762,50**	
				Unit Price (TRY)	**680.262,50**	

Item No	Analysis Name					UoM
35.701.1306						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1306	12 / 24 / 8 / _ / 25 / 400 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	514.805,73	514.805,73	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
				Total Excluding Profit (TRY)	514.805,73	34.210,00
				Material and Installation w/o Profit (TRY)	549.015,73	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**42.762,50**	
				Unit Price (TRY)	**686.269,66**	

Item No	Analysis Name					UoM
35.701.1309						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1309	12 / 24 / 8 / _ / 50 / 500 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	730.856,82	730.856,82	
	Installation Components					
10.100.1062	Unskilled worker	h	7,5	165,00		1.237,50
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
				Total Excluding Profit (TRY)	730.856,82	46.407,50
				Material and Installation w/o Profit (TRY)	777.264,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**58.009,38**	
				Unit Price (TRY)	**971.580,40**	

Item No	Analysis Name					UoM
35.701.1312						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1312	12 / 24 / 15 / _ / 60 / 600 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	786.332,67	786.332,67	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
				Total Excluding Profit (TRY)	786.332,67	49.540,00
				Material and Installation w/o Profit (TRY)	835.872,67	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**61.925,00**	
				Unit Price (TRY)	**1.044.840,84**	

Item No	Analysis Name					UoM
35.701.1315						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1315	12 / 24 / 15 / _ / 60 / 700 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	829.640,96	829.640,96	
	Installation Components					
10.100.1062	Unskilled worker	h	8,5	165,00		1.402,50
10.100.1081	Master electrician	h	17	250,00		4.250,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	63	700,00		44.100,00
				Total Excluding Profit (TRY)	829.640,96	51.972,50
				Material and Installation w/o Profit (TRY)	881.613,46	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**64.965,63**	
				Unit Price (TRY)	**1.102.016,82**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1318						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1318	12 / 24 / 15 / _ / 60 / 800 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	840.596,36	840.596,36	
	Installation Components					
10.100.1062	Unskilled worker	h	8,5	165,00		1.402,50
10.100.1081	Master electrician	h	17	250,00		4.250,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
				Total Excluding Profit (TRY)	840.596,36	52.672,50
				Material and Installation w/o Profit (TRY)	893.268,86	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**65.840,63**	
				Unit Price (TRY)	**1.116.586,07**	

Item No	Analysis Name					UoM
35.701.1321						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1321	12 / 24 / 15 / _ / 80 / 1000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	904.756,13	904.756,13	
	Installation Components					
10.100.1062	Unskilled worker	h	9	165,00		1.485,00
10.100.1081	Master electrician	h	18	250,00		4.500,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	69	700,00		48.300,00
				Total Excluding Profit (TRY)	904.756,13	56.505,00
				Material and Installation w/o Profit (TRY)	961.261,13	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**70.631,25**	
				Unit Price (TRY)	**1.201.576,41**	

Item No	Analysis Name					UoM
35.701.1324						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1324	12 / 24 / 15 / _ / 80 / 1200 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	959.179,73	959.179,73	
	Installation Components					
10.100.1062	Unskilled worker	h	9,5	165,00		1.567,50
10.100.1081	Master electrician	h	19	250,00		4.750,00
10.100.1083	Master electrician’s helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	73	700,00		51.100,00
		Total Excluding Profit (TRY)			959.179,73	59.637,50
		Material and Installation w/o Profit (TRY)			1.018.817,23	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**74.546,88**	
		Unit Price (TRY)			**1.273.521,54**	

Item No	Analysis Name					UoM
35.701.1327						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1327	12 / 24 / 15 / _ / 80 / 1500 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	997.806,35	997.806,35	
	Installation Components					
10.100.1062	Unskilled worker	h	9,5	165,00		1.567,50
10.100.1081	Master electrician	h	19	250,00		4.750,00
10.100.1083	Master electrician’s helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
		Total Excluding Profit (TRY)			997.806,35	61.737,50
		Material and Installation w/o Profit (TRY)			1.059.543,85	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**77.171,88**	
		Unit Price (TRY)			**1.324.429,81**	

Item No	Analysis Name					UoM
35.701.1330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1330	12 / 24 / 15 / _ / 90 / 1800 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.062.116,31	1.062.116,31	
	Installation Components					
10.100.1062	Unskilled worker	h	10	165,00		1.650,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	81	700,00		56.700,00
				Total Excluding Profit (TRY)	1.062.116,31	65.570,00
				Material and Installation w/o Profit (TRY)	1.127.686,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**81.962,50**	
				Unit Price (TRY)	**1.409.607,89**	

Item No	Analysis Name					UoM
35.701.1333						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1333	12 / 24 / 30 / _ / 100 / 2000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.118.633,81	1.118.633,81	
	Installation Components					
10.100.1062	Unskilled worker	h	10,5	165,00		1.732,50
10.100.1081	Master electrician	h	21	250,00		5.250,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	85	700,00		59.500,00
				Total Excluding Profit (TRY)	1.118.633,81	68.702,50
				Material and Installation w/o Profit (TRY)	1.187.336,31	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85.878,13**	
				Unit Price (TRY)	**1.484.170,39**	

Item No	Analysis Name					UoM
35.701.1336						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1336	12 / 24 / 30 / _ / 120 / 2250 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.186.309,91	1.186.309,91	
	Installation Components					
10.100.1062	Unskilled worker	h	11	165,00		1.815,00
10.100.1081	Master electrician	h	22	250,00		5.500,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	90	700,00		63.000,00
				Total Excluding Profit (TRY)	1.186.309,91	72.535,00
				Material and Installation w/o Profit (TRY)	1.258.844,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**90.668,75**	
				Unit Price (TRY)	**1.573.556,14**	

Item No	Analysis Name					UoM
35.701.1339						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1339	12 / 24 / 30 / _ / 120 / 2500 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.439.670,94	1.439.670,94	
	Installation Components					
10.100.1062	Unskilled worker	h	12,5	165,00		2.062,50
10.100.1081	Master electrician	h	25	250,00		6.250,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	109	700,00		76.300,00
				Total Excluding Profit (TRY)	1.439.670,94	86.832,50
				Material and Installation w/o Profit (TRY)	1.526.503,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**108.540,63**	
				Unit Price (TRY)	**1.908.129,30**	

Item No	Analysis Name					UoM
35.701.1342						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1342	12 / 24 / 30 / _ / 150 / 2750 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.559.894,08	1.559.894,08	
	Installation Components					
10.100.1062	Unskilled worker	h	13,5	165,00		2.227,50
10.100.1081	Master electrician	h	27	250,00		6.750,00
10.100.1083	Master electrician’s helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	118	700,00		82.600,00
				Total Excluding Profit (TRY)	1.559.894,08	93.797,50
				Material and Installation w/o Profit (TRY)	1.653.691,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**117.246,88**	
				Unit Price (TRY)	**2.067.114,48**	

Item No	Analysis Name					UoM
35.701.1345						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1345	12 / 24 / 30 / _ / 200 / 3000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.706.184,01	1.706.184,01	
	Installation Components					
10.100.1062	Unskilled worker	h	14,5	165,00		2.392,50
10.100.1081	Master electrician	h	29	250,00		7.250,00
10.100.1083	Master electrician’s helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	129	700,00		90.300,00
				Total Excluding Profit (TRY)	1.706.184,01	102.162,50
				Material and Installation w/o Profit (TRY)	1.808.346,51	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**127.703,13**	
				Unit Price (TRY)	**2.260.433,14**	

Item No	Analysis Name					UoM
35.701.1348						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1348	12 / 24 / 30 / _ / 250 / 3500 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.861.764,83	1.861.764,83	
	Installation Components					
10.100.1062	Unskilled worker	h	15,5	165,00		2.557,50
10.100.1081	Master electrician	h	31	250,00		7.750,00
10.100.1083	Master electrician’s helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	140	700,00		98.000,00
				Total Excluding Profit (TRY)	1.861.764,83	110.527,50
				Material and Installation w/o Profit (TRY)	1.972.292,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**138.159,38**	
				Unit Price (TRY)	**2.465.365,41**	

Item No	Analysis Name					UoM
35.701.1351						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1351	12 / 24 / 30 / _ / 270 / 4000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.992.501,62	1.992.501,62	
	Installation Components					
10.100.1062	Unskilled worker	h	16,5	165,00		2.722,50
10.100.1081	Master electrician	h	33	250,00		8.250,00
10.100.1083	Master electrician’s helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	150	700,00		105.000,00
				Total Excluding Profit (TRY)	1.992.501,62	118.192,50
				Material and Installation w/o Profit (TRY)	2.110.694,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**147.740,63**	
				Unit Price (TRY)	**2.638.367,65**	

Item No	Analysis Name					UoM
35.701.1354						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1354	12 / 24 / 30 / _ / 300 / 4500 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.153.093,65	2.153.093,65	
	Installation Components					
10.100.1062	Unskilled worker	h	17,5	165,00		2.887,50
10.100.1081	Master electrician	h	35	250,00		8.750,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	162	700,00		113.400,00
				Total Excluding Profit (TRY)	2.153.093,65	127.257,50
				Material and Installation w/o Profit (TRY)	2.280.351,15	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**159.071,88**	
				Unit Price (TRY)	**2.850.438,94**	

Item No	Analysis Name					UoM
35.701.1357						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1357	12 / 24 / 30 / _ / 350 / 5000 / With minimum 2 processors and 50% expansion capacity. / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.402.491,57	2.402.491,57	
	Installation Components					
10.100.1062	Unskilled worker	h	18	165,00		2.970,00
10.100.1081	Master electrician	h	36	250,00		9.000,00
10.100.1083	Master electrician's helper	h	36	185,00		6.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	180	700,00		126.000,00
				Total Excluding Profit (TRY)	2.402.491,57	144.630,00
				Material and Installation w/o Profit (TRY)	2.547.121,57	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**180.787,50**	
				Unit Price (TRY)	**3.183.901,96**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1600						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1600	0/32/8/0/0/32 Far-end module / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	51.793,17	51.793,17	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	51.793,17	6.940,00
				Material and Installation w/o Profit (TRY)	58.733,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.675,00**	
				Unit Price (TRY)	**73.416,46**	

Item No	Analysis Name					UoM
35.701.1605						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1605	0/64/8/0/0/64 Far-end module / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	88.559,64	88.559,64	
	Installation Components					
10.100.1062	Unskilled worker	h	4,5	165,00		742,50
10.100.1081	Master electrician	h	9	250,00		2.250,00
10.100.1083	Master electrician's helper	h	9	185,00		1.665,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	88.559,64	11.657,50
				Material and Installation w/o Profit (TRY)	100.217,14	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.571,88**	
				Unit Price (TRY)	**125.271,43**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1610						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1610	0/112/8/0/0/112 Far-end module / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	155.491,80	155.491,80	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician's helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	20	700,00		14.000,00
				Total Excluding Profit (TRY)	155.491,80	19.175,00
				Material and Installation w/o Profit (TRY)	174.666,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**23.968,75**	
				Unit Price (TRY)	**218.333,50**	

Item No	Analysis Name					UoM
35.701.1615						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1615	0/240/8/0/0/224 Far-end module / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	299.902,48	299.902,48	
	Installation Components					
10.100.1062	Unskilled worker	h	7	165,00		1.155,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
				Total Excluding Profit (TRY)	299.902,48	28.245,00
				Material and Installation w/o Profit (TRY)	328.147,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**35.306,25**	
				Unit Price (TRY)	**410.184,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1620						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1620	0/480/8/0/0/448 Far-end module / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	579.459,55	579.459,55	
	Installation Components					
10.100.1062	Unskilled worker	h	8	165,00		1.320,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician's helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
		Total Excluding Profit (TRY)			579.459,55	50.280,00
		Material and Installation w/o Profit (TRY)			629.739,55	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**62.850,00**	
		Unit Price (TRY)			**787.174,44**	

Item No	Analysis Name					UoM
35.701.1700						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1700	20 IP Trunk, 100 IP subscribers added / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	124.459,18	124.459,18	
		Total Excluding Profit (TRY)			124.459,18	
		Material and Installation w/o Profit (TRY)			124.459,18	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**155.573,97**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1705						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.1705	**Material Components** 40 IP Trunk, 200 IP subscribers added / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	189.157,00	189.157,00	
				Total Excluding Profit (TRY)	189.157,00	
				Material and Installation w/o Profit (TRY)	189.157,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**236.446,25**	

Item No	Analysis Name					UoM
35.701.1710						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.1710	**Material Components** 50 IP Trunk, 450 IP subscribers added / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	249.329,53	249.329,53	
				Total Excluding Profit (TRY)	249.329,53	
				Material and Installation w/o Profit (TRY)	249.329,53	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**311.661,91**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1715						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.1715	**Material Components** 100 IP Trunk, 900 IP subscribers added / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	528.507,58	528.507,58	
				Total Excluding Profit (TRY)	528.507,58	
				Material and Installation w/o Profit (TRY)	528.507,58	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**660.634,47**	

Item No	Analysis Name					UoM
35.701.1720						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.1720	**Material Components** 150 IP Trunk, 1850 IP subscribers added / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	801.713,17	801.713,17	
				Total Excluding Profit (TRY)	801.713,17	
				Material and Installation w/o Profit (TRY)	801.713,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**1.002.141,46**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.1725						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1725	200 IP Trunk, 3850 IP subscribers added / Hybrid (Analog-Digital or Analog-Digital-IP) Telephone Exchange Capacities / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.268.748,05	1.268.748,05	
				Total Excluding Profit (TRY)	1.268.748,05	
				Material and Installation w/o Profit (TRY)	1.268.748,05	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**1.585.935,06**	

Item No	Analysis Name					UoM
35.701.1910	**ISDN PRA CONNECTION**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.1910	ISDN PRA CONNECTION / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	8.495,76	8.495,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	8.495,76	952,50
				Material and Installation w/o Profit (TRY)	9.448,26	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.190,63**	
				Unit Price (TRY)	**11.810,33**	

Item No	Analysis Name					UoM
35.701.3110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3110	**Material Components** Type 1 digital telephone set / Telephone Sets / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	7.463,37	7.463,37	
		Total Excluding Profit (TRY)			7.463,37	
		Material and Installation w/o Profit (TRY)			7.463,37	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**9.329,21**	

Item No	Analysis Name					UoM
35.701.3120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3120	**Material Components** Type 2 digital telephone set / Telephone Sets / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	6.025,03	6.025,03	
		Total Excluding Profit (TRY)			6.025,03	
		Material and Installation w/o Profit (TRY)			6.025,03	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**7.531,29**	

Item No	Analysis Name					UoM
35.701.3130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3130	**Material Components** Type 1 IP telephone set (Entry level user) / Telephone Sets / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	1.917,19	1.917,19	
		Total Excluding Profit (TRY)			1.917,19	
		Material and Installation w/o Profit (TRY)			1.917,19	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**				
		Unit Price (TRY)			**2.396,49**	

Item No	Analysis Name					UoM
35.701.3140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3140	**Material Components** Type 2 IP telephone set: (Entry level user Gigabit) / Telephone Sets / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	2.760,94	2.760,94	
				Total Excluding Profit (TRY)	2.760,94	
				Material and Installation w/o Profit (TRY)	2.760,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**3.451,18**	

Item No	Analysis Name					UoM
35.701.3150						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3150	**Material Components** Type 3 IP telephone set: (Intermediate Controller Gigabit) / Telephone Sets / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	4.183,81	4.183,81	
				Total Excluding Profit (TRY)	4.183,81	
				Material and Installation w/o Profit (TRY)	4.183,81	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**5.229,76**	

Item No	Analysis Name					UoM
35.701.3160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3160	**Material Components** Type 4 IP telephone set: (Controller and Telephone System Gigabit) / Telephone Sets / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	6.300,24	6.300,24	
				Total Excluding Profit (TRY)	6.300,24	
				Material and Installation w/o Profit (TRY)	6.300,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**7.875,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.3170						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.3170	Type 4.1 IP telephone DSS Expansion Module: (Controller and Telephone System DSS) / Telephone Sets / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	4.240,80	4.240,80	
				Total Excluding Profit (TRY)	4.240,80	
				Material and Installation w/o Profit (TRY)	4.240,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**5.301,00**	

Item No	Analysis Name					UoM
35.701.3200						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.701.3200	IP Dect Base Station / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE Market price	Qty	1	14.798,63	14.798,63	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician’s helper	h	1	185,00		185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	14.798,63	3.317,50
				Material and Installation w/o Profit (TRY)	18.116,13	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.146,88**	
				Unit Price (TRY)	**22.645,16**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.701.3210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3210	**Material Components** IP Dect Handheld Device (Type-1) / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	3.587,01	3.587,01	
				Total Excluding Profit (TRY)	3.587,01	
				Material and Installation w/o Profit (TRY)	3.587,01	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**4.483,76**	

Item No	Analysis Name					UoM
35.701.3220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3220	**Material Components** IP Dect Handheld Device (Type-2) / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	7.182,85	7.182,85	
				Total Excluding Profit (TRY)	7.182,85	
				Material and Installation w/o Profit (TRY)	7.182,85	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**8.978,56**	

Item No	Analysis Name					UoM
35.701.3300						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.701.3300	**Material Components** Robot operator / HYBRID (ANALOG-DIGITAL or ANALOG-DIGITAL-IP) TELEPHONE EXCHANGE (Market price)	Qty	1	19.878,75	19.878,75	
				Total Excluding Profit (TRY)	19.878,75	
				Material and Installation w/o Profit (TRY)	19.878,75	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**24.848,44**	

Item No	Analysis Name					UoM
35.710.1101	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1101	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	646.048,00	646.048,00	
	Installation Components					
10.100.1062	Unskilled worker	h	38	165,00		6.270,00
10.100.1081	Master electrician	h	38	250,00		9.500,00
10.100.1083	Master electrician's helper	h	38	185,00		7.030,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
		Total Excluding Profit (TRY)			646.048,00	41.141,76
		Material and Installation w/o Profit (TRY)			687.189,76	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**51.427,20**	
		Unit Price (TRY)			**858.987,20**	

Item No	Analysis Name					UoM
35.710.1102	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1102	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	672.755,20	672.755,20	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician's helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
		Total Excluding Profit (TRY)			672.755,20	55.177,20
		Material and Installation w/o Profit (TRY)			727.932,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**68.971,50**	
		Unit Price (TRY)			**909.915,50**	

Item No	Analysis Name					UoM
35.710.1103	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1103	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	697.278,40	697.278,40	
	Installation Components					
10.100.1062	Unskilled worker	h	66	165,00		10.890,00
10.100.1081	Master electrician	h	66	250,00		16.500,00
10.100.1083	Master electrician’s helper	h	66	185,00		12.210,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	697.278,40	69.212,64
				Material and Installation w/o Profit (TRY)	766.491,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**86.515,80**	
				Unit Price (TRY)	**958.113,80**	

Item No	Analysis Name					UoM
35.710.1104	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1104	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	724.817,60	724.817,60	
	Installation Components					
10.100.1062	Unskilled worker	h	80	165,00		13.200,00
10.100.1081	Master electrician	h	80	250,00		20.000,00
10.100.1083	Master electrician’s helper	h	80	185,00		14.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	724.817,60	83.248,08
				Material and Installation w/o Profit (TRY)	808.065,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**104.060,10**	
				Unit Price (TRY)	**1.010.082,10**	

Item No	Analysis Name					UoM
35.710.1105	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1105	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	752.648,00	752.648,00	
	Installation Components					
10.100.1062	Unskilled worker	h	94	165,00		15.510,00
10.100.1081	Master electrician	h	94	250,00		23.500,00
10.100.1083	Master electrician's helper	h	94	185,00		17.390,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			752.648,00	97.283,52
		Material and Installation w/o Profit (TRY)			849.931,52	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**121.604,40**	
		Unit Price (TRY)			**1.062.414,40**	

Item No	Analysis Name					UoM
35.710.1106	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1106	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	781.175,20	781.175,20	
	Installation Components					
10.100.1062	Unskilled worker	h	108	165,00		17.820,00
10.100.1081	Master electrician	h	108	250,00		27.000,00
10.100.1083	Master electrician's helper	h	108	185,00		19.980,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			781.175,20	111.318,96
		Material and Installation w/o Profit (TRY)			892.494,16	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**139.148,70**	
		Unit Price (TRY)			**1.115.617,70**	

Item No	Analysis Name					UoM
35.710.1107	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1107	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	809.536,00	809.536,00	
	Installation Components					
10.100.1062	Unskilled worker	h	122	165,00		20.130,00
10.100.1081	Master electrician	h	122	250,00		30.500,00
10.100.1083	Master electrician’s helper	h	122	185,00		22.570,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	809.536,00	125.354,40
				Material and Installation w/o Profit (TRY)	934.890,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**156.693,00**	
				Unit Price (TRY)	**1.168.613,00**	

Item No	Analysis Name					UoM
35.710.1108	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1108	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	845.312,00	845.312,00	
	Installation Components					
10.100.1062	Unskilled worker	h	136	165,00		22.440,00
10.100.1081	Master electrician	h	136	250,00		34.000,00
10.100.1083	Master electrician’s helper	h	136	185,00		25.160,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	845.312,00	139.389,84
				Material and Installation w/o Profit (TRY)	984.701,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.237,30**	
				Unit Price (TRY)	**1.230.877,30**	

Item No	Analysis Name					UoM
35.710.1109	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1109	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	874.952,00	874.952,00	
	Installation Components					
10.100.1062	Unskilled worker	h	150	165,00		24.750,00
10.100.1081	Master electrician	h	150	250,00		37.500,00
10.100.1083	Master electrician's helper	h	150	185,00		27.750,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	874.952,00	153.425,28
				Material and Installation w/o Profit (TRY)	1.028.377,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**191.781,60**	
				Unit Price (TRY)	**1.285.471,60**	

Item No	Analysis Name					UoM
35.710.1110	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1110	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	929.968,00	929.968,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician's helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	929.968,00	167.460,72
				Material and Installation w/o Profit (TRY)	1.097.428,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**209.325,90**	
				Unit Price (TRY)	**1.371.785,90**	

Item No	Analysis Name					UoM
35.710.1111	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1111	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	962.000,00	962.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	178	165,00		29.370,00
10.100.1081	Master electrician	h	178	250,00		44.500,00
10.100.1083	Master electrician's helper	h	178	185,00		32.930,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	962.000,00	181.496,16
				Material and Installation w/o Profit (TRY)	1.143.496,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**226.870,20**	
				Unit Price (TRY)	**1.429.370,20**	

Item No	Analysis Name					UoM
35.710.1112	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1112	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	997.672,00	997.672,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician's helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	997.672,00	195.531,60
				Material and Installation w/o Profit (TRY)	1.193.203,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**244.414,50**	
				Unit Price (TRY)	**1.491.504,50**	

Item No	Analysis Name					UoM
35.710.1113	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1113	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.043.120,00	1.043.120,00	
	Installation Components					
10.100.1062	Unskilled worker	h	206	165,00		33.990,00
10.100.1081	Master electrician	h	206	250,00		51.500,00
10.100.1083	Master electrician's helper	h	206	185,00		38.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.043.120,00	209.567,04
				Material and Installation w/o Profit (TRY)	1.252.687,04	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**261.958,80**	
				Unit Price (TRY)	**1.565.858,80**	

Item No	Analysis Name					UoM
35.710.1114	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1114	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.106.976,00	1.106.976,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician's helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.106.976,00	223.602,48
				Material and Installation w/o Profit (TRY)	1.330.578,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**279.503,10**	
				Unit Price (TRY)	**1.663.223,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1151	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1151	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	682.229,60	682.229,60	
	Installation Components					
10.100.1062	Unskilled worker	h	41	165,00		6.765,00
10.100.1081	Master electrician	h	41	250,00		10.250,00
10.100.1083	Master electrician’s helper	h	41	185,00		7.585,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
		Total Excluding Profit (TRY)			682.229,60	42.941,76
		Material and Installation w/o Profit (TRY)			725.171,36	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**53.677,20**	
		Unit Price (TRY)			**906.464,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1152	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1152	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	712.264,80	712.264,80	
	Installation Components					
10.100.1062	Unskilled worker	h	56	165,00		9.240,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician’s helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
		Total Excluding Profit (TRY)			712.264,80	57.577,20
		Material and Installation w/o Profit (TRY)			769.842,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**71.971,50**	
		Unit Price (TRY)			**962.302,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1153	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1153	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	735.373,60	735.373,60	
	Installation Components					
10.100.1062	Unskilled worker	h	71	165,00		11.715,00
10.100.1081	Master electrician	h	71	250,00		17.750,00
10.100.1083	Master electrician’s helper	h	71	185,00		13.135,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			735.373,60	72.212,64
		Material and Installation w/o Profit (TRY)			807.586,24	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**90.265,80**	
		Unit Price (TRY)			**1.009.482,80**	

Item No	Analysis Name					UoM
35.710.1154	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1154	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	762.548,80	762.548,80	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician’s helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
		Total Excluding Profit (TRY)			762.548,80	86.848,08
		Material and Installation w/o Profit (TRY)			849.396,88	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**108.560,10**	
		Unit Price (TRY)			**1.061.746,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1155	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1155	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	791.596,00	791.596,00	
	Installation Components					
10.100.1062	Unskilled worker	h	101	165,00		16.665,00
10.100.1081	Master electrician	h	101	250,00		25.250,00
10.100.1083	Master electrician’s helper	h	101	185,00		18.685,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			791.596,00	101.483,52
		Material and Installation w/o Profit (TRY)			893.079,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**126.854,40**	
		Unit Price (TRY)			**1.116.349,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1156	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1156	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	822.931,20	822.931,20	
	Installation Components					
10.100.1062	Unskilled worker	h	116	165,00		19.140,00
10.100.1081	Master electrician	h	116	250,00		29.000,00
10.100.1083	Master electrician’s helper	h	116	185,00		21.460,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			822.931,20	116.118,96
		Material and Installation w/o Profit (TRY)			939.050,16	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**145.148,70**	
		Unit Price (TRY)			**1.173.812,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1157	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1157	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	846.456,00	846.456,00	
	Installation Components					
10.100.1062	Unskilled worker	h	131	165,00		21.615,00
10.100.1081	Master electrician	h	131	250,00		32.750,00
10.100.1083	Master electrician’s helper	h	131	185,00		24.235,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
		Total Excluding Profit (TRY)			846.456,00	130.754,40
		Material and Installation w/o Profit (TRY)			977.210,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**163.443,00**	
		Unit Price (TRY)			**1.221.513,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1158	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1158	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	888.056,00	888.056,00	
	Installation Components					
10.100.1062	Unskilled worker	h	146	165,00		24.090,00
10.100.1081	Master electrician	h	146	250,00		36.500,00
10.100.1083	Master electrician’s helper	h	146	185,00		27.010,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
		Total Excluding Profit (TRY)			888.056,00	145.389,84
		Material and Installation w/o Profit (TRY)			1.033.445,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**181.737,30**	
		Unit Price (TRY)			**1.291.807,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1159	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1159	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	934.128,00	934.128,00	
	Installation Components					
10.100.1062	Unskilled worker	h	161	165,00		26.565,00
10.100.1081	Master electrician	h	161	250,00		40.250,00
10.100.1083	Master electrician’s helper	h	161	185,00		29.785,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
		Total Excluding Profit (TRY)			934.128,00	160.025,28
		Material and Installation w/o Profit (TRY)			1.094.153,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**200.031,60**	
		Unit Price (TRY)			**1.367.691,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1160	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1160	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	970.632,00	970.632,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
		Total Excluding Profit (TRY)			970.632,00	174.660,72
		Material and Installation w/o Profit (TRY)			1.145.292,72	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**218.325,90**	
		Unit Price (TRY)			**1.431.615,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1161	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1161	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.008.696,00	1.008.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	191	165,00		31.515,00
10.100.1081	Master electrician	h	191	250,00		47.750,00
10.100.1083	Master electrician’s helper	h	191	185,00		35.335,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.008.696,00	189.296,16
				Material and Installation w/o Profit (TRY)	1.197.992,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.620,20**	
				Unit Price (TRY)	**1.497.490,20**	

Item No	Analysis Name					UoM
35.710.1162	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1162	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.039.480,00	1.039.480,00	
	Installation Components					
10.100.1062	Unskilled worker	h	206	165,00		33.990,00
10.100.1081	Master electrician	h	206	250,00		51.500,00
10.100.1083	Master electrician’s helper	h	206	185,00		38.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.039.480,00	203.931,60
				Material and Installation w/o Profit (TRY)	1.243.411,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**254.914,50**	
				Unit Price (TRY)	**1.554.264,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1163	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1163	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.087.424,00	1.087.424,00	
	Installation Components					
10.100.1062	Unskilled worker	h	221	165,00		36.465,00
10.100.1081	Master electrician	h	221	250,00		55.250,00
10.100.1083	Master electrician’s helper	h	221	185,00		40.885,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.087.424,00	218.567,04
				Material and Installation w/o Profit (TRY)	1.305.991,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**273.208,80**	
				Unit Price (TRY)	**1.632.488,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1164	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1164	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 800 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.151.696,00	1.151.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.151.696,00	233.202,48
				Material and Installation w/o Profit (TRY)	1.384.898,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**291.503,10**	
				Unit Price (TRY)	**1.731.123,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1201	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1201	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	743.693,60	743.693,60	
	Installation Components					
10.100.1062	Unskilled worker	h	44	165,00		7.260,00
10.100.1081	Master electrician	h	44	250,00		11.000,00
10.100.1083	Master electrician’s helper	h	44	185,00		8.140,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
		Total Excluding Profit (TRY)			743.693,60	44.741,76
		Material and Installation w/o Profit (TRY)			788.435,36	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**55.927,20**	
		Unit Price (TRY)			**985.544,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1202	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1202	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	773.312,80	773.312,80	
	Installation Components					
10.100.1062	Unskilled worker	h	60	165,00		9.900,00
10.100.1081	Master electrician	h	60	250,00		15.000,00
10.100.1083	Master electrician’s helper	h	60	185,00		11.100,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
		Total Excluding Profit (TRY)			773.312,80	59.977,20
		Material and Installation w/o Profit (TRY)			833.290,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**74.971,50**	
		Unit Price (TRY)			**1.041.612,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1203	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1203	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	798.636,80	798.636,80	
	Installation Components					
10.100.1062	Unskilled worker	h	76	165,00		12.540,00
10.100.1081	Master electrician	h	76	250,00		19.000,00
10.100.1083	Master electrician’s helper	h	76	185,00		14.060,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			798.636,80	75.212,64
		Material and Installation w/o Profit (TRY)			873.849,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**94.015,80**	
		Unit Price (TRY)			**1.092.311,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1204	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1204	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	829.951,20	829.951,20	
	Installation Components					
10.100.1062	Unskilled worker	h	92	165,00		15.180,00
10.100.1081	Master electrician	h	92	250,00		23.000,00
10.100.1083	Master electrician’s helper	h	92	185,00		17.020,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
		Total Excluding Profit (TRY)			829.951,20	90.448,08
		Material and Installation w/o Profit (TRY)			920.399,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**113.060,10**	
		Unit Price (TRY)			**1.150.499,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1205	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1205	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	858.884,00	858.884,00	
	Installation Components					
10.100.1062	Unskilled worker	h	108	165,00		17.820,00
10.100.1081	Master electrician	h	108	250,00		27.000,00
10.100.1083	Master electrician’s helper	h	108	185,00		19.980,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			858.884,00	105.683,52
		Material and Installation w/o Profit (TRY)			964.567,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**132.104,40**	
		Unit Price (TRY)			**1.205.709,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1206	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1206	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	885.497,60	885.497,60	
	Installation Components					
10.100.1062	Unskilled worker	h	124	165,00		20.460,00
10.100.1081	Master electrician	h	124	250,00		31.000,00
10.100.1083	Master electrician’s helper	h	124	185,00		22.940,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			885.497,60	120.918,96
		Material and Installation w/o Profit (TRY)			1.006.416,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**151.148,70**	
		Unit Price (TRY)			**1.258.020,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1207	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1207	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	914.472,00	914.472,00	
	Installation Components					
10.100.1062	Unskilled worker	h	140	165,00		23.100,00
10.100.1081	Master electrician	h	140	250,00		35.000,00
10.100.1083	Master electrician’s helper	h	140	185,00		25.900,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
		Total Excluding Profit (TRY)			914.472,00	136.154,40
		Material and Installation w/o Profit (TRY)			1.050.626,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**170.193,00**	
		Unit Price (TRY)			**1.313.283,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1208	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1208	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	958.256,00	958.256,00	
	Installation Components					
10.100.1062	Unskilled worker	h	156	165,00		25.740,00
10.100.1081	Master electrician	h	156	250,00		39.000,00
10.100.1083	Master electrician’s helper	h	156	185,00		28.860,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
		Total Excluding Profit (TRY)			958.256,00	151.389,84
		Material and Installation w/o Profit (TRY)			1.109.645,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**189.237,30**	
		Unit Price (TRY)			**1.387.057,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1209	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1209	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.002.768,00	1.002.768,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.002.768,00	166.625,28
				Material and Installation w/o Profit (TRY)	1.169.393,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.281,60**	
				Unit Price (TRY)	**1.461.741,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1210	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1210	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.065.584,00	1.065.584,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.065.584,00	181.860,72
				Material and Installation w/o Profit (TRY)	1.247.444,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.325,90**	
				Unit Price (TRY)	**1.559.305,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1211	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1211	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.100.424,00	1.100.424,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.100.424,00	197.096,16
				Material and Installation w/o Profit (TRY)	1.297.520,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.370,20**	
				Unit Price (TRY)	**1.621.900,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1212	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1212	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.130.376,00	1.130.376,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.130.376,00	212.331,60
				Material and Installation w/o Profit (TRY)	1.342.707,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.414,50**	
				Unit Price (TRY)	**1.678.384,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1213	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1213	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.176.136,00	1.176.136,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.176.136,00	227.567,04
				Material and Installation w/o Profit (TRY)	1.403.703,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**284.458,80**	
				Unit Price (TRY)	**1.754.628,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1214	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1214	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.248.000,00	1.248.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	252	165,00		41.580,00
10.100.1081	Master electrician	h	252	250,00		63.000,00
10.100.1083	Master electrician’s helper	h	252	185,00		46.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.248.000,00	242.802,48
				Material and Installation w/o Profit (TRY)	1.490.802,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**303.503,10**	
				Unit Price (TRY)	**1.863.503,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1251	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1251	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	831.230,40	831.230,40	
	Installation Components					
10.100.1062	Unskilled worker	h	49	165,00		8.085,00
10.100.1081	Master electrician	h	49	250,00		12.250,00
10.100.1083	Master electrician’s helper	h	49	185,00		9.065,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			831.230,40	54.812,64
		Material and Installation w/o Profit (TRY)			886.043,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**68.515,80**	
		Unit Price (TRY)			**1.107.553,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1252	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1252	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	864.645,60	864.645,60	
	Installation Components					
10.100.1062	Unskilled worker	h	67	165,00		11.055,00
10.100.1081	Master electrician	h	67	250,00		16.750,00
10.100.1083	Master electrician’s helper	h	67	185,00		12.395,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
		Total Excluding Profit (TRY)			864.645,60	73.015,80
		Material and Installation w/o Profit (TRY)			937.661,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**91.269,75**	
		Unit Price (TRY)			**1.172.076,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1253	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1253	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	892.288,80	892.288,80	
	Installation Components					
10.100.1062	Unskilled worker	h	85	165,00		14.025,00
10.100.1081	Master electrician	h	85	250,00		21.250,00
10.100.1083	Master electrician’s helper	h	85	185,00		15.725,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			892.288,80	91.218,96
		Material and Installation w/o Profit (TRY)			983.507,76	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**114.023,70**	
		Unit Price (TRY)			**1.229.384,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1254	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1254	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	924.289,60	924.289,60	
	Installation Components					
10.100.1062	Unskilled worker	h	103	165,00		16.995,00
10.100.1081	Master electrician	h	103	250,00		25.750,00
10.100.1083	Master electrician’s helper	h	103	185,00		19.055,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	21	687,95		14.446,95
19.100.1113	Mobile crane	h	21	1.079,77		22.675,17
		Total Excluding Profit (TRY)			924.289,60	109.422,12
		Material and Installation w/o Profit (TRY)			1.033.711,72	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**136.777,65**	
		Unit Price (TRY)			**1.292.139,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1255	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1255	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	953.503,20	953.503,20	
	Installation Components					
10.100.1062	Unskilled worker	h	121	165,00		19.965,00
10.100.1081	Master electrician	h	121	250,00		30.250,00
10.100.1083	Master electrician’s helper	h	121	185,00		22.385,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
		Total Excluding Profit (TRY)			953.503,20	127.625,28
		Material and Installation w/o Profit (TRY)			1.081.128,48	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**159.531,60**	
		Unit Price (TRY)			**1.351.410,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1256	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1256	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	982.904,00	982.904,00	
	Installation Components					
10.100.1062	Unskilled worker	h	139	165,00		22.935,00
10.100.1081	Master electrician	h	139	250,00		34.750,00
10.100.1083	Master electrician’s helper	h	139	185,00		25.715,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	27	687,95		18.574,65
19.100.1113	Mobile crane	h	27	1.079,77		29.153,79
		Total Excluding Profit (TRY)			982.904,00	145.828,44
		Material and Installation w/o Profit (TRY)			1.128.732,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**182.285,55**	
		Unit Price (TRY)			**1.410.915,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1257	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1257	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.015.768,00	1.015.768,00	
	Installation Components					
10.100.1062	Unskilled worker	h	157	165,00		25.905,00
10.100.1081	Master electrician	h	157	250,00		39.250,00
10.100.1083	Master electrician’s helper	h	157	185,00		29.045,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.015.768,00	164.031,60
				Material and Installation w/o Profit (TRY)	1.179.799,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**205.039,50**	
				Unit Price (TRY)	**1.474.749,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1258	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1258	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.061.944,00	1.061.944,00	
	Installation Components					
10.100.1062	Unskilled worker	h	175	165,00		28.875,00
10.100.1081	Master electrician	h	175	250,00		43.750,00
10.100.1083	Master electrician’s helper	h	175	185,00		32.375,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	33	687,95		22.702,35
19.100.1113	Mobile crane	h	33	1.079,77		35.632,41
				Total Excluding Profit (TRY)	1.061.944,00	182.234,76
				Material and Installation w/o Profit (TRY)	1.244.178,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.793,45**	
				Unit Price (TRY)	**1.555.223,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1259	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1259	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.110.200,00	1.110.200,00	
	Installation Components					
10.100.1062	Unskilled worker	h	193	165,00		31.845,00
10.100.1081	Master electrician	h	193	250,00		48.250,00
10.100.1083	Master electrician’s helper	h	193	185,00		35.705,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.110.200,00	200.437,92
				Material and Installation w/o Profit (TRY)	1.310.637,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.547,40**	
				Unit Price (TRY)	**1.638.297,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1260	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1260	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.174.264,00	1.174.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	211	165,00		34.815,00
10.100.1081	Master electrician	h	211	250,00		52.750,00
10.100.1083	Master electrician’s helper	h	211	185,00		39.035,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	39	687,95		26.830,05
19.100.1113	Mobile crane	h	39	1.079,77		42.111,03
				Total Excluding Profit (TRY)	1.174.264,00	218.641,08
				Material and Installation w/o Profit (TRY)	1.392.905,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**273.301,35**	
				Unit Price (TRY)	**1.741.131,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1261	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1261	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.208.896,00	1.208.896,00	
	Installation Components					
10.100.1062	Unskilled worker	h	229	165,00		37.785,00
10.100.1081	Master electrician	h	229	250,00		57.250,00
10.100.1083	Master electrician’s helper	h	229	185,00		42.365,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	42	687,95		28.893,90
19.100.1113	Mobile crane	h	42	1.079,77		45.350,34
				Total Excluding Profit (TRY)	1.208.896,00	236.844,24
				Material and Installation w/o Profit (TRY)	1.445.740,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**296.055,30**	
				Unit Price (TRY)	**1.807.175,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1262	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1262	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.248.520,00	1.248.520,00	
	Installation Components					
10.100.1062	Unskilled worker	h	247	165,00		40.755,00
10.100.1081	Master electrician	h	247	250,00		61.750,00
10.100.1083	Master electrician’s helper	h	247	185,00		45.695,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	45	687,95		30.957,75
19.100.1113	Mobile crane	h	45	1.079,77		48.589,65
				Total Excluding Profit (TRY)	1.248.520,00	255.047,40
				Material and Installation w/o Profit (TRY)	1.503.567,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**318.809,25**	
				Unit Price (TRY)	**1.879.459,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1263	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1263	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.306.240,00	1.306.240,00	
	Installation Components					
10.100.1062	Unskilled worker	h	265	165,00		43.725,00
10.100.1081	Master electrician	h	265	250,00		66.250,00
10.100.1083	Master electrician’s helper	h	265	185,00		49.025,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.306.240,00	273.250,56
				Material and Installation w/o Profit (TRY)	1.579.490,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**341.563,20**	
				Unit Price (TRY)	**1.974.363,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1264	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1264	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1275 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.354.184,00	1.354.184,00	
	Installation Components					
10.100.1062	Unskilled worker	h	283	165,00		46.695,00
10.100.1081	Master electrician	h	283	250,00		70.750,00
10.100.1083	Master electrician’s helper	h	283	185,00		52.355,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	51	687,95		35.085,45
19.100.1113	Mobile crane	h	51	1.079,77		55.068,27
				Total Excluding Profit (TRY)	1.354.184,00	291.453,72
				Material and Installation w/o Profit (TRY)	1.645.637,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**364.317,15**	
				Unit Price (TRY)	**2.057.047,15**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1501	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1501	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	914.264,00	914.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician’s helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			914.264,00	56.612,64
		Material and Installation w/o Profit (TRY)			970.876,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**70.765,80**	
		Unit Price (TRY)			**1.213.595,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1502	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1502	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	946.420,80	946.420,80	
	Installation Components					
10.100.1062	Unskilled worker	h	71	165,00		11.715,00
10.100.1081	Master electrician	h	71	250,00		17.750,00
10.100.1083	Master electrician’s helper	h	71	185,00		13.135,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
		Total Excluding Profit (TRY)			946.420,80	75.415,80
		Material and Installation w/o Profit (TRY)			1.021.836,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**94.269,75**	
		Unit Price (TRY)			**1.277.295,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1503	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1503	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	982.436,00	982.436,00	
	Installation Components					
10.100.1062	Unskilled worker	h	90	165,00		14.850,00
10.100.1081	Master electrician	h	90	250,00		22.500,00
10.100.1083	Master electrician’s helper	h	90	185,00		16.650,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			982.436,00	94.218,96
		Material and Installation w/o Profit (TRY)			1.076.654,96	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**117.773,70**	
		Unit Price (TRY)			**1.345.818,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1504	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1504	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.013.532,00	1.013.532,00	
	Installation Components					
10.100.1062	Unskilled worker	h	109	165,00		17.985,00
10.100.1081	Master electrician	h	109	250,00		27.250,00
10.100.1083	Master electrician’s helper	h	109	185,00		20.165,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	21	687,95		14.446,95
19.100.1113	Mobile crane	h	21	1.079,77		22.675,17
				Total Excluding Profit (TRY)	1.013.532,00	113.022,12
				Material and Installation w/o Profit (TRY)	1.126.554,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**141.277,65**	
				Unit Price (TRY)	**1.408.192,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1505	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1505	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.047.280,00	1.047.280,00	
	Installation Components					
10.100.1062	Unskilled worker	h	128	165,00		21.120,00
10.100.1081	Master electrician	h	128	250,00		32.000,00
10.100.1083	Master electrician’s helper	h	128	185,00		23.680,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.047.280,00	131.825,28
				Material and Installation w/o Profit (TRY)	1.179.105,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**164.781,60**	
				Unit Price (TRY)	**1.473.881,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1506	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1506	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.078.688,00	1.078.688,00	
	Installation Components					
10.100.1062	Unskilled worker	h	147	165,00		24.255,00
10.100.1081	Master electrician	h	147	250,00		36.750,00
10.100.1083	Master electrician’s helper	h	147	185,00		27.195,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	27	687,95		18.574,65
19.100.1113	Mobile crane	h	27	1.079,77		29.153,79
				Total Excluding Profit (TRY)	1.078.688,00	150.628,44
				Material and Installation w/o Profit (TRY)	1.229.316,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**188.285,55**	
				Unit Price (TRY)	**1.536.645,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1507	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1507	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.110.304,00	1.110.304,00	
	Installation Components					
10.100.1062	Unskilled worker	h	166	165,00		27.390,00
10.100.1081	Master electrician	h	166	250,00		41.500,00
10.100.1083	Master electrician’s helper	h	166	185,00		30.710,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.110.304,00	169.431,60
				Material and Installation w/o Profit (TRY)	1.279.735,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**211.789,50**	
				Unit Price (TRY)	**1.599.669,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1508	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1508	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.154.296,00	1.154.296,00	
	Installation Components					
10.100.1062	Unskilled worker	h	185	165,00		30.525,00
10.100.1081	Master electrician	h	185	250,00		46.250,00
10.100.1083	Master electrician’s helper	h	185	185,00		34.225,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	33	687,95		22.702,35
19.100.1113	Mobile crane	h	33	1.079,77		35.632,41
				Total Excluding Profit (TRY)	1.154.296,00	188.234,76
				Material and Installation w/o Profit (TRY)	1.342.530,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**235.293,45**	
				Unit Price (TRY)	**1.678.163,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1509	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1509	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.203.072,00	1.203.072,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.203.072,00	207.037,92
				Material and Installation w/o Profit (TRY)	1.410.109,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258.797,40**	
				Unit Price (TRY)	**1.762.637,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1510	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1510	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.278.368,00	1.278.368,00	
	Installation Components					
10.100.1062	Unskilled worker	h	223	165,00		36.795,00
10.100.1081	Master electrician	h	223	250,00		55.750,00
10.100.1083	Master electrician’s helper	h	223	185,00		41.255,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	39	687,95		26.830,05
19.100.1113	Mobile crane	h	39	1.079,77		42.111,03
				Total Excluding Profit (TRY)	1.278.368,00	225.841,08
				Material and Installation w/o Profit (TRY)	1.504.209,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**282.301,35**	
				Unit Price (TRY)	**1.880.261,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1511	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1511	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.311.856,00	1.311.856,00	
	Installation Components					
10.100.1062	Unskilled worker	h	242	165,00		39.930,00
10.100.1081	Master electrician	h	242	250,00		60.500,00
10.100.1083	Master electrician’s helper	h	242	185,00		44.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	42	687,95		28.893,90
19.100.1113	Mobile crane	h	42	1.079,77		45.350,34
				Total Excluding Profit (TRY)	1.311.856,00	244.644,24
				Material and Installation w/o Profit (TRY)	1.556.500,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**305.805,30**	
				Unit Price (TRY)	**1.945.625,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1512	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1512	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.353.352,00	1.353.352,00	
	Installation Components					
10.100.1062	Unskilled worker	h	261	165,00		43.065,00
10.100.1081	Master electrician	h	261	250,00		65.250,00
10.100.1083	Master electrician’s helper	h	261	185,00		48.285,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	45	687,95		30.957,75
19.100.1113	Mobile crane	h	45	1.079,77		48.589,65
				Total Excluding Profit (TRY)	1.353.352,00	263.447,40
				Material and Installation w/o Profit (TRY)	1.616.799,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**329.309,25**	
				Unit Price (TRY)	**2.020.999,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1513	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1513	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.402.232,00	1.402.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	280	165,00		46.200,00
10.100.1081	Master electrician	h	280	250,00		70.000,00
10.100.1083	Master electrician’s helper	h	280	185,00		51.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.402.232,00	282.250,56
				Material and Installation w/o Profit (TRY)	1.684.482,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**352.813,20**	
				Unit Price (TRY)	**2.105.603,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1514	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1514	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.460.056,00	1.460.056,00	
	Installation Components					
10.100.1062	Unskilled worker	h	299	165,00		49.335,00
10.100.1081	Master electrician	h	299	250,00		74.750,00
10.100.1083	Master electrician’s helper	h	299	185,00		55.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	51	687,95		35.085,45
19.100.1113	Mobile crane	h	51	1.079,77		55.068,27
				Total Excluding Profit (TRY)	1.460.056,00	301.053,72
				Material and Installation w/o Profit (TRY)	1.761.109,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**376.317,15**	
				Unit Price (TRY)	**2.201.387,15**	

Item No	Analysis Name					UoM
35.710.1551	**2 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1551	2 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	943.800,00	943.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician’s helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			943.800,00	56.612,64
		Material and Installation w/o Profit (TRY)			1.000.412,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**70.765,80**	
		Unit Price (TRY)			**1.250.515,80**	

Item No	Analysis Name					UoM
35.710.1552	**3 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1552	3 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	979.877,60	979.877,60	
	Installation Components					
10.100.1062	Unskilled worker	h	71	165,00		11.715,00
10.100.1081	Master electrician	h	71	250,00		17.750,00
10.100.1083	Master electrician’s helper	h	71	185,00		13.135,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
		Total Excluding Profit (TRY)			979.877,60	75.415,80
		Material and Installation w/o Profit (TRY)			1.055.293,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**94.269,75**	
		Unit Price (TRY)			**1.319.116,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1553	**4 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1553	4 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.015.404,00	1.015.404,00	
	Installation Components					
10.100.1062	Unskilled worker	h	90	165,00		14.850,00
10.100.1081	Master electrician	h	90	250,00		22.500,00
10.100.1083	Master electrician’s helper	h	90	185,00		16.650,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.015.404,00	94.218,96
				Material and Installation w/o Profit (TRY)	1.109.622,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**117.773,70**	
				Unit Price (TRY)	**1.387.028,70**	

Item No	Analysis Name					UoM
35.710.1554	**5 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1554	5 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.052.760,80	1.052.760,80	
	Installation Components					
10.100.1062	Unskilled worker	h	109	165,00		17.985,00
10.100.1081	Master electrician	h	109	250,00		27.250,00
10.100.1083	Master electrician’s helper	h	109	185,00		20.165,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	21	687,95		14.446,95
19.100.1113	Mobile crane	h	21	1.079,77		22.675,17
		Total Excluding Profit (TRY)			1.052.760,80	113.022,12
		Material and Installation w/o Profit (TRY)			1.165.782,92	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**141.277,65**	
		Unit Price (TRY)			**1.457.228,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1555	**6 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1555	6 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.083.680,00	1.083.680,00	
	Installation Components					
10.100.1062	Unskilled worker	h	128	165,00		21.120,00
10.100.1081	Master electrician	h	128	250,00		32.000,00
10.100.1083	Master electrician’s helper	h	128	185,00		23.680,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.083.680,00	131.825,28
				Material and Installation w/o Profit (TRY)	1.215.505,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**164.781,60**	
				Unit Price (TRY)	**1.519.381,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1556	**7 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1556	7 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.114.880,00	1.114.880,00	
	Installation Components					
10.100.1062	Unskilled worker	h	147	165,00		24.255,00
10.100.1081	Master electrician	h	147	250,00		36.750,00
10.100.1083	Master electrician’s helper	h	147	185,00		27.195,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	27	687,95		18.574,65
19.100.1113	Mobile crane	h	27	1.079,77		29.153,79
				Total Excluding Profit (TRY)	1.114.880,00	150.628,44
				Material and Installation w/o Profit (TRY)	1.265.508,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**188.285,55**	
				Unit Price (TRY)	**1.581.885,55**	

Item No	Analysis Name					UoM
35.710.1557	**8 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1557	8 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.154.920,00	1.154.920,00	
	Installation Components					
10.100.1062	Unskilled worker	h	166	165,00		27.390,00
10.100.1081	Master electrician	h	166	250,00		41.500,00
10.100.1083	Master electrician’s helper	h	166	185,00		30.710,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.154.920,00	169.431,60
				Material and Installation w/o Profit (TRY)	1.324.351,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**211.789,50**	
				Unit Price (TRY)	**1.655.439,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1558	**9 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1558	9 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.209.832,00	1.209.832,00	
	Installation Components					
10.100.1062	Unskilled worker	h	185	165,00		30.525,00
10.100.1081	Master electrician	h	185	250,00		46.250,00
10.100.1083	Master electrician’s helper	h	185	185,00		34.225,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	33	687,95		22.702,35
19.100.1113	Mobile crane	h	33	1.079,77		35.632,41
				Total Excluding Profit (TRY)	1.209.832,00	188.234,76
				Material and Installation w/o Profit (TRY)	1.398.066,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**235.293,45**	
				Unit Price (TRY)	**1.747.583,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1559	**10 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1559	10 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.253.720,00	1.253.720,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.253.720,00	207.037,92
				Material and Installation w/o Profit (TRY)	1.460.757,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258.797,40**	
				Unit Price (TRY)	**1.825.947,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1560	**11 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1560	11 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.325.792,00	1.325.792,00	
	Installation Components					
10.100.1062	Unskilled worker	h	223	165,00		36.795,00
10.100.1081	Master electrician	h	223	250,00		55.750,00
10.100.1083	Master electrician’s helper	h	223	185,00		41.255,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	39	687,95		26.830,05
19.100.1113	Mobile crane	h	39	1.079,77		42.111,03
				Total Excluding Profit (TRY)	1.325.792,00	225.841,08
				Material and Installation w/o Profit (TRY)	1.551.633,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**282.301,35**	
				Unit Price (TRY)	**1.939.541,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1561	**12 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1561	12 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.356.056,00	1.356.056,00	
	Installation Components					
10.100.1062	Unskilled worker	h	242	165,00		39.930,00
10.100.1081	Master electrician	h	242	250,00		60.500,00
10.100.1083	Master electrician’s helper	h	242	185,00		44.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	42	687,95		28.893,90
19.100.1113	Mobile crane	h	42	1.079,77		45.350,34
				Total Excluding Profit (TRY)	1.356.056,00	244.644,24
				Material and Installation w/o Profit (TRY)	1.600.700,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**305.805,30**	
				Unit Price (TRY)	**2.000.875,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1562	**13 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1562	13 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.407.952,00	1.407.952,00	
	Installation Components					
10.100.1062	Unskilled worker	h	261	165,00		43.065,00
10.100.1081	Master electrician	h	261	250,00		65.250,00
10.100.1083	Master electrician’s helper	h	261	185,00		48.285,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	45	687,95		30.957,75
19.100.1113	Mobile crane	h	45	1.079,77		48.589,65
				Total Excluding Profit (TRY)	1.407.952,00	263.447,40
				Material and Installation w/o Profit (TRY)	1.671.399,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**329.309,25**	
				Unit Price (TRY)	**2.089.249,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1563	**14 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1563	14 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.464.840,00	1.464.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	280	165,00		46.200,00
10.100.1081	Master electrician	h	280	250,00		70.000,00
10.100.1083	Master electrician’s helper	h	280	185,00		51.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.464.840,00	282.250,56
				Material and Installation w/o Profit (TRY)	1.747.090,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**352.813,20**	
				Unit Price (TRY)	**2.183.863,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1564	**15 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1564	15 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 1600 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.509.560,00	1.509.560,00	
	Installation Components					
10.100.1062	Unskilled worker	h	299	165,00		49.335,00
10.100.1081	Master electrician	h	299	250,00		74.750,00
10.100.1083	Master electrician’s helper	h	299	185,00		55.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	51	687,95		35.085,45
19.100.1113	Mobile crane	h	51	1.079,77		55.068,27
				Total Excluding Profit (TRY)	1.509.560,00	301.053,72
				Material and Installation w/o Profit (TRY)	1.810.613,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**376.317,15**	
				Unit Price (TRY)	**2.263.267,15**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1601	**2 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1601	2 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.221.521,60	1.221.521,60	
	Installation Components					
10.100.1062	Unskilled worker	h	60	165,00		9.900,00
10.100.1081	Master electrician	h	60	250,00		15.000,00
10.100.1083	Master electrician’s helper	h	60	185,00		11.100,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	1.221.521,60	68.483,52
				Material and Installation w/o Profit (TRY)	1.290.005,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85.604,40**	
				Unit Price (TRY)	**1.612.506,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1602	**3 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1602	3 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.265.201,60	1.265.201,60	
	Installation Components					
10.100.1062	Unskilled worker	h	82	165,00		13.530,00
10.100.1081	Master electrician	h	82	250,00		20.500,00
10.100.1083	Master electrician’s helper	h	82	185,00		15.170,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	1.265.201,60	90.854,40
				Material and Installation w/o Profit (TRY)	1.356.056,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**113.568,00**	
				Unit Price (TRY)	**1.695.070,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1603	**4 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1603	4 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.309.526,40	1.309.526,40	
	Installation Components					
10.100.1062	Unskilled worker	h	104	165,00		17.160,00
10.100.1081	Master electrician	h	104	250,00		26.000,00
10.100.1083	Master electrician’s helper	h	104	185,00		19.240,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.309.526,40	113.225,28
				Material and Installation w/o Profit (TRY)	1.422.751,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**141.531,60**	
				Unit Price (TRY)	**1.778.439,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1604	**5 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1604	5 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.361.984,00	1.361.984,00	
	Installation Components					
10.100.1062	Unskilled worker	h	126	165,00		20.790,00
10.100.1081	Master electrician	h	126	250,00		31.500,00
10.100.1083	Master electrician’s helper	h	126	185,00		23.310,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.361.984,00	135.596,16
				Material and Installation w/o Profit (TRY)	1.497.580,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**169.495,20**	
				Unit Price (TRY)	**1.871.975,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1605	**6 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1605	6 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.415.544,00	1.415.544,00	
	Installation Components					
10.100.1062	Unskilled worker	h	148	165,00		24.420,00
10.100.1081	Master electrician	h	148	250,00		37.000,00
10.100.1083	Master electrician’s helper	h	148	185,00		27.380,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.415.544,00	157.967,04
				Material and Installation w/o Profit (TRY)	1.573.511,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**197.458,80**	
				Unit Price (TRY)	**1.966.888,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1606	**7 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1606	7 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.488.032,00	1.488.032,00	
	Installation Components					
10.100.1062	Unskilled worker	h	170	165,00		28.050,00
10.100.1081	Master electrician	h	170	250,00		42.500,00
10.100.1083	Master electrician’s helper	h	170	185,00		31.450,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.488.032,00	180.337,92
				Material and Installation w/o Profit (TRY)	1.668.369,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**225.422,40**	
				Unit Price (TRY)	**2.085.462,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1607	**8 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1607	8 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.541.904,00	1.541.904,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	40	687,95		27.518,00
19.100.1113	Mobile crane	h	40	1.079,77		43.190,80
				Total Excluding Profit (TRY)	1.541.904,00	202.708,80
				Material and Installation w/o Profit (TRY)	1.744.612,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**253.386,00**	
				Unit Price (TRY)	**2.180.766,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1608	**9 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1608	9 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.614.704,00	1.614.704,00	
	Installation Components					
10.100.1062	Unskilled worker	h	214	165,00		35.310,00
10.100.1081	Master electrician	h	214	250,00		53.500,00
10.100.1083	Master electrician’s helper	h	214	185,00		39.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	44	687,95		30.269,80
19.100.1113	Mobile crane	h	44	1.079,77		47.509,88
				Total Excluding Profit (TRY)	1.614.704,00	225.079,68
				Material and Installation w/o Profit (TRY)	1.839.783,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**281.349,60**	
				Unit Price (TRY)	**2.299.729,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1609	**10 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1609	10 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.629.472,00	1.629.472,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.629.472,00	247.450,56
				Material and Installation w/o Profit (TRY)	1.876.922,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**309.313,20**	
				Unit Price (TRY)	**2.346.153,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1610	**11 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1610	11 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.788.072,00	1.788.072,00	
	Installation Components					
10.100.1062	Unskilled worker	h	258	165,00		42.570,00
10.100.1081	Master electrician	h	258	250,00		64.500,00
10.100.1083	Master electrician’s helper	h	258	185,00		47.730,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	52	687,95		35.773,40
19.100.1113	Mobile crane	h	52	1.079,77		56.148,04
				Total Excluding Profit (TRY)	1.788.072,00	269.821,44
				Material and Installation w/o Profit (TRY)	2.057.893,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**337.276,80**	
				Unit Price (TRY)	**2.572.366,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1611	**12 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1611	12 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.850.680,00	1.850.680,00	
	Installation Components					
10.100.1062	Unskilled worker	h	280	165,00		46.200,00
10.100.1081	Master electrician	h	280	250,00		70.000,00
10.100.1083	Master electrician’s helper	h	280	185,00		51.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	56	687,95		38.525,20
19.100.1113	Mobile crane	h	56	1.079,77		60.467,12
				Total Excluding Profit (TRY)	1.850.680,00	292.192,32
				Material and Installation w/o Profit (TRY)	2.142.872,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**365.240,40**	
				Unit Price (TRY)	**2.678.590,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1612	**13 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1612	13 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.866.800,00	1.866.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	302	165,00		49.830,00
10.100.1081	Master electrician	h	302	250,00		75.500,00
10.100.1083	Master electrician’s helper	h	302	185,00		55.870,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	60	687,95		41.277,00
19.100.1113	Mobile crane	h	60	1.079,77		64.786,20
				Total Excluding Profit (TRY)	1.866.800,00	314.563,20
				Material and Installation w/o Profit (TRY)	2.181.363,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**393.204,00**	
				Unit Price (TRY)	**2.726.704,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1613	**14 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1613	14 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.929.616,00	1.929.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	324	165,00		53.460,00
10.100.1081	Master electrician	h	324	250,00		81.000,00
10.100.1083	Master electrician’s helper	h	324	185,00		59.940,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	64	687,95		44.028,80
19.100.1113	Mobile crane	h	64	1.079,77		69.105,28
				Total Excluding Profit (TRY)	1.929.616,00	336.934,08
				Material and Installation w/o Profit (TRY)	2.266.550,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**421.167,60**	
				Unit Price (TRY)	**2.833.187,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1614	**15 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1614	15 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2000 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	2.000.648,00	2.000.648,00	
	Installation Components					
10.100.1062	Unskilled worker	h	346	165,00		57.090,00
10.100.1081	Master electrician	h	346	250,00		86.500,00
10.100.1083	Master electrician’s helper	h	346	185,00		64.010,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	68	687,95		46.780,60
19.100.1113	Mobile crane	h	68	1.079,77		73.424,36
				Total Excluding Profit (TRY)	2.000.648,00	359.304,96
				Material and Installation w/o Profit (TRY)	2.359.952,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**449.131,20**	
				Unit Price (TRY)	**2.949.941,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1651	**2 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1651	2 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.421.253,60	1.421.253,60	
	Installation Components					
10.100.1062	Unskilled worker	h	63	165,00		10.395,00
10.100.1081	Master electrician	h	63	250,00		15.750,00
10.100.1083	Master electrician’s helper	h	63	185,00		11.655,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	1.421.253,60	70.283,52
				Material and Installation w/o Profit (TRY)	1.491.537,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**87.854,40**	
				Unit Price (TRY)	**1.864.421,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1652	**3 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1652	3 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.459.536,00	1.459.536,00	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician’s helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	1.459.536,00	93.254,40
				Material and Installation w/o Profit (TRY)	1.552.790,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**116.568,00**	
				Unit Price (TRY)	**1.940.988,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1653	**4 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1653	4 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.477.528,00	1.477.528,00	
	Installation Components					
10.100.1062	Unskilled worker	h	109	165,00		17.985,00
10.100.1081	Master electrician	h	109	250,00		27.250,00
10.100.1083	Master electrician’s helper	h	109	185,00		20.165,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.477.528,00	116.225,28
				Material and Installation w/o Profit (TRY)	1.593.753,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**145.281,60**	
				Unit Price (TRY)	**1.992.191,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1654	**5 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1654	5 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.537.744,00	1.537.744,00	
	Installation Components					
10.100.1062	Unskilled worker	h	132	165,00		21.780,00
10.100.1081	Master electrician	h	132	250,00		33.000,00
10.100.1083	Master electrician’s helper	h	132	185,00		24.420,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.537.744,00	139.196,16
				Material and Installation w/o Profit (TRY)	1.676.940,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**173.995,20**	
				Unit Price (TRY)	**2.096.175,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1655	**6 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1655	6 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.590.784,00	1.590.784,00	
	Installation Components					
10.100.1062	Unskilled worker	h	155	165,00		25.575,00
10.100.1081	Master electrician	h	155	250,00		38.750,00
10.100.1083	Master electrician’s helper	h	155	185,00		28.675,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.590.784,00	162.167,04
				Material and Installation w/o Profit (TRY)	1.752.951,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**202.708,80**	
				Unit Price (TRY)	**2.191.188,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1656	**7 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1656	7 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.672.008,00	1.672.008,00	
	Installation Components					
10.100.1062	Unskilled worker	h	178	165,00		29.370,00
10.100.1081	Master electrician	h	178	250,00		44.500,00
10.100.1083	Master electrician’s helper	h	178	185,00		32.930,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.672.008,00	185.137,92
				Material and Installation w/o Profit (TRY)	1.857.145,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.422,40**	
				Unit Price (TRY)	**2.321.432,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1657	**8 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1657	8 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.733.680,00	1.733.680,00	
	Installation Components					
10.100.1062	Unskilled worker	h	201	165,00		33.165,00
10.100.1081	Master electrician	h	201	250,00		50.250,00
10.100.1083	Master electrician’s helper	h	201	185,00		37.185,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	40	687,95		27.518,00
19.100.1113	Mobile crane	h	40	1.079,77		43.190,80
				Total Excluding Profit (TRY)	1.733.680,00	208.108,80
				Material and Installation w/o Profit (TRY)	1.941.788,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.136,00**	
				Unit Price (TRY)	**2.427.236,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1658	**9 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1658	9 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.806.168,00	1.806.168,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	44	687,95		30.269,80
19.100.1113	Mobile crane	h	44	1.079,77		47.509,88
				Total Excluding Profit (TRY)	1.806.168,00	231.079,68
				Material and Installation w/o Profit (TRY)	2.037.247,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**288.849,60**	
				Unit Price (TRY)	**2.546.559,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1659	**10 Stops and 1.00 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1659	10 Stops and 1.00 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.873.144,00	1.873.144,00	
	Installation Components					
10.100.1062	Unskilled worker	h	247	165,00		40.755,00
10.100.1081	Master electrician	h	247	250,00		61.750,00
10.100.1083	Master electrician’s helper	h	247	185,00		45.695,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.873.144,00	254.050,56
				Material and Installation w/o Profit (TRY)	2.127.194,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**317.563,20**	
				Unit Price (TRY)	**2.658.993,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1660	**11 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1660	11 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.993.992,00	1.993.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	270	165,00		44.550,00
10.100.1081	Master electrician	h	270	250,00		67.500,00
10.100.1083	Master electrician’s helper	h	270	185,00		49.950,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	52	687,95		35.773,40
19.100.1113	Mobile crane	h	52	1.079,77		56.148,04
				Total Excluding Profit (TRY)	1.993.992,00	277.021,44
				Material and Installation w/o Profit (TRY)	2.271.013,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**346.276,80**	
				Unit Price (TRY)	**2.838.766,80**	

Item No	Analysis Name					UoM
35.710.1661	**12 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1661	12 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	2.055.976,00	2.055.976,00	
	Installation Components					
10.100.1062	Unskilled worker	h	293	165,00		48.345,00
10.100.1081	Master electrician	h	293	250,00		73.250,00
10.100.1083	Master electrician’s helper	h	293	185,00		54.205,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	56	687,95		38.525,20
19.100.1113	Mobile crane	h	56	1.079,77		60.467,12
				Total Excluding Profit (TRY)	2.055.976,00	299.992,32
				Material and Installation w/o Profit (TRY)	2.355.968,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**374.990,40**	
				Unit Price (TRY)	**2.944.960,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1662	**13 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1662	13 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	2.141.256,00	2.141.256,00	
	Installation Components					
10.100.1062	Unskilled worker	h	316	165,00		52.140,00
10.100.1081	Master electrician	h	316	250,00		79.000,00
10.100.1083	Master electrician’s helper	h	316	185,00		58.460,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	60	687,95		41.277,00
19.100.1113	Mobile crane	h	60	1.079,77		64.786,20
				Total Excluding Profit (TRY)	2.141.256,00	322.963,20
				Material and Installation w/o Profit (TRY)	2.464.219,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**403.704,00**	
				Unit Price (TRY)	**3.080.274,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1663	**14 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1663	14 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	2.210.416,00	2.210.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	339	165,00		55.935,00
10.100.1081	Master electrician	h	339	250,00		84.750,00
10.100.1083	Master electrician’s helper	h	339	185,00		62.715,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	64	687,95		44.028,80
19.100.1113	Mobile crane	h	64	1.079,77		69.105,28
				Total Excluding Profit (TRY)	2.210.416,00	345.934,08
				Material and Installation w/o Profit (TRY)	2.556.350,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**432.417,60**	
				Unit Price (TRY)	**3.195.437,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1664	**15 Stops and 1.60 m/s speed / Class III lifts (The lifts designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1664	15 Stops and 1.60 m/s speed / Class III elevators (The elevators designed principally to carry patients and stretchers in healthcare facilities, and to carry non-patient passengers when necessary.) Variable-speed, Rated load capacity: 2500 kg / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	2.292.992,00	2.292.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	362	165,00		59.730,00
10.100.1081	Master electrician	h	362	250,00		90.500,00
10.100.1083	Master electrician’s helper	h	362	185,00		66.970,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	68	687,95		46.780,60
19.100.1113	Mobile crane	h	68	1.079,77		73.424,36
				Total Excluding Profit (TRY)	2.292.992,00	368.904,96
				Material and Installation w/o Profit (TRY)	2.661.896,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**461.131,20**	
				Unit Price (TRY)	**3.327.371,20**	

Item No	Analysis Name					UoM
35.710.1701	**2 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1701	2 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	653.224,00	653.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	38	165,00		6.270,00
10.100.1081	Master electrician	h	38	250,00		9.500,00
10.100.1083	Master electrician’s helper	h	38	185,00		7.030,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
		Total Excluding Profit (TRY)			653.224,00	41.141,76
		Material and Installation w/o Profit (TRY)			694.365,76	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**51.427,20**	
		Unit Price (TRY)			**867.957,20**	

Item No	Analysis Name					UoM
35.710.1702	**3 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1702	3 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	682.323,20	682.323,20	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician’s helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
		Total Excluding Profit (TRY)			682.323,20	55.177,20
		Material and Installation w/o Profit (TRY)			737.500,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**68.971,50**	
		Unit Price (TRY)			**921.875,50**	

Item No	Analysis Name					UoM
35.710.1703	**4 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1703	4 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	710.070,40	710.070,40	
	Installation Components					
10.100.1062	Unskilled worker	h	66	165,00		10.890,00
10.100.1081	Master electrician	h	66	250,00		16.500,00
10.100.1083	Master electrician’s helper	h	66	185,00		12.210,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			710.070,40	69.212,64
		Material and Installation w/o Profit (TRY)			779.283,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**86.515,80**	
		Unit Price (TRY)			**974.103,80**	

Item No	Analysis Name					UoM
35.710.1704	**5 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1704	5 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	737.609,60	737.609,60	
	Installation Components					
10.100.1062	Unskilled worker	h	80	165,00		13.200,00
10.100.1081	Master electrician	h	80	250,00		20.000,00
10.100.1083	Master electrician’s helper	h	80	185,00		14.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
		Total Excluding Profit (TRY)			737.609,60	83.248,08
		Material and Installation w/o Profit (TRY)			820.857,68	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**104.060,10**	
		Unit Price (TRY)			**1.026.072,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1705	**6 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1705	6 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	768.456,00	768.456,00	
	Installation Components					
10.100.1062	Unskilled worker	h	94	165,00		15.510,00
10.100.1081	Master electrician	h	94	250,00		23.500,00
10.100.1083	Master electrician’s helper	h	94	185,00		17.390,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			768.456,00	97.283,52
		Material and Installation w/o Profit (TRY)			865.739,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**121.604,40**	
		Unit Price (TRY)			**1.082.174,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1706	**7 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1706	7 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	798.959,20	798.959,20	
	Installation Components					
10.100.1062	Unskilled worker	h	108	165,00		17.820,00
10.100.1081	Master electrician	h	108	250,00		27.000,00
10.100.1083	Master electrician’s helper	h	108	185,00		19.980,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	798.959,20	111.318,96
				Material and Installation w/o Profit (TRY)	910.278,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**139.148,70**	
				Unit Price (TRY)	**1.137.847,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1707	**8 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1707	8 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	826.904,00	826.904,00	
	Installation Components					
10.100.1062	Unskilled worker	h	122	165,00		20.130,00
10.100.1081	Master electrician	h	122	250,00		30.500,00
10.100.1083	Master electrician’s helper	h	122	185,00		22.570,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
		Total Excluding Profit (TRY)			826.904,00	125.354,40
		Material and Installation w/o Profit (TRY)			952.258,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**156.693,00**	
		Unit Price (TRY)			**1.190.323,00**	

Item No	Analysis Name					UoM
35.710.1708	**9 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1708	9 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	861.120,00	861.120,00	
	Installation Components					
10.100.1062	Unskilled worker	h	136	165,00		22.440,00
10.100.1081	Master electrician	h	136	250,00		34.000,00
10.100.1083	Master electrician’s helper	h	136	185,00		25.160,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
		Total Excluding Profit (TRY)			861.120,00	139.389,84
		Material and Installation w/o Profit (TRY)			1.000.509,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**174.237,30**	
		Unit Price (TRY)			**1.250.637,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1709	**10 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1709	10 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	894.296,00	894.296,00	
	Installation Components					
10.100.1062	Unskilled worker	h	150	165,00		24.750,00
10.100.1081	Master electrician	h	150	250,00		37.500,00
10.100.1083	Master electrician’s helper	h	150	185,00		27.750,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
		Total Excluding Profit (TRY)			894.296,00	153.425,28
		Material and Installation w/o Profit (TRY)			1.047.721,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**191.781,60**	
		Unit Price (TRY)			**1.309.651,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1710	**11 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1710	11 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	928.928,00	928.928,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	928.928,00	167.460,72
				Material and Installation w/o Profit (TRY)	1.096.388,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**209.325,90**	
				Unit Price (TRY)	**1.370.485,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1711	**12 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1711	12 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	964.080,00	964.080,00	
	Installation Components					
10.100.1062	Unskilled worker	h	178	165,00		29.370,00
10.100.1081	Master electrician	h	178	250,00		44.500,00
10.100.1083	Master electrician’s helper	h	178	185,00		32.930,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	964.080,00	181.496,16
				Material and Installation w/o Profit (TRY)	1.145.576,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**226.870,20**	
				Unit Price (TRY)	**1.431.970,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1712	**13 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1712	13 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.002.144,00	1.002.144,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.002.144,00	195.531,60
				Material and Installation w/o Profit (TRY)	1.197.675,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**244.414,50**	
				Unit Price (TRY)	**1.497.094,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1713	**14 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1713	14 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.048.840,00	1.048.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	206	165,00		33.990,00
10.100.1081	Master electrician	h	206	250,00		51.500,00
10.100.1083	Master electrician’s helper	h	206	185,00		38.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.048.840,00	209.567,04
				Material and Installation w/o Profit (TRY)	1.258.407,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**261.958,80**	
				Unit Price (TRY)	**1.573.008,80**	

Item No	Analysis Name					UoM
35.710.1714	**15 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1714	15 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 630 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.114.568,00	1.114.568,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.114.568,00	223.602,48
				Material and Installation w/o Profit (TRY)	1.338.170,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**279.503,10**	
				Unit Price (TRY)	**1.672.713,10**	

Item No	Analysis Name					UoM
35.710.1751	**2 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1751	2 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	752.013,60	752.013,60	
	Installation Components					
10.100.1062	Unskilled worker	h	44	165,00		7.260,00
10.100.1081	Master electrician	h	44	250,00		11.000,00
10.100.1083	Master electrician’s helper	h	44	185,00		8.140,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
		Total Excluding Profit (TRY)			752.013,60	44.741,76
		Material and Installation w/o Profit (TRY)			796.755,36	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**55.927,20**	
		Unit Price (TRY)			**995.944,20**	

Item No	Analysis Name					UoM
35.710.1752	**3 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1752	3 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	784.856,80	784.856,80	
	Installation Components					
10.100.1062	Unskilled worker	h	60	165,00		9.900,00
10.100.1081	Master electrician	h	60	250,00		15.000,00
10.100.1083	Master electrician’s helper	h	60	185,00		11.100,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
		Total Excluding Profit (TRY)			784.856,80	59.977,20
		Material and Installation w/o Profit (TRY)			844.834,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**74.971,50**	
		Unit Price (TRY)			**1.056.042,50**	

Item No	Analysis Name					UoM
35.710.1753	**4 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1753	4 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	809.556,80	809.556,80	
	Installation Components					
10.100.1062	Unskilled worker	h	76	165,00		12.540,00
10.100.1081	Master electrician	h	76	250,00		19.000,00
10.100.1083	Master electrician’s helper	h	76	185,00		14.060,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			809.556,80	75.212,64
		Material and Installation w/o Profit (TRY)			884.769,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**94.015,80**	
		Unit Price (TRY)			**1.105.961,80**	

Item No	Analysis Name					UoM
35.710.1754	**5 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1754	5 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	840.455,20	840.455,20	
	Installation Components					
10.100.1062	Unskilled worker	h	92	165,00		15.180,00
10.100.1081	Master electrician	h	92	250,00		23.000,00
10.100.1083	Master electrician’s helper	h	92	185,00		17.020,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
		Total Excluding Profit (TRY)			840.455,20	90.448,08
		Material and Installation w/o Profit (TRY)			930.903,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**113.060,10**	
		Unit Price (TRY)			**1.163.629,10**	

Item No	Analysis Name					UoM
35.710.1755	**6 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1755	6 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	869.700,00	869.700,00	
	Installation Components					
10.100.1062	Unskilled worker	h	108	165,00		17.820,00
10.100.1081	Master electrician	h	108	250,00		27.000,00
10.100.1083	Master electrician’s helper	h	108	185,00		19.980,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			869.700,00	105.683,52
		Material and Installation w/o Profit (TRY)			975.383,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**132.104,40**	
		Unit Price (TRY)			**1.219.229,40**	

Item No	Analysis Name					UoM
35.710.1756	**7 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1756	7 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	895.793,60	895.793,60	
	Installation Components					
10.100.1062	Unskilled worker	h	124	165,00		20.460,00
10.100.1081	Master electrician	h	124	250,00		31.000,00
10.100.1083	Master electrician’s helper	h	124	185,00		22.940,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			895.793,60	120.918,96
		Material and Installation w/o Profit (TRY)			1.016.712,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**151.148,70**	
		Unit Price (TRY)			**1.270.890,70**	

Item No	Analysis Name					UoM
35.710.1757	**8 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1757	8 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	925.912,00	925.912,00	
	Installation Components					
10.100.1062	Unskilled worker	h	140	165,00		23.100,00
10.100.1081	Master electrician	h	140	250,00		35.000,00
10.100.1083	Master electrician’s helper	h	140	185,00		25.900,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
		Total Excluding Profit (TRY)			925.912,00	136.154,40
		Material and Installation w/o Profit (TRY)			1.062.066,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**170.193,00**	
		Unit Price (TRY)			**1.327.583,00**	

Item No	Analysis Name					UoM
35.710.1758	**9 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1758	9 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	969.904,00	969.904,00	
	Installation Components					
10.100.1062	Unskilled worker	h	156	165,00		25.740,00
10.100.1081	Master electrician	h	156	250,00		39.000,00
10.100.1083	Master electrician’s helper	h	156	185,00		28.860,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	969.904,00	151.389,84
				Material and Installation w/o Profit (TRY)	1.121.293,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.237,30**	
				Unit Price (TRY)	**1.401.617,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1759	**10 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1759	10 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.014.416,00	1.014.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.014.416,00	166.625,28
				Material and Installation w/o Profit (TRY)	1.181.041,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.281,60**	
				Unit Price (TRY)	**1.476.301,60**	

Item No	Analysis Name					UoM
35.710.1760	**11 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1760	11 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.049.464,00	1.049.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.049.464,00	181.860,72
				Material and Installation w/o Profit (TRY)	1.231.324,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.325,90**	
				Unit Price (TRY)	**1.539.155,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1761	**12 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1761	12 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.084.616,00	1.084.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.084.616,00	197.096,16
				Material and Installation w/o Profit (TRY)	1.281.712,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.370,20**	
				Unit Price (TRY)	**1.602.140,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1762	**13 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1762	13 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.117.168,00	1.117.168,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.117.168,00	212.331,60
				Material and Installation w/o Profit (TRY)	1.329.499,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.414,50**	
				Unit Price (TRY)	**1.661.874,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1763	**14 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1763	14 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.164.696,00	1.164.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.164.696,00	227.567,04
				Material and Installation w/o Profit (TRY)	1.392.263,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**284.458,80**	
				Unit Price (TRY)	**1.740.328,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1764	**15 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1764	15 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.239.160,00	1.239.160,00	
	Installation Components					
10.100.1062	Unskilled worker	h	252	165,00		41.580,00
10.100.1081	Master electrician	h	252	250,00		63.000,00
10.100.1083	Master electrician’s helper	h	252	185,00		46.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.239.160,00	242.802,48
				Material and Installation w/o Profit (TRY)	1.481.962,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**303.503,10**	
				Unit Price (TRY)	**1.852.453,10**	

Item No	Analysis Name					UoM
35.710.1801	**2 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1801	2 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	920.192,00	920.192,00	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician’s helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			920.192,00	56.612,64
		Material and Installation w/o Profit (TRY)			976.804,64	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**70.765,80**	
		Unit Price (TRY)			**1.221.005,80**	

Item No	Analysis Name					UoM
35.710.1802	**3 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1802	3 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	958.900,80	958.900,80	
	Installation Components					
10.100.1062	Unskilled worker	h	71	165,00		11.715,00
10.100.1081	Master electrician	h	71	250,00		17.750,00
10.100.1083	Master electrician’s helper	h	71	185,00		13.135,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
		Total Excluding Profit (TRY)			958.900,80	75.415,80
		Material and Installation w/o Profit (TRY)			1.034.316,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**94.269,75**	
		Unit Price (TRY)			**1.292.895,75**	

Item No	Analysis Name					UoM
35.710.1803	**4 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1803	4 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	989.196,00	989.196,00	
	Installation Components					
10.100.1062	Unskilled worker	h	90	165,00		14.850,00
10.100.1081	Master electrician	h	90	250,00		22.500,00
10.100.1083	Master electrician’s helper	h	90	185,00		16.650,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			989.196,00	94.218,96
		Material and Installation w/o Profit (TRY)			1.083.414,96	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**117.773,70**	
		Unit Price (TRY)			**1.354.268,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1804	**5 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1804	5 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.016.548,00	1.016.548,00	
	Installation Components					
10.100.1062	Unskilled worker	h	109	165,00		17.985,00
10.100.1081	Master electrician	h	109	250,00		27.250,00
10.100.1083	Master electrician’s helper	h	109	185,00		20.165,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	21	687,95		14.446,95
19.100.1113	Mobile crane	h	21	1.079,77		22.675,17
		Total Excluding Profit (TRY)			1.016.548,00	113.022,12
		Material and Installation w/o Profit (TRY)			1.129.570,12	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**141.277,65**	
		Unit Price (TRY)			**1.411.962,65**	

Item No	Analysis Name					UoM
35.710.1805	**6 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1805	6 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.048.424,00	1.048.424,00	
	Installation Components					
10.100.1062	Unskilled worker	h	128	165,00		21.120,00
10.100.1081	Master electrician	h	128	250,00		32.000,00
10.100.1083	Master electrician’s helper	h	128	185,00		23.680,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
		Total Excluding Profit (TRY)			1.048.424,00	131.825,28
		Material and Installation w/o Profit (TRY)			1.180.249,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**164.781,60**	
		Unit Price (TRY)			**1.475.311,60**	

Item No	Analysis Name					UoM
35.710.1806	**7 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1806	7 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.078.688,00	1.078.688,00	
	Installation Components					
10.100.1062	Unskilled worker	h	147	165,00		24.255,00
10.100.1081	Master electrician	h	147	250,00		36.750,00
10.100.1083	Master electrician’s helper	h	147	185,00		27.195,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	27	687,95		18.574,65
19.100.1113	Mobile crane	h	27	1.079,77		29.153,79
				Total Excluding Profit (TRY)	1.078.688,00	150.628,44
				Material and Installation w/o Profit (TRY)	1.229.316,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**188.285,55**	
				Unit Price (TRY)	**1.536.645,55**	

Item No	Analysis Name					UoM
35.710.1807	**8 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1807	8 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.108.120,00	1.108.120,00	
	Installation Components					
10.100.1062	Unskilled worker	h	166	165,00		27.390,00
10.100.1081	Master electrician	h	166	250,00		41.500,00
10.100.1083	Master electrician’s helper	h	166	185,00		30.710,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
		Total Excluding Profit (TRY)			1.108.120,00	169.431,60
		Material and Installation w/o Profit (TRY)			1.277.551,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**211.789,50**	
		Unit Price (TRY)			**1.596.939,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1808	**9 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1808	9 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.145.976,00	1.145.976,00	
	Installation Components					
10.100.1062	Unskilled worker	h	185	165,00		30.525,00
10.100.1081	Master electrician	h	185	250,00		46.250,00
10.100.1083	Master electrician’s helper	h	185	185,00		34.225,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	33	687,95		22.702,35
19.100.1113	Mobile crane	h	33	1.079,77		35.632,41
				Total Excluding Profit (TRY)	1.145.976,00	188.234,76
				Material and Installation w/o Profit (TRY)	1.334.210,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**235.293,45**	
				Unit Price (TRY)	**1.667.763,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1809	**10 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1809	10 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.192.776,00	1.192.776,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.192.776,00	207.037,92
				Material and Installation w/o Profit (TRY)	1.399.813,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258.797,40**	
				Unit Price (TRY)	**1.749.767,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1810	**11 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1810	11 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.233.336,00	1.233.336,00	
	Installation Components					
10.100.1062	Unskilled worker	h	223	165,00		36.795,00
10.100.1081	Master electrician	h	223	250,00		55.750,00
10.100.1083	Master electrician’s helper	h	223	185,00		41.255,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	39	687,95		26.830,05
19.100.1113	Mobile crane	h	39	1.079,77		42.111,03
				Total Excluding Profit (TRY)	1.233.336,00	225.841,08
				Material and Installation w/o Profit (TRY)	1.459.177,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**282.301,35**	
				Unit Price (TRY)	**1.823.971,35**	

Item No	Analysis Name					UoM
35.710.1811	**12 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1811	12 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.266.616,00	1.266.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	242	165,00		39.930,00
10.100.1081	Master electrician	h	242	250,00		60.500,00
10.100.1083	Master electrician’s helper	h	242	185,00		44.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	42	687,95		28.893,90
19.100.1113	Mobile crane	h	42	1.079,77		45.350,34
				Total Excluding Profit (TRY)	1.266.616,00	244.644,24
				Material and Installation w/o Profit (TRY)	1.511.260,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**305.805,30**	
				Unit Price (TRY)	**1.889.075,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1812	**13 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1812	13 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.304.472,00	1.304.472,00	
	Installation Components					
10.100.1062	Unskilled worker	h	261	165,00		43.065,00
10.100.1081	Master electrician	h	261	250,00		65.250,00
10.100.1083	Master electrician’s helper	h	261	185,00		48.285,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	45	687,95		30.957,75
19.100.1113	Mobile crane	h	45	1.079,77		48.589,65
				Total Excluding Profit (TRY)	1.304.472,00	263.447,40
				Material and Installation w/o Profit (TRY)	1.567.919,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**329.309,25**	
				Unit Price (TRY)	**1.959.899,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1813	**14 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1813	14 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.351.168,00	1.351.168,00	
	Installation Components					
10.100.1062	Unskilled worker	h	280	165,00		46.200,00
10.100.1081	Master electrician	h	280	250,00		70.000,00
10.100.1083	Master electrician’s helper	h	280	185,00		51.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.351.168,00	282.250,56
				Material and Installation w/o Profit (TRY)	1.633.418,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**352.813,20**	
				Unit Price (TRY)	**2.041.773,20**	

Item No	Analysis Name					UoM
35.710.1814	**15 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1814	15 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 1600 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.404.728,00	1.404.728,00	
	Installation Components					
10.100.1062	Unskilled worker	h	299	165,00		49.335,00
10.100.1081	Master electrician	h	299	250,00		74.750,00
10.100.1083	Master electrician’s helper	h	299	185,00		55.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	51	687,95		35.085,45
19.100.1113	Mobile crane	h	51	1.079,77		55.068,27
				Total Excluding Profit (TRY)	1.404.728,00	301.053,72
				Material and Installation w/o Profit (TRY)	1.705.781,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**376.317,15**	
				Unit Price (TRY)	**2.132.227,15**	

Item No	Analysis Name					UoM
35.710.1851	**2 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1851	2 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.179.089,60	1.179.089,60	
	Installation Components					
10.100.1062	Unskilled worker	h	60	165,00		9.900,00
10.100.1081	Master electrician	h	60	250,00		15.000,00
10.100.1083	Master electrician’s helper	h	60	185,00		11.100,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	1.179.089,60	68.483,52
				Material and Installation w/o Profit (TRY)	1.247.573,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**85.604,40**	
				Unit Price (TRY)	**1.559.466,40**	

Item No	Analysis Name					UoM
35.710.1852	**3 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1852	3 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.223.081,60	1.223.081,60	
	Installation Components					
10.100.1062	Unskilled worker	h	82	165,00		13.530,00
10.100.1081	Master electrician	h	82	250,00		20.500,00
10.100.1083	Master electrician’s helper	h	82	185,00		15.170,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
		Total Excluding Profit (TRY)			1.223.081,60	90.854,40
		Material and Installation w/o Profit (TRY)			1.313.936,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**113.568,00**	
		Unit Price (TRY)			**1.642.420,00**	

Item No	Analysis Name					UoM
35.710.1853	**4 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1853	4 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.264.910,40	1.264.910,40	
	Installation Components					
10.100.1062	Unskilled worker	h	104	165,00		17.160,00
10.100.1081	Master electrician	h	104	250,00		26.000,00
10.100.1083	Master electrician’s helper	h	104	185,00		19.240,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.264.910,40	113.225,28
				Material and Installation w/o Profit (TRY)	1.378.135,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**141.531,60**	
				Unit Price (TRY)	**1.722.669,60**	

Item No	Analysis Name					UoM
35.710.1854	**5 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1854	5 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.316.848,00	1.316.848,00	
	Installation Components					
10.100.1062	Unskilled worker	h	126	165,00		20.790,00
10.100.1081	Master electrician	h	126	250,00		31.500,00
10.100.1083	Master electrician's helper	h	126	185,00		23.310,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.316.848,00	135.596,16
				Material and Installation w/o Profit (TRY)	1.452.444,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**169.495,20**	
				Unit Price (TRY)	**1.815.555,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1855	**6 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1855	6 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.370.928,00	1.370.928,00	
	Installation Components					
10.100.1062	Unskilled worker	h	148	165,00		24.420,00
10.100.1081	Master electrician	h	148	250,00		37.000,00
10.100.1083	Master electrician’s helper	h	148	185,00		27.380,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
		Total Excluding Profit (TRY)			1.370.928,00	157.967,04
		Material and Installation w/o Profit (TRY)			1.528.895,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**197.458,80**	
		Unit Price (TRY)			**1.911.118,80**	

Item No	Analysis Name					UoM
35.710.1856	**7 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1856	7 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.442.584,00	1.442.584,00	
	Installation Components					
10.100.1062	Unskilled worker	h	170	165,00		28.050,00
10.100.1081	Master electrician	h	170	250,00		42.500,00
10.100.1083	Master electrician’s helper	h	170	185,00		31.450,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
		Total Excluding Profit (TRY)			1.442.584,00	180.337,92
		Material and Installation w/o Profit (TRY)			1.622.921,92	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**225.422,40**	
		Unit Price (TRY)			**2.028.652,40**	

Item No	Analysis Name					UoM
35.710.1857	**8 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1857	8 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.501.136,00	1.501.136,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	40	687,95		27.518,00
19.100.1113	Mobile crane	h	40	1.079,77		43.190,80
				Total Excluding Profit (TRY)	1.501.136,00	202.708,80
				Material and Installation w/o Profit (TRY)	1.703.844,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**253.386,00**	
				Unit Price (TRY)	**2.129.806,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1858	**9 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1858	9 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.577.264,00	1.577.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	214	165,00		35.310,00
10.100.1081	Master electrician	h	214	250,00		53.500,00
10.100.1083	Master electrician’s helper	h	214	185,00		39.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	44	687,95		30.269,80
19.100.1113	Mobile crane	h	44	1.079,77		47.509,88
				Total Excluding Profit (TRY)	1.577.264,00	225.079,68
				Material and Installation w/o Profit (TRY)	1.802.343,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**281.349,60**	
				Unit Price (TRY)	**2.252.929,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1859	**10 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1859	10 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.640.080,00	1.640.080,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.640.080,00	247.450,56
				Material and Installation w/o Profit (TRY)	1.887.530,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**309.313,20**	
				Unit Price (TRY)	**2.359.413,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1860	**11 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1860	11 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.707.368,00	1.707.368,00	
	Installation Components					
10.100.1062	Unskilled worker	h	258	165,00		42.570,00
10.100.1081	Master electrician	h	258	250,00		64.500,00
10.100.1083	Master electrician’s helper	h	258	185,00		47.730,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	52	687,95		35.773,40
19.100.1113	Mobile crane	h	52	1.079,77		56.148,04
				Total Excluding Profit (TRY)	1.707.368,00	269.821,44
				Material and Installation w/o Profit (TRY)	1.977.189,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**337.276,80**	
				Unit Price (TRY)	**2.471.486,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.710.1861	**12 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1861	12 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.765.816,00	1.765.816,00	
	Installation Components					
10.100.1062	Unskilled worker	h	280	165,00		46.200,00
10.100.1081	Master electrician	h	280	250,00		70.000,00
10.100.1083	Master electrician’s helper	h	280	185,00		51.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	56	687,95		38.525,20
19.100.1113	Mobile crane	h	56	1.079,77		60.467,12
				Total Excluding Profit (TRY)	1.765.816,00	292.192,32
				Material and Installation w/o Profit (TRY)	2.058.008,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**365.240,40**	
				Unit Price (TRY)	**2.572.510,40**	

Item No	Analysis Name					UoM
35.710.1862	**13 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1862	13 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.838.512,00	1.838.512,00	
	Installation Components					
10.100.1062	Unskilled worker	h	302	165,00		49.830,00
10.100.1081	Master electrician	h	302	250,00		75.500,00
10.100.1083	Master electrician’s helper	h	302	185,00		55.870,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	60	687,95		41.277,00
19.100.1113	Mobile crane	h	60	1.079,77		64.786,20
				Total Excluding Profit (TRY)	1.838.512,00	314.563,20
				Material and Installation w/o Profit (TRY)	2.153.075,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**393.204,00**	
				Unit Price (TRY)	**2.691.344,00**	

Item No	Analysis Name					UoM
35.710.1863	**14 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1863	14 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.904.032,00	1.904.032,00	
	Installation Components					
10.100.1062	Unskilled worker	h	324	165,00		53.460,00
10.100.1081	Master electrician	h	324	250,00		81.000,00
10.100.1083	Master electrician’s helper	h	324	185,00		59.940,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	64	687,95		44.028,80
19.100.1113	Mobile crane	h	64	1.079,77		69.105,28
				Total Excluding Profit (TRY)	1.904.032,00	336.934,08
				Material and Installation w/o Profit (TRY)	2.240.966,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**421.167,60**	
				Unit Price (TRY)	**2.801.207,60**	

Item No	Analysis Name					UoM
35.710.1864	**15 Stops 1.00 m/s speed / Class IV lift (The lifts designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Lift Installation (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.710.1864	15 Stops 1.00 m/s speed / Class IV elevator (The elevators designed principally to carry objects under the supervision of an accompanying person). Variable-speed, 2000 kg capacity, / Normal Elevator Installation (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.978.496,00	1.978.496,00	
	Installation Components					
10.100.1062	Unskilled worker	h	346	165,00		57.090,00
10.100.1081	Master electrician	h	346	250,00		86.500,00
10.100.1083	Master electrician's helper	h	346	185,00		64.010,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	68	687,95		46.780,60
19.100.1113	Mobile crane	h	68	1.079,77		73.424,36
				Total Excluding Profit (TRY)	1.978.496,00	359.304,96
				Material and Installation w/o Profit (TRY)	2.337.800,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**449.131,20**	
				Unit Price (TRY)	**2.922.251,20**	

Item No	Analysis Name					UoM
35.715.1101	**2 stops / Hydraulic passenger lift, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1101	2 stops / Hydraulic passenger elevator, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Elevators (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	436.540,00	436.540,00	
	Installation Components					
10.100.1062	Unskilled worker	h	37	165,00		6.105,00
10.100.1081	Master electrician	h	37	250,00		9.250,00
10.100.1083	Master electrician's helper	h	37	185,00		6.845,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	436.540,00	40.541,76
				Material and Installation w/o Profit (TRY)	477.081,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50.677,20**	
				Unit Price (TRY)	**596.352,20**	

Item No	Analysis Name					UoM
35.715.1102	**3 stops / Hydraulic passenger lift, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1102	3 stops / Hydraulic passenger elevator, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Elevators (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	498.149,60	498.149,60	
	Installation Components					
10.100.1062	Unskilled worker	h	50,5	165,00		8.332,50
10.100.1081	Master electrician	h	50,5	250,00		12.625,00
10.100.1083	Master electrician's helper	h	50,5	185,00		9.342,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	498.149,60	54.277,20
				Material and Installation w/o Profit (TRY)	552.426,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**67.846,50**	
				Unit Price (TRY)	**690.533,50**	

Item No	Analysis Name					UoM
35.715.1103	**4 stops / Hydraulic passenger lift, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1103	4 stops / Hydraulic passenger elevator, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Elevators (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	567.881,60	567.881,60	
	Installation Components					
10.100.1062	Unskilled worker	h	64	165,00		10.560,00
10.100.1081	Master electrician	h	64	250,00		16.000,00
10.100.1083	Master electrician's helper	h	64	185,00		11.840,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	567.881,60	68.012,64
				Material and Installation w/o Profit (TRY)	635.894,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85.015,80**	
				Unit Price (TRY)	**794.867,80**	

Item No	Analysis Name					UoM
35.715.1104	**5 stops / Hydraulic passenger lift, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1104	5 stops / Hydraulic passenger elevator, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Elevators (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	608.493,60	608.493,60	
	Installation Components					
10.100.1062	Unskilled worker	h	77,5	165,00		12.787,50
10.100.1081	Master electrician	h	77,5	250,00		19.375,00
10.100.1083	Master electrician's helper	h	77,5	185,00		14.337,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	608.493,60	81.748,08
				Material and Installation w/o Profit (TRY)	690.241,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**102.185,10**	
				Unit Price (TRY)	**862.802,10**	

Item No	Analysis Name					UoM
35.715.1105	**6 stops / Hydraulic passenger lift, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1105	6 stops / Hydraulic passenger elevator, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Elevators (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	680.399,20	680.399,20	
	Installation Components					
10.100.1062	Unskilled worker	h	91	165,00		15.015,00
10.100.1081	Master electrician	h	91	250,00		22.750,00
10.100.1083	Master electrician's helper	h	91	185,00		16.835,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	680.399,20	95.483,52
				Material and Installation w/o Profit (TRY)	775.882,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**119.354,40**	
				Unit Price (TRY)	**969.853,40**	

Item No	Analysis Name					UoM
35.715.1106	**7 stops / Hydraulic passenger lift, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1106	7 stops / Hydraulic passenger elevator, Lifting capacity: 630 kg, Carriage speed: 0.60 m/s / Hydraulic Elevators (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	741.104,00	741.104,00	
	Installation Components					
10.100.1062	Unskilled worker	h	104,5	165,00		17.242,50
10.100.1081	Master electrician	h	104,5	250,00		26.125,00
10.100.1083	Master electrician's helper	h	104,5	185,00		19.332,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	741.104,00	109.218,96
				Material and Installation w/o Profit (TRY)	850.322,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**136.523,70**	
				Unit Price (TRY)	**1.062.903,70**	

Item No	Analysis Name					UoM
35.715.1151	**2 stops / Hydraulic freight lift, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1151	2 stops / Hydraulic freight elevator, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	450.164,00	450.164,00	
	Installation Components					
10.100.1062	Unskilled worker	h	37	165,00		6.105,00
10.100.1081	Master electrician	h	37	250,00		9.250,00
10.100.1083	Master electrician's helper	h	37	185,00		6.845,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	450.164,00	40.541,76
				Material and Installation w/o Profit (TRY)	490.705,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**50.677,20**	
				Unit Price (TRY)	**613.382,20**	

Item No	Analysis Name					UoM
35.715.1152	**3 stops / Hydraulic freight lift, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1152	3 stops / Hydraulic freight elevator, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	511.669,60	511.669,60	
	Installation Components					
10.100.1062	Unskilled worker	h	50,5	165,00		8.332,50
10.100.1081	Master electrician	h	50,5	250,00		12.625,00
10.100.1083	Master electrician's helper	h	50,5	185,00		9.342,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	511.669,60	54.277,20
				Material and Installation w/o Profit (TRY)	565.946,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**67.846,50**	
				Unit Price (TRY)	**707.433,50**	

Item No	Analysis Name					UoM
35.715.1153	**4 stops / Hydraulic freight lift, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1153	4 stops / Hydraulic freight elevator, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	584.313,60	584.313,60	
	Installation Components					
10.100.1062	Unskilled worker	h	64	165,00		10.560,00
10.100.1081	Master electrician	h	64	250,00		16.000,00
10.100.1083	Master electrician's helper	h	64	185,00		11.840,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	584.313,60	68.012,64
				Material and Installation w/o Profit (TRY)	652.326,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**85.015,80**	
				Unit Price (TRY)	**815.407,80**	

Item No	Analysis Name					UoM
35.715.1154	**5 stops / Hydraulic freight lift, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1154	5 stops / Hydraulic freight elevator, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	621.493,60	621.493,60	
	Installation Components					
10.100.1062	Unskilled worker	h	77,5	165,00		12.787,50
10.100.1081	Master electrician	h	77,5	250,00		19.375,00
10.100.1083	Master electrician's helper	h	77,5	185,00		14.337,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	621.493,60	81.748,08
				Material and Installation w/o Profit (TRY)	703.241,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**102.185,10**	
				Unit Price (TRY)	**879.052,10**	

Item No	Analysis Name					UoM
35.715.1155	**6 stops / Hydraulic freight lift, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1155	6 stops / Hydraulic freight elevator, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	694.647,20	694.647,20	
	Installation Components					
10.100.1062	Unskilled worker	h	91	165,00		15.015,00
10.100.1081	Master electrician	h	91	250,00		22.750,00
10.100.1083	Master electrician's helper	h	91	185,00		16.835,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	694.647,20	95.483,52
				Material and Installation w/o Profit (TRY)	790.130,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**119.354,40**	
				Unit Price (TRY)	**987.663,40**	

Item No	Analysis Name					UoM
35.715.1156	**7 stops / Hydraulic freight lift, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1156	7 stops / Hydraulic freight elevator, Lifting capacity: 630 kg, Carriage speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	753.584,00	753.584,00	
	Installation Components					
10.100.1062	Unskilled worker	h	104,5	165,00		17.242,50
10.100.1081	Master electrician	h	104,5	250,00		26.125,00
10.100.1083	Master electrician's helper	h	104,5	185,00		19.332,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	753.584,00	109.218,96
				Material and Installation w/o Profit (TRY)	862.802,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**136.523,70**	
				Unit Price (TRY)	**1.078.503,70**	

Item No	Analysis Name					UoM
35.715.1201	**2 stops / Hydraulic passenger lift, Lifting capacity: 800 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1201	2 stops / Hydraulic passenger elevator, Lifting capacity: 800 kg, Carriage speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	509.745,60	509.745,60	
	Installation Components					
10.100.1062	Unskilled worker	h	39,5	165,00		6.517,50
10.100.1081	Master electrician	h	39,5	250,00		9.875,00
10.100.1083	Master electrician's helper	h	39,5	185,00		7.307,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	509.745,60	42.041,76
				Material and Installation w/o Profit (TRY)	551.787,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**52.552,20**	
				Unit Price (TRY)	**689.734,20**	

Item No	Analysis Name					UoM
35.715.1202	**3 stops / Hydraulic passenger lift, Lifting capacity: 800 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1202	3 stops / Hydraulic passenger elevator, Lifting capacity: 800 kg, Carriage speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	574.995,20	574.995,20	
	Installation Components					
10.100.1062	Unskilled worker	h	54	165,00		8.910,00
10.100.1081	Master electrician	h	54	250,00		13.500,00
10.100.1083	Master electrician's helper	h	54	185,00		9.990,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	574.995,20	56.377,20
				Material and Installation w/o Profit (TRY)	631.372,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**70.471,50**	
				Unit Price (TRY)	**789.215,50**	

Item No	Analysis Name					UoM
35.715.1203	**4 stops / Hydraulic passenger lift, Lifting capacity: 800 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1203	4 stops / Hydraulic passenger elevator, Lifting capacity: 800 kg, Carriage speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	640.369,60	640.369,60	
	Installation Components					
10.100.1062	Unskilled worker	h	68,5	165,00		11.302,50
10.100.1081	Master electrician	h	68,5	250,00		17.125,00
10.100.1083	Master electrician's helper	h	68,5	185,00		12.672,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	640.369,60	70.712,64
				Material and Installation w/o Profit (TRY)	711.082,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**88.390,80**	
				Unit Price (TRY)	**888.852,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.715.1204	**5 stops / Hydraulic passenger lift, Lifting capacity: 800 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1204	5 stops / Hydraulic passenger elevator, Lifting capacity: 800 kg, Carriage speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	671.715,20	671.715,20	
	Installation Components					
10.100.1062	Unskilled worker	h	83	165,00		13.695,00
10.100.1081	Master electrician	h	83	250,00		20.750,00
10.100.1083	Master electrician's helper	h	83	185,00		15.355,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
			Total Excluding Profit (TRY)		671.715,20	85.048,08
			Material and Installation w/o Profit (TRY)		756.763,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106.310,10**	
				Unit Price (TRY)	**945.954,10**	

Item No	Analysis Name					UoM
35.715.1205	**6 stops / Hydraulic passenger lift, Lifting capacity: 800 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1205	6 stops / Hydraulic passenger elevator, Lifting capacity: 800 kg, Carriage speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	732.992,00	732.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	97,5	165,00		16.087,50
10.100.1081	Master electrician	h	97,5	250,00		24.375,00
10.100.1083	Master electrician's helper	h	97,5	185,00		18.037,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
			Total Excluding Profit (TRY)		732.992,00	99.383,52
			Material and Installation w/o Profit (TRY)		832.375,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**124.229,40**	
				Unit Price (TRY)	**1.040.469,40**	

Item No	Analysis Name					UoM
35.715.1206	**7 stops / Hydraulic passenger lift, Lifting capacity: 800 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1206	7 stops / Hydraulic passenger elevator, Lifting capacity: 800 kg, Carriage speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	781.144,00	781.144,00	
	Installation Components					
10.100.1062	Unskilled worker	h	112	165,00		18.480,00
10.100.1081	Master electrician	h	112	250,00		28.000,00
10.100.1083	Master electrician's helper	h	112	185,00		20.720,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	781.144,00	113.718,96
				Material and Installation w/o Profit (TRY)	894.862,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**142.148,70**	
				Unit Price (TRY)	**1.118.578,70**	

Item No	Analysis Name					UoM
35.715.1251	**2 stops / Hydraulic passenger lift, Lifting capacity: 1000 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1251	2 stops / Hydraulic passenger elevator, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	608.816,00	608.816,00	
	Installation Components					
10.100.1062	Unskilled worker	h	42	165,00		6.930,00
10.100.1081	Master electrician	h	42	250,00		10.500,00
10.100.1083	Master electrician's helper	h	42	185,00		7.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	608.816,00	43.541,76
				Material and Installation w/o Profit (TRY)	652.357,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**54.427,20**	
				Unit Price (TRY)	**815.447,20**	

Item No	Analysis Name					UoM
35.715.1252	**3 stops / Hydraulic passenger lift, Lifting capacity: 1000 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1252	3 stops / Hydraulic passenger elevator, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	663.000,00	663.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	57,5	165,00		9.487,50
10.100.1081	Master electrician	h	57,5	250,00		14.375,00
10.100.1083	Master electrician's helper	h	57,5	185,00		10.637,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	663.000,00	58.477,20
				Material and Installation w/o Profit (TRY)	721.477,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**73.096,50**	
				Unit Price (TRY)	**901.846,50**	

Item No	Analysis Name					UoM
35.715.1253	**4 stops / Hydraulic passenger lift, Lifting capacity: 1000 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1253	4 stops / Hydraulic passenger elevator, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	729.435,20	729.435,20	
	Installation Components					
10.100.1062	Unskilled worker	h	73	165,00		12.045,00
10.100.1081	Master electrician	h	73	250,00		18.250,00
10.100.1083	Master electrician's helper	h	73	185,00		13.505,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	729.435,20	73.412,64
				Material and Installation w/o Profit (TRY)	802.847,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**91.765,80**	
				Unit Price (TRY)	**1.003.559,80**	

Item No	Analysis Name					UoM
35.715.1254	**5 stops / Hydraulic passenger lift, Lifting capacity: 1000 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1254	5 stops / Hydraulic passenger elevator, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	785.283,20	785.283,20	
	Installation Components					
10.100.1062	Unskilled worker	h	88,5	165,00		14.602,50
10.100.1081	Master electrician	h	88,5	250,00		22.125,00
10.100.1083	Master electrician's helper	h	88,5	185,00		16.372,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	785.283,20	88.348,08
				Material and Installation w/o Profit (TRY)	873.631,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**110.435,10**	
				Unit Price (TRY)	**1.092.039,10**	

Item No	Analysis Name					UoM
35.715.1255	**6 stops / Hydraulic passenger lift, Lifting capacity: 1000 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1255	6 stops / Hydraulic passenger elevator, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	867.068,80	867.068,80	
	Installation Components					
10.100.1062	Unskilled worker	h	104	165,00		17.160,00
10.100.1081	Master electrician	h	104	250,00		26.000,00
10.100.1083	Master electrician's helper	h	104	185,00		19.240,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	867.068,80	103.283,52
				Material and Installation w/o Profit (TRY)	970.352,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129.104,40**	
				Unit Price (TRY)	**1.212.940,40**	

Item No	Analysis Name					UoM
35.715.1256	**7 stops / Hydraulic passenger lift, Lifting capacity: 1000 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1256	7 stops / Hydraulic passenger elevator, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	944.392,80	944.392,80	
	Installation Components					
10.100.1062	Unskilled worker	h	119,5	165,00		19.717,50
10.100.1081	Master electrician	h	119,5	250,00		29.875,00
10.100.1083	Master electrician's helper	h	119,5	185,00		22.107,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	944.392,80	118.218,96
				Material and Installation w/o Profit (TRY)	1.062.611,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**147.773,70**	
				Unit Price (TRY)	**1.328.264,70**	

Item No	Analysis Name					UoM
35.715.1301	**2 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1301	2 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	571.168,00	571.168,00	
	Installation Components					
10.100.1062	Unskilled worker	h	42	165,00		6.930,00
10.100.1081	Master electrician	h	42	250,00		10.500,00
10.100.1083	Master electrician's helper	h	42	185,00		7.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	571.168,00	43.541,76
				Material and Installation w/o Profit (TRY)	614.709,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**54.427,20**	
				Unit Price (TRY)	**768.387,20**	

Item No	Analysis Name					UoM
35.715.1302	**3 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1302	3 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	659.360,00	659.360,00	
	Installation Components					
10.100.1062	Unskilled worker	h	57,5	165,00		9.487,50
10.100.1081	Master electrician	h	57,5	250,00		14.375,00
10.100.1083	Master electrician's helper	h	57,5	185,00		10.637,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	659.360,00	58.477,20
				Material and Installation w/o Profit (TRY)	717.837,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**73.096,50**	
				Unit Price (TRY)	**897.296,50**	

Item No	Analysis Name					UoM
35.715.1303	**4 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1303	4 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	710.299,20	710.299,20	
	Installation Components					
10.100.1062	Unskilled worker	h	73	165,00		12.045,00
10.100.1081	Master electrician	h	73	250,00		18.250,00
10.100.1083	Master electrician's helper	h	73	185,00		13.505,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	710.299,20	73.412,64
				Material and Installation w/o Profit (TRY)	783.711,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**91.765,80**	
				Unit Price (TRY)	**979.639,80**	

Item No	Analysis Name					UoM
35.715.1304	**5 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1304	5 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	793.291,20	793.291,20	
	Installation Components					
10.100.1062	Unskilled worker	h	88,5	165,00		14.602,50
10.100.1081	Master electrician	h	88,5	250,00		22.125,00
10.100.1083	Master electrician's helper	h	88,5	185,00		16.372,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	793.291,20	88.348,08
				Material and Installation w/o Profit (TRY)	881.639,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**110.435,10**	
				Unit Price (TRY)	**1.102.049,10**	

Item No	Analysis Name					UoM
35.715.1305	**6 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1305	6 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	858.228,80	858.228,80	
	Installation Components					
10.100.1062	Unskilled worker	h	104	165,00		17.160,00
10.100.1081	Master electrician	h	104	250,00		26.000,00
10.100.1083	Master electrician's helper	h	104	185,00		19.240,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	858.228,80	103.283,52
				Material and Installation w/o Profit (TRY)	961.512,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129.104,40**	
				Unit Price (TRY)	**1.201.890,40**	

Item No	Analysis Name					UoM
35.715.1306	**7 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1306	7 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	909.864,80	909.864,80	
	Installation Components					
10.100.1062	Unskilled worker	h	119,5	165,00		19.717,50
10.100.1081	Master electrician	h	119,5	250,00		29.875,00
10.100.1083	Master electrician's helper	h	119,5	185,00		22.107,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	909.864,80	118.218,96
				Material and Installation w/o Profit (TRY)	1.028.083,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**147.773,70**	
				Unit Price (TRY)	**1.285.104,70**	

Item No	Analysis Name					UoM
35.715.1351	**2 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1351	2 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	574.184,00	574.184,00	
	Installation Components					
10.100.1062	Unskilled worker	h	42	165,00		6.930,00
10.100.1081	Master electrician	h	42	250,00		10.500,00
10.100.1083	Master electrician's helper	h	42	185,00		7.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	574.184,00	43.541,76
				Material and Installation w/o Profit (TRY)	617.725,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**54.427,20**	
				Unit Price (TRY)	**772.157,20**	

Item No	Analysis Name					UoM
35.715.1352	**3 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1352	3 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	661.960,00	661.960,00	
	Installation Components					
10.100.1062	Unskilled worker	h	57,5	165,00		9.487,50
10.100.1081	Master electrician	h	57,5	250,00		14.375,00
10.100.1083	Master electrician's helper	h	57,5	185,00		10.637,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	661.960,00	58.477,20
				Material and Installation w/o Profit (TRY)	720.437,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**73.096,50**	
				Unit Price (TRY)	**900.546,50**	

Item No	Analysis Name					UoM
35.715.1353	**4 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1353	4 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	713.003,20	713.003,20	
	Installation Components					
10.100.1062	Unskilled worker	h	73	165,00		12.045,00
10.100.1081	Master electrician	h	73	250,00		18.250,00
10.100.1083	Master electrician's helper	h	73	185,00		13.505,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	713.003,20	73.412,64
				Material and Installation w/o Profit (TRY)	786.415,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**91.765,80**	
				Unit Price (TRY)	**983.019,80**	

Item No	Analysis Name					UoM
35.715.1354	**5 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1354	5 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	796.619,20	796.619,20	
	Installation Components					
10.100.1062	Unskilled worker	h	88,5	165,00		14.602,50
10.100.1081	Master electrician	h	88,5	250,00		22.125,00
10.100.1083	Master electrician's helper	h	88,5	185,00		16.372,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	796.619,20	88.348,08
				Material and Installation w/o Profit (TRY)	884.967,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**110.435,10**	
				Unit Price (TRY)	**1.106.209,10**	

Item No	Analysis Name					UoM
35.715.1355	**6 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1355	6 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	880.588,80	880.588,80	
	Installation Components					
10.100.1062	Unskilled worker	h	104	165,00		17.160,00
10.100.1081	Master electrician	h	104	250,00		26.000,00
10.100.1083	Master electrician's helper	h	104	185,00		19.240,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	880.588,80	103.283,52
				Material and Installation w/o Profit (TRY)	983.872,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**129.104,40**	
				Unit Price (TRY)	**1.229.840,40**	

Item No	Analysis Name					UoM
35.715.1356	**7 stops / Hydraulic freight lift, Lifting capacity: 1000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1356	7 stops/ Hydraulic freight elevator, Lifting capacity: 1000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	943.560,80	943.560,80	
	Installation Components					
10.100.1062	Unskilled worker	h	119,5	165,00		19.717,50
10.100.1081	Master electrician	h	119,5	250,00		29.875,00
10.100.1083	Master electrician's helper	h	119,5	185,00		22.107,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	943.560,80	118.218,96
				Material and Installation w/o Profit (TRY)	1.061.779,76	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**147.773,70**	
				Unit Price (TRY)	**1.327.224,70**	

Item No	Analysis Name					UoM
35.715.1401	**2 stops / Hydraulic passenger lift, Lifting capacity: 1275 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1401	2 stops / Hydraulic passenger elevator, Lifting capacity: 1275 kg, Carriage Speed: 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	673.909,60	673.909,60	
	Installation Components					
10.100.1062	Unskilled worker	h	46,5	165,00		7.672,50
10.100.1081	Master electrician	h	46,5	250,00		11.625,00
10.100.1083	Master electrician's helper	h	46,5	185,00		8.602,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	11	687,95		7.567,45
19.100.1113	Mobile crane	h	11	1.079,77		11.877,47
				Total Excluding Profit (TRY)	673.909,60	51.544,92
				Material and Installation w/o Profit (TRY)	725.454,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**64.431,15**	
				Unit Price (TRY)	**906.818,15**	

Item No	Analysis Name					UoM
35.715.1402	**3 stops / Hydraulic passenger lift, Lifting capacity: 1275 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1402	3 stops / Hydraulic passenger elevator, Lifting capacity: 1275 kg, Carriage Speed: 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	725.441,60	725.441,60	
	Installation Components					
10.100.1062	Unskilled worker	h	64	165,00		10.560,00
10.100.1081	Master electrician	h	64	250,00		16.000,00
10.100.1083	Master electrician's helper	h	64	185,00		11.840,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	725.441,60	69.448,08
				Material and Installation w/o Profit (TRY)	794.889,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**86.810,10**	
				Unit Price (TRY)	**993.612,10**	

Item No	Analysis Name					UoM
35.715.1403	**4 stops / Hydraulic passenger lift, Lifting capacity: 1275 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1403	4 stops / Hydraulic passenger elevator, Lifting capacity: 1275 kg, Carriage Speed: 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	809.525,60	809.525,60	
	Installation Components					
10.100.1062	Unskilled worker	h	81,5	165,00		13.447,50
10.100.1081	Master electrician	h	81,5	250,00		20.375,00
10.100.1083	Master electrician's helper	h	81,5	185,00		15.077,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	17	687,95		11.695,15
19.100.1113	Mobile crane	h	17	1.079,77		18.356,09
				Total Excluding Profit (TRY)	809.525,60	87.351,24
				Material and Installation w/o Profit (TRY)	896.876,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**109.189,05**	
				Unit Price (TRY)	**1.121.096,05**	

Item No	Analysis Name					UoM
35.715.1404	**5 stops / Hydraulic passenger lift, Lifting capacity: 1275 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1404	5 stops / Hydraulic passenger elevator, Lifting capacity: 1275 kg, Carriage Speed: 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	873.215,20	873.215,20	
	Installation Components					
10.100.1062	Unskilled worker	h	99	165,00		16.335,00
10.100.1081	Master electrician	h	99	250,00		24.750,00
10.100.1083	Master electrician's helper	h	99	185,00		18.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	873.215,20	105.254,40
				Material and Installation w/o Profit (TRY)	978.469,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**131.568,00**	
				Unit Price (TRY)	**1.223.087,00**	

Item No	Analysis Name					UoM
35.715.1405	**6 stops / Hydraulic passenger lift, Lifting capacity: 1275 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1405	6 stops / Hydraulic passenger elevator, Lifting capacity: 1275 kg, Carriage Speed: 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	924.144,00	924.144,00	
	Installation Components					
10.100.1062	Unskilled worker	h	116,5	165,00		19.222,50
10.100.1081	Master electrician	h	116,5	250,00		29.125,00
10.100.1083	Master electrician's helper	h	116,5	185,00		21.552,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	23	687,95		15.822,85
19.100.1113	Mobile crane	h	23	1.079,77		24.834,71
				Total Excluding Profit (TRY)	924.144,00	123.157,56
				Material and Installation w/o Profit (TRY)	1.047.301,56	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**153.946,95**	
				Unit Price (TRY)	**1.309.126,95**	

Item No	Analysis Name					UoM
35.715.1406	**7 stops / Hydraulic passenger lift, Lifting capacity: 1275 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1406	7 stops / Hydraulic passenger elevator, Lifting capacity: 1275 kg, Carriage Speed: 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.003.246,40	1.003.246,40	
	Installation Components					
10.100.1062	Unskilled worker	h	134	165,00		22.110,00
10.100.1081	Master electrician	h	134	250,00		33.500,00
10.100.1083	Master electrician's helper	h	134	185,00		24.790,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.003.246,40	141.060,72
				Material and Installation w/o Profit (TRY)	1.144.307,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**176.325,90**	
				Unit Price (TRY)	**1.430.383,90**	

Item No	Analysis Name					UoM
35.715.1451	**2 stops / Hydraulic passenger lift, Lifting capacity: 1600 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1451	2 stops / Hydraulic passenger elevator, Lifting capacity: 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	842.545,60	842.545,60	
	Installation Components					
10.100.1062	Unskilled worker	h	49	165,00		8.085,00
10.100.1081	Master electrician	h	49	250,00		12.250,00
10.100.1083	Master electrician's helper	h	49	185,00		9.065,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	11	687,95		7.567,45
19.100.1113	Mobile crane	h	11	1.079,77		11.877,47
				Total Excluding Profit (TRY)	842.545,60	53.044,92
				Material and Installation w/o Profit (TRY)	895.590,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66.306,15**	
				Unit Price (TRY)	**1.119.488,15**	

Item No	Analysis Name					UoM
35.715.1452	**3 stops / Hydraulic passenger lift, Lifting capacity: 1600 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1452	3 stops / Hydraulic passenger elevator, Lifting capacity: 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	921.221,60	921.221,60	
	Installation Components					
10.100.1062	Unskilled worker	h	67,5	165,00		11.137,50
10.100.1081	Master electrician	h	67,5	250,00		16.875,00
10.100.1083	Master electrician's helper	h	67,5	185,00		12.487,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	921.221,60	71.548,08
				Material and Installation w/o Profit (TRY)	992.769,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**89.435,10**	
				Unit Price (TRY)	**1.240.962,10**	

Item No	Analysis Name					UoM
35.715.1453	**4 stops / Hydraulic passenger lift, Lifting capacity: 1600 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1453	4 stops / Hydraulic passenger elevator, Lifting capacity: 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	998.847,20	998.847,20	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician's helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	17	687,95		11.695,15
19.100.1113	Mobile crane	h	17	1.079,77		18.356,09
				Total Excluding Profit (TRY)	998.847,20	90.051,24
				Material and Installation w/o Profit (TRY)	1.088.898,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**112.564,05**	
				Unit Price (TRY)	**1.361.123,05**	

Item No	Analysis Name					UoM
35.715.1454	**5 stops / Hydraulic passenger lift, Lifting capacity: 1600 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1454	5 stops / Hydraulic passenger elevator, Lifting capacity: 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.078.896,00	1.078.896,00	
	Installation Components					
10.100.1062	Unskilled worker	h	104,5	165,00		17.242,50
10.100.1081	Master electrician	h	104,5	250,00		26.125,00
10.100.1083	Master electrician's helper	h	104,5	185,00		19.332,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	1.078.896,00	108.554,40
				Material and Installation w/o Profit (TRY)	1.187.450,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**135.693,00**	
				Unit Price (TRY)	**1.484.313,00**	

Item No	Analysis Name					UoM
35.715.1455	**6 stops / Hydraulic passenger lift, Lifting capacity: 1600 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1455	6 stops / Hydraulic passenger elevator, Lifting capacity: 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.094.142,40	1.094.142,40	
	Installation Components					
10.100.1062	Unskilled worker	h	123	165,00		20.295,00
10.100.1081	Master electrician	h	123	250,00		30.750,00
10.100.1083	Master electrician's helper	h	123	185,00		22.755,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	23	687,95		15.822,85
19.100.1113	Mobile crane	h	23	1.079,77		24.834,71
				Total Excluding Profit (TRY)	1.094.142,40	127.057,56
				Material and Installation w/o Profit (TRY)	1.221.199,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**158.821,95**	
				Unit Price (TRY)	**1.526.499,95**	

Item No	Analysis Name					UoM
35.715.1456	**7 stops / Hydraulic passenger lift, Lifting capacity: 1600 kg, Carriage speed: 0.60 m/s / Hydraulic Lifts (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1456	7 stops / Hydraulic passenger elevator, Lifting capacity: 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.169.906,40	1.169.906,40	
	Installation Components					
10.100.1062	Unskilled worker	h	141,5	165,00		23.347,50
10.100.1081	Master electrician	h	141,5	250,00		35.375,00
10.100.1083	Master electrician's helper	h	141,5	185,00		26.177,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.169.906,40	145.560,72
				Material and Installation w/o Profit (TRY)	1.315.467,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**181.950,90**	
				Unit Price (TRY)	**1.644.333,90**	

Item No	Analysis Name					UoM
35.715.1501	**2 stops / Hydraulic patient lift, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1501	2 stops / Hydraulic patient elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	819.249,60	819.249,60	
	Installation Components					
10.100.1062	Unskilled worker	h	49	165,00		8.085,00
10.100.1081	Master electrician	h	49	250,00		12.250,00
10.100.1083	Master electrician's helper	h	49	185,00		9.065,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	11	687,95		7.567,45
19.100.1113	Mobile crane	h	11	1.079,77		11.877,47
				Total Excluding Profit (TRY)	819.249,60	53.044,92
				Material and Installation w/o Profit (TRY)	872.294,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66.306,15**	
				Unit Price (TRY)	**1.090.368,15**	

Item No	Analysis Name					UoM
35.715.1502	**3 stops / Hydraulic patient lift, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1502	3 stops / Hydraulic patient elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	898.549,60	898.549,60	
	Installation Components					
10.100.1062	Unskilled worker	h	67,5	165,00		11.137,50
10.100.1081	Master electrician	h	67,5	250,00		16.875,00
10.100.1083	Master electrician's helper	h	67,5	185,00		12.487,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	898.549,60	71.548,08
				Material and Installation w/o Profit (TRY)	970.097,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**89.435,10**	
				Unit Price (TRY)	**1.212.622,10**	

Item No	Analysis Name					UoM
35.715.1503	**4 stops / Hydraulic patient lift, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1503	4 stops / Hydraulic patient elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	976.071,20	976.071,20	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician's helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	17	687,95		11.695,15
19.100.1113	Mobile crane	h	17	1.079,77		18.356,09
				Total Excluding Profit (TRY)	976.071,20	90.051,24
				Material and Installation w/o Profit (TRY)	1.066.122,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**112.564,05**	
				Unit Price (TRY)	**1.332.653,05**	

Item No	Analysis Name					UoM
35.715.1504	**5 stops / Hydraulic patient lift, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1504	5 stops / Hydraulic patient elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.054.768,00	1.054.768,00	
	Installation Components					
10.100.1062	Unskilled worker	h	104,5	165,00		17.242,50
10.100.1081	Master electrician	h	104,5	250,00		26.125,00
10.100.1083	Master electrician's helper	h	104,5	185,00		19.332,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	1.054.768,00	108.554,40
				Material and Installation w/o Profit (TRY)	1.163.322,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**135.693,00**	
				Unit Price (TRY)	**1.454.153,00**	

Item No	Analysis Name					UoM
35.715.1505	**6 stops / Hydraulic patient lift, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1505	6 stops / Hydraulic patient elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.071.158,40	1.071.158,40	
	Installation Components					
10.100.1062	Unskilled worker	h	123	165,00		20.295,00
10.100.1081	Master electrician	h	123	250,00		30.750,00
10.100.1083	Master electrician's helper	h	123	185,00		22.755,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	23	687,95		15.822,85
19.100.1113	Mobile crane	h	23	1.079,77		24.834,71
				Total Excluding Profit (TRY)	1.071.158,40	127.057,56
				Material and Installation w/o Profit (TRY)	1.198.215,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**158.821,95**	
				Unit Price (TRY)	**1.497.769,95**	

Item No	Analysis Name					UoM
35.715.1506	**7 stops / Hydraulic patient lift, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.1506	7 stops / Hydraulic patient elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.147.130,40	1.147.130,40	
	Installation Components					
10.100.1062	Unskilled worker	h	141,5	165,00		23.347,50
10.100.1081	Master electrician	h	141,5	250,00		35.375,00
10.100.1083	Master electrician's helper	h	141,5	185,00		26.177,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.147.130,40	145.560,72
				Material and Installation w/o Profit (TRY)	1.292.691,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**181.950,90**	
				Unit Price (TRY)	**1.615.863,90**	

Item No	Analysis Name					UoM
35.715.2001	**2 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2001	2 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	833.601,60	833.601,60	
	Installation Components					
10.100.1062	Unskilled worker	h	49	165,00		8.085,00
10.100.1081	Master electrician	h	49	250,00		12.250,00
10.100.1083	Master electrician's helper	h	49	185,00		9.065,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	11	687,95		7.567,45
19.100.1113	Mobile crane	h	11	1.079,77		11.877,47
				Total Excluding Profit (TRY)	833.601,60	53.044,92
				Material and Installation w/o Profit (TRY)	886.646,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66.306,15**	
				Unit Price (TRY)	**1.108.308,15**	

Item No	Analysis Name					UoM
35.715.2002	**3 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2002	3 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	912.173,60	912.173,60	
	Installation Components					
10.100.1062	Unskilled worker	h	67,5	165,00		11.137,50
10.100.1081	Master electrician	h	67,5	250,00		16.875,00
10.100.1083	Master electrician's helper	h	67,5	185,00		12.487,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	912.173,60	71.548,08
				Material and Installation w/o Profit (TRY)	983.721,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**89.435,10**	
				Unit Price (TRY)	**1.229.652,10**	

Item No	Analysis Name					UoM
35.715.2003	**4 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2003	4 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	990.527,20	990.527,20	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician's helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	17	687,95		11.695,15
19.100.1113	Mobile crane	h	17	1.079,77		18.356,09
				Total Excluding Profit (TRY)	990.527,20	90.051,24
				Material and Installation w/o Profit (TRY)	1.080.578,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**112.564,05**	
				Unit Price (TRY)	**1.350.723,05**	

Item No	Analysis Name					UoM
35.715.2004	**5 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2004	5 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.069.536,00	1.069.536,00	
	Installation Components					
10.100.1062	Unskilled worker	h	104,5	165,00		17.242,50
10.100.1081	Master electrician	h	104,5	250,00		26.125,00
10.100.1083	Master electrician's helper	h	104,5	185,00		19.332,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	1.069.536,00	108.554,40
				Material and Installation w/o Profit (TRY)	1.178.090,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**135.693,00**	
				Unit Price (TRY)	**1.472.613,00**	

Item No	Analysis Name					UoM
35.715.2005	**6 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2005	6 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.086.134,40	1.086.134,40	
	Installation Components					
10.100.1062	Unskilled worker	h	123	165,00		20.295,00
10.100.1081	Master electrician	h	123	250,00		30.750,00
10.100.1083	Master electrician's helper	h	123	185,00		22.755,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	23	687,95		15.822,85
19.100.1113	Mobile crane	h	23	1.079,77		24.834,71
				Total Excluding Profit (TRY)	1.086.134,40	127.057,56
				Material and Installation w/o Profit (TRY)	1.213.191,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**158.821,95**	
				Unit Price (TRY)	**1.516.489,95**	

Item No	Analysis Name					UoM
35.715.2006	**7 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2006	7 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.228.146,40	1.228.146,40	
	Installation Components					
10.100.1062	Unskilled worker	h	141,5	165,00		23.347,50
10.100.1081	Master electrician	h	141,5	250,00		35.375,00
10.100.1083	Master electrician's helper	h	141,5	185,00		26.177,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.228.146,40	145.560,72
				Material and Installation w/o Profit (TRY)	1.373.707,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**181.950,90**	
				Unit Price (TRY)	**1.717.133,90**	

Item No	Analysis Name					UoM
35.715.2101	**2 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2101	2 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	839.945,60	839.945,60	
	Installation Components					
10.100.1062	Unskilled worker	h	49	165,00		8.085,00
10.100.1081	Master electrician	h	49	250,00		12.250,00
10.100.1083	Master electrician's helper	h	49	185,00		9.065,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	11	687,95		7.567,45
19.100.1113	Mobile crane	h	11	1.079,77		11.877,47
				Total Excluding Profit (TRY)	839.945,60	53.044,92
				Material and Installation w/o Profit (TRY)	892.990,52	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**66.306,15**	
				Unit Price (TRY)	**1.116.238,15**	

Item No	Analysis Name					UoM
35.715.2102	**3 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2102	3 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	919.349,60	919.349,60	
	Installation Components					
10.100.1062	Unskilled worker	h	67,5	165,00		11.137,50
10.100.1081	Master electrician	h	67,5	250,00		16.875,00
10.100.1083	Master electrician's helper	h	67,5	185,00		12.487,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	919.349,60	71.548,08
				Material and Installation w/o Profit (TRY)	990.897,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**89.435,10**	
				Unit Price (TRY)	**1.238.622,10**	

Item No	Analysis Name					UoM
35.715.2103	**4 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2103	4 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	997.183,20	997.183,20	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician's helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	17	687,95		11.695,15
19.100.1113	Mobile crane	h	17	1.079,77		18.356,09
				Total Excluding Profit (TRY)	997.183,20	90.051,24
				Material and Installation w/o Profit (TRY)	1.087.234,44	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**112.564,05**	
				Unit Price (TRY)	**1.359.043,05**	

Item No	Analysis Name					UoM
35.715.2104	**5 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2104	5 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.075.360,00	1.075.360,00	
	Installation Components					
10.100.1062	Unskilled worker	h	104,5	165,00		17.242,50
10.100.1081	Master electrician	h	104,5	250,00		26.125,00
10.100.1083	Master electrician's helper	h	104,5	185,00		19.332,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	1.075.360,00	108.554,40
				Material and Installation w/o Profit (TRY)	1.183.914,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**135.693,00**	
				Unit Price (TRY)	**1.479.893,00**	

Item No	Analysis Name					UoM
35.715.2105	**6 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2105	6 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.091.646,40	1.091.646,40	
	Installation Components					
10.100.1062	Unskilled worker	h	123	165,00		20.295,00
10.100.1081	Master electrician	h	123	250,00		30.750,00
10.100.1083	Master electrician's helper	h	123	185,00		22.755,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	23	687,95		15.822,85
19.100.1113	Mobile crane	h	23	1.079,77		24.834,71
				Total Excluding Profit (TRY)	1.091.646,40	127.057,56
				Material and Installation w/o Profit (TRY)	1.218.703,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**158.821,95**	
				Unit Price (TRY)	**1.523.379,95**	

Item No	Analysis Name					UoM
35.715.2106	**7 stops / Hydraulic freight lift, Lifting capacity: 1600 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2106	7 stops / Hydraulic freight elevator, Lifting capacity 1600 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.166.266,40	1.166.266,40	
	Installation Components					
10.100.1062	Unskilled worker	h	141,5	165,00		23.347,50
10.100.1081	Master electrician	h	141,5	250,00		35.375,00
10.100.1083	Master electrician's helper	h	141,5	185,00		26.177,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.166.266,40	145.560,72
				Material and Installation w/o Profit (TRY)	1.311.827,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**181.950,90**	
				Unit Price (TRY)	**1.639.783,90**	

Item No	Analysis Name					UoM
35.715.2151	**2 stops / Hydraulic patient lift, Lifting capacity 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2151	2 stops / Hydraulic patient elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.055.797,60	1.055.797,60	
	Installation Components					
10.100.1062	Unskilled worker	h	56	165,00		9.240,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician's helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	1.055.797,60	62.548,08
				Material and Installation w/o Profit (TRY)	1.118.345,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**78.185,10**	
				Unit Price (TRY)	**1.397.932,10**	

Item No	Analysis Name					UoM
35.715.2152	**3 stops / Hydraulic patient lift, Lifting capacity 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2152	3 stops / Hydraulic patient elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.138.623,20	1.138.623,20	
	Installation Components					
10.100.1062	Unskilled worker	h	77,5	165,00		12.787,50
10.100.1081	Master electrician	h	77,5	250,00		19.375,00
10.100.1083	Master electrician's helper	h	77,5	185,00		14.337,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.138.623,20	84.618,96
				Material and Installation w/o Profit (TRY)	1.223.242,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**105.773,70**	
				Unit Price (TRY)	**1.529.052,70**	

Item No	Analysis Name					UoM
35.715.2153	**4 stops / Hydraulic patient lift, Lifting capacity 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2153	4 stops / Hydraulic patient elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.222.104,00	1.222.104,00	
	Installation Components					
10.100.1062	Unskilled worker	h	99	165,00		16.335,00
10.100.1081	Master electrician	h	99	250,00		24.750,00
10.100.1083	Master electrician's helper	h	99	185,00		18.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.222.104,00	106.689,84
				Material and Installation w/o Profit (TRY)	1.328.793,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133.362,30**	
				Unit Price (TRY)	**1.660.992,30**	

Item No	Analysis Name					UoM
35.715.2154	**5 stops / Hydraulic patient lift, Lifting capacity 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2154	5 stops / Hydraulic patient elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.304.378,40	1.304.378,40	
	Installation Components					
10.100.1062	Unskilled worker	h	120,5	165,00		19.882,50
10.100.1081	Master electrician	h	120,5	250,00		30.125,00
10.100.1083	Master electrician's helper	h	120,5	185,00		22.292,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.304.378,40	128.760,72
				Material and Installation w/o Profit (TRY)	1.433.139,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**160.950,90**	
				Unit Price (TRY)	**1.791.423,90**	

Item No	Analysis Name					UoM
35.715.2155	**6 stops / Hydraulic patient lift, Lifting capacity 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2155	6 stops / Hydraulic patient elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.358.656,00	1.358.656,00	
	Installation Components					
10.100.1062	Unskilled worker	h	142	165,00		23.430,00
10.100.1081	Master electrician	h	142	250,00		35.500,00
10.100.1083	Master electrician's helper	h	142	185,00		26.270,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.358.656,00	150.831,60
				Material and Installation w/o Profit (TRY)	1.509.487,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**188.539,50**	
				Unit Price (TRY)	**1.886.859,50**	

Item No	Analysis Name					UoM
35.715.2156	**7 stops / Hydraulic patient lift, Lifting capacity 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2156	7 stops / Hydraulic patient elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.393.288,00	1.393.288,00	
	Installation Components					
10.100.1062	Unskilled worker	h	163,5	165,00		26.977,50
10.100.1081	Master electrician	h	163,5	250,00		40.875,00
10.100.1083	Master electrician's helper	h	163,5	185,00		30.247,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.393.288,00	172.902,48
				Material and Installation w/o Profit (TRY)	1.566.190,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**216.128,10**	
				Unit Price (TRY)	**1.957.738,10**	

Item No	Analysis Name					UoM
35.715.2201	**2 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2201	2 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.078.261,60	1.078.261,60	
	Installation Components					
10.100.1062	Unskilled worker	h	56	165,00		9.240,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician's helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	1.078.261,60	62.548,08
				Material and Installation w/o Profit (TRY)	1.140.809,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**78.185,10**	
				Unit Price (TRY)	**1.426.012,10**	

Item No	Analysis Name					UoM
35.715.2202	**3 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2202	3 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.160.255,20	1.160.255,20	
	Installation Components					
10.100.1062	Unskilled worker	h	77,5	165,00		12.787,50
10.100.1081	Master electrician	h	77,5	250,00		19.375,00
10.100.1083	Master electrician's helper	h	77,5	185,00		14.337,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.160.255,20	84.618,96
				Material and Installation w/o Profit (TRY)	1.244.874,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**105.773,70**	
				Unit Price (TRY)	**1.556.092,70**	

Item No	Analysis Name					UoM
35.715.2203	**4 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2203	4 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.218.464,00	1.218.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	99	165,00		16.335,00
10.100.1081	Master electrician	h	99	250,00		24.750,00
10.100.1083	Master electrician's helper	h	99	185,00		18.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.218.464,00	106.689,84
				Material and Installation w/o Profit (TRY)	1.325.153,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133.362,30**	
				Unit Price (TRY)	**1.656.442,30**	

Item No	Analysis Name					UoM
35.715.2204	**5 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2204	5 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.299.698,40	1.299.698,40	
	Installation Components					
10.100.1062	Unskilled worker	h	120,5	165,00		19.882,50
10.100.1081	Master electrician	h	120,5	250,00		30.125,00
10.100.1083	Master electrician's helper	h	120,5	185,00		22.292,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.299.698,40	128.760,72
				Material and Installation w/o Profit (TRY)	1.428.459,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**160.950,90**	
				Unit Price (TRY)	**1.785.573,90**	

Item No	Analysis Name					UoM
35.715.2205	**6 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2205	6 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.380.496,00	1.380.496,00	
	Installation Components					
10.100.1062	Unskilled worker	h	142	165,00		23.430,00
10.100.1081	Master electrician	h	142	250,00		35.500,00
10.100.1083	Master electrician's helper	h	142	185,00		26.270,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.380.496,00	150.831,60
				Material and Installation w/o Profit (TRY)	1.531.327,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**188.539,50**	
				Unit Price (TRY)	**1.914.159,50**	

Item No	Analysis Name					UoM
35.715.2206	**7 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2206	7 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.462.344,00	1.462.344,00	
	Installation Components					
10.100.1062	Unskilled worker	h	163,5	165,00		26.977,50
10.100.1081	Master electrician	h	163,5	250,00		40.875,00
10.100.1083	Master electrician's helper	h	163,5	185,00		30.247,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.462.344,00	172.902,48
				Material and Installation w/o Profit (TRY)	1.635.246,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**216.128,10**	
				Unit Price (TRY)	**2.044.058,10**	

Item No	Analysis Name					UoM
35.715.2251	**2 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2251	2 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.084.605,60	1.084.605,60	
	Installation Components					
10.100.1062	Unskilled worker	h	56	165,00		9.240,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician's helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	1.084.605,60	62.548,08
				Material and Installation w/o Profit (TRY)	1.147.153,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**78.185,10**	
				Unit Price (TRY)	**1.433.942,10**	

Item No	Analysis Name					UoM
35.715.2252	**3 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2252	3 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.168.263,20	1.168.263,20	
	Installation Components					
10.100.1062	Unskilled worker	h	77,5	165,00		12.787,50
10.100.1081	Master electrician	h	77,5	250,00		19.375,00
10.100.1083	Master electrician's helper	h	77,5	185,00		14.337,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.168.263,20	84.618,96
				Material and Installation w/o Profit (TRY)	1.252.882,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**105.773,70**	
				Unit Price (TRY)	**1.566.102,70**	

Item No	Analysis Name					UoM
35.715.2253	**4 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2253	4 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.250.912,00	1.250.912,00	
	Installation Components					
10.100.1062	Unskilled worker	h	99	165,00		16.335,00
10.100.1081	Master electrician	h	99	250,00		24.750,00
10.100.1083	Master electrician's helper	h	99	185,00		18.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.250.912,00	106.689,84
				Material and Installation w/o Profit (TRY)	1.357.601,84	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**133.362,30**	
				Unit Price (TRY)	**1.697.002,30**	

Item No	Analysis Name					UoM
35.715.2254	**5 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2254	5 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.306.354,40	1.306.354,40	
	Installation Components					
10.100.1062	Unskilled worker	h	120,5	165,00		19.882,50
10.100.1081	Master electrician	h	120,5	250,00		30.125,00
10.100.1083	Master electrician's helper	h	120,5	185,00		22.292,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.306.354,40	128.760,72
				Material and Installation w/o Profit (TRY)	1.435.115,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**160.950,90**	
				Unit Price (TRY)	**1.793.893,90**	

Item No	Analysis Name					UoM
35.715.2255	**6 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2255	6 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.387.984,00	1.387.984,00	
	Installation Components					
10.100.1062	Unskilled worker	h	142	165,00		23.430,00
10.100.1081	Master electrician	h	142	250,00		35.500,00
10.100.1083	Master electrician's helper	h	142	185,00		26.270,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.387.984,00	150.831,60
				Material and Installation w/o Profit (TRY)	1.538.815,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**188.539,50**	
				Unit Price (TRY)	**1.923.519,50**	

Item No	Analysis Name					UoM
35.715.2256	**7 stops / Hydraulic freight lift, Lifting capacity: 2000 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2256	7 stops / Hydraulic freight elevator, Lifting capacity: 2000 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.469.000,00	1.469.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	163,5	165,00		26.977,50
10.100.1081	Master electrician	h	163,5	250,00		40.875,00
10.100.1083	Master electrician's helper	h	163,5	185,00		30.247,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.469.000,00	172.902,48
				Material and Installation w/o Profit (TRY)	1.641.902,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**216.128,10**	
				Unit Price (TRY)	**2.052.378,10**	

Item No	Analysis Name					UoM
35.715.2301	**2 stops / Hydraulic patient lift, Lifting capacity 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2301	2 stops / Hydraulic patient elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.202.687,20	1.202.687,20	
	Installation Components					
10.100.1062	Unskilled worker	h	58,5	165,00		9.652,50
10.100.1081	Master electrician	h	58,5	250,00		14.625,00
10.100.1083	Master electrician's helper	h	58,5	185,00		10.822,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	1.202.687,20	64.048,08
				Material and Installation w/o Profit (TRY)	1.266.735,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**80.060,10**	
				Unit Price (TRY)	**1.583.419,10**	

Item No	Analysis Name					UoM
35.715.2302	**3 stops / Hydraulic patient lift, Lifting capacity 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2302	3 stops / Hydraulic patient elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.285.232,00	1.285.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	81	165,00		13.365,00
10.100.1081	Master electrician	h	81	250,00		20.250,00
10.100.1083	Master electrician's helper	h	81	185,00		14.985,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.285.232,00	86.718,96
				Material and Installation w/o Profit (TRY)	1.371.950,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**108.398,70**	
				Unit Price (TRY)	**1.714.938,70**	

Item No	Analysis Name					UoM
35.715.2303	**4 stops / Hydraulic patient lift, Lifting capacity 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2303	4 stops / Hydraulic patient elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.340.414,40	1.340.414,40	
	Installation Components					
10.100.1062	Unskilled worker	h	103,5	165,00		17.077,50
10.100.1081	Master electrician	h	103,5	250,00		25.875,00
10.100.1083	Master electrician's helper	h	103,5	185,00		19.147,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.340.414,40	109.389,84
				Material and Installation w/o Profit (TRY)	1.449.804,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**136.737,30**	
				Unit Price (TRY)	**1.812.255,30**	

Item No	Analysis Name					UoM
35.715.2304	**5 stops / Hydraulic patient lift, Lifting capacity 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2304	5 stops / Hydraulic patient elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.421.264,00	1.421.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	126	165,00		20.790,00
10.100.1081	Master electrician	h	126	250,00		31.500,00
10.100.1083	Master electrician's helper	h	126	185,00		23.310,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.421.264,00	132.060,72
				Material and Installation w/o Profit (TRY)	1.553.324,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**165.075,90**	
				Unit Price (TRY)	**1.941.655,90**	

Item No	Analysis Name					UoM
35.715.2305	**6 stops / Hydraulic patient lift, Lifting capacity 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2305	6 stops / Hydraulic patient elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.503.008,00	1.503.008,00	
	Installation Components					
10.100.1062	Unskilled worker	h	148,5	165,00		24.502,50
10.100.1081	Master electrician	h	148,5	250,00		37.125,00
10.100.1083	Master electrician's helper	h	148,5	185,00		27.472,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.503.008,00	154.731,60
				Material and Installation w/o Profit (TRY)	1.657.739,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**193.414,50**	
				Unit Price (TRY)	**2.072.174,50**	

Item No	Analysis Name					UoM
35.715.2306	**7 stops / Hydraulic patient lift, Lifting capacity 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2306	7 stops / Hydraulic patient elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.585.896,00	1.585.896,00	
	Installation Components					
10.100.1062	Unskilled worker	h	171	165,00		28.215,00
10.100.1081	Master electrician	h	171	250,00		42.750,00
10.100.1083	Master electrician's helper	h	171	185,00		31.635,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.585.896,00	177.402,48
				Material and Installation w/o Profit (TRY)	1.763.298,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221.753,10**	
				Unit Price (TRY)	**2.204.123,10**	

Item No	Analysis Name					UoM
35.715.2351	**2 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2351	2 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.219.535,20	1.219.535,20	
	Installation Components					
10.100.1062	Unskilled worker	h	58,5	165,00		9.652,50
10.100.1081	Master electrician	h	58,5	250,00		14.625,00
10.100.1083	Master electrician's helper	h	58,5	185,00		10.822,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	1.219.535,20	64.048,08
				Material and Installation w/o Profit (TRY)	1.283.583,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**80.060,10**	
				Unit Price (TRY)	**1.604.479,10**	

Item No	Analysis Name					UoM
35.715.2352	**3 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2352	3 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.278.992,00	1.278.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	81	165,00		13.365,00
10.100.1081	Master electrician	h	81	250,00		20.250,00
10.100.1083	Master electrician's helper	h	81	185,00		14.985,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.278.992,00	86.718,96
				Material and Installation w/o Profit (TRY)	1.365.710,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**108.398,70**	
				Unit Price (TRY)	**1.707.138,70**	

Item No	Analysis Name					UoM
35.715.2353	**4 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2353	4 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.362.358,40	1.362.358,40	
	Installation Components					
10.100.1062	Unskilled worker	h	103,5	165,00		17.077,50
10.100.1081	Master electrician	h	103,5	250,00		25.875,00
10.100.1083	Master electrician's helper	h	103,5	185,00		19.147,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.362.358,40	109.389,84
				Material and Installation w/o Profit (TRY)	1.471.748,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**136.737,30**	
				Unit Price (TRY)	**1.839.685,30**	

Item No	Analysis Name					UoM
35.715.2354	**5 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2354	5 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.414.608,00	1.414.608,00	
	Installation Components					
10.100.1062	Unskilled worker	h	126	165,00		20.790,00
10.100.1081	Master electrician	h	126	250,00		31.500,00
10.100.1083	Master electrician's helper	h	126	185,00		23.310,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.414.608,00	132.060,72
				Material and Installation w/o Profit (TRY)	1.546.668,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**165.075,90**	
				Unit Price (TRY)	**1.933.335,90**	

Item No	Analysis Name					UoM
35.715.2355	**6 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2355	6 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.494.688,00	1.494.688,00	
	Installation Components					
10.100.1062	Unskilled worker	h	148,5	165,00		24.502,50
10.100.1081	Master electrician	h	148,5	250,00		37.125,00
10.100.1083	Master electrician's helper	h	148,5	185,00		27.472,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.494.688,00	154.731,60
				Material and Installation w/o Profit (TRY)	1.649.419,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**193.414,50**	
				Unit Price (TRY)	**2.061.774,50**	

Item No	Analysis Name					UoM
35.715.2356	**7 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.40 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2356	7 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.40 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.577.888,00	1.577.888,00	
	Installation Components					
10.100.1062	Unskilled worker	h	171	165,00		28.215,00
10.100.1081	Master electrician	h	171	250,00		42.750,00
10.100.1083	Master electrician's helper	h	171	185,00		31.635,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.577.888,00	177.402,48
				Material and Installation w/o Profit (TRY)	1.755.290,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221.753,10**	
				Unit Price (TRY)	**2.194.113,10**	

Item No	Analysis Name					UoM
35.715.2401	**2 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2401	2 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.227.335,20	1.227.335,20	
	Installation Components					
10.100.1062	Unskilled worker	h	58,5	165,00		9.652,50
10.100.1081	Master electrician	h	58,5	250,00		14.625,00
10.100.1083	Master electrician's helper	h	58,5	185,00		10.822,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	1.227.335,20	64.048,08
				Material and Installation w/o Profit (TRY)	1.291.383,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**80.060,10**	
				Unit Price (TRY)	**1.614.229,10**	

Item No	Analysis Name					UoM
35.715.2402	**3 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2402	3 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.285.232,00	1.285.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	81	165,00		13.365,00
10.100.1081	Master electrician	h	81	250,00		20.250,00
10.100.1083	Master electrician's helper	h	81	185,00		14.985,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.285.232,00	86.718,96
				Material and Installation w/o Profit (TRY)	1.371.950,96	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**108.398,70**	
				Unit Price (TRY)	**1.714.938,70**	

Item No	Analysis Name					UoM
35.715.2403	**4 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2403	4 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.369.014,40	1.369.014,40	
	Installation Components					
10.100.1062	Unskilled worker	h	103,5	165,00		17.077,50
10.100.1081	Master electrician	h	103,5	250,00		25.875,00
10.100.1083	Master electrician's helper	h	103,5	185,00		19.147,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.369.014,40	109.389,84
				Material and Installation w/o Profit (TRY)	1.478.404,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**136.737,30**	
				Unit Price (TRY)	**1.848.005,30**	

Item No	Analysis Name					UoM
35.715.2404	**5 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2404	5 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.421.264,00	1.421.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	126	165,00		20.790,00
10.100.1081	Master electrician	h	126	250,00		31.500,00
10.100.1083	Master electrician's helper	h	126	185,00		23.310,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.421.264,00	132.060,72
				Material and Installation w/o Profit (TRY)	1.553.324,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**165.075,90**	
				Unit Price (TRY)	**1.941.655,90**	

Item No	Analysis Name					UoM
35.715.2405	**6 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2405	6 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.502.488,00	1.502.488,00	
	Installation Components					
10.100.1062	Unskilled worker	h	148,5	165,00		24.502,50
10.100.1081	Master electrician	h	148,5	250,00		37.125,00
10.100.1083	Master electrician's helper	h	148,5	185,00		27.472,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.502.488,00	154.731,60
				Material and Installation w/o Profit (TRY)	1.657.219,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**193.414,50**	
				Unit Price (TRY)	**2.071.524,50**	

Item No	Analysis Name					UoM
35.715.2406	**7 stops / Hydraulic freight lift, Lifting capacity: 2500 kg, Carriage speed 0.60 m/s, / Hydraulic Lifts, (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.715.2406	7 stops / Hydraulic freight elevator, Lifting capacity: 2500 kg, Carriage Speed 0.60 m/s, / Hydraulic Elevators, (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.584.232,00	1.584.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	171	165,00		28.215,00
10.100.1081	Master electrician	h	171	250,00		42.750,00
10.100.1083	Master electrician's helper	h	171	185,00		31.635,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.584.232,00	177.402,48
				Material and Installation w/o Profit (TRY)	1.761.634,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**221.753,10**	
				Unit Price (TRY)	**2.202.043,10**	

Item No	Analysis Name					UoM
35.720.1101	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1101	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	734.541,60	734.541,60	
	Installation Components					
10.100.1062	Unskilled worker	h	38	165,00		6.270,00
10.100.1081	Master electrician	h	38	250,00		9.500,00
10.100.1083	Master electrician's helper	h	38	185,00		7.030,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	734.541,60	41.141,76
				Material and Installation w/o Profit (TRY)	775.683,36	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**51.427,20**	
				Unit Price (TRY)	**969.604,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1102	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1102	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	761.560,80	761.560,80	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician’s helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
		Total Excluding Profit (TRY)			761.560,80	55.177,20
		Material and Installation w/o Profit (TRY)			816.738,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**68.971,50**	
		Unit Price (TRY)			**1.020.922,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1103	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1103	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	793.748,80	793.748,80	
	Installation Components					
10.100.1062	Unskilled worker	h	66	165,00		10.890,00
10.100.1081	Master electrician	h	66	250,00		16.500,00
10.100.1083	Master electrician’s helper	h	66	185,00		12.210,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			793.748,80	69.212,64
		Material and Installation w/o Profit (TRY)			862.961,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**86.515,80**	
		Unit Price (TRY)			**1.078.701,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1104	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1104	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	826.623,20	826.623,20	
	Installation Components					
10.100.1062	Unskilled worker	h	80	165,00		13.200,00
10.100.1081	Master electrician	h	80	250,00		20.000,00
10.100.1083	Master electrician’s helper	h	80	185,00		14.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
		Total Excluding Profit (TRY)			826.623,20	83.248,08
		Material and Installation w/o Profit (TRY)			909.871,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**104.060,10**	
		Unit Price (TRY)			**1.137.339,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1105	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1105	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	875.836,00	875.836,00	
	Installation Components					
10.100.1062	Unskilled worker	h	94	165,00		15.510,00
10.100.1081	Master electrician	h	94	250,00		23.500,00
10.100.1083	Master electrician’s helper	h	94	185,00		17.390,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			875.836,00	97.283,52
		Material and Installation w/o Profit (TRY)			973.119,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**121.604,40**	
		Unit Price (TRY)			**1.216.399,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1106	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1106	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	913.785,60	913.785,60	
	Installation Components					
10.100.1062	Unskilled worker	h	108	165,00		17.820,00
10.100.1081	Master electrician	h	108	250,00		27.000,00
10.100.1083	Master electrician’s helper	h	108	185,00		19.980,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			913.785,60	111.318,96
		Material and Installation w/o Profit (TRY)			1.025.104,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**139.148,70**	
		Unit Price (TRY)			**1.281.380,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1107	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1107	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	950.456,00	950.456,00	
	Installation Components					
10.100.1062	Unskilled worker	h	122	165,00		20.130,00
10.100.1081	Master electrician	h	122	250,00		30.500,00
10.100.1083	Master electrician’s helper	h	122	185,00		22.570,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
		Total Excluding Profit (TRY)			950.456,00	125.354,40
		Material and Installation w/o Profit (TRY)			1.075.810,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**156.693,00**	
		Unit Price (TRY)			**1.344.763,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1108	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1108	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	991.328,00	991.328,00	
	Installation Components					
10.100.1062	Unskilled worker	h	136	165,00		22.440,00
10.100.1081	Master electrician	h	136	250,00		34.000,00
10.100.1083	Master electrician’s helper	h	136	185,00		25.160,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
		Total Excluding Profit (TRY)			991.328,00	139.389,84
		Material and Installation w/o Profit (TRY)			1.130.717,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**174.237,30**	
		Unit Price (TRY)			**1.413.397,30**	

Item No	Analysis Name					UoM
35.720.1109	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1109	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.032.616,00	1.032.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	150	165,00		24.750,00
10.100.1081	Master electrician	h	150	250,00		37.500,00
10.100.1083	Master electrician’s helper	h	150	185,00		27.750,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.032.616,00	153.425,28
				Material and Installation w/o Profit (TRY)	1.186.041,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**191.781,60**	
				Unit Price (TRY)	**1.482.551,60**	

Item No	Analysis Name					UoM
35.720.1110	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1110	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.093.768,00	1.093.768,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.093.768,00	167.460,72
				Material and Installation w/o Profit (TRY)	1.261.228,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**209.325,90**	
				Unit Price (TRY)	**1.576.535,90**	

Item No	Analysis Name					UoM
35.720.1111	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1111	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.137.032,00	1.137.032,00	
	Installation Components					
10.100.1062	Unskilled worker	h	178	165,00		29.370,00
10.100.1081	Master electrician	h	178	250,00		44.500,00
10.100.1083	Master electrician’s helper	h	178	185,00		32.930,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.137.032,00	181.496,16
				Material and Installation w/o Profit (TRY)	1.318.528,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**226.870,20**	
				Unit Price (TRY)	**1.648.160,20**	

Item No	Analysis Name					UoM
35.720.1112	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1112	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.180.816,00	1.180.816,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.180.816,00	195.531,60
				Material and Installation w/o Profit (TRY)	1.376.347,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**244.414,50**	
				Unit Price (TRY)	**1.720.434,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1113	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1113	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.235.000,00	1.235.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	206	165,00		33.990,00
10.100.1081	Master electrician	h	206	250,00		51.500,00
10.100.1083	Master electrician’s helper	h	206	185,00		38.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.235.000,00	209.567,04
				Material and Installation w/o Profit (TRY)	1.444.567,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**261.958,80**	
				Unit Price (TRY)	**1.805.708,80**	

Item No	Analysis Name					UoM
35.720.1114	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1114	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). No engine room, Variable-speed, 630 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.307.384,00	1.307.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.307.384,00	223.602,48
				Material and Installation w/o Profit (TRY)	1.530.986,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**279.503,10**	
				Unit Price (TRY)	**1.913.733,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1201	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1201	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	762.226,40	762.226,40	
	Installation Components					
10.100.1062	Unskilled worker	h	41	165,00		6.765,00
10.100.1081	Master electrician	h	41	250,00		10.250,00
10.100.1083	Master electrician’s helper	h	41	185,00		7.585,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	762.226,40	42.941,76
				Material and Installation w/o Profit (TRY)	805.168,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**53.677,20**	
				Unit Price (TRY)	**1.006.460,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1202	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1202	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	827.725,60	827.725,60	
	Installation Components					
10.100.1062	Unskilled worker	h	56	165,00		9.240,00
10.100.1081	Master electrician	h	56	250,00		14.000,00
10.100.1083	Master electrician’s helper	h	56	185,00		10.360,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	827.725,60	57.577,20
				Material and Installation w/o Profit (TRY)	885.302,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**71.971,50**	
				Unit Price (TRY)	**1.106.628,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1203	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1203	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	861.452,80	861.452,80	
	Installation Components					
10.100.1062	Unskilled worker	h	71	165,00		11.715,00
10.100.1081	Master electrician	h	71	250,00		17.750,00
10.100.1083	Master electrician’s helper	h	71	185,00		13.135,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			861.452,80	72.212,64
		Material and Installation w/o Profit (TRY)			933.665,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**90.265,80**	
		Unit Price (TRY)			**1.167.081,80**	

Item No	Analysis Name					UoM
35.720.1204	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1204	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	897.364,00	897.364,00	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician’s helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
		Total Excluding Profit (TRY)			897.364,00	86.848,08
		Material and Installation w/o Profit (TRY)			984.212,08	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**108.560,10**	
		Unit Price (TRY)			**1.230.265,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1205	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1205	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	937.820,00	937.820,00	
	Installation Components					
10.100.1062	Unskilled worker	h	101	165,00		16.665,00
10.100.1081	Master electrician	h	101	250,00		25.250,00
10.100.1083	Master electrician’s helper	h	101	185,00		18.685,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			937.820,00	101.483,52
		Material and Installation w/o Profit (TRY)			1.039.303,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**126.854,40**	
		Unit Price (TRY)			**1.299.129,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1206	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1206	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	981.552,00	981.552,00	
	Installation Components					
10.100.1062	Unskilled worker	h	116	165,00		19.140,00
10.100.1081	Master electrician	h	116	250,00		29.000,00
10.100.1083	Master electrician’s helper	h	116	185,00		21.460,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			981.552,00	116.118,96
		Material and Installation w/o Profit (TRY)			1.097.670,96	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**145.148,70**	
		Unit Price (TRY)			**1.372.088,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1207	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1207	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	978.848,00	978.848,00	
	Installation Components					
10.100.1062	Unskilled worker	h	131	165,00		21.615,00
10.100.1081	Master electrician	h	131	250,00		32.750,00
10.100.1083	Master electrician’s helper	h	131	185,00		24.235,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
		Total Excluding Profit (TRY)			978.848,00	130.754,40
		Material and Installation w/o Profit (TRY)			1.109.602,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**163.443,00**	
		Unit Price (TRY)			**1.387.003,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1208	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1208	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.063.400,00	1.063.400,00	
	Installation Components					
10.100.1062	Unskilled worker	h	146	165,00		24.090,00
10.100.1081	Master electrician	h	146	250,00		36.500,00
10.100.1083	Master electrician’s helper	h	146	185,00		27.010,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.063.400,00	145.389,84
				Material and Installation w/o Profit (TRY)	1.208.789,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**181.737,30**	
				Unit Price (TRY)	**1.510.987,30**	

Item No	Analysis Name					UoM
35.720.1209	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1209	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.107.496,00	1.107.496,00	
	Installation Components					
10.100.1062	Unskilled worker	h	161	165,00		26.565,00
10.100.1081	Master electrician	h	161	250,00		40.250,00
10.100.1083	Master electrician’s helper	h	161	185,00		29.785,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.107.496,00	160.025,28
				Material and Installation w/o Profit (TRY)	1.267.521,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**200.031,60**	
				Unit Price (TRY)	**1.584.401,60**	

Item No	Analysis Name					UoM
35.720.1210	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1210	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.121.224,00	1.121.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.121.224,00	174.660,72
				Material and Installation w/o Profit (TRY)	1.295.884,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**218.325,90**	
				Unit Price (TRY)	**1.619.855,90**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1211	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1211	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.159.496,00	1.159.496,00	
	Installation Components					
10.100.1062	Unskilled worker	h	191	165,00		31.515,00
10.100.1081	Master electrician	h	191	250,00		47.750,00
10.100.1083	Master electrician’s helper	h	191	185,00		35.335,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.159.496,00	189.296,16
				Material and Installation w/o Profit (TRY)	1.348.792,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.620,20**	
				Unit Price (TRY)	**1.685.990,20**	

Item No	Analysis Name					UoM
35.720.1212	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1212	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.213.368,00	1.213.368,00	
	Installation Components					
10.100.1062	Unskilled worker	h	206	165,00		33.990,00
10.100.1081	Master electrician	h	206	250,00		51.500,00
10.100.1083	Master electrician’s helper	h	206	185,00		38.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.213.368,00	203.931,60
				Material and Installation w/o Profit (TRY)	1.417.299,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**254.914,50**	
				Unit Price (TRY)	**1.771.624,50**	

Item No	Analysis Name					UoM
35.720.1213	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1213	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.280.760,00	1.280.760,00	
	Installation Components					
10.100.1062	Unskilled worker	h	221	165,00		36.465,00
10.100.1081	Master electrician	h	221	250,00		55.250,00
10.100.1083	Master electrician’s helper	h	221	185,00		40.885,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.280.760,00	218.567,04
				Material and Installation w/o Profit (TRY)	1.499.327,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**273.208,80**	
				Unit Price (TRY)	**1.874.158,80**	

Item No	Analysis Name					UoM
35.720.1214	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1214	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 800 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.380.392,00	1.380.392,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.380.392,00	233.202,48
				Material and Installation w/o Profit (TRY)	1.613.594,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**291.503,10**	
				Unit Price (TRY)	**2.016.993,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1301	**2 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1301	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	839.581,60	839.581,60	
	Installation Components					
10.100.1062	Unskilled worker	h	44	165,00		7.260,00
10.100.1081	Master electrician	h	44	250,00		11.000,00
10.100.1083	Master electrician’s helper	h	44	185,00		8.140,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
		Total Excluding Profit (TRY)			839.581,60	44.741,76
		Material and Installation w/o Profit (TRY)			884.323,36	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**55.927,20**	
		Unit Price (TRY)			**1.105.404,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1302	**3 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1302	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	872.258,40	872.258,40	
	Installation Components					
10.100.1062	Unskilled worker	h	60	165,00		9.900,00
10.100.1081	Master electrician	h	60	250,00		15.000,00
10.100.1083	Master electrician’s helper	h	60	185,00		11.100,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
		Total Excluding Profit (TRY)			872.258,40	59.977,20
		Material and Installation w/o Profit (TRY)			932.235,60	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**74.971,50**	
		Unit Price (TRY)			**1.165.294,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1303	**4 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1303	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	908.502,40	908.502,40	
	Installation Components					
10.100.1062	Unskilled worker	h	76	165,00		12.540,00
10.100.1081	Master electrician	h	76	250,00		19.000,00
10.100.1083	Master electrician’s helper	h	76	185,00		14.060,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			908.502,40	75.212,64
		Material and Installation w/o Profit (TRY)			983.715,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**94.015,80**	
		Unit Price (TRY)			**1.229.643,80**	

Item No	Analysis Name					UoM
35.720.1304	**5 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1304	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	946.472,80	946.472,80	
	Installation Components					
10.100.1062	Unskilled worker	h	92	165,00		15.180,00
10.100.1081	Master electrician	h	92	250,00		23.000,00
10.100.1083	Master electrician’s helper	h	92	185,00		17.020,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
		Total Excluding Profit (TRY)			946.472,80	90.448,08
		Material and Installation w/o Profit (TRY)			1.036.920,88	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**113.060,10**	
		Unit Price (TRY)			**1.296.151,10**	

Item No	Analysis Name					UoM
35.720.1305	**6 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1305	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	983.434,40	983.434,40	
	Installation Components					
10.100.1062	Unskilled worker	h	108	165,00		17.820,00
10.100.1081	Master electrician	h	108	250,00		27.000,00
10.100.1083	Master electrician’s helper	h	108	185,00		19.980,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
		Total Excluding Profit (TRY)			983.434,40	105.683,52
		Material and Installation w/o Profit (TRY)			1.089.117,92	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**132.104,40**	
		Unit Price (TRY)			**1.361.397,40**	

Item No	Analysis Name					UoM
35.720.1306	**7 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1306	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.025.440,00	1.025.440,00	
	Installation Components					
10.100.1062	Unskilled worker	h	124	165,00		20.460,00
10.100.1081	Master electrician	h	124	250,00		31.000,00
10.100.1083	Master electrician’s helper	h	124	185,00		22.940,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
				Total Excluding Profit (TRY)	1.025.440,00	120.918,96
				Material and Installation w/o Profit (TRY)	1.146.358,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**151.148,70**	
				Unit Price (TRY)	**1.432.948,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1307	**8 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1307	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.069.224,00	1.069.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	140	165,00		23.100,00
10.100.1081	Master electrician	h	140	250,00		35.000,00
10.100.1083	Master electrician’s helper	h	140	185,00		25.900,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	20	687,95		13.759,00
19.100.1113	Mobile crane	h	20	1.079,77		21.595,40
				Total Excluding Profit (TRY)	1.069.224,00	136.154,40
				Material and Installation w/o Profit (TRY)	1.205.378,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**170.193,00**	
				Unit Price (TRY)	**1.506.723,00**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1308	**9 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1308	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.120.912,00	1.120.912,00	
	Installation Components					
10.100.1062	Unskilled worker	h	156	165,00		25.740,00
10.100.1081	Master electrician	h	156	250,00		39.000,00
10.100.1083	Master electrician’s helper	h	156	185,00		28.860,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	22	687,95		15.134,90
19.100.1113	Mobile crane	h	22	1.079,77		23.754,94
				Total Excluding Profit (TRY)	1.120.912,00	151.389,84
				Material and Installation w/o Profit (TRY)	1.272.301,84	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.237,30**	
				Unit Price (TRY)	**1.590.377,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1309	**10 stops and 1.00 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1309	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.182.376,00	1.182.376,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.182.376,00	166.625,28
				Material and Installation w/o Profit (TRY)	1.349.001,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.281,60**	
				Unit Price (TRY)	**1.686.251,60**	

Item No	Analysis Name					UoM
35.720.1310	**11 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1310	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.229.384,00	1.229.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	26	687,95		17.886,70
19.100.1113	Mobile crane	h	26	1.079,77		28.074,02
				Total Excluding Profit (TRY)	1.229.384,00	181.860,72
				Material and Installation w/o Profit (TRY)	1.411.244,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.325,90**	
				Unit Price (TRY)	**1.764.055,90**	

Item No	Analysis Name					UoM
35.720.1311	**12 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1311	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.286.376,00	1.286.376,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	28	687,95		19.262,60
19.100.1113	Mobile crane	h	28	1.079,77		30.233,56
				Total Excluding Profit (TRY)	1.286.376,00	197.096,16
				Material and Installation w/o Profit (TRY)	1.483.472,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.370,20**	
				Unit Price (TRY)	**1.854.340,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1312	**13 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1312	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.359.384,00	1.359.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.359.384,00	212.331,60
				Material and Installation w/o Profit (TRY)	1.571.715,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.414,50**	
				Unit Price (TRY)	**1.964.644,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1313	**14 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1313	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.397.864,00	1.397.864,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	32	687,95		22.014,40
19.100.1113	Mobile crane	h	32	1.079,77		34.552,64
				Total Excluding Profit (TRY)	1.397.864,00	227.567,04
				Material and Installation w/o Profit (TRY)	1.625.431,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**284.458,80**	
				Unit Price (TRY)	**2.031.788,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1314	**15 stops and 1.60 m/s speed / Class I lifts (The lifts designed for carrying passengers). Class II lifts (The lifts designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Lift Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1314	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). No engine room, Variable-speed, 1000 kg capacity, / Elevator Installation without engine room (in compliance with TS EN 81-20 and TS EN 81-50) (Market price)	Qty	1	1.439.880,00	1.439.880,00	
	Installation Components					
10.100.1062	Unskilled worker	h	252	165,00		41.580,00
10.100.1081	Master electrician	h	252	250,00		63.000,00
10.100.1083	Master electrician’s helper	h	252	185,00		46.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	34	687,95		23.390,30
19.100.1113	Mobile crane	h	34	1.079,77		36.712,18
				Total Excluding Profit (TRY)	1.439.880,00	242.802,48
				Material and Installation w/o Profit (TRY)	1.682.682,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**303.503,10**	
				Unit Price (TRY)	**2.103.353,10**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1401						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1401	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	878.935,20	878.935,20	
	Installation Components					
10.100.1062	Unskilled worker	h	49	165,00		8.085,00
10.100.1081	Master electrician	h	49	250,00		12.250,00
10.100.1083	Master electrician’s helper	h	49	185,00		9.065,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			878.935,20	54.812,64
		Material and Installation w/o Profit (TRY)			933.747,84	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**68.515,80**	
		Unit Price (TRY)			**1.167.184,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1402						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1402	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	921.076,00	921.076,00	
	Installation Components					
10.100.1062	Unskilled worker	h	67	165,00		11.055,00
10.100.1081	Master electrician	h	67	250,00		16.750,00
10.100.1083	Master electrician’s helper	h	67	185,00		12.395,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
				Total Excluding Profit (TRY)	921.076,00	73.015,80
				Material and Installation w/o Profit (TRY)	994.091,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**91.269,75**	
				Unit Price (TRY)	**1.242.614,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1403						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1403	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	956.103,20	956.103,20	
	Installation Components					
10.100.1062	Unskilled worker	h	85	165,00		14.025,00
10.100.1081	Master electrician	h	85	250,00		21.250,00
10.100.1083	Master electrician’s helper	h	85	185,00		15.725,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			956.103,20	91.218,96
		Material and Installation w/o Profit (TRY)			1.047.322,16	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**114.023,70**	
		Unit Price (TRY)			**1.309.152,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1404						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1404	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	991.546,40	991.546,40	
	Installation Components					
10.100.1062	Unskilled worker	h	103	165,00		16.995,00
10.100.1081	Master electrician	h	103	250,00		25.750,00
10.100.1083	Master electrician’s helper	h	103	185,00		19.055,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	21	687,95		14.446,95
19.100.1113	Mobile crane	h	21	1.079,77		22.675,17
		Total Excluding Profit (TRY)			991.546,40	109.422,12
		Material and Installation w/o Profit (TRY)			1.100.968,52	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**136.777,65**	
		Unit Price (TRY)			**1.376.210,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1405						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1405	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.027.312,00	1.027.312,00	
	Installation Components					
10.100.1062	Unskilled worker	h	121	165,00		19.965,00
10.100.1081	Master electrician	h	121	250,00		30.250,00
10.100.1083	Master electrician’s helper	h	121	185,00		22.385,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
		Total Excluding Profit (TRY)			1.027.312,00	127.625,28
		Material and Installation w/o Profit (TRY)			1.154.937,28	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**159.531,60**	
		Unit Price (TRY)			**1.443.671,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1406						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1406	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.062.464,00	1.062.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	139	165,00		22.935,00
10.100.1081	Master electrician	h	139	250,00		34.750,00
10.100.1083	Master electrician’s helper	h	139	185,00		25.715,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	27	687,95		18.574,65
19.100.1113	Mobile crane	h	27	1.079,77		29.153,79
				Total Excluding Profit (TRY)	1.062.464,00	145.828,44
				Material and Installation w/o Profit (TRY)	1.208.292,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**182.285,55**	
				Unit Price (TRY)	**1.510.365,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1407						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1407	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.097.512,00	1.097.512,00	
	Installation Components					
10.100.1062	Unskilled worker	h	157	165,00		25.905,00
10.100.1081	Master electrician	h	157	250,00		39.250,00
10.100.1083	Master electrician’s helper	h	157	185,00		29.045,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.097.512,00	164.031,60
				Material and Installation w/o Profit (TRY)	1.261.543,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**205.039,50**	
				Unit Price (TRY)	**1.576.929,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1408						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1408	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.130.896,00	1.130.896,00	
	Installation Components					
10.100.1062	Unskilled worker	h	175	165,00		28.875,00
10.100.1081	Master electrician	h	175	250,00		43.750,00
10.100.1083	Master electrician’s helper	h	175	185,00		32.375,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	33	687,95		22.702,35
19.100.1113	Mobile crane	h	33	1.079,77		35.632,41
				Total Excluding Profit (TRY)	1.130.896,00	182.234,76
				Material and Installation w/o Profit (TRY)	1.313.130,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.793,45**	
				Unit Price (TRY)	**1.641.413,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1409						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1409	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.182.792,00	1.182.792,00	
	Installation Components					
10.100.1062	Unskilled worker	h	193	165,00		31.845,00
10.100.1081	Master electrician	h	193	250,00		48.250,00
10.100.1083	Master electrician’s helper	h	193	185,00		35.705,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.182.792,00	200.437,92
				Material and Installation w/o Profit (TRY)	1.383.229,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.547,40**	
				Unit Price (TRY)	**1.729.037,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1410						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1410	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.237.808,00	1.237.808,00	
	Installation Components					
10.100.1062	Unskilled worker	h	211	165,00		34.815,00
10.100.1081	Master electrician	h	211	250,00		52.750,00
10.100.1083	Master electrician’s helper	h	211	185,00		39.035,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	39	687,95		26.830,05
19.100.1113	Mobile crane	h	39	1.079,77		42.111,03
				Total Excluding Profit (TRY)	1.237.808,00	218.641,08
				Material and Installation w/o Profit (TRY)	1.456.449,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**273.301,35**	
				Unit Price (TRY)	**1.820.561,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1411						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1411	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.293.240,00	1.293.240,00	
	Installation Components					
10.100.1062	Unskilled worker	h	229	165,00		37.785,00
10.100.1081	Master electrician	h	229	250,00		57.250,00
10.100.1083	Master electrician’s helper	h	229	185,00		42.365,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	42	687,95		28.893,90
19.100.1113	Mobile crane	h	42	1.079,77		45.350,34
		Total Excluding Profit (TRY)			1.293.240,00	236.844,24
		Material and Installation w/o Profit (TRY)			1.530.084,24	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**296.055,30**	
		Unit Price (TRY)			**1.912.605,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1412						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1412	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.348.776,00	1.348.776,00	
	Installation Components					
10.100.1062	Unskilled worker	h	247	165,00		40.755,00
10.100.1081	Master electrician	h	247	250,00		61.750,00
10.100.1083	Master electrician’s helper	h	247	185,00		45.695,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	45	687,95		30.957,75
19.100.1113	Mobile crane	h	45	1.079,77		48.589,65
				Total Excluding Profit (TRY)	1.348.776,00	255.047,40
				Material and Installation w/o Profit (TRY)	1.603.823,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**318.809,25**	
				Unit Price (TRY)	**2.004.779,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1413						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1413	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.404.208,00	1.404.208,00	
	Installation Components					
10.100.1062	Unskilled worker	h	265	165,00		43.725,00
10.100.1081	Master electrician	h	265	250,00		66.250,00
10.100.1083	Master electrician’s helper	h	265	185,00		49.025,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
				Total Excluding Profit (TRY)	1.404.208,00	273.250,56
				Material and Installation w/o Profit (TRY)	1.677.458,56	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**341.563,20**	
				Unit Price (TRY)	**2.096.823,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1414						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1414	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1250 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.459.224,00	1.459.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	283	165,00		46.695,00
10.100.1081	Master electrician	h	283	250,00		70.750,00
10.100.1083	Master electrician’s helper	h	283	185,00		52.355,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	51	687,95		35.085,45
19.100.1113	Mobile crane	h	51	1.079,77		55.068,27
				Total Excluding Profit (TRY)	1.459.224,00	291.453,72
				Material and Installation w/o Profit (TRY)	1.750.677,72	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**364.317,15**	
				Unit Price (TRY)	**2.188.347,15**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1501						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1501	2 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	954.137,60	954.137,60	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician’s helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
		Total Excluding Profit (TRY)			954.137,60	56.612,64
		Material and Installation w/o Profit (TRY)			1.010.750,24	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**70.765,80**	
		Unit Price (TRY)			**1.263.437,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1502						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1502	3 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	999.076,00	999.076,00	
	Installation Components					
10.100.1062	Unskilled worker	h	71	165,00		11.715,00
10.100.1081	Master electrician	h	71	250,00		17.750,00
10.100.1083	Master electrician’s helper	h	71	185,00		13.135,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
		Total Excluding Profit (TRY)			999.076,00	75.415,80
		Material and Installation w/o Profit (TRY)			1.074.491,80	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**94.269,75**	
		Unit Price (TRY)			**1.343.114,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1503						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1503	4 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.039.168,00	1.039.168,00	
	Installation Components					
10.100.1062	Unskilled worker	h	90	165,00		14.850,00
10.100.1081	Master electrician	h	90	250,00		22.500,00
10.100.1083	Master electrician’s helper	h	90	185,00		16.650,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	18	687,95		12.383,10
19.100.1113	Mobile crane	h	18	1.079,77		19.435,86
		Total Excluding Profit (TRY)			1.039.168,00	94.218,96
		Material and Installation w/o Profit (TRY)			1.133.386,96	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**117.773,70**	
		Unit Price (TRY)			**1.416.733,70**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1504						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1504	5 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.078.136,80	1.078.136,80	
	Installation Components					
10.100.1062	Unskilled worker	h	109	165,00		17.985,00
10.100.1081	Master electrician	h	109	250,00		27.250,00
10.100.1083	Master electrician’s helper	h	109	185,00		20.165,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	21	687,95		14.446,95
19.100.1113	Mobile crane	h	21	1.079,77		22.675,17
		Total Excluding Profit (TRY)			1.078.136,80	113.022,12
		Material and Installation w/o Profit (TRY)			1.191.158,92	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**141.277,65**	
		Unit Price (TRY)			**1.488.948,65**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1505						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1505	6 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.116.960,00	1.116.960,00	
	Installation Components					
10.100.1062	Unskilled worker	h	128	165,00		21.120,00
10.100.1081	Master electrician	h	128	250,00		32.000,00
10.100.1083	Master electrician’s helper	h	128	185,00		23.680,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	24	687,95		16.510,80
19.100.1113	Mobile crane	h	24	1.079,77		25.914,48
				Total Excluding Profit (TRY)	1.116.960,00	131.825,28
				Material and Installation w/o Profit (TRY)	1.248.785,28	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**164.781,60**	
				Unit Price (TRY)	**1.560.981,60**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1506						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1506	7 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.155.024,00	1.155.024,00	
	Installation Components					
10.100.1062	Unskilled worker	h	147	165,00		24.255,00
10.100.1081	Master electrician	h	147	250,00		36.750,00
10.100.1083	Master electrician’s helper	h	147	185,00		27.195,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	27	687,95		18.574,65
19.100.1113	Mobile crane	h	27	1.079,77		29.153,79
				Total Excluding Profit (TRY)	1.155.024,00	150.628,44
				Material and Installation w/o Profit (TRY)	1.305.652,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**188.285,55**	
				Unit Price (TRY)	**1.632.065,55**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1507						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1507	8 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.193.712,00	1.193.712,00	
	Installation Components					
10.100.1062	Unskilled worker	h	166	165,00		27.390,00
10.100.1081	Master electrician	h	166	250,00		41.500,00
10.100.1083	Master electrician’s helper	h	166	185,00		30.710,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	30	687,95		20.638,50
19.100.1113	Mobile crane	h	30	1.079,77		32.393,10
				Total Excluding Profit (TRY)	1.193.712,00	169.431,60
				Material and Installation w/o Profit (TRY)	1.363.143,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**211.789,50**	
				Unit Price (TRY)	**1.703.929,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1508						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1508	9 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.230.840,00	1.230.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	185	165,00		30.525,00
10.100.1081	Master electrician	h	185	250,00		46.250,00
10.100.1083	Master electrician’s helper	h	185	185,00		34.225,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	33	687,95		22.702,35
19.100.1113	Mobile crane	h	33	1.079,77		35.632,41
				Total Excluding Profit (TRY)	1.230.840,00	188.234,76
				Material and Installation w/o Profit (TRY)	1.419.074,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**235.293,45**	
				Unit Price (TRY)	**1.773.843,45**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1509						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1509	10 stops and 1.00 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.285.232,00	1.285.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	36	687,95		24.766,20
19.100.1113	Mobile crane	h	36	1.079,77		38.871,72
				Total Excluding Profit (TRY)	1.285.232,00	207.037,92
				Material and Installation w/o Profit (TRY)	1.492.269,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**258.797,40**	
				Unit Price (TRY)	**1.865.337,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1510						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1510	11 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.346.800,00	1.346.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	223	165,00		36.795,00
10.100.1081	Master electrician	h	223	250,00		55.750,00
10.100.1083	Master electrician’s helper	h	223	185,00		41.255,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	39	687,95		26.830,05
19.100.1113	Mobile crane	h	39	1.079,77		42.111,03
				Total Excluding Profit (TRY)	1.346.800,00	225.841,08
				Material and Installation w/o Profit (TRY)	1.572.641,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**282.301,35**	
				Unit Price (TRY)	**1.965.801,35**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1511						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1511	12 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.408.264,00	1.408.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	242	165,00		39.930,00
10.100.1081	Master electrician	h	242	250,00		60.500,00
10.100.1083	Master electrician’s helper	h	242	185,00		44.770,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	42	687,95		28.893,90
19.100.1113	Mobile crane	h	42	1.079,77		45.350,34
				Total Excluding Profit (TRY)	1.408.264,00	244.644,24
				Material and Installation w/o Profit (TRY)	1.652.908,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**305.805,30**	
				Unit Price (TRY)	**2.066.135,30**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1512						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1512	13 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.468.480,00	1.468.480,00	
	Installation Components					
10.100.1062	Unskilled worker	h	261	165,00		43.065,00
10.100.1081	Master electrician	h	261	250,00		65.250,00
10.100.1083	Master electrician’s helper	h	261	185,00		48.285,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	45	687,95		30.957,75
19.100.1113	Mobile crane	h	45	1.079,77		48.589,65
				Total Excluding Profit (TRY)	1.468.480,00	263.447,40
				Material and Installation w/o Profit (TRY)	1.731.927,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**329.309,25**	
				Unit Price (TRY)	**2.164.909,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.720.1513						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1513	14 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.529.736,00	1.529.736,00	
	Installation Components					
10.100.1062	Unskilled worker	h	280	165,00		46.200,00
10.100.1081	Master electrician	h	280	250,00		70.000,00
10.100.1083	Master electrician’s helper	h	280	185,00		51.800,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	48	687,95		33.021,60
19.100.1113	Mobile crane	h	48	1.079,77		51.828,96
		Total Excluding Profit (TRY)			1.529.736,00	282.250,56
		Material and Installation w/o Profit (TRY)			1.811.986,56	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**352.813,20**	
		Unit Price (TRY)			**2.264.983,20**	

Item No	Analysis Name					UoM
35.720.1514						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.720.1514	15 stops and 1.60 m/s speed / Class I elevators (The elevators designed for carrying passengers). Class II elevators (The elevators designed principally to carry passengers, and to carry other objects when necessary). Without engine room, Variable-speed, Rated capacity: 1600 kg / ELEVATOR INSTALLATION WITHOUT MACHINE ROOM (Market price)	Qty	1	1.588.184,00	1.588.184,00	
	Installation Components					
10.100.1062	Unskilled worker	h	299	165,00		49.335,00
10.100.1081	Master electrician	h	299	250,00		74.750,00
10.100.1083	Master electrician's helper	h	299	185,00		55.315,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	51	687,95		35.085,45
19.100.1113	Mobile crane	h	51	1.079,77		55.068,27
				Total Excluding Profit (TRY)	1.588.184,00	301.053,72
				Material and Installation w/o Profit (TRY)	1.889.237,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**376.317,15**	
				Unit Price (TRY)	**2.361.547,15**	

Item No	Analysis Name					UoM
35.725.1101	**2 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1101	2 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	131.840,80	131.840,80	
	Installation Components					
10.100.1062	Unskilled worker	h	22	165,00		3.630,00
10.100.1081	Master electrician	h	22	250,00		5.500,00
10.100.1083	Master electrician's helper	h	22	185,00		4.070,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	4	687,95		2.751,80
19.100.1113	Mobile crane	h	4	1.079,77		4.319,08
				Total Excluding Profit (TRY)	131.840,80	24.470,88
				Material and Installation w/o Profit (TRY)	156.311,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**30.588,60**	
				Unit Price (TRY)	**195.389,60**	

Item No	Analysis Name					UoM
35.725.1102	**3 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1102	3 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	136.905,60	136.905,60	
	Installation Components					
10.100.1062	Unskilled worker	h	30	165,00		4.950,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician’s helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	5	687,95		3.439,75
19.100.1113	Mobile crane	h	5	1.079,77		5.398,85
				Total Excluding Profit (TRY)	136.905,60	33.138,60
				Material and Installation w/o Profit (TRY)	170.044,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**41.423,25**	
				Unit Price (TRY)	**212.555,25**	

Item No	Analysis Name					UoM
35.725.1103	**4 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1103	4 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	144.300,00	144.300,00	
	Installation Components					
10.100.1062	Unskilled worker	h	38	165,00		6.270,00
10.100.1081	Master electrician	h	38	250,00		9.500,00
10.100.1083	Master electrician’s helper	h	38	185,00		7.030,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	6	687,95		4.127,70
19.100.1113	Mobile crane	h	6	1.079,77		6.478,62
				Total Excluding Profit (TRY)	144.300,00	41.806,32
				Material and Installation w/o Profit (TRY)	186.106,32	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**52.257,90**	
				Unit Price (TRY)	**232.632,90**	

Item No	Analysis Name					UoM
35.725.1104	**5 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1104	5 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	151.299,20	151.299,20	
	Installation Components					
10.100.1062	Unskilled worker	h	46	165,00		7.590,00
10.100.1081	Master electrician	h	46	250,00		11.500,00
10.100.1083	Master electrician’s helper	h	46	185,00		8.510,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	7	687,95		4.815,65
19.100.1113	Mobile crane	h	7	1.079,77		7.558,39
				Total Excluding Profit (TRY)	151.299,20	50.474,04
				Material and Installation w/o Profit (TRY)	201.773,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**63.092,55**	
				Unit Price (TRY)	**252.216,55**	

Item No	Analysis Name					UoM
35.725.1105	**6 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1105	6 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	158.392,00	158.392,00	
	Installation Components					
10.100.1062	Unskilled worker	h	54	165,00		8.910,00
10.100.1081	Master electrician	h	54	250,00		13.500,00
10.100.1083	Master electrician’s helper	h	54	185,00		9.990,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	158.392,00	59.141,76
				Material and Installation w/o Profit (TRY)	217.533,76	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**73.927,20**	
				Unit Price (TRY)	**271.917,20**	

Item No	Analysis Name					UoM
35.725.1106	**7 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1106	7 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	164.465,60	164.465,60	
	Installation Components					
10.100.1062	Unskilled worker	h	62	165,00		10.230,00
10.100.1081	Master electrician	h	62	250,00		15.500,00
10.100.1083	Master electrician’s helper	h	62	185,00		11.470,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	164.465,60	67.809,48
				Material and Installation w/o Profit (TRY)	232.275,08	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**84.761,85**	
				Unit Price (TRY)	**290.343,85**	

Item No	Analysis Name					UoM
35.725.1107	**8 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1107	8 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	171.048,80	171.048,80	
	Installation Components					
10.100.1062	Unskilled worker	h	70	165,00		11.550,00
10.100.1081	Master electrician	h	70	250,00		17.500,00
10.100.1083	Master electrician’s helper	h	70	185,00		12.950,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	171.048,80	76.477,20
				Material and Installation w/o Profit (TRY)	247.526,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**95.596,50**	
				Unit Price (TRY)	**309.407,50**	

Item No	Analysis Name					UoM
35.725.1108	**9 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1108	9 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	180.658,40	180.658,40	
	Installation Components					
10.100.1062	Unskilled worker	h	78	165,00		12.870,00
10.100.1081	Master electrician	h	78	250,00		19.500,00
10.100.1083	Master electrician's helper	h	78	185,00		14.430,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	11	687,95		7.567,45
19.100.1113	Mobile crane	h	11	1.079,77		11.877,47
				Total Excluding Profit (TRY)	180.658,40	85.144,92
				Material and Installation w/o Profit (TRY)	265.803,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**106.431,15**	
				Unit Price (TRY)	**332.254,15**	

Item No	Analysis Name					UoM
35.725.1109	**10 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1109	10 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	193.377,60	193.377,60	
	Installation Components					
10.100.1062	Unskilled worker	h	86	165,00		14.190,00
10.100.1081	Master electrician	h	86	250,00		21.500,00
10.100.1083	Master electrician's helper	h	86	185,00		15.910,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	193.377,60	93.812,64
				Material and Installation w/o Profit (TRY)	287.190,24	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**117.265,80**	
				Unit Price (TRY)	**358.987,80**	

Item No	Analysis Name					UoM
35.725.1110	**11 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1110	11 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	204.921,60	204.921,60	
	Installation Components					
10.100.1062	Unskilled worker	h	94	165,00		15.510,00
10.100.1081	Master electrician	h	94	250,00		23.500,00
10.100.1083	Master electrician’s helper	h	94	185,00		17.390,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	13	687,95		8.943,35
19.100.1113	Mobile crane	h	13	1.079,77		14.037,01
				Total Excluding Profit (TRY)	204.921,60	102.480,36
				Material and Installation w/o Profit (TRY)	307.401,96	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**128.100,45**	
				Unit Price (TRY)	**384.252,45**	

Item No	Analysis Name					UoM
35.725.1111	**12 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1111	12 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	218.753,60	218.753,60	
	Installation Components					
10.100.1062	Unskilled worker	h	102	165,00		16.830,00
10.100.1081	Master electrician	h	102	250,00		25.500,00
10.100.1083	Master electrician’s helper	h	102	185,00		18.870,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	218.753,60	111.148,08
				Material and Installation w/o Profit (TRY)	329.901,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**138.935,10**	
				Unit Price (TRY)	**412.377,10**	

Item No	Analysis Name					UoM
35.725.1112	**13 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1112	13 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	234.956,80	234.956,80	
	Installation Components					
10.100.1062	Unskilled worker	h	110	165,00		18.150,00
10.100.1081	Master electrician	h	110	250,00		27.500,00
10.100.1083	Master electrician's helper	h	110	185,00		20.350,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
				Total Excluding Profit (TRY)	234.956,80	119.815,80
				Material and Installation w/o Profit (TRY)	354.772,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**149.769,75**	
				Unit Price (TRY)	**443.465,75**	

Item No	Analysis Name					UoM
35.725.1113	**14 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1113	14 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	249.090,40	249.090,40	
	Installation Components					
10.100.1062	Unskilled worker	h	118	165,00		19.470,00
10.100.1081	Master electrician	h	118	250,00		29.500,00
10.100.1083	Master electrician's helper	h	118	185,00		21.830,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	249.090,40	128.483,52
				Material and Installation w/o Profit (TRY)	377.573,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**160.604,40**	
				Unit Price (TRY)	**471.967,40**	

Item No	Analysis Name					UoM
35.725.1114	**15 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects). Single-speed.**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1114	15 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). Single-speed. (Market price)	Qty	1	264.867,20	264.867,20	
	Installation Components					
10.100.1062	Unskilled worker	h	126	165,00		20.790,00
10.100.1081	Master electrician	h	126	250,00		31.500,00
10.100.1083	Master electrician’s helper	h	126	185,00		23.310,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	17	687,95		11.695,15
19.100.1113	Mobile crane	h	17	1.079,77		18.356,09
				Total Excluding Profit (TRY)	264.867,20	137.151,24
				Material and Installation w/o Profit (TRY)	402.018,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**171.439,05**	
				Unit Price (TRY)	**502.523,05**	

Item No	Analysis Name					UoM
35.725.1201	**2 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1201	2 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	223.017,60	223.017,60	
	Installation Components					
10.100.1062	Unskilled worker	h	30	165,00		4.950,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician’s helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1112	Forklift	h	4	687,95		2.751,80
19.100.1113	Mobile crane	h	4	1.079,77		4.319,08
				Total Excluding Profit (TRY)	223.017,60	29.270,88
				Material and Installation w/o Profit (TRY)	252.288,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**36.588,60**	
				Unit Price (TRY)	**315.360,60**	

Item No	Analysis Name					UoM
35.725.1202	**3 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1202	3 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	232.065,60	232.065,60	
	Installation Components					
10.100.1062	Unskilled worker	h	41	165,00		6.765,00
10.100.1081	Master electrician	h	41	250,00		10.250,00
10.100.1083	Master electrician’s helper	h	41	185,00		7.585,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1112	Forklift	h	5	687,95		3.439,75
19.100.1113	Mobile crane	h	5	1.079,77		5.398,85
				Total Excluding Profit (TRY)	232.065,60	39.738,60
				Material and Installation w/o Profit (TRY)	271.804,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**49.673,25**	
				Unit Price (TRY)	**339.755,25**	

Item No	Analysis Name					UoM
35.725.1203	**4 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1203	4 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	242.340,80	242.340,80	
	Installation Components					
10.100.1062	Unskilled worker	h	52	165,00		8.580,00
10.100.1081	Master electrician	h	52	250,00		13.000,00
10.100.1083	Master electrician’s helper	h	52	185,00		9.620,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1112	Forklift	h	6	687,95		4.127,70
19.100.1113	Mobile crane	h	6	1.079,77		6.478,62
				Total Excluding Profit (TRY)	242.340,80	50.206,32
				Material and Installation w/o Profit (TRY)	292.547,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**62.757,90**	
				Unit Price (TRY)	**365.683,90**	

Item No	Analysis Name					UoM
35.725.1204	**5 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1204	5 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	247.811,20	247.811,20	
	Installation Components					
10.100.1062	Unskilled worker	h	63	165,00		10.395,00
10.100.1081	Master electrician	h	63	250,00		15.750,00
10.100.1083	Master electrician’s helper	h	63	185,00		11.655,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1112	Forklift	h	7	687,95		4.815,65
19.100.1113	Mobile crane	h	7	1.079,77		7.558,39
				Total Excluding Profit (TRY)	247.811,20	60.674,04
				Material and Installation w/o Profit (TRY)	308.485,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**75.842,55**	
				Unit Price (TRY)	**385.606,55**	

Item No	Analysis Name					UoM
35.725.1205	**6 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1205	6 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	257.722,40	257.722,40	
	Installation Components					
10.100.1062	Unskilled worker	h	74	165,00		12.210,00
10.100.1081	Master electrician	h	74	250,00		18.500,00
10.100.1083	Master electrician’s helper	h	74	185,00		13.690,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	257.722,40	71.141,76
				Material and Installation w/o Profit (TRY)	328.864,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**88.927,20**	
				Unit Price (TRY)	**411.080,20**	

Item No	Analysis Name					UoM
35.725.1206	**7 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1206	7 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	268.788,00	268.788,00	
	Installation Components					
10.100.1062	Unskilled worker	h	85	165,00		14.025,00
10.100.1081	Master electrician	h	85	250,00		21.250,00
10.100.1083	Master electrician’s helper	h	85	185,00		15.725,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	21	700,00		14.700,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	268.788,00	81.609,48
				Material and Installation w/o Profit (TRY)	350.397,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**102.011,85**	
				Unit Price (TRY)	**437.996,85**	

Item No	Analysis Name					UoM
35.725.1207	**8 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1207	8 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	290.960,80	290.960,80	
	Installation Components					
10.100.1062	Unskilled worker	h	96	165,00		15.840,00
10.100.1081	Master electrician	h	96	250,00		24.000,00
10.100.1083	Master electrician’s helper	h	96	185,00		17.760,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	24	700,00		16.800,00
19.100.1112	Forklift	h	10	687,95		6.879,50
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	290.960,80	92.077,20
				Material and Installation w/o Profit (TRY)	383.038,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**115.096,50**	
				Unit Price (TRY)	**478.797,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.725.1208	**9 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1208	9 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	294.091,20	294.091,20	
	Installation Components					
10.100.1062	Unskilled worker	h	107	165,00		17.655,00
10.100.1081	Master electrician	h	107	250,00		26.750,00
10.100.1083	Master electrician’s helper	h	107	185,00		19.795,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	27	700,00		18.900,00
19.100.1112	Forklift	h	11	687,95		7.567,45
19.100.1113	Mobile crane	h	11	1.079,77		11.877,47
				Total Excluding Profit (TRY)	294.091,20	102.544,92
				Material and Installation w/o Profit (TRY)	396.636,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**128.181,15**	
				Unit Price (TRY)	**495.795,15**	

Item No	Analysis Name					UoM
35.725.1209	**10 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1209	10 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	307.288,80	307.288,80	
	Installation Components					
10.100.1062	Unskilled worker	h	118	165,00		19.470,00
10.100.1081	Master electrician	h	118	250,00		29.500,00
10.100.1083	Master electrician’s helper	h	118	185,00		21.830,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	30	700,00		21.000,00
19.100.1112	Forklift	h	12	687,95		8.255,40
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	307.288,80	113.012,64
				Material and Installation w/o Profit (TRY)	420.301,44	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**141.265,80**	
				Unit Price (TRY)	**525.376,80**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.725.1210	**11 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1210	11 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	325.832,00	325.832,00	
	Installation Components					
10.100.1062	Unskilled worker	h	129	165,00		21.285,00
10.100.1081	Master electrician	h	129	250,00		32.250,00
10.100.1083	Master electrician’s helper	h	129	185,00		23.865,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	33	700,00		23.100,00
19.100.1112	Forklift	h	13	687,95		8.943,35
19.100.1113	Mobile crane	h	13	1.079,77		14.037,01
				Total Excluding Profit (TRY)	325.832,00	123.480,36
				Material and Installation w/o Profit (TRY)	449.312,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**154.350,45**	
				Unit Price (TRY)	**561.640,45**	

Item No	Analysis Name					UoM
35.725.1211	**12 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1211	12 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	340.225,60	340.225,60	
	Installation Components					
10.100.1062	Unskilled worker	h	140	165,00		23.100,00
10.100.1081	Master electrician	h	140	250,00		35.000,00
10.100.1083	Master electrician’s helper	h	140	185,00		25.900,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	36	700,00		25.200,00
19.100.1112	Forklift	h	14	687,95		9.631,30
19.100.1113	Mobile crane	h	14	1.079,77		15.116,78
				Total Excluding Profit (TRY)	340.225,60	133.948,08
				Material and Installation w/o Profit (TRY)	474.173,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**167.435,10**	
				Unit Price (TRY)	**592.717,10**	

Item No	Analysis Name					UoM
35.725.1212	**13 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1212	13 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	351.436,80	351.436,80	
	Installation Components					
10.100.1062	Unskilled worker	h	151	165,00		24.915,00
10.100.1081	Master electrician	h	151	250,00		37.750,00
10.100.1083	Master electrician’s helper	h	151	185,00		27.935,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	39	700,00		27.300,00
19.100.1112	Forklift	h	15	687,95		10.319,25
19.100.1113	Mobile crane	h	15	1.079,77		16.196,55
				Total Excluding Profit (TRY)	351.436,80	144.415,80
				Material and Installation w/o Profit (TRY)	495.852,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**180.519,75**	
				Unit Price (TRY)	**619.815,75**	

Item No	Analysis Name					UoM
35.725.1213	**14 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1213	14 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	365.622,40	365.622,40	
	Installation Components					
10.100.1062	Unskilled worker	h	162	165,00		26.730,00
10.100.1081	Master electrician	h	162	250,00		40.500,00
10.100.1083	Master electrician’s helper	h	162	185,00		29.970,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	16	687,95		11.007,20
19.100.1113	Mobile crane	h	16	1.079,77		17.276,32
				Total Excluding Profit (TRY)	365.622,40	154.883,52
				Material and Installation w/o Profit (TRY)	520.505,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.604,40**	
				Unit Price (TRY)	**650.632,40**	

Item No	Analysis Name					UoM
35.725.1214	**15 Stops / Class V Lift (Lifts sized too small for passengers, and designed to lift small objects).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.1214	15 Stops / Class V Elevator (Elevators sized too small for passengers, and designed to elevator small objects). (Market price)	Qty	1	379.548,00	379.548,00	
	Installation Components					
10.100.1062	Unskilled worker	h	173	165,00		28.545,00
10.100.1081	Master electrician	h	173	250,00		43.250,00
10.100.1083	Master electrician’s helper	h	173	185,00		32.005,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	45	700,00		31.500,00
19.100.1112	Forklift	h	17	687,95		11.695,15
19.100.1113	Mobile crane	h	17	1.079,77		18.356,09
				Total Excluding Profit (TRY)	379.548,00	165.351,24
				Material and Installation w/o Profit (TRY)	544.899,24	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**206.689,05**	
				Unit Price (TRY)	**681.124,05**	

Item No	Analysis Name					UoM
35.725.2001	**4 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2001	4 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	18.085,60	18.085,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	18.085,60	3.835,00
				Material and Installation w/o Profit (TRY)	21.920,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**4.793,75**	
				Unit Price (TRY)	**27.400,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.725.2002	**5 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2002	5 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	18.834,40	18.834,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
				Total Excluding Profit (TRY)	18.834,40	4.535,00
				Material and Installation w/o Profit (TRY)	23.369,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**5.668,75**	
				Unit Price (TRY)	**29.211,75**	

Item No	Analysis Name					UoM
35.725.2003	**6 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2003	6 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	20.134,40	20.134,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
				Total Excluding Profit (TRY)	20.134,40	5.235,00
				Material and Installation w/o Profit (TRY)	25.369,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**6.543,75**	
				Unit Price (TRY)	**31.711,75**	

Item No	Analysis Name					UoM
35.725.2004	**7 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2004	7 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	21.122,40	21.122,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
				Total Excluding Profit (TRY)	21.122,40	5.935,00
				Material and Installation w/o Profit (TRY)	27.057,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.418,75**	
				Unit Price (TRY)	**33.821,75**	

Item No	Analysis Name					UoM
35.725.2005	**8 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2005	8 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	21.684,00	21.684,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
				Total Excluding Profit (TRY)	21.684,00	6.635,00
				Material and Installation w/o Profit (TRY)	28.319,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**8.293,75**	
				Unit Price (TRY)	**35.398,75**	

Item No	Analysis Name					UoM
35.725.2006	**9 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2006	9 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	22.599,20	22.599,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
				Total Excluding Profit (TRY)	22.599,20	7.335,00
				Material and Installation w/o Profit (TRY)	29.934,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**9.168,75**	
				Unit Price (TRY)	**37.417,75**	

Item No	Analysis Name					UoM
35.725.2007	**10 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2007	10 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	22.838,40	22.838,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
				Total Excluding Profit (TRY)	22.838,40	8.035,00
				Material and Installation w/o Profit (TRY)	30.873,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**10.043,75**	
				Unit Price (TRY)	**38.591,75**	

Item No	Analysis Name					UoM
35.725.2008	**11 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2008	11 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	23.545,60	23.545,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	11	700,00		7.700,00
				Total Excluding Profit (TRY)	23.545,60	8.735,00
				Material and Installation w/o Profit (TRY)	32.280,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**10.918,75**	
				Unit Price (TRY)	**40.350,75**	

Item No	Analysis Name					UoM
35.725.2009	**12 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2009	12 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	23.795,20	23.795,20	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
				Total Excluding Profit (TRY)	23.795,20	9.435,00
				Material and Installation w/o Profit (TRY)	33.230,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**11.793,75**	
				Unit Price (TRY)	**41.537,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.725.2010	**13 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2010	13 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	25.022,40	25.022,40	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	13	700,00		9.100,00
				Total Excluding Profit (TRY)	25.022,40	10.135,00
				Material and Installation w/o Profit (TRY)	35.157,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**12.668,75**	
				Unit Price (TRY)	**43.946,75**	

Item No	Analysis Name					UoM
35.725.2011	**14 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2011	14 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	25.324,00	25.324,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
				Total Excluding Profit (TRY)	25.324,00	10.835,00
				Material and Installation w/o Profit (TRY)	36.159,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**13.543,75**	
				Unit Price (TRY)	**45.198,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.725.2012	**15 stops / Control Equipment Group (Collective System)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2012	15 stops / Control Equipment Group (Collective System) (Market price)	Qty	1	25.833,60	25.833,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
				Total Excluding Profit (TRY)	25.833,60	11.535,00
				Material and Installation w/o Profit (TRY)	37.368,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**14.418,75**	
				Unit Price (TRY)	**46.710,75**	

Item No	Analysis Name					UoM
35.725.2100	**PRICE DIFFERENCE FOR DUAL-ENTRANCE CARRIAGES,**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2100	PRICE DIFFERENCE FOR DUAL-ENTRANCE CARRIAGES / ELEVATOR INSTALLATION (Market price)	Qty	1	9.318,40	9.318,40	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician's helper	h	6	185,00		1.110,00
				Total Excluding Profit (TRY)	9.318,40	3.105,00
				Material and Installation w/o Profit (TRY)	12.423,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**3.881,25**	
				Unit Price (TRY)	**15.529,25**	

Item No	Analysis Name					UoM
35.725.2201	**Passenger lifts / ADDITIONAL FULLY AUTOMATIC CARRIAGE DOORS**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2201	Passenger elevators / ADDITIONAL FULLY AUTOMATIC CARRIAGE DOORS / ELEVATOR INSTALLATION (Market price)	Qty	1	38.688,00	38.688,00	
	Installation Components					
10.100.1062	Unskilled worker	h	3,4	165,00		561,00
10.100.1081	Master electrician	h	3,4	250,00		850,00
10.100.1083	Master electrician’s helper	h	3,4	185,00		629,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	38.688,00	2.108,80
				Material and Installation w/o Profit (TRY)	40.796,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.636,00**	
				Unit Price (TRY)	**50.996,00**	

Item No	Analysis Name					UoM
35.725.2202	**Passenger and freight lifts / ADDITIONAL FULLY AUTOMATIC CARRIAGE DOORS**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2202	Passenger and freight elevators / ADDITIONAL FULLY AUTOMATIC CARRIAGE DOORS / ELEVATOR INSTALLATION (Market price)	Qty	1	47.840,00	47.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	4,14	165,00		683,10
10.100.1081	Master electrician	h	4,14	250,00		1.035,00
10.100.1083	Master electrician’s helper	h	4,14	185,00		765,90
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	47.840,00	2.552,80
				Material and Installation w/o Profit (TRY)	50.392,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.191,00**	
				Unit Price (TRY)	**62.991,00**	

Item No	Analysis Name					UoM
35.725.2251	**For passenger lifts / ADDITIONAL FULLY AUTOMATIC FLOOR DOORS**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2251	For passenger elevators / ADDITIONAL FULLY AUTOMATIC FLOOR DOORS / ELEVATOR INSTALLATION (Market price)	Qty	1	22.193,60	22.193,60	
	Installation Components					
10.100.1062	Unskilled worker	h	3,4	165,00		561,00
10.100.1081	Master electrician	h	3,4	250,00		850,00
10.100.1083	Master electrician’s helper	h	3,4	185,00		629,00
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	22.193,60	2.108,80
				Material and Installation w/o Profit (TRY)	24.302,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.636,00**	
				Unit Price (TRY)	**30.378,00**	

Item No	Analysis Name					UoM
35.725.2252	**For patient and freight lifts / ADDITIONAL FULLY AUTOMATIC FLOOR DOORS**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2252	For patient and freight elevators / ADDITIONAL FULLY AUTOMATIC FLOOR DOORS / ELEVATOR INSTALLATION (Market price)	Qty	1	29.036,80	29.036,80	
	Installation Components					
10.100.1062	Unskilled worker	h	4,14	165,00		683,10
10.100.1081	Master electrician	h	4,14	250,00		1.035,00
10.100.1083	Master electrician’s helper	h	4,14	185,00		765,90
19.100.1112	Forklift	h	0,1	687,95		68,80
				Total Excluding Profit (TRY)	29.036,80	2.552,80
				Material and Installation w/o Profit (TRY)	31.589,60	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**3.191,00**	
				Unit Price (TRY)	**39.487,00**	

Item No	Analysis Name					UoM
35.725.2302	**For service lifts / Additional Landing Doors,**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2302	For service elevators / Additional Landing Doors / ELEVATOR INSTALLATION (Market price)	Qty	1	1.063,92	1.063,92	
	Installation Components					
10.100.1062	Unskilled worker	h	2,5	165,00		412,50
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
19.100.1112	Forklift	h	0,1	687,95		68,80
		Total Excluding Profit (TRY)			1.063,92	1.568,80
		Material and Installation w/o Profit (TRY)			2.632,72	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.961,00**	
		Unit Price (TRY)			**3.290,90**	

Item No	Analysis Name					UoM
35.725.2410	**For variable-speed passenger lifts**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2410	For variable-speed passenger elevators / Price Difference for Floor Height / ELEVATOR INSTALLATION (Market price)	m	1	1.171,04	1.171,04	
	Installation Components					
10.100.1062	Unskilled worker	h	3	165,00		495,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
		Total Excluding Profit (TRY)			1.171,04	1.800,00
		Material and Installation w/o Profit (TRY)			2.971,04	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.250,00**	
		Unit Price (TRY)			**3.713,80**	

Item No	Analysis Name					UoM
35.725.2420	**For patient and freight lifts / Price Difference for Floor Height**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2420	For patient and freight elevators / Price Difference for Floor Height / ELEVATOR INSTALLATION (Market price)	m	1	1.285,44	1.285,44	
	Installation Components					
10.100.1062	Unskilled worker	h	3,92	165,00		646,80
10.100.1081	Master electrician	h	3,92	250,00		980,00
10.100.1083	Master electrician’s helper	h	3,92	185,00		725,20
		Total Excluding Profit (TRY)			1.285,44	2.352,00
		Material and Installation w/o Profit (TRY)			3.637,44	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.940,00**	
		Unit Price (TRY)			**4.546,80**	

Item No	Analysis Name					UoM
35.725.2430	**For service lifts / Price Difference for Floor Height**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.725.2430	For service elevators / Price Difference for Floor Height / ELEVATOR INSTALLATION (Market price)	m	1	341,12	341,12	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	1,5	250,00		375,00
10.100.1083	Master electrician’s helper	h	1,5	185,00		277,50
		Total Excluding Profit (TRY)			341,12	900,00
		Material and Installation w/o Profit (TRY)			1.241,12	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**1.125,00**	
		Unit Price (TRY)			**1.551,40**	

Item No	Analysis Name					UoM
35.730.1102	**H 3000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1102	H 3000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	1.920.360,00	1.920.360,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	1.920.360,00	139.909,48
				Material and Installation w/o Profit (TRY)	2.060.269,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**2.575.336,85**	

Item No	Analysis Name					UoM
35.730.1103	**H 3250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1103	H 3250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	1.972.568,00	1.972.568,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	1.972.568,00	143.709,48
				Material and Installation w/o Profit (TRY)	2.116.277,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**2.645.346,85**	

Item No	Analysis Name					UoM
35.730.1104	**H 3500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1104	H 3500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.005.640,00	2.005.640,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.005.640,00	147.509,48
				Material and Installation w/o Profit (TRY)	2.153.149,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**2.691.436,85**	

Item No	Analysis Name					UoM
35.730.1105	**H 3750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1105	H 3750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.058.056,00	2.058.056,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.058.056,00	151.309,48
				Material and Installation w/o Profit (TRY)	2.209.365,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**2.761.706,85**	

Item No	Analysis Name					UoM
35.730.1106	**H 4000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1106	H 4000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.094.976,00	2.094.976,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.094.976,00	155.109,48
				Material and Installation w/o Profit (TRY)	2.250.085,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**2.812.606,85**	

Item No	Analysis Name					UoM
35.730.1107	**H 4250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1107	H 4250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.146.248,00	2.146.248,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.146.248,00	158.909,48
				Material and Installation w/o Profit (TRY)	2.305.157,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**2.881.446,85**	

Item No	Analysis Name					UoM
35.730.1108	**H 4500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1108	H 4500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.180.672,00	2.180.672,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.180.672,00	162.709,48
				Material and Installation w/o Profit (TRY)	2.343.381,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**2.929.226,85**	

Item No	Analysis Name					UoM
35.730.1109	**H 4750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1109	H 4750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.251.184,00	2.251.184,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.251.184,00	166.509,48
				Material and Installation w/o Profit (TRY)	2.417.693,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**3.022.116,85**	

Item No	Analysis Name					UoM
35.730.1110	**H 5000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1110	H 5000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.285.712,00	2.285.712,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.285.712,00	170.309,48
				Material and Installation w/o Profit (TRY)	2.456.021,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**3.070.026,85**	

Item No	Analysis Name					UoM
35.730.1111	**H 5250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1111	H 5250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.337.920,00	2.337.920,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.337.920,00	174.109,48
				Material and Installation w/o Profit (TRY)	2.512.029,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**3.140.036,85**	

Item No	Analysis Name					UoM
35.730.1112	**H 5500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1112	H 5500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.377.024,00	2.377.024,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.377.024,00	177.909,48
				Material and Installation w/o Profit (TRY)	2.554.933,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**3.193.666,85**	

Item No	Analysis Name					UoM
35.730.1113	**H 5750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1113	H 5750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.427.464,00	2.427.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.427.464,00	181.709,48
				Material and Installation w/o Profit (TRY)	2.609.173,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**3.261.466,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1114	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1114	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.476.032,00	2.476.032,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.476.032,00	185.509,48
				Material and Installation w/o Profit (TRY)	2.661.541,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**3.326.926,85**	

Item No	Analysis Name					UoM
35.730.1115	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1115	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.564.224,00	2.564.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.564.224,00	189.309,48
				Material and Installation w/o Profit (TRY)	2.753.533,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**3.441.916,85**	

Item No	Analysis Name					UoM
35.730.1116	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1116	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.652.208,00	2.652.208,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.652.208,00	193.109,48
				Material and Installation w/o Profit (TRY)	2.845.317,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**3.556.646,85**	

Item No	Analysis Name					UoM
35.730.1117	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1117	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.739.464,00	2.739.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.739.464,00	196.909,48
				Material and Installation w/o Profit (TRY)	2.936.373,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**3.670.466,85**	

Item No	Analysis Name					UoM
35.730.1118	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1118	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.827.448,00	2.827.448,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.827.448,00	200.709,48
				Material and Installation w/o Profit (TRY)	3.028.157,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**3.785.196,85**	

Item No	Analysis Name					UoM
35.730.1119	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1119	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.915.432,00	2.915.432,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.915.432,00	204.509,48
				Material and Installation w/o Profit (TRY)	3.119.941,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**3.899.926,85**	

Item No	Analysis Name					UoM
35.730.1120	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1120	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.003.624,00	3.003.624,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.003.624,00	208.309,48
				Material and Installation w/o Profit (TRY)	3.211.933,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**4.014.916,85**	

Item No	Analysis Name					UoM
35.730.1121	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1121	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.091.712,00	3.091.712,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.091.712,00	212.109,48
				Material and Installation w/o Profit (TRY)	3.303.821,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**4.129.776,85**	

Item No	Analysis Name					UoM
35.730.1122	**H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1122	H 6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.179.904,00	3.179.904,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.179.904,00	215.909,48
				Material and Installation w/o Profit (TRY)	3.395.813,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**4.244.766,85**	

Item No	Analysis Name					UoM
35.730.1151	**H3000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1151	H3000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	1.922.440,00	1.922.440,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	1.922.440,00	139.909,48
				Material and Installation w/o Profit (TRY)	2.062.349,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**2.577.936,85**	

Item No	Analysis Name					UoM
35.730.1152	**H3250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1152	H3250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	1.982.864,00	1.982.864,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	1.982.864,00	143.709,48
				Material and Installation w/o Profit (TRY)	2.126.573,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**2.658.216,85**	

Item No	Analysis Name					UoM
35.730.1153	**H3500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1153	H3500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.020.512,00	2.020.512,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.020.512,00	147.509,48
				Material and Installation w/o Profit (TRY)	2.168.021,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**2.710.026,85**	

Item No	Analysis Name					UoM
35.730.1154	**H3750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1154	H3750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.071.472,00	2.071.472,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.071.472,00	151.309,48
				Material and Installation w/o Profit (TRY)	2.222.781,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**2.778.476,85**	

Item No	Analysis Name					UoM
35.730.1155	**H4000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1155	H4000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.254.720,00	2.254.720,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.254.720,00	155.109,48
				Material and Installation w/o Profit (TRY)	2.409.829,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**3.012.286,85**	

Item No	Analysis Name					UoM
35.730.1156	**H4250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1156	H4250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.309.424,00	2.309.424,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.309.424,00	158.909,48
				Material and Installation w/o Profit (TRY)	2.468.333,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**3.085.416,85**	

Item No	Analysis Name					UoM
35.730.1157	**H4500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1157	H4500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.346.760,00	2.346.760,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.346.760,00	162.709,48
				Material and Installation w/o Profit (TRY)	2.509.469,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**3.136.836,85**	

Item No	Analysis Name					UoM
35.730.1158	**H4750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1158	H4750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.424.656,00	2.424.656,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.424.656,00	166.509,48
				Material and Installation w/o Profit (TRY)	2.591.165,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**3.238.956,85**	

Item No	Analysis Name					UoM
35.730.1159	**H5000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1159	H5000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.462.720,00	2.462.720,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.462.720,00	170.309,48
				Material and Installation w/o Profit (TRY)	2.633.029,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**3.291.286,85**	

Item No	Analysis Name					UoM
35.730.1160	**H5250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1160	H5250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.469.688,00	2.469.688,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.469.688,00	174.109,48
				Material and Installation w/o Profit (TRY)	2.643.797,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**3.304.746,85**	

Item No	Analysis Name					UoM
35.730.1161	**H5500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1161	H5500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.509.936,00	2.509.936,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.509.936,00	177.909,48
				Material and Installation w/o Profit (TRY)	2.687.845,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**3.359.806,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1162	**H5750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1162	H5750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.560.272,00	2.560.272,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.560.272,00	181.709,48
				Material and Installation w/o Profit (TRY)	2.741.981,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**3.427.476,85**	

Item No	Analysis Name					UoM
35.730.1163	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1163	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.600.000,00	2.600.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.600.000,00	185.509,48
				Material and Installation w/o Profit (TRY)	2.785.509,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**3.481.886,85**	

Item No	Analysis Name					UoM
35.730.1164	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1164	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.688.192,00	2.688.192,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.688.192,00	189.309,48
				Material and Installation w/o Profit (TRY)	2.877.501,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**3.596.876,85**	

Item No	Analysis Name					UoM
35.730.1165	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1165	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.775.240,00	2.775.240,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.775.240,00	193.109,48
				Material and Installation w/o Profit (TRY)	2.968.349,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**3.710.436,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1166	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1166	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.863.744,00	2.863.744,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.863.744,00	196.909,48
				Material and Installation w/o Profit (TRY)	3.060.653,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**3.825.816,85**	

Item No	Analysis Name					UoM
35.730.1167	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1167	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.951.416,00	2.951.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.951.416,00	200.709,48
				Material and Installation w/o Profit (TRY)	3.152.125,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**3.940.156,85**	

Item No	Analysis Name					UoM
35.730.1168	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1168	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.039.712,00	3.039.712,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.039.712,00	204.509,48
				Material and Installation w/o Profit (TRY)	3.244.221,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**4.055.276,85**	

Item No	Analysis Name					UoM
35.730.1169	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1169	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.127.488,00	3.127.488,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.127.488,00	208.309,48
				Material and Installation w/o Profit (TRY)	3.335.797,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**4.169.746,85**	

Item No	Analysis Name					UoM
35.730.1170	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1170	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.215.992,00	3.215.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.215.992,00	212.109,48
				Material and Installation w/o Profit (TRY)	3.428.101,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**4.285.126,85**	

Item No	Analysis Name					UoM
35.730.1171	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1171	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.304.288,00	3.304.288,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.304.288,00	215.909,48
				Material and Installation w/o Profit (TRY)	3.520.197,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**4.400.246,85**	

Item No	Analysis Name					UoM
35.730.1201	**H3000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1201	H3000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.052.024,00	2.052.024,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.052.024,00	139.909,48
				Material and Installation w/o Profit (TRY)	2.191.933,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**2.739.916,85**	

Item No	Analysis Name					UoM
35.730.1202	**H3250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1202	H3250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.106.000,00	2.106.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.106.000,00	143.709,48
				Material and Installation w/o Profit (TRY)	2.249.709,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**2.812.136,85**	

Item No	Analysis Name					UoM
35.730.1203	**H3500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1203	H3500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.144.480,00	2.144.480,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.144.480,00	147.509,48
				Material and Installation w/o Profit (TRY)	2.291.989,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**2.864.986,85**	

Item No	Analysis Name					UoM
35.730.1204	**H3750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1204	H3750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.197.624,00	2.197.624,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.197.624,00	151.309,48
				Material and Installation w/o Profit (TRY)	2.348.933,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**2.936.166,85**	

Item No	Analysis Name					UoM
35.730.1205	**H4000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1205	H4000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.299.128,00	2.299.128,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.299.128,00	155.109,48
				Material and Installation w/o Profit (TRY)	2.454.237,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**3.067.796,85**	

Item No	Analysis Name					UoM
35.730.1206	**H4250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1206	H4250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.356.640,00	2.356.640,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.356.640,00	158.909,48
				Material and Installation w/o Profit (TRY)	2.515.549,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**3.144.436,85**	

Item No	Analysis Name					UoM
35.730.1207	**H4500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1207	H4500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.392.624,00	2.392.624,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.392.624,00	162.709,48
				Material and Installation w/o Profit (TRY)	2.555.333,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**3.194.166,85**	

Item No	Analysis Name					UoM
35.730.1208	**H4750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1208	H4750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.470.416,00	2.470.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.470.416,00	166.509,48
				Material and Installation w/o Profit (TRY)	2.636.925,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**3.296.156,85**	

Item No	Analysis Name					UoM
35.730.1209	**H5000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1209	H5000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.504.320,00	2.504.320,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.504.320,00	170.309,48
				Material and Installation w/o Profit (TRY)	2.674.629,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**3.343.286,85**	

Item No	Analysis Name					UoM
35.730.1210	**H5250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1210	H5250mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.567.240,00	2.567.240,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.567.240,00	174.109,48
				Material and Installation w/o Profit (TRY)	2.741.349,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**3.426.686,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1211	**H5500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1211	H5500mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.601.144,00	2.601.144,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.601.144,00	177.909,48
				Material and Installation w/o Profit (TRY)	2.779.053,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**3.473.816,85**	

Item No	Analysis Name					UoM
35.730.1212	**H5750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1212	H5750mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.634.112,00	2.634.112,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.634.112,00	181.709,48
				Material and Installation w/o Profit (TRY)	2.815.821,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**3.519.776,85**	

Item No	Analysis Name					UoM
35.730.1213	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1213	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.668.224,00	2.668.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.668.224,00	185.509,48
				Material and Installation w/o Profit (TRY)	2.853.733,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**3.567.166,85**	

Item No	Analysis Name					UoM
35.730.1214	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1214	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.755.792,00	2.755.792,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.755.792,00	189.309,48
				Material and Installation w/o Profit (TRY)	2.945.101,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**3.681.376,85**	

Item No	Analysis Name					UoM
35.730.1215	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1215	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.844.296,00	2.844.296,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.844.296,00	193.109,48
				Material and Installation w/o Profit (TRY)	3.037.405,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**3.796.756,85**	

Item No	Analysis Name					UoM
35.730.1216	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1216	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.932.384,00	2.932.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.932.384,00	196.909,48
				Material and Installation w/o Profit (TRY)	3.129.293,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**3.911.616,85**	

Item No	Analysis Name					UoM
35.730.1217	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1217	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.020.368,00	3.020.368,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.020.368,00	200.709,48
				Material and Installation w/o Profit (TRY)	3.221.077,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**4.026.346,85**	

Item No	Analysis Name					UoM
35.730.1218	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1218	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.108.144,00	3.108.144,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.108.144,00	204.509,48
				Material and Installation w/o Profit (TRY)	3.312.653,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**4.140.816,85**	

Item No	Analysis Name					UoM
35.730.1219	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1219	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.197.064,00	3.197.064,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.197.064,00	208.309,48
				Material and Installation w/o Profit (TRY)	3.405.373,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**4.256.716,85**	

Item No	Analysis Name					UoM
35.730.1220	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1220	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.284.528,00	3.284.528,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.284.528,00	212.109,48
				Material and Installation w/o Profit (TRY)	3.496.637,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**4.370.796,85**	

Item No	Analysis Name					UoM
35.730.1221	**H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1221	H6000mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.373.240,00	3.373.240,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.373.240,00	215.909,48
				Material and Installation w/o Profit (TRY)	3.589.149,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**4.486.436,85**	

Item No	Analysis Name					UoM
35.730.1311	**H3000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1311	H3000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	1.982.864,00	1.982.864,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	1.982.864,00	139.909,48
				Material and Installation w/o Profit (TRY)	2.122.773,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**2.653.466,85**	

Item No	Analysis Name					UoM
35.730.1312	**H3250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1312	H3250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.036.008,00	2.036.008,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.036.008,00	143.709,48
				Material and Installation w/o Profit (TRY)	2.179.717,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**2.724.646,85**	

Item No	Analysis Name					UoM
35.730.1313	**H3500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1313	H3500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.071.472,00	2.071.472,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.071.472,00	147.509,48
				Material and Installation w/o Profit (TRY)	2.218.981,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**2.773.726,85**	

Item No	Analysis Name					UoM
35.730.1314	**H3750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1314	H3750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.124.096,00	2.124.096,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.124.096,00	151.309,48
				Material and Installation w/o Profit (TRY)	2.275.405,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**2.844.256,85**	

Item No	Analysis Name					UoM
35.730.1315	**H4000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1315	H4000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.331.264,00	2.331.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.331.264,00	155.109,48
				Material and Installation w/o Profit (TRY)	2.486.373,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**3.107.966,85**	

Item No	Analysis Name					UoM
35.730.1316	**H4250 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1316	H4250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.390.336,00	2.390.336,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.390.336,00	158.909,48
				Material and Installation w/o Profit (TRY)	2.549.245,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**3.186.556,85**	

Item No	Analysis Name					UoM
35.730.1317	**H4500 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1317	H4500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.410.200,00	2.410.200,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.410.200,00	162.709,48
				Material and Installation w/o Profit (TRY)	2.572.909,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**3.216.136,85**	

Item No	Analysis Name					UoM
35.730.1318	**H4750 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1318	H4750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.424.136,00	2.424.136,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.424.136,00	166.509,48
				Material and Installation w/o Profit (TRY)	2.590.645,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**3.238.306,85**	

Item No	Analysis Name					UoM
35.730.1319	**H5000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1319	H5000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.500.368,00	2.500.368,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.500.368,00	170.309,48
				Material and Installation w/o Profit (TRY)	2.670.677,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**3.338.346,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1320	**H5250 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1320	H5250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.594.488,00	2.594.488,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.594.488,00	174.109,48
				Material and Installation w/o Profit (TRY)	2.768.597,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**3.460.746,85**	

Item No	Analysis Name					UoM
35.730.1321	**H5500 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1321	H5500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.633.072,00	2.633.072,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.633.072,00	177.909,48
				Material and Installation w/o Profit (TRY)	2.810.981,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**3.513.726,85**	

Item No	Analysis Name					UoM
35.730.1322	**H5750 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1322	H5750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.681.120,00	2.681.120,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.681.120,00	181.709,48
				Material and Installation w/o Profit (TRY)	2.862.829,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**3.578.536,85**	

Item No	Analysis Name					UoM
35.730.1323	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1323	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.729.272,00	2.729.272,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.729.272,00	185.509,48
				Material and Installation w/o Profit (TRY)	2.914.781,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**3.643.476,85**	

Item No	Analysis Name					UoM
35.730.1324	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1324	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.816.632,00	2.816.632,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.816.632,00	189.309,48
				Material and Installation w/o Profit (TRY)	3.005.941,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**3.757.426,85**	

Item No	Analysis Name					UoM
35.730.1325	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1325	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.905.032,00	2.905.032,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.905.032,00	193.109,48
				Material and Installation w/o Profit (TRY)	3.098.141,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**3.872.676,85**	

Item No	Analysis Name					UoM
35.730.1326	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1326	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.992.704,00	2.992.704,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.992.704,00	196.909,48
				Material and Installation w/o Profit (TRY)	3.189.613,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**3.987.016,85**	

Item No	Analysis Name					UoM
35.730.1327	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1327	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.081.208,00	3.081.208,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.081.208,00	200.709,48
				Material and Installation w/o Profit (TRY)	3.281.917,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**4.102.396,85**	

Item No	Analysis Name					UoM
35.730.1328	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1328	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.168.880,00	3.168.880,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.168.880,00	204.509,48
				Material and Installation w/o Profit (TRY)	3.373.389,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**4.216.736,85**	

Item No	Analysis Name					UoM
35.730.1329	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1329	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.256.864,00	3.256.864,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.256.864,00	208.309,48
				Material and Installation w/o Profit (TRY)	3.465.173,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**4.331.466,85**	

Item No	Analysis Name					UoM
35.730.1330	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1330	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.345.160,00	3.345.160,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.345.160,00	212.109,48
				Material and Installation w/o Profit (TRY)	3.557.269,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**4.446.586,85**	

Item No	Analysis Name					UoM
35.730.1331	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1331	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.433.352,00	3.433.352,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.433.352,00	215.909,48
				Material and Installation w/o Profit (TRY)	3.649.261,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**4.561.576,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1351	**H3000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1351	H3000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.112.656,00	2.112.656,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.112.656,00	139.909,48
				Material and Installation w/o Profit (TRY)	2.252.565,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**2.815.706,85**	

Item No	Analysis Name					UoM
35.730.1352	**H3250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1352	H3250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.169.960,00	2.169.960,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.169.960,00	143.709,48
				Material and Installation w/o Profit (TRY)	2.313.669,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**2.892.086,85**	

Item No	Analysis Name					UoM
35.730.1353	**H3500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1353	H3500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.207.504,00	2.207.504,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.207.504,00	147.509,48
				Material and Installation w/o Profit (TRY)	2.355.013,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**2.943.766,85**	

Item No	Analysis Name					UoM
35.730.1354	**H3750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1354	H3750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.219.464,00	2.219.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.219.464,00	151.309,48
				Material and Installation w/o Profit (TRY)	2.370.773,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**2.963.466,85**	

Item No	Analysis Name					UoM
35.730.1355	**H4000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1355	H4000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.362.568,00	2.362.568,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.362.568,00	155.109,48
				Material and Installation w/o Profit (TRY)	2.517.677,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**3.147.096,85**	

Item No	Analysis Name					UoM
35.730.1356	**H4250 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1356	H4250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.422.992,00	2.422.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.422.992,00	158.909,48
				Material and Installation w/o Profit (TRY)	2.581.901,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**3.227.376,85**	

Item No	Analysis Name					UoM
35.730.1357	**H4500 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1357	H4500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.460.744,00	2.460.744,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.460.744,00	162.709,48
				Material and Installation w/o Profit (TRY)	2.623.453,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**3.279.316,85**	

Item No	Analysis Name					UoM
35.730.1358	**H4750 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1358	H4750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.493.192,00	2.493.192,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.493.192,00	166.509,48
				Material and Installation w/o Profit (TRY)	2.659.701,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**3.324.626,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1359	**H5000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1359	H5000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.526.680,00	2.526.680,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.526.680,00	170.309,48
				Material and Installation w/o Profit (TRY)	2.696.989,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**3.371.236,85**	

Item No	Analysis Name					UoM
35.730.1360	**H5250 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1360	H5250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.637.960,00	2.637.960,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.637.960,00	174.109,48
				Material and Installation w/o Profit (TRY)	2.812.069,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**3.515.086,85**	

Item No	Analysis Name					UoM
35.730.1361	**H5500 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1361	H5500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.673.840,00	2.673.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.673.840,00	177.909,48
				Material and Installation w/o Profit (TRY)	2.851.749,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**3.564.686,85**	

Item No	Analysis Name					UoM
35.730.1362	**H5750 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1362	H5750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.730.312,00	2.730.312,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.730.312,00	181.709,48
				Material and Installation w/o Profit (TRY)	2.912.021,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**3.640.026,85**	

Item No	Analysis Name					UoM
35.730.1363	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1363	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.770.664,00	2.770.664,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.770.664,00	185.509,48
				Material and Installation w/o Profit (TRY)	2.956.173,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**3.695.216,85**	

Item No	Analysis Name					UoM
35.730.1364	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1364	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.858.232,00	2.858.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.858.232,00	189.309,48
				Material and Installation w/o Profit (TRY)	3.047.541,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**3.809.426,85**	

Item No	Analysis Name					UoM
35.730.1365	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1365	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.946.528,00	2.946.528,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.946.528,00	193.109,48
				Material and Installation w/o Profit (TRY)	3.139.637,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**3.924.546,85**	

Item No	Analysis Name					UoM
35.730.1366	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1366	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.034.720,00	3.034.720,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.034.720,00	196.909,48
				Material and Installation w/o Profit (TRY)	3.231.629,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**4.039.536,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1367	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1367	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.121.872,00	3.121.872,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.121.872,00	200.709,48
				Material and Installation w/o Profit (TRY)	3.322.581,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**4.153.226,85**	

Item No	Analysis Name					UoM
35.730.1368	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1368	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.209.648,00	3.209.648,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.209.648,00	204.509,48
				Material and Installation w/o Profit (TRY)	3.414.157,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**4.267.696,85**	

Item No	Analysis Name					UoM
35.730.1369	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1369	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.298.048,00	3.298.048,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.298.048,00	208.309,48
				Material and Installation w/o Profit (TRY)	3.506.357,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**4.382.946,85**	

Item No	Analysis Name					UoM
35.730.1370	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1370	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.386.760,00	3.386.760,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.386.760,00	212.109,48
				Material and Installation w/o Profit (TRY)	3.598.869,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**4.498.586,85**	

Item No	Analysis Name					UoM
35.730.1371	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1371	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.473.704,00	3.473.704,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.473.704,00	215.909,48
				Material and Installation w/o Profit (TRY)	3.689.613,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**4.612.016,85**	

Item No	Analysis Name					UoM
35.730.1401	**H3000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1401	H3000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.158.624,00	2.158.624,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.158.624,00	139.909,48
				Material and Installation w/o Profit (TRY)	2.298.533,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**2.873.166,85**	

Item No	Analysis Name					UoM
35.730.1402	**H3250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1402	H3250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.211.976,00	2.211.976,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.211.976,00	143.709,48
				Material and Installation w/o Profit (TRY)	2.355.685,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**2.944.606,85**	

Item No	Analysis Name					UoM
35.730.1403	**H3500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1403	H3500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.252.120,00	2.252.120,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.252.120,00	147.509,48
				Material and Installation w/o Profit (TRY)	2.399.629,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**2.999.536,85**	

Item No	Analysis Name					UoM
35.730.1404	**H3750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1404	H3750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.306.824,00	2.306.824,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.306.824,00	151.309,48
				Material and Installation w/o Profit (TRY)	2.458.133,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**3.072.666,85**	

Item No	Analysis Name					UoM
35.730.1405	**H4000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1405	H4000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.455.440,00	2.455.440,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.455.440,00	155.109,48
				Material and Installation w/o Profit (TRY)	2.610.549,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**3.263.186,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1406	**H4250 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1406	H4250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.517.840,00	2.517.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.517.840,00	158.909,48
				Material and Installation w/o Profit (TRY)	2.676.749,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**3.345.936,85**	

Item No	Analysis Name					UoM
35.730.1407	**H4500 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1407	H4500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.554.136,00	2.554.136,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.554.136,00	162.709,48
				Material and Installation w/o Profit (TRY)	2.716.845,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**3.396.056,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1408	**H4750 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1408	H4750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.560.896,00	2.560.896,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.560.896,00	166.509,48
				Material and Installation w/o Profit (TRY)	2.727.405,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**3.409.256,85**	

Item No	Analysis Name					UoM
35.730.1409	**H5000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1409	H5000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.604.472,00	2.604.472,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.604.472,00	170.309,48
				Material and Installation w/o Profit (TRY)	2.774.781,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**3.468.476,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1410	**H5250 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1410	H5250mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.660.840,00	2.660.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.660.840,00	174.109,48
				Material and Installation w/o Profit (TRY)	2.834.949,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**3.543.686,85**	

Item No	Analysis Name					UoM
35.730.1411	**H5500 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1411	H5500mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.696.616,00	2.696.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.696.616,00	177.909,48
				Material and Installation w/o Profit (TRY)	2.874.525,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**3.593.156,85**	

Item No	Analysis Name					UoM
35.730.1412	**H5750 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1412	H5750mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.773.576,00	2.773.576,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.773.576,00	181.709,48
				Material and Installation w/o Profit (TRY)	2.955.285,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**3.694.106,85**	

Item No	Analysis Name					UoM
35.730.1413	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1413	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.873.208,00	2.873.208,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.873.208,00	185.509,48
				Material and Installation w/o Profit (TRY)	3.058.717,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**3.823.396,85**	

Item No	Analysis Name					UoM
35.730.1414	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1414	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	2.960.048,00	2.960.048,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.960.048,00	189.309,48
				Material and Installation w/o Profit (TRY)	3.149.357,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**3.936.696,85**	

Item No	Analysis Name					UoM
35.730.1415	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1415	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.048.656,00	3.048.656,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.048.656,00	193.109,48
				Material and Installation w/o Profit (TRY)	3.241.765,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**4.052.206,85**	

Item No	Analysis Name					UoM
35.730.1416	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1416	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.136.952,00	3.136.952,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.136.952,00	196.909,48
				Material and Installation w/o Profit (TRY)	3.333.861,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**4.167.326,85**	

Item No	Analysis Name					UoM
35.730.1417	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1417	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.225.144,00	3.225.144,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.225.144,00	200.709,48
				Material and Installation w/o Profit (TRY)	3.425.853,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**4.282.316,85**	

Item No	Analysis Name					UoM
35.730.1418	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1418	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.313.024,00	3.313.024,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.313.024,00	204.509,48
				Material and Installation w/o Profit (TRY)	3.517.533,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**4.396.916,85**	

Item No	Analysis Name					UoM
35.730.1419	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1419	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.401.216,00	3.401.216,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.401.216,00	208.309,48
				Material and Installation w/o Profit (TRY)	3.609.525,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**4.511.906,85**	

Item No	Analysis Name					UoM
35.730.1420	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1420	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.489.096,00	3.489.096,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.489.096,00	212.109,48
				Material and Installation w/o Profit (TRY)	3.701.205,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**4.626.506,85**	

Item No	Analysis Name					UoM
35.730.1421	**H6000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1421	H6000mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators (Market price)	Qty	1	3.577.496,00	3.577.496,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.577.496,00	215.909,48
				Material and Installation w/o Profit (TRY)	3.793.405,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**4.741.756,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1461	**H 3000 mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1461	H 3000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	2.773.992,00	2.773.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.773.992,00	139.909,48
				Material and Installation w/o Profit (TRY)	2.913.901,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**3.642.376,85**	

Item No	Analysis Name					UoM
35.730.1462	**H 3250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1462	H 3250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	2.792.504,00	2.792.504,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.792.504,00	143.709,48
				Material and Installation w/o Profit (TRY)	2.936.213,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**3.670.266,85**	

Item No	Analysis Name					UoM
35.730.1463	**H 3500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1463	H 3500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	2.840.448,00	2.840.448,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician's helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.840.448,00	147.509,48
				Material and Installation w/o Profit (TRY)	2.987.957,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**3.734.946,85**	

Item No	Analysis Name					UoM
35.730.1464	**H 3750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1464	H 3750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	2.911.896,00	2.911.896,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician's helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.911.896,00	151.309,48
				Material and Installation w/o Profit (TRY)	3.063.205,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**3.829.006,85**	

Item No	Analysis Name					UoM
35.730.1465	**H 4000mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1465	H 4000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.111.472,00	3.111.472,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.111.472,00	155.109,48
				Material and Installation w/o Profit (TRY)	3.266.581,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**4.083.226,85**	

Item No	Analysis Name					UoM
35.730.1466	**H 4250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1466	H 4250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.188.224,00	3.188.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.188.224,00	158.909,48
				Material and Installation w/o Profit (TRY)	3.347.133,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**4.183.916,85**	

Item No	Analysis Name					UoM
35.730.1467	**H 4500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1467	H 4500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.240.432,00	3.240.432,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.240.432,00	162.709,48
				Material and Installation w/o Profit (TRY)	3.403.141,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**4.253.926,85**	

Item No	Analysis Name					UoM
35.730.1468	**H 4750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1468	H 4750 mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.300.856,00	3.300.856,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.300.856,00	166.509,48
				Material and Installation w/o Profit (TRY)	3.467.365,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**4.334.206,85**	

Item No	Analysis Name					UoM
35.730.1469	**H 5000mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1469	H 5000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.351.920,00	3.351.920,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.351.920,00	170.309,48
				Material and Installation w/o Profit (TRY)	3.522.229,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**4.402.786,85**	

Item No	Analysis Name					UoM
35.730.1470	**H 5250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1470	H 5250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.372.200,00	3.372.200,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.372.200,00	174.109,48
				Material and Installation w/o Profit (TRY)	3.546.309,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**4.432.886,85**	

Item No	Analysis Name					UoM
35.730.1471	**H 5500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1471	H 5500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.425.344,00	3.425.344,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.425.344,00	177.909,48
				Material and Installation w/o Profit (TRY)	3.603.253,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**4.504.066,85**	

Item No	Analysis Name					UoM
35.730.1472	**H 5750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1472	H 5750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.467.776,00	3.467.776,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.467.776,00	181.709,48
				Material and Installation w/o Profit (TRY)	3.649.485,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**4.561.856,85**	

Item No	Analysis Name					UoM
35.730.1473	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1473	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.480.256,00	3.480.256,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.480.256,00	185.509,48
				Material and Installation w/o Profit (TRY)	3.665.765,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**4.582.206,85**	

Item No	Analysis Name					UoM
35.730.1474	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1474	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.567.408,00	3.567.408,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.567.408,00	189.309,48
				Material and Installation w/o Profit (TRY)	3.756.717,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**4.695.896,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1475	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1475	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.655.600,00	3.655.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician's helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.655.600,00	193.109,48
				Material and Installation w/o Profit (TRY)	3.848.709,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**4.810.886,85**	

Item No	Analysis Name					UoM
35.730.1476	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1476	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.744.312,00	3.744.312,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician's helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.744.312,00	196.909,48
				Material and Installation w/o Profit (TRY)	3.941.221,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**4.926.526,85**	

Item No	Analysis Name					UoM
35.730.1477	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1477	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.832.192,00	3.832.192,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.832.192,00	200.709,48
				Material and Installation w/o Profit (TRY)	4.032.901,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**5.041.126,85**	

Item No	Analysis Name					UoM
35.730.1478	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1478	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.920.384,00	3.920.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.920.384,00	204.509,48
				Material and Installation w/o Profit (TRY)	4.124.893,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**5.156.116,85**	

Item No	Analysis Name					UoM
35.730.1479	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1479	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.008.368,00	4.008.368,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.008.368,00	208.309,48
				Material and Installation w/o Profit (TRY)	4.216.677,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**5.270.846,85**	

Item No	Analysis Name					UoM
35.730.1480	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1480	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.096.352,00	4.096.352,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.096.352,00	212.109,48
				Material and Installation w/o Profit (TRY)	4.308.461,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**5.385.576,85**	

Item No	Analysis Name					UoM
35.730.1481	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1481	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.184.648,00	4.184.648,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.184.648,00	215.909,48
				Material and Installation w/o Profit (TRY)	4.400.557,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**5.500.696,85**	

Item No	Analysis Name					UoM
35.730.1501	**H 3000 mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1501	H 3000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	2.928.536,00	2.928.536,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.928.536,00	139.909,48
				Material and Installation w/o Profit (TRY)	3.068.445,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**3.835.556,85**	

Item No	Analysis Name					UoM
35.730.1502	**H 3250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1502	H 3250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	2.977.832,00	2.977.832,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	2.977.832,00	143.709,48
				Material and Installation w/o Profit (TRY)	3.121.541,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**3.901.926,85**	

Item No	Analysis Name					UoM
35.730.1503	**H 3500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1503	H 3500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.002.064,00	3.002.064,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.002.064,00	147.509,48
				Material and Installation w/o Profit (TRY)	3.149.573,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**3.936.966,85**	

Item No	Analysis Name					UoM
35.730.1504	**H 3750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1504	H 3750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.053.856,00	3.053.856,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.053.856,00	151.309,48
				Material and Installation w/o Profit (TRY)	3.205.165,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**4.006.456,85**	

Item No	Analysis Name					UoM
35.730.1505	**H 4000mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1505	H 4000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.253.848,00	3.253.848,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.253.848,00	155.109,48
				Material and Installation w/o Profit (TRY)	3.408.957,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**4.261.196,85**	

Item No	Analysis Name					UoM
35.730.1506	**H 4250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1506	H 4250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.270.592,00	3.270.592,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.270.592,00	158.909,48
				Material and Installation w/o Profit (TRY)	3.429.501,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**4.286.876,85**	

Item No	Analysis Name					UoM
35.730.1507	**H 4500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1507	H 4500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.322.696,00	3.322.696,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.322.696,00	162.709,48
				Material and Installation w/o Profit (TRY)	3.485.405,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**4.356.756,85**	

Item No	Analysis Name					UoM
35.730.1508	**H 4750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1508	H 4750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.365.440,00	3.365.440,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician's helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.365.440,00	166.509,48
				Material and Installation w/o Profit (TRY)	3.531.949,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**4.414.936,85**	

Item No	Analysis Name					UoM
35.730.1509	**H 5000mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1509	H 5000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.415.984,00	3.415.984,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician's helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.415.984,00	170.309,48
				Material and Installation w/o Profit (TRY)	3.586.293,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**4.482.866,85**	

Item No	Analysis Name					UoM
35.730.1510	**H 5250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1510	H 5250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.493.776,00	3.493.776,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.493.776,00	174.109,48
				Material and Installation w/o Profit (TRY)	3.667.885,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**4.584.856,85**	

Item No	Analysis Name					UoM
35.730.1511	**H 5500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1511	H 5500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.545.464,00	3.545.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.545.464,00	177.909,48
				Material and Installation w/o Profit (TRY)	3.723.373,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**4.654.216,85**	

Item No	Analysis Name					UoM
35.730.1512	**H 5750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1512	H 5750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.624.192,00	3.624.192,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician's helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.624.192,00	181.709,48
				Material and Installation w/o Profit (TRY)	3.805.901,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**4.757.376,85**	

Item No	Analysis Name					UoM
35.730.1513	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1513	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.641.248,00	3.641.248,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician's helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.641.248,00	185.509,48
				Material and Installation w/o Profit (TRY)	3.826.757,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**4.783.446,85**	

Item No	Analysis Name					UoM
35.730.1514	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1514	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.729.648,00	3.729.648,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.729.648,00	189.309,48
				Material and Installation w/o Profit (TRY)	3.918.957,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**4.898.696,85**	

Item No	Analysis Name					UoM
35.730.1515	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1515	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.817.944,00	3.817.944,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.817.944,00	193.109,48
				Material and Installation w/o Profit (TRY)	4.011.053,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**5.013.816,85**	

Item No	Analysis Name					UoM
35.730.1516	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1516	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.906.032,00	3.906.032,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.906.032,00	196.909,48
				Material and Installation w/o Profit (TRY)	4.102.941,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**5.128.676,85**	

Item No	Analysis Name					UoM
35.730.1517	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1517	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.993.912,00	3.993.912,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.993.912,00	200.709,48
				Material and Installation w/o Profit (TRY)	4.194.621,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**5.243.276,85**	

Item No	Analysis Name					UoM
35.730.1518	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1518	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.082.104,00	4.082.104,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.082.104,00	204.509,48
				Material and Installation w/o Profit (TRY)	4.286.613,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**5.358.266,85**	

Item No	Analysis Name					UoM
35.730.1519	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1519	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.169.152,00	4.169.152,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.169.152,00	208.309,48
				Material and Installation w/o Profit (TRY)	4.377.461,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**5.471.826,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1520	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1520	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.257.760,00	4.257.760,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.257.760,00	212.109,48
				Material and Installation w/o Profit (TRY)	4.469.869,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**5.587.336,85**	

Item No	Analysis Name					UoM
35.730.1521	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1521	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.346.160,00	4.346.160,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.346.160,00	215.909,48
				Material and Installation w/o Profit (TRY)	4.562.069,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**5.702.586,85**	

Item No	Analysis Name					UoM
35.730.1551	**H 3000 mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1551	H 3000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.018.600,00	3.018.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician's helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.018.600,00	139.909,48
				Material and Installation w/o Profit (TRY)	3.158.509,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**3.948.136,85**	

Item No	Analysis Name					UoM
35.730.1552	**H 3250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1552	H3250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.100.240,00	3.100.240,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician's helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.100.240,00	143.709,48
				Material and Installation w/o Profit (TRY)	3.243.949,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**4.054.936,85**	

Item No	Analysis Name					UoM
35.730.1553	**H 3500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1553	H 3500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.151.616,00	3.151.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician's helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.151.616,00	147.509,48
				Material and Installation w/o Profit (TRY)	3.299.125,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**4.123.906,85**	

Item No	Analysis Name					UoM
35.730.1554	**H 3750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1554	H 3750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.172.832,00	3.172.832,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician's helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.172.832,00	151.309,48
				Material and Installation w/o Profit (TRY)	3.324.141,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**4.155.176,85**	

Item No	Analysis Name					UoM
35.730.1555	**H 4000mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1555	H 4000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.319.784,00	3.319.784,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.319.784,00	155.109,48
				Material and Installation w/o Profit (TRY)	3.474.893,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**4.343.616,85**	

Item No	Analysis Name					UoM
35.730.1556	**H 4250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1556	H 4250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.366.376,00	3.366.376,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.366.376,00	158.909,48
				Material and Installation w/o Profit (TRY)	3.525.285,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**4.406.606,85**	

Item No	Analysis Name					UoM
35.730.1557	**H 4500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1557	H 4500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.419.416,00	3.419.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.419.416,00	162.709,48
				Material and Installation w/o Profit (TRY)	3.582.125,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**4.477.656,85**	

Item No	Analysis Name					UoM
35.730.1558	**H 4750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1558	H 4750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.531.840,00	3.531.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.531.840,00	166.509,48
				Material and Installation w/o Profit (TRY)	3.698.349,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**4.622.936,85**	

Item No	Analysis Name					UoM
35.730.1559	**H 5000mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1559	H 5000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.548.584,00	3.548.584,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.548.584,00	170.309,48
				Material and Installation w/o Profit (TRY)	3.718.893,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**4.648.616,85**	

Item No	Analysis Name					UoM
35.730.1560	**H 5250mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1560	H 5250mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.631.888,00	3.631.888,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.631.888,00	174.109,48
				Material and Installation w/o Profit (TRY)	3.805.997,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**4.757.496,85**	

Item No	Analysis Name					UoM
35.730.1561	**H 5500mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1561	H 5500mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.684.200,00	3.684.200,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.684.200,00	177.909,48
				Material and Installation w/o Profit (TRY)	3.862.109,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**4.827.636,85**	

Item No	Analysis Name					UoM
35.730.1562	**H 5750mm / Escalators with 35-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1562	H 5750mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.765.112,00	3.765.112,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.765.112,00	181.709,48
				Material and Installation w/o Profit (TRY)	3.946.821,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**4.933.526,85**	

Item No	Analysis Name					UoM
35.730.1563	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1563	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.818.464,00	3.818.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.818.464,00	185.509,48
				Material and Installation w/o Profit (TRY)	4.003.973,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**5.004.966,85**	

Item No	Analysis Name					UoM
35.730.1564	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1564	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.907.072,00	3.907.072,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.907.072,00	189.309,48
				Material and Installation w/o Profit (TRY)	4.096.381,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**5.120.476,85**	

Item No	Analysis Name					UoM
35.730.1565	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1565	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.995.264,00	3.995.264,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.995.264,00	193.109,48
				Material and Installation w/o Profit (TRY)	4.188.373,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**5.235.466,85**	

Item No	Analysis Name					UoM
35.730.1566	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1566	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.083.456,00	4.083.456,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.083.456,00	196.909,48
				Material and Installation w/o Profit (TRY)	4.280.365,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**5.350.456,85**	

Item No	Analysis Name					UoM
35.730.1567	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1567	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.171.960,00	4.171.960,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.171.960,00	200.709,48
				Material and Installation w/o Profit (TRY)	4.372.669,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**5.465.836,85**	

Item No	Analysis Name					UoM
35.730.1568	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1568	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.259.528,00	4.259.528,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.259.528,00	204.509,48
				Material and Installation w/o Profit (TRY)	4.464.037,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**5.580.046,85**	

Item No	Analysis Name					UoM
35.730.1569	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1569	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.347.616,00	4.347.616,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.347.616,00	208.309,48
				Material and Installation w/o Profit (TRY)	4.555.925,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**5.694.906,85**	

Item No	Analysis Name					UoM
35.730.1570	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1570	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.436.432,00	4.436.432,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.436.432,00	212.109,48
				Material and Installation w/o Profit (TRY)	4.648.541,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**5.810.676,85**	

Item No	Analysis Name					UoM
35.730.1571	**H 6000 mm / Escalators with 35-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1571	H 6000mm / Escalators with 35-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.524.208,00	4.524.208,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.524.208,00	215.909,48
				Material and Installation w/o Profit (TRY)	4.740.117,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**5.925.146,85**	

Item No	Analysis Name					UoM
35.730.1611	**H 3000 mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1611	H3000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators (Market price)	Qty	1	3.006.536,00	3.006.536,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.006.536,00	139.909,48
				Material and Installation w/o Profit (TRY)	3.146.445,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**3.933.056,85**	

Item No	Analysis Name					UoM
35.730.1612	**H 3250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1612	H 3250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.081.936,00	3.081.936,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.081.936,00	143.709,48
				Material and Installation w/o Profit (TRY)	3.225.645,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**4.032.056,85**	

Item No	Analysis Name					UoM
35.730.1613	**H 3500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1613	H 3500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.110.224,00	3.110.224,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.110.224,00	147.509,48
				Material and Installation w/o Profit (TRY)	3.257.733,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**4.072.166,85**	

Item No	Analysis Name					UoM
35.730.1614	**H 3750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1614	H 3750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.156.296,00	3.156.296,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.156.296,00	151.309,48
				Material and Installation w/o Profit (TRY)	3.307.605,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**4.134.506,85**	

Item No	Analysis Name					UoM
35.730.1615	**H 4000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1615	H 4000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.270.592,00	3.270.592,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.270.592,00	155.109,48
				Material and Installation w/o Profit (TRY)	3.425.701,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**4.282.126,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1616	**H 4250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1616	H 4250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.348.384,00	3.348.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.348.384,00	158.909,48
				Material and Installation w/o Profit (TRY)	3.507.293,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**4.384.116,85**	

Item No	Analysis Name					UoM
35.730.1617	**H 4500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1617	H 4500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.400.384,00	3.400.384,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.400.384,00	162.709,48
				Material and Installation w/o Profit (TRY)	3.563.093,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**4.453.866,85**	

Item No	Analysis Name					UoM
35.730.1618	**H 4750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1618	H 4750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.505.424,00	3.505.424,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.505.424,00	166.509,48
				Material and Installation w/o Profit (TRY)	3.671.933,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**4.589.916,85**	

Item No	Analysis Name					UoM
35.730.1619	**H 5000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1619	H 5000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.527.056,00	3.527.056,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.527.056,00	170.309,48
				Material and Installation w/o Profit (TRY)	3.697.365,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**4.621.706,85**	

Item No	Analysis Name					UoM
35.730.1620	**H 5250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1620	H 5250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.572.504,00	3.572.504,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.572.504,00	174.109,48
				Material and Installation w/o Profit (TRY)	3.746.613,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**4.683.266,85**	

Item No	Analysis Name					UoM
35.730.1621	**H 5500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1621	H 5500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.693.248,00	3.693.248,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.693.248,00	177.909,48
				Material and Installation w/o Profit (TRY)	3.871.157,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**4.838.946,85**	

Item No	Analysis Name					UoM
35.730.1622	**H 5750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1622	H 5750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.758.976,00	3.758.976,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.758.976,00	181.709,48
				Material and Installation w/o Profit (TRY)	3.940.685,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**4.925.856,85**	

Item No	Analysis Name					UoM
35.730.1623	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1623	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.824.392,00	3.824.392,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.824.392,00	185.509,48
				Material and Installation w/o Profit (TRY)	4.009.901,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**5.012.376,85**	

Item No	Analysis Name					UoM
35.730.1624	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1624	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.913.000,00	3.913.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.913.000,00	189.309,48
				Material and Installation w/o Profit (TRY)	4.102.309,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**5.127.886,85**	

Item No	Analysis Name					UoM
35.730.1625	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1625	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.001.608,00	4.001.608,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.001.608,00	193.109,48
				Material and Installation w/o Profit (TRY)	4.194.717,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**5.243.396,85**	

Item No	Analysis Name					UoM
35.730.1626	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1626	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.089.280,00	4.089.280,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.089.280,00	196.909,48
				Material and Installation w/o Profit (TRY)	4.286.189,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**5.357.736,85**	

Item No	Analysis Name					UoM
35.730.1627	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1627	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.176.640,00	4.176.640,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.176.640,00	200.709,48
				Material and Installation w/o Profit (TRY)	4.377.349,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**5.471.686,85**	

Item No	Analysis Name					UoM
35.730.1628	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1628	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.264.520,00	4.264.520,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.264.520,00	204.509,48
				Material and Installation w/o Profit (TRY)	4.469.029,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**5.586.286,85**	

Item No	Analysis Name					UoM
35.730.1629	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1629	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.352.920,00	4.352.920,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.352.920,00	208.309,48
				Material and Installation w/o Profit (TRY)	4.561.229,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**5.701.536,85**	

Item No	Analysis Name					UoM
35.730.1630	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1630	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.440.800,00	4.440.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.440.800,00	212.109,48
				Material and Installation w/o Profit (TRY)	4.652.909,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**5.816.136,85**	

Item No	Analysis Name					UoM
35.730.1631	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1631	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.528.992,00	4.528.992,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.528.992,00	215.909,48
				Material and Installation w/o Profit (TRY)	4.744.901,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**5.931.126,85**	

Item No	Analysis Name					UoM
35.730.1651	**H 3000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1651	H 3000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators (Market price)	Qty	1	3.050.216,00	3.050.216,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.050.216,00	139.909,48
				Material and Installation w/o Profit (TRY)	3.190.125,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**3.987.656,85**	

Item No	Analysis Name					UoM
35.730.1652	**H 3250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1652	H 3250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.132.480,00	3.132.480,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.132.480,00	143.709,48
				Material and Installation w/o Profit (TRY)	3.276.189,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**4.095.236,85**	

Item No	Analysis Name					UoM
35.730.1653	**H 3500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1653	H 3500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.184.792,00	3.184.792,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.184.792,00	147.509,48
				Material and Installation w/o Profit (TRY)	3.332.301,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**4.165.376,85**	

Item No	Analysis Name					UoM
35.730.1654	**H 3750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1654	H 3750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.205.072,00	3.205.072,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.205.072,00	151.309,48
				Material and Installation w/o Profit (TRY)	3.356.381,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**4.195.476,85**	

Item No	Analysis Name					UoM
35.730.1655	**H 4000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1655	H 4000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.346.824,00	3.346.824,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.346.824,00	155.109,48
				Material and Installation w/o Profit (TRY)	3.501.933,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**4.377.416,85**	

Item No	Analysis Name					UoM
35.730.1656	**H 4250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1656	H 4250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.428.672,00	3.428.672,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.428.672,00	158.909,48
				Material and Installation w/o Profit (TRY)	3.587.581,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**4.484.476,85**	

Item No	Analysis Name					UoM
35.730.1657	**H 4500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1657	H 4500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.482.232,00	3.482.232,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.482.232,00	162.709,48
				Material and Installation w/o Profit (TRY)	3.644.941,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**4.556.176,85**	

Item No	Analysis Name					UoM
35.730.1658	**H 4750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1658	H 4750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.525.080,00	3.525.080,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.525.080,00	166.509,48
				Material and Installation w/o Profit (TRY)	3.691.589,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**4.614.486,85**	

Item No	Analysis Name					UoM
35.730.1659	**H 5000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1659	H 5000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.580.096,00	3.580.096,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.580.096,00	170.309,48
				Material and Installation w/o Profit (TRY)	3.750.405,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**4.688.006,85**	

Item No	Analysis Name					UoM
35.730.1660	**H 5250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1660	H 5250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.624.296,00	3.624.296,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.624.296,00	174.109,48
				Material and Installation w/o Profit (TRY)	3.798.405,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**4.748.006,85**	

Item No	Analysis Name					UoM
35.730.1661	**H 5500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1661	H 5500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.714.464,00	3.714.464,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.714.464,00	177.909,48
				Material and Installation w/o Profit (TRY)	3.892.373,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**4.865.466,85**	

Item No	Analysis Name					UoM
35.730.1662	**H 5750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1662	H 5750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.805.360,00	3.805.360,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.805.360,00	181.709,48
				Material and Installation w/o Profit (TRY)	3.987.069,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**4.983.836,85**	

Item No	Analysis Name					UoM
35.730.1663	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1663	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.844.776,00	3.844.776,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.844.776,00	185.509,48
				Material and Installation w/o Profit (TRY)	4.030.285,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**5.037.856,85**	

Item No	Analysis Name					UoM
35.730.1664	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1664	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.933.488,00	3.933.488,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician’s helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.933.488,00	189.309,48
				Material and Installation w/o Profit (TRY)	4.122.797,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**5.153.496,85**	

Item No	Analysis Name					UoM
35.730.1665	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1665	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.021.888,00	4.021.888,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician’s helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.021.888,00	193.109,48
				Material and Installation w/o Profit (TRY)	4.214.997,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**5.268.746,85**	

Item No	Analysis Name					UoM
35.730.1666	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1666	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.108.936,00	4.108.936,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.108.936,00	196.909,48
				Material and Installation w/o Profit (TRY)	4.305.845,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**5.382.306,85**	

Item No	Analysis Name					UoM
35.730.1667	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1667	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.197.440,00	4.197.440,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.197.440,00	200.709,48
				Material and Installation w/o Profit (TRY)	4.398.149,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**5.497.686,85**	

Item No	Analysis Name					UoM
35.730.1668	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1668	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.284.800,00	4.284.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.284.800,00	204.509,48
				Material and Installation w/o Profit (TRY)	4.489.309,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**5.611.636,85**	

Item No	Analysis Name					UoM
35.730.1669	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1669	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.371.640,00	4.371.640,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.371.640,00	208.309,48
				Material and Installation w/o Profit (TRY)	4.579.949,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**5.724.936,85**	

Item No	Analysis Name					UoM
35.730.1670	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1670	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.460.872,00	4.460.872,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.460.872,00	212.109,48
				Material and Installation w/o Profit (TRY)	4.672.981,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**5.841.226,85**	

Item No	Analysis Name					UoM
35.730.1671	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1671	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.548.856,00	4.548.856,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.548.856,00	215.909,48
				Material and Installation w/o Profit (TRY)	4.764.765,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**5.955.956,85**	

Item No	Analysis Name					UoM
35.730.1701	**H 3000 mm / Escalators with 30-degree escalating angle (For interior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1701	H 3000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators (Market price)	Qty	1	3.172.416,00	3.172.416,00	
	Installation Components					
10.100.1062	Unskilled worker	h	160	165,00		26.400,00
10.100.1081	Master electrician	h	160	250,00		40.000,00
10.100.1083	Master electrician’s helper	h	160	185,00		29.600,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	40	700,00		28.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.172.416,00	139.909,48
				Material and Installation w/o Profit (TRY)	3.312.325,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**174.886,85**	
				Unit Price (TRY)	**4.140.406,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1702	**H 3250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1702	H 3250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.253.848,00	3.253.848,00	
	Installation Components					
10.100.1062	Unskilled worker	h	164	165,00		27.060,00
10.100.1081	Master electrician	h	164	250,00		41.000,00
10.100.1083	Master electrician’s helper	h	164	185,00		30.340,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	42	700,00		29.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.253.848,00	143.709,48
				Material and Installation w/o Profit (TRY)	3.397.557,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**179.636,85**	
				Unit Price (TRY)	**4.246.946,85**	

Item No	Analysis Name					UoM
35.730.1703	**H 3500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1703	H 3500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.281.824,00	3.281.824,00	
	Installation Components					
10.100.1062	Unskilled worker	h	168	165,00		27.720,00
10.100.1081	Master electrician	h	168	250,00		42.000,00
10.100.1083	Master electrician’s helper	h	168	185,00		31.080,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	44	700,00		30.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.281.824,00	147.509,48
				Material and Installation w/o Profit (TRY)	3.429.333,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**184.386,85**	
				Unit Price (TRY)	**4.286.666,85**	

Item No	Analysis Name					UoM
35.730.1704	**H 3750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1704	H 3750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.329.872,00	3.329.872,00	
	Installation Components					
10.100.1062	Unskilled worker	h	172	165,00		28.380,00
10.100.1081	Master electrician	h	172	250,00		43.000,00
10.100.1083	Master electrician’s helper	h	172	185,00		31.820,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	46	700,00		32.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.329.872,00	151.309,48
				Material and Installation w/o Profit (TRY)	3.481.181,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**189.136,85**	
				Unit Price (TRY)	**4.351.476,85**	

Item No	Analysis Name					UoM
35.730.1705	**H 4000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1705	H 4000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.445.312,00	3.445.312,00	
	Installation Components					
10.100.1062	Unskilled worker	h	176	165,00		29.040,00
10.100.1081	Master electrician	h	176	250,00		44.000,00
10.100.1083	Master electrician’s helper	h	176	185,00		32.560,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	48	700,00		33.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.445.312,00	155.109,48
				Material and Installation w/o Profit (TRY)	3.600.421,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**193.886,85**	
				Unit Price (TRY)	**4.500.526,85**	

Item No	Analysis Name					UoM
35.730.1706	**H 4250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1706	H 4250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.533.296,00	3.533.296,00	
	Installation Components					
10.100.1062	Unskilled worker	h	180	165,00		29.700,00
10.100.1081	Master electrician	h	180	250,00		45.000,00
10.100.1083	Master electrician’s helper	h	180	185,00		33.300,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	50	700,00		35.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.533.296,00	158.909,48
				Material and Installation w/o Profit (TRY)	3.692.205,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**198.636,85**	
				Unit Price (TRY)	**4.615.256,85**	

Item No	Analysis Name					UoM
35.730.1707	**H 4500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1707	H 4500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.588.936,00	3.588.936,00	
	Installation Components					
10.100.1062	Unskilled worker	h	184	165,00		30.360,00
10.100.1081	Master electrician	h	184	250,00		46.000,00
10.100.1083	Master electrician’s helper	h	184	185,00		34.040,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	52	700,00		36.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.588.936,00	162.709,48
				Material and Installation w/o Profit (TRY)	3.751.645,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**203.386,85**	
				Unit Price (TRY)	**4.689.556,85**	

Item No	Analysis Name					UoM
35.730.1708	**H 4750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1708	H 4750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.664.336,00	3.664.336,00	
	Installation Components					
10.100.1062	Unskilled worker	h	188	165,00		31.020,00
10.100.1081	Master electrician	h	188	250,00		47.000,00
10.100.1083	Master electrician’s helper	h	188	185,00		34.780,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	54	700,00		37.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.664.336,00	166.509,48
				Material and Installation w/o Profit (TRY)	3.830.845,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**208.136,85**	
				Unit Price (TRY)	**4.788.556,85**	

Item No	Analysis Name					UoM
35.730.1709	**H 5000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1709	H 5000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.717.792,00	3.717.792,00	
	Installation Components					
10.100.1062	Unskilled worker	h	192	165,00		31.680,00
10.100.1081	Master electrician	h	192	250,00		48.000,00
10.100.1083	Master electrician’s helper	h	192	185,00		35.520,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	56	700,00		39.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.717.792,00	170.309,48
				Material and Installation w/o Profit (TRY)	3.888.101,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**212.886,85**	
				Unit Price (TRY)	**4.860.126,85**	

Item No	Analysis Name					UoM
35.730.1710	**H 5250mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1710	H 5250mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.726.216,00	3.726.216,00	
	Installation Components					
10.100.1062	Unskilled worker	h	196	165,00		32.340,00
10.100.1081	Master electrician	h	196	250,00		49.000,00
10.100.1083	Master electrician’s helper	h	196	185,00		36.260,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	58	700,00		40.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.726.216,00	174.109,48
				Material and Installation w/o Profit (TRY)	3.900.325,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**217.636,85**	
				Unit Price (TRY)	**4.875.406,85**	

Item No	Analysis Name					UoM
35.730.1711	**H 5500mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1711	H 5500mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.885.752,00	3.885.752,00	
	Installation Components					
10.100.1062	Unskilled worker	h	200	165,00		33.000,00
10.100.1081	Master electrician	h	200	250,00		50.000,00
10.100.1083	Master electrician’s helper	h	200	185,00		37.000,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	60	700,00		42.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.885.752,00	177.909,48
				Material and Installation w/o Profit (TRY)	4.063.661,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**222.386,85**	
				Unit Price (TRY)	**5.079.576,85**	

Item No	Analysis Name					UoM
35.730.1712	**H 5750mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1712	H 5750mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.898.544,00	3.898.544,00	
	Installation Components					
10.100.1062	Unskilled worker	h	204	165,00		33.660,00
10.100.1081	Master electrician	h	204	250,00		51.000,00
10.100.1083	Master electrician’s helper	h	204	185,00		37.740,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	62	700,00		43.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.898.544,00	181.709,48
				Material and Installation w/o Profit (TRY)	4.080.253,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**227.136,85**	
				Unit Price (TRY)	**5.100.316,85**	

Item No	Analysis Name					UoM
35.730.1713	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1713	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	3.992.768,00	3.992.768,00	
	Installation Components					
10.100.1062	Unskilled worker	h	208	165,00		34.320,00
10.100.1081	Master electrician	h	208	250,00		52.000,00
10.100.1083	Master electrician’s helper	h	208	185,00		38.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	64	700,00		44.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.992.768,00	185.509,48
				Material and Installation w/o Profit (TRY)	4.178.277,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**231.886,85**	
				Unit Price (TRY)	**5.222.846,85**	

Item No	Analysis Name					UoM
35.730.1714	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1714	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.080.648,00	4.080.648,00	
	Installation Components					
10.100.1062	Unskilled worker	h	212	165,00		34.980,00
10.100.1081	Master electrician	h	212	250,00		53.000,00
10.100.1083	Master electrician's helper	h	212	185,00		39.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	66	700,00		46.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.080.648,00	189.309,48
				Material and Installation w/o Profit (TRY)	4.269.957,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**236.636,85**	
				Unit Price (TRY)	**5.337.446,85**	

Item No	Analysis Name					UoM
35.730.1715	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1715	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.167.592,00	4.167.592,00	
	Installation Components					
10.100.1062	Unskilled worker	h	216	165,00		35.640,00
10.100.1081	Master electrician	h	216	250,00		54.000,00
10.100.1083	Master electrician's helper	h	216	185,00		39.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	68	700,00		47.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.167.592,00	193.109,48
				Material and Installation w/o Profit (TRY)	4.360.701,48	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**241.386,85**	
				Unit Price (TRY)	**5.450.876,85**	

Item No	Analysis Name					UoM
35.730.1716	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1716	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.255.888,00	4.255.888,00	
	Installation Components					
10.100.1062	Unskilled worker	h	220	165,00		36.300,00
10.100.1081	Master electrician	h	220	250,00		55.000,00
10.100.1083	Master electrician’s helper	h	220	185,00		40.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	70	700,00		49.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.255.888,00	196.909,48
				Material and Installation w/o Profit (TRY)	4.452.797,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**246.136,85**	
				Unit Price (TRY)	**5.565.996,85**	

Item No	Analysis Name					UoM
35.730.1717	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1717	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.344.288,00	4.344.288,00	
	Installation Components					
10.100.1062	Unskilled worker	h	224	165,00		36.960,00
10.100.1081	Master electrician	h	224	250,00		56.000,00
10.100.1083	Master electrician’s helper	h	224	185,00		41.440,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	72	700,00		50.400,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.344.288,00	200.709,48
				Material and Installation w/o Profit (TRY)	4.544.997,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**250.886,85**	
				Unit Price (TRY)	**5.681.246,85**	

Item No	Analysis Name					UoM
35.730.1718	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1718	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.432.064,00	4.432.064,00	
	Installation Components					
10.100.1062	Unskilled worker	h	228	165,00		37.620,00
10.100.1081	Master electrician	h	228	250,00		57.000,00
10.100.1083	Master electrician’s helper	h	228	185,00		42.180,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	74	700,00		51.800,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.432.064,00	204.509,48
				Material and Installation w/o Profit (TRY)	4.636.573,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**255.636,85**	
				Unit Price (TRY)	**5.795.716,85**	

Item No	Analysis Name					UoM
35.730.1719	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1719	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.520.672,00	4.520.672,00	
	Installation Components					
10.100.1062	Unskilled worker	h	232	165,00		38.280,00
10.100.1081	Master electrician	h	232	250,00		58.000,00
10.100.1083	Master electrician’s helper	h	232	185,00		42.920,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	76	700,00		53.200,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.520.672,00	208.309,48
				Material and Installation w/o Profit (TRY)	4.728.981,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**260.386,85**	
				Unit Price (TRY)	**5.911.226,85**	

Item No	Analysis Name					UoM
35.730.1720	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1720	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.609.280,00	4.609.280,00	
	Installation Components					
10.100.1062	Unskilled worker	h	236	165,00		38.940,00
10.100.1081	Master electrician	h	236	250,00		59.000,00
10.100.1083	Master electrician’s helper	h	236	185,00		43.660,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	78	700,00		54.600,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.609.280,00	212.109,48
				Material and Installation w/o Profit (TRY)	4.821.389,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**265.136,85**	
				Unit Price (TRY)	**6.026.736,85**	

Item No	Analysis Name					UoM
35.730.1721	**H 6000mm / Escalators with 30-degree escalating angle (For exterior environments) / Escalators**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1721	H 6000mm / Escalators with 30-degree escalating angle (For outer environments) / Escalators (Market price)	Qty	1	4.696.120,00	4.696.120,00	
	Installation Components					
10.100.1062	Unskilled worker	h	240	165,00		39.600,00
10.100.1081	Master electrician	h	240	250,00		60.000,00
10.100.1083	Master electrician’s helper	h	240	185,00		44.400,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	80	700,00		56.000,00
19.100.1112	Forklift	h	9	687,95		6.191,55
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	4.696.120,00	215.909,48
				Material and Installation w/o Profit (TRY)	4.912.029,48	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**269.886,85**	
				Unit Price (TRY)	**6.140.036,85**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.730.1750	**Difference to be paid for side surface paneling of escalators / Escalators**					**m²**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1750	Difference to be paid for side surface paneling of escalators / Escalators (Market price)	m²	1	3.282,24	3.282,24	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	3.282,24	517,50
				Material and Installation w/o Profit (TRY)	3.799,74	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**4.749,67**	

Item No	Analysis Name					UoM
35.730.1760	**Difference to be paid for side surface paneling of escalators / Escalators**					**m²**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.730.1760	Difference to be paid for side surface paneling of escalators / Escalators (Market price)	m²	1	8.183,76	8.183,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	8.183,76	517,50
				Material and Installation w/o Profit (TRY)	8.701,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**10.876,58**	

Item No	Analysis Name					UoM
35.735.1101	**Max. travel distance: 1500 mm / Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1101	Max. travel distance: 1500 mm / Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	318.884,80	318.884,80	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	20	185,00		3.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	6	687,95		4.127,70
19.100.1113	Mobile crane	h	6	1.079,77		6.478,62
				Total Excluding Profit (TRY)	318.884,80	25.406,32
				Material and Installation w/o Profit (TRY)	344.291,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.757,90**	
				Unit Price (TRY)	**430.363,90**	

Item No	Analysis Name					UoM
35.735.1102	**Max. travel distance: 2000 mm / Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1102	Max. travel distance: 2000 mm / Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	339.924,00	339.924,00	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	20	185,00		3.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	6	687,95		4.127,70
19.100.1113	Mobile crane	h	6	1.079,77		6.478,62
				Total Excluding Profit (TRY)	339.924,00	25.406,32
				Material and Installation w/o Profit (TRY)	365.330,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.757,90**	
				Unit Price (TRY)	**456.662,90**	

Item No	Analysis Name					UoM
35.735.1103	**Max. travel distance: 2500 mm / Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1103	Max. travel distance: 2500 mm / Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	345.238,40	345.238,40	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	25	250,00		6.250,00
10.100.1083	Master electrician's helper	h	25	185,00		4.625,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	345.238,40	31.941,76
				Material and Installation w/o Profit (TRY)	377.180,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39.927,20**	
				Unit Price (TRY)	**471.475,20**	

Item No	Analysis Name					UoM
35.735.1104	**Max. travel distance: 3000 mm / Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1104	Max. travel distance: 3000 mm / Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	378.206,40	378.206,40	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	25	250,00		6.250,00
10.100.1083	Master electrician's helper	h	25	185,00		4.625,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	378.206,40	31.941,76
				Material and Installation w/o Profit (TRY)	410.148,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39.927,20**	
				Unit Price (TRY)	**512.685,20**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.735.1201	**Max. travel distance: 1500 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1201	Max. travel distance: 1500 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	283.212,80	283.212,80	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	20	185,00		3.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	6	687,95		4.127,70
19.100.1113	Mobile crane	h	6	1.079,77		6.478,62
				Total Excluding Profit (TRY)	283.212,80	25.406,32
				Material and Installation w/o Profit (TRY)	308.619,12	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.757,90**	
				Unit Price (TRY)	**385.773,90**	

Item No	Analysis Name					UoM
35.735.1202	**Max. travel distance: 2000 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1202	Max. travel distance: 2000 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	355.212,00	355.212,00	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	20	250,00		5.000,00
10.100.1083	Master electrician's helper	h	20	185,00		3.700,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	6	687,95		4.127,70
19.100.1113	Mobile crane	h	6	1.079,77		6.478,62
				Total Excluding Profit (TRY)	355.212,00	25.406,32
				Material and Installation w/o Profit (TRY)	380.618,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**31.757,90**	
				Unit Price (TRY)	**475.772,90**	

Item No	Analysis Name					UoM
35.735.1203	**Max. travel distance: 2500 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1203	Max. travel distance: 2500 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	360.838,40	360.838,40	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	25	250,00		6.250,00
10.100.1083	Master electrician's helper	h	25	185,00		4.625,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	360.838,40	31.941,76
				Material and Installation w/o Profit (TRY)	392.780,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39.927,20**	
				Unit Price (TRY)	**490.975,20**	

Item No	Analysis Name					UoM
35.735.1204	**Max. travel distance: 3000 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1204	Max. travel distance: 3000 mm / (Hydraulic) Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	393.494,40	393.494,40	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	25	250,00		6.250,00
10.100.1083	Master electrician's helper	h	25	185,00		4.625,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1112	Forklift	h	8	687,95		5.503,60
19.100.1113	Mobile crane	h	8	1.079,77		8.638,16
				Total Excluding Profit (TRY)	393.494,40	31.941,76
				Material and Installation w/o Profit (TRY)	425.436,16	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39.927,20**	
				Unit Price (TRY)	**531.795,20**	

Item No	Analysis Name					UoM
35.735.1250						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1250	Straight Stair-type, Foldable Wheelchair Platform / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	223.600,00	223.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	30	165,00		4.950,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician's helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1112	Forklift	h	10	687,95		6.879,50
				Total Excluding Profit (TRY)	223.600,00	31.879,50
				Material and Installation w/o Profit (TRY)	255.479,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**39.849,38**	
				Unit Price (TRY)	**319.349,38**	

Item No	Analysis Name					UoM
35.735.1270	**Travel distance difference for Straight Stair-type, Foldable Wheelchair Platform / Platform Lifts with Wheelchair Platform**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.735.1270	Travel distance difference for Straight Stair-type, Foldable Wheelchair Platform / Platform Elevators with Wheelchair Platform (Market price)	m	1	18.376,80	18.376,80	
				Total Excluding Profit (TRY)	18.376,80	
				Material and Installation w/o Profit (TRY)	18.376,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**22.971,00**	

Item No	Analysis Name					UoM
35.735.1280	**Travel distance difference for Enclosed Vertical Lifting Platform / Platform Lifts with Wheelchair Platform**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.735.1280	**Material Components** Travel distance difference for Enclosed Vertical Lifting Platform / Platform Elevators with Wheelchair Platform (Market price)	m	1	23.618,40	23.618,40	
				Total Excluding Profit (TRY)	23.618,40	
				Material and Installation w/o Profit (TRY)	23.618,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**		
				Unit Price (TRY)	**29.523,00**	

Item No	Analysis Name					UoM
35.735.1290	**Additional landing doors for Enclosed Vertical Lifting Platform / Straight Stair-type, Foldable Wheelchair Platform, Materials on construction site: 80% / Platform Lifts with Wheelchair Platform**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
30.735.1290	**Material Components** Additional landing doors for Enclosed Vertical Lifting Platform / Straight Stair-type, Foldable Wheelchair Platform, Materials on construction site: 80% / Platform Elevators with Wheelchair Platform (Market price)	Qty	1	25.833,60	25.833,60	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	0,5	700,00		350,00
19.100.1112	Forklift	h	1	687,95		687,95
				Total Excluding Profit (TRY)	25.833,60	2.072,95
				Material and Installation w/o Profit (TRY)	27.906,55	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.591,19**	
				Unit Price (TRY)	**34.883,19**	

Item No	Analysis Name					UoM
35.740.1101	**10 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1101	10 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	146.529,60	146.529,60	
	Installation Components					
10.100.1062	Unskilled worker	h	10	165,00		1.650,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician’s helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
19.100.1113	Mobile crane	h	4	1.079,77		4.319,08
				Total Excluding Profit (TRY)	146.529,60	12.419,08
				Material and Installation w/o Profit (TRY)	158.948,68	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**15.523,85**	
				Unit Price (TRY)	**198.685,85**	

Item No	Analysis Name					UoM
35.740.1102	**20 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1102	20 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	183.344,00	183.344,00	
	Installation Components					
10.100.1062	Unskilled worker	h	11,2	165,00		1.848,00
10.100.1081	Master electrician	h	11,2	250,00		2.800,00
10.100.1083	Master electrician’s helper	h	11,2	185,00		2.072,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,5	700,00		2.450,00
19.100.1113	Mobile crane	h	4,5	1.079,77		4.858,97
				Total Excluding Profit (TRY)	183.344,00	14.028,97
				Material and Installation w/o Profit (TRY)	197.372,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**17.536,21**	
				Unit Price (TRY)	**246.716,21**	

Item No	Analysis Name					UoM
35.740.1103	**30 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1103	30 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	214.580,80	214.580,80	
	Installation Components					
10.100.1062	Unskilled worker	h	11,2	165,00		1.848,00
10.100.1081	Master electrician	h	11,2	250,00		2.800,00
10.100.1083	Master electrician’s helper	h	11,2	185,00		2.072,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
19.100.1113	Mobile crane	h	4,5	1.079,77		4.858,97
				Total Excluding Profit (TRY)	214.580,80	14.378,97
				Material and Installation w/o Profit (TRY)	228.959,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**17.973,71**	
				Unit Price (TRY)	**286.199,71**	

Item No	Analysis Name					UoM
35.740.1104	**36 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1104	36 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	228.289,60	228.289,60	
	Installation Components					
10.100.1062	Unskilled worker	h	11,3	165,00		1.864,50
10.100.1081	Master electrician	h	11,3	250,00		2.825,00
10.100.1083	Master electrician’s helper	h	11,3	185,00		2.090,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4,5	700,00		3.150,00
19.100.1113	Mobile crane	h	4,5	1.079,77		4.858,97
				Total Excluding Profit (TRY)	228.289,60	14.788,97
				Material and Installation w/o Profit (TRY)	243.078,57	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**18.486,21**	
				Unit Price (TRY)	**303.848,21**	

Item No	Analysis Name					UoM
35.740.1105	**50 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1105	50 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	298.816,00	298.816,00	
	Installation Components					
10.100.1062	Unskilled worker	h	11,4	165,00		1.881,00
10.100.1081	Master electrician	h	11,4	250,00		2.850,00
10.100.1083	Master electrician’s helper	h	11,4	185,00		2.109,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
19.100.1113	Mobile crane	h	4,5	1.079,77		4.858,97
				Total Excluding Profit (TRY)	298.816,00	15.198,97
				Material and Installation w/o Profit (TRY)	314.014,97	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**18.998,71**	
				Unit Price (TRY)	**392.518,71**	

Item No	Analysis Name					UoM
35.740.1106	**63 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1106	63 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	322.672,00	322.672,00	
	Installation Components					
10.100.1062	Unskilled worker	h	11,6	165,00		1.914,00
10.100.1081	Master electrician	h	11,6	250,00		2.900,00
10.100.1083	Master electrician’s helper	h	11,6	185,00		2.146,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5,5	700,00		3.850,00
19.100.1113	Mobile crane	h	4,6	1.079,77		4.966,94
				Total Excluding Profit (TRY)	322.672,00	15.776,94
				Material and Installation w/o Profit (TRY)	338.448,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**19.721,17**	
				Unit Price (TRY)	**423.061,17**	

Item No	Analysis Name					UoM
35.740.1107	**75 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1107	75 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	342.126,00	342.126,00	
	Installation Components					
10.100.1062	Unskilled worker	h	11,7	165,00		1.930,50
10.100.1081	Master electrician	h	11,7	250,00		2.925,00
10.100.1083	Master electrician’s helper	h	11,7	185,00		2.164,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
19.100.1113	Mobile crane	h	4,7	1.079,77		5.074,92
				Total Excluding Profit (TRY)	342.126,00	16.294,92
				Material and Installation w/o Profit (TRY)	358.420,92	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**20.368,65**	
				Unit Price (TRY)	**448.026,15**	

Item No	Analysis Name					UoM
35.740.1108	**100 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1108	100 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	376.835,20	376.835,20	
	Installation Components					
10.100.1062	Unskilled worker	h	11,8	165,00		1.947,00
10.100.1081	Master electrician	h	11,8	250,00		2.950,00
10.100.1083	Master electrician’s helper	h	11,8	185,00		2.183,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6,5	700,00		4.550,00
19.100.1113	Mobile crane	h	4,7	1.079,77		5.074,92
				Total Excluding Profit (TRY)	376.835,20	16.704,92
				Material and Installation w/o Profit (TRY)	393.540,12	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**20.881,15**	
				Unit Price (TRY)	**491.925,15**	

Item No	Analysis Name					UoM
35.740.1109	**150 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1109	150 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	511.044,80	511.044,80	
	Installation Components					
10.100.1062	Unskilled worker	h	12	165,00		1.980,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7	700,00		4.900,00
19.100.1113	Mobile crane	h	4,8	1.079,77		5.182,90
				Total Excluding Profit (TRY)	511.044,80	17.282,90
				Material and Installation w/o Profit (TRY)	528.327,70	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**21.603,63**	
				Unit Price (TRY)	**660.409,63**	

Item No	Analysis Name					UoM
35.740.1110	**200 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1110	200 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	636.294,40	636.294,40	
	Installation Components					
10.100.1062	Unskilled worker	h	12,4	165,00		2.046,00
10.100.1081	Master electrician	h	12,4	250,00		3.100,00
10.100.1083	Master electrician's helper	h	12,4	185,00		2.294,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	7,5	700,00		5.250,00
19.100.1113	Mobile crane	h	5	1.079,77		5.398,85
				Total Excluding Profit (TRY)	636.294,40	18.088,85
				Material and Installation w/o Profit (TRY)	654.383,25	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**22.611,06**	
				Unit Price (TRY)	**817.979,06**	

Item No	Analysis Name					UoM
35.740.1111	**235 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1111	235 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	674.441,60	674.441,60	
	Installation Components					
10.100.1062	Unskilled worker	h	13,1	165,00		2.161,50
10.100.1081	Master electrician	h	13,1	250,00		3.275,00
10.100.1083	Master electrician’s helper	h	13,1	185,00		2.423,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	5,2	1.079,77		5.614,80
				Total Excluding Profit (TRY)	674.441,60	19.074,80
				Material and Installation w/o Profit (TRY)	693.516,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**23.843,50**	
				Unit Price (TRY)	**866.895,50**	

Item No	Analysis Name					UoM
35.740.1112	**250 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1112	250 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	744.710,40	744.710,40	
	Installation Components					
10.100.1062	Unskilled worker	h	13,4	165,00		2.211,00
10.100.1081	Master electrician	h	13,4	250,00		3.350,00
10.100.1083	Master electrician’s helper	h	13,4	185,00		2.479,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8,5	700,00		5.950,00
19.100.1113	Mobile crane	h	5,4	1.079,77		5.830,76
				Total Excluding Profit (TRY)	744.710,40	19.820,76
				Material and Installation w/o Profit (TRY)	764.531,16	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**24.775,95**	
				Unit Price (TRY)	**955.663,95**	

Item No	Analysis Name					UoM
35.740.1113	**300 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1113	300 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	846.417,60	846.417,60	
	Installation Components					
10.100.1062	Unskilled worker	h	13,5	165,00		2.227,50
10.100.1081	Master electrician	h	13,5	250,00		3.375,00
10.100.1083	Master electrician’s helper	h	13,5	185,00		2.497,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9	700,00		6.300,00
19.100.1113	Mobile crane	h	5,4	1.079,77		5.830,76
				Total Excluding Profit (TRY)	846.417,60	20.230,76
				Material and Installation w/o Profit (TRY)	866.648,36	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**25.288,45**	
				Unit Price (TRY)	**1.083.310,45**	

Item No	Analysis Name					UoM
35.740.1114	**350 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1114	350 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	1.006.723,20	1.006.723,20	
	Installation Components					
10.100.1062	Unskilled worker	h	14,3	165,00		2.359,50
10.100.1081	Master electrician	h	14,3	250,00		3.575,00
10.100.1083	Master electrician’s helper	h	14,3	185,00		2.645,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	9,5	700,00		6.650,00
19.100.1113	Mobile crane	h	5,7	1.079,77		6.154,69
				Total Excluding Profit (TRY)	1.006.723,20	21.384,69
				Material and Installation w/o Profit (TRY)	1.028.107,89	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**26.730,86**	
				Unit Price (TRY)	**1.285.134,86**	

Item No	Analysis Name					UoM
35.740.1115	**375 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1115	375 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	1.042.630,40	1.042.630,40	
	Installation Components					
10.100.1062	Unskilled worker	h	14,6	165,00		2.409,00
10.100.1081	Master electrician	h	14,6	250,00		3.650,00
10.100.1083	Master electrician’s helper	h	14,6	185,00		2.701,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	10	700,00		7.000,00
19.100.1113	Mobile crane	h	5,9	1.079,77		6.370,64
				Total Excluding Profit (TRY)	1.042.630,40	22.130,64
				Material and Installation w/o Profit (TRY)	1.064.761,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**27.663,30**	
				Unit Price (TRY)	**1.330.951,30**	

Item No	Analysis Name					UoM
35.740.1116	**400 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1116	400 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	1.223.812,80	1.223.812,80	
	Installation Components					
10.100.1062	Unskilled worker	h	15,3	165,00		2.524,50
10.100.1081	Master electrician	h	15,3	250,00		3.825,00
10.100.1083	Master electrician’s helper	h	15,3	185,00		2.830,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	11	700,00		7.700,00
19.100.1113	Mobile crane	h	6,1	1.079,77		6.586,60
				Total Excluding Profit (TRY)	1.223.812,80	23.466,60
				Material and Installation w/o Profit (TRY)	1.247.279,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**29.333,25**	
				Unit Price (TRY)	**1.559.099,25**	

Item No	Analysis Name					UoM
35.740.1117	**500 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1117	500 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	1.464.915,20	1.464.915,20	
	Installation Components					
10.100.1062	Unskilled worker	h	15,6	165,00		2.574,00
10.100.1081	Master electrician	h	15,6	250,00		3.900,00
10.100.1083	Master electrician’s helper	h	15,6	185,00		2.886,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	12	700,00		8.400,00
19.100.1113	Mobile crane	h	6,2	1.079,77		6.694,57
				Total Excluding Profit (TRY)	1.464.915,20	24.454,57
				Material and Installation w/o Profit (TRY)	1.489.369,77	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**30.568,21**	
				Unit Price (TRY)	**1.861.712,21**	

Item No	Analysis Name					UoM
35.740.1118	**625 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1118	625 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	2.120.630,40	2.120.630,40	
	Installation Components					
10.100.1062	Unskilled worker	h	17,9	165,00		2.953,50
10.100.1081	Master electrician	h	17,9	250,00		4.475,00
10.100.1083	Master electrician’s helper	h	17,9	185,00		3.311,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	13	700,00		9.100,00
19.100.1113	Mobile crane	h	7,2	1.079,77		7.774,34
				Total Excluding Profit (TRY)	2.120.630,40	27.614,34
				Material and Installation w/o Profit (TRY)	2.148.244,74	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**34.517,93**	
				Unit Price (TRY)	**2.685.305,92**	

Item No	Analysis Name					UoM
35.740.1119	**750 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1119	750 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	2.372.921,60	2.372.921,60	
	Installation Components					
10.100.1062	Unskilled worker	h	17,9	165,00		2.953,50
10.100.1081	Master electrician	h	17,9	250,00		4.475,00
10.100.1083	Master electrician’s helper	h	17,9	185,00		3.311,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	14	700,00		9.800,00
19.100.1113	Mobile crane	h	7,2	1.079,77		7.774,34
				Total Excluding Profit (TRY)	2.372.921,60	28.314,34
				Material and Installation w/o Profit (TRY)	2.401.235,94	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**35.392,93**	
				Unit Price (TRY)	**3.001.544,92**	

Item No	Analysis Name					UoM
35.740.1120	**875 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1120	875 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	3.528.011,20	3.528.011,20	
	Installation Components					
10.100.1062	Unskilled worker	h	19,6	165,00		3.234,00
10.100.1081	Master electrician	h	19,6	250,00		4.900,00
10.100.1083	Master electrician’s helper	h	19,6	185,00		3.626,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	15	700,00		10.500,00
19.100.1113	Mobile crane	h	7,9	1.079,77		8.530,18
				Total Excluding Profit (TRY)	3.528.011,20	30.790,18
				Material and Installation w/o Profit (TRY)	3.558.801,38	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**38.487,72**	
				Unit Price (TRY)	**4.448.501,73**	

Item No	Analysis Name					UoM
35.740.1121	**1000 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1121	1000 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	3.817.766,40	3.817.766,40	
	Installation Components					
10.100.1062	Unskilled worker	h	22,4	165,00		3.696,00
10.100.1081	Master electrician	h	22,4	250,00		5.600,00
10.100.1083	Master electrician’s helper	h	22,4	185,00		4.144,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	16	700,00		11.200,00
19.100.1113	Mobile crane	h	9	1.079,77		9.717,93
				Total Excluding Profit (TRY)	3.817.766,40	34.357,93
				Material and Installation w/o Profit (TRY)	3.852.124,33	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**42.947,41**	
				Unit Price (TRY)	**4.815.155,41**	

Item No	Analysis Name					UoM
35.740.1122	**1250 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1122	1250 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	5.295.494,40	5.295.494,40	
	Installation Components					
10.100.1062	Unskilled worker	h	24,3	165,00		4.009,50
10.100.1081	Master electrician	h	24,3	250,00		6.075,00
10.100.1083	Master electrician’s helper	h	24,3	185,00		4.495,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	17	700,00		11.900,00
19.100.1113	Mobile crane	h	9,7	1.079,77		10.473,77
				Total Excluding Profit (TRY)	5.295.494,40	36.953,77
				Material and Installation w/o Profit (TRY)	5.332.448,17	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**46.192,21**	
				Unit Price (TRY)	**6.665.560,21**	

Item No	Analysis Name					UoM
35.740.1123	**1500 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1123	1500 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	6.308.792,00	6.308.792,00	
	Installation Components					
10.100.1062	Unskilled worker	h	25	165,00		4.125,00
10.100.1081	Master electrician	h	25	250,00		6.250,00
10.100.1083	Master electrician’s helper	h	25	185,00		4.625,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	18	700,00		12.600,00
19.100.1113	Mobile crane	h	10	1.079,77		10.797,70
				Total Excluding Profit (TRY)	6.308.792,00	38.397,70
				Material and Installation w/o Profit (TRY)	6.347.189,70	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**47.997,13**	
				Unit Price (TRY)	**7.933.987,13**	

Item No	Analysis Name					UoM
35.740.1124	**1750 kVa (Prime power) / Diesel engine cooling with water or air, 1500 rpm / Diesel Electric Generator Group Installations (in compliance with TS EN 12601, TS EN 60204-31, TS EN 60204-32 Machinery Directive (98/37/EC) and Low Voltage Directive (72/23/EEC), and CE certified).**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.1124	1750 kVA 500 kVA (prime power) diesel generator with a water- or air-cooled engine, operating at 1,500 rpm / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	7.472.404,80	7.472.404,80	
	Installation Components					
10.100.1062	Unskilled worker	h	30	165,00		4.950,00
10.100.1081	Master electrician	h	30	250,00		7.500,00
10.100.1083	Master electrician’s helper	h	30	185,00		5.550,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	19	700,00		13.300,00
19.100.1113	Mobile crane	h	12	1.079,77		12.957,24
				Total Excluding Profit (TRY)	7.472.404,80	44.257,24
				Material and Installation w/o Profit (TRY)	7.516.662,04	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**55.321,55**	
				Unit Price (TRY)	**9.395.827,55**	

Item No	Analysis Name					UoM
35.740.5100	**Hand-operated (Manual) / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5100	Manually Operated (Manual) / Synchronization Assembly / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	100.475,20	100.475,20	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician’s helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	100.475,20	6.940,00
				Material and Installation w/o Profit (TRY)	107.415,20	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**8.675,00**	
				Unit Price (TRY)	**134.269,00**	

Item No	Analysis Name					UoM
35.740.5200	**Automatic / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5200	Automatic / Synchronization Assembly / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	115.136,00	115.136,00	
	Installation Components					
10.100.1062	Unskilled worker	h	4	165,00		660,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician’s helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	115.136,00	7.810,00
				Material and Installation w/o Profit (TRY)	122.946,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**9.762,50**	
				Unit Price (TRY)	**153.682,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.740.5300	**Synchronization assembly 1250 - 2000 kVA (Automatic) / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5300	Synchronization assembly 1250 - 2000 kVA (Automatic) / Synchronization Assembly / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	225.982,40	225.982,40	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	15	250,00		3.750,00
10.100.1083	Master electrician’s helper	h	15	185,00		2.775,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	6	700,00		4.200,00
		Total Excluding Profit (TRY)			225.982,40	11.715,00
		Material and Installation w/o Profit (TRY)			237.697,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**14.643,75**	
		Unit Price (TRY)			**297.121,75**	

Item No	Analysis Name					UoM
35.740.5401						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5401	10 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	31.543,20	31.543,20	
	Installation Components					
10.100.1062	Unskilled worker	h	5	165,00		825,00
10.100.1081	Master electrician	h	5	250,00		1.250,00
10.100.1083	Master electrician’s helper	h	5	185,00		925,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1	700,00		700,00
		Total Excluding Profit (TRY)			31.543,20	3.700,00
		Material and Installation w/o Profit (TRY)			35.243,20	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**4.625,00**	
		Unit Price (TRY)			**44.054,00**	

Item No	Analysis Name					UoM
35.740.5402						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5402	20 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	35.006,40	35.006,40	
	Installation Components					
10.100.1062	Unskilled worker	h	5,6	165,00		924,00
10.100.1081	Master electrician	h	5,6	250,00		1.400,00
10.100.1083	Master electrician's helper	h	5,6	185,00		1.036,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,17	700,00		819,00
		Total Excluding Profit (TRY)			35.006,40	4.179,00
		Material and Installation w/o Profit (TRY)			39.185,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**5.223,75**	
		Unit Price (TRY)			**48.981,75**	

Item No	Analysis Name					UoM
35.740.5403						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5403	30 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	37.419,20	37.419,20	
	Installation Components					
10.100.1062	Unskilled worker	h	5,6	165,00		924,00
10.100.1081	Master electrician	h	5,6	250,00		1.400,00
10.100.1083	Master electrician's helper	h	5,6	185,00		1.036,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,33	700,00		931,00
		Total Excluding Profit (TRY)			37.419,20	4.291,00
		Material and Installation w/o Profit (TRY)			41.710,20	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**5.363,75**	
		Unit Price (TRY)			**52.137,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.740.5404						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5404	36 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	40.955,20	40.955,20	
	Installation Components					
10.100.1062	Unskilled worker	h	5,65	165,00		932,25
10.100.1081	Master electrician	h	5,65	250,00		1.412,50
10.100.1083	Master electrician's helper	h	5,65	185,00		1.045,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,5	700,00		1.050,00
				Total Excluding Profit (TRY)	40.955,20	4.440,00
				Material and Installation w/o Profit (TRY)	45.395,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**5.550,00**	
				Unit Price (TRY)	**56.744,00**	

Item No	Analysis Name					UoM
35.740.5405						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5405	50 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	44.127,20	44.127,20	
	Installation Components					
10.100.1062	Unskilled worker	h	5,7	165,00		940,50
10.100.1081	Master electrician	h	5,7	250,00		1.425,00
10.100.1083	Master electrician's helper	h	5,7	185,00		1.054,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,67	700,00		1.169,00
				Total Excluding Profit (TRY)	44.127,20	4.589,00
				Material and Installation w/o Profit (TRY)	48.716,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**5.736,25**	
				Unit Price (TRY)	**60.895,25**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.740.5406						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5406	63 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	54.995,20	54.995,20	
	Installation Components					
10.100.1062	Unskilled worker	h	5,8	165,00		957,00
10.100.1081	Master electrician	h	5,8	250,00		1.450,00
10.100.1083	Master electrician's helper	h	5,8	185,00		1.073,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	1,83	700,00		1.281,00
		Total Excluding Profit (TRY)			54.995,20	4.761,00
		Material and Installation w/o Profit (TRY)			59.756,20	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**5.951,25**	
		Unit Price (TRY)			**74.695,25**	

Item No	Analysis Name					UoM
35.740.5407						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5407	75 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	56.274,40	56.274,40	
	Installation Components					
10.100.1062	Unskilled worker	h	5,85	165,00		965,25
10.100.1081	Master electrician	h	5,85	250,00		1.462,50
10.100.1083	Master electrician's helper	h	5,85	185,00		1.082,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2	700,00		1.400,00
		Total Excluding Profit (TRY)			56.274,40	4.910,00
		Material and Installation w/o Profit (TRY)			61.184,40	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**6.137,50**	
		Unit Price (TRY)			**76.480,50**	

Item No	Analysis Name					UoM
35.740.5408	**100 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5408	100 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	59.914,40	59.914,40	
	Installation Components					
10.100.1062	Unskilled worker	h	5,9	165,00		973,50
10.100.1081	Master electrician	h	5,9	250,00		1.475,00
10.100.1083	Master electrician’s helper	h	5,9	185,00		1.091,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,17	700,00		1.519,00
		Total Excluding Profit (TRY)			59.914,40	5.059,00
		Material and Installation w/o Profit (TRY)			64.973,40	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**6.323,75**	
		Unit Price (TRY)			**81.216,75**	

Item No	Analysis Name					UoM
35.740.5409	**150 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5409	150 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	82.368,00	82.368,00	
	Installation Components					
10.100.1062	Unskilled worker	h	6	165,00		990,00
10.100.1081	Master electrician	h	6	250,00		1.500,00
10.100.1083	Master electrician’s helper	h	6	185,00		1.110,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,33	700,00		1.631,00
		Total Excluding Profit (TRY)			82.368,00	5.231,00
		Material and Installation w/o Profit (TRY)			87.599,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**6.538,75**	
		Unit Price (TRY)			**109.498,75**	

Item No	Analysis Name					UoM
35.740.5410	**200 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5410	200 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	95.659,20	95.659,20	
	Installation Components					
10.100.1062	Unskilled worker	h	6,2	165,00		1.023,00
10.100.1081	Master electrician	h	6,2	250,00		1.550,00
10.100.1083	Master electrician's helper	h	6,2	185,00		1.147,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,5	700,00		1.750,00
				Total Excluding Profit (TRY)	95.659,20	5.470,00
				Material and Installation w/o Profit (TRY)	101.129,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**6.837,50**	
				Unit Price (TRY)	**126.411,50**	

Item No	Analysis Name					UoM
35.740.5411	**250 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5411	250 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	96.605,60	96.605,60	
	Installation Components					
10.100.1062	Unskilled worker	h	6,55	165,00		1.080,75
10.100.1081	Master electrician	h	6,55	250,00		1.637,50
10.100.1083	Master electrician's helper	h	6,55	185,00		1.211,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,67	700,00		1.869,00
				Total Excluding Profit (TRY)	96.605,60	5.799,00
				Material and Installation w/o Profit (TRY)	102.404,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**7.248,75**	
				Unit Price (TRY)	**128.005,75**	

Item No	Analysis Name					UoM
35.740.5412	**300 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5412	300 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	116.334,40	116.334,40	
	Installation Components					
10.100.1062	Unskilled worker	h	6,7	165,00		1.105,50
10.100.1081	Master electrician	h	6,7	250,00		1.675,00
10.100.1083	Master electrician’s helper	h	6,7	185,00		1.239,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	2,83	700,00		1.981,00
				Total Excluding Profit (TRY)	116.334,40	6.001,00
				Material and Installation w/o Profit (TRY)	122.335,40	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.501,25**	
				Unit Price (TRY)	**152.919,25**	

Item No	Analysis Name					UoM
35.740.5413	**400 kVa / Sound insulation cabinet**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5413	400 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	131.216,80	131.216,80	
	Installation Components					
10.100.1062	Unskilled worker	h	6,75	165,00		1.113,75
10.100.1081	Master electrician	h	6,75	250,00		1.687,50
10.100.1083	Master electrician’s helper	h	6,75	185,00		1.248,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3	700,00		2.100,00
				Total Excluding Profit (TRY)	131.216,80	6.150,00
				Material and Installation w/o Profit (TRY)	137.366,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**7.687,50**	
				Unit Price (TRY)	**171.708,50**	

Item No	Analysis Name					UoM
35.740.5414	**500 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5414	500 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	162.812,00	162.812,00	
	Installation Components					
10.100.1062	Unskilled worker	h	7,15	165,00		1.179,75
10.100.1081	Master electrician	h	7,15	250,00		1.787,50
10.100.1083	Master electrician's helper	h	7,15	185,00		1.322,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,17	700,00		2.219,00
				Total Excluding Profit (TRY)	162.812,00	6.509,00
				Material and Installation w/o Profit (TRY)	169.321,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.136,25**	
				Unit Price (TRY)	**211.651,25**	

Item No	Analysis Name					UoM
35.740.5415	**625 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5415	625 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	196.580,80	196.580,80	
	Installation Components					
10.100.1062	Unskilled worker	h	7,3	165,00		1.204,50
10.100.1081	Master electrician	h	7,3	250,00		1.825,00
10.100.1083	Master electrician's helper	h	7,3	185,00		1.350,50
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,33	700,00		2.331,00
				Total Excluding Profit (TRY)	196.580,80	6.711,00
				Material and Installation w/o Profit (TRY)	203.291,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.388,75**	
				Unit Price (TRY)	**254.114,75**	

Item No	Analysis Name					UoM
35.740.5416	**750 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5416	750 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	209.123,20	209.123,20	
	Installation Components					
10.100.1062	Unskilled worker	h	7,65	165,00		1.262,25
10.100.1081	Master electrician	h	7,65	250,00		1.912,50
10.100.1083	Master electrician's helper	h	7,65	185,00		1.415,25
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	3,67	700,00		2.569,00
				Total Excluding Profit (TRY)	209.123,20	7.159,00
				Material and Installation w/o Profit (TRY)	216.282,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**8.948,75**	
				Unit Price (TRY)	**270.352,75**	

Item No	Analysis Name					UoM
35.740.5417	**875 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5417	875 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	281.840,00	281.840,00	
	Installation Components					
10.100.1062	Unskilled worker	h	7,8	165,00		1.287,00
10.100.1081	Master electrician	h	7,8	250,00		1.950,00
10.100.1083	Master electrician's helper	h	7,8	185,00		1.443,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4	700,00		2.800,00
				Total Excluding Profit (TRY)	281.840,00	7.480,00
				Material and Installation w/o Profit (TRY)	289.320,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**9.350,00**	
				Unit Price (TRY)	**361.650,00**	

Item No	Analysis Name					UoM
35.740.5418	**1000 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5418	1000 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	285.095,20	285.095,20	
	Installation Components					
10.100.1062	Unskilled worker	h	8,95	165,00		1.476,75
10.100.1081	Master electrician	h	8,95	250,00		2.237,50
10.100.1083	Master electrician's helper	h	8,95	185,00		1.655,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4,33	700,00		3.031,00
				Total Excluding Profit (TRY)	285.095,20	8.401,00
				Material and Installation w/o Profit (TRY)	293.496,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**10.501,25**	
				Unit Price (TRY)	**366.870,25**	

Item No	Analysis Name					UoM
35.740.5419	**1250 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5419	1250 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	391.164,80	391.164,80	
	Installation Components					
10.100.1062	Unskilled worker	h	8,95	165,00		1.476,75
10.100.1081	Master electrician	h	8,95	250,00		2.237,50
10.100.1083	Master electrician's helper	h	8,95	185,00		1.655,75
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	4,67	700,00		3.269,00
				Total Excluding Profit (TRY)	391.164,80	8.639,00
				Material and Installation w/o Profit (TRY)	399.803,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**10.798,75**	
				Unit Price (TRY)	**499.754,75**	

Item No	Analysis Name					UoM
35.740.5420	**1500 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5420	1500 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	465.899,20	465.899,20	
	Installation Components					
10.100.1062	Unskilled worker	h	9,8	165,00		1.617,00
10.100.1081	Master electrician	h	9,8	250,00		2.450,00
10.100.1083	Master electrician's helper	h	9,8	185,00		1.813,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5	700,00		3.500,00
				Total Excluding Profit (TRY)	465.899,20	9.380,00
				Material and Installation w/o Profit (TRY)	475.279,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**11.725,00**	
				Unit Price (TRY)	**594.099,00**	

Item No	Analysis Name					UoM
35.740.5421	**1750 kVA / Sound insulation cabinet / Synchronization Assembly**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.740.5421	1750 kVA / Soundproof enclosure / DIESEL GENERATOR SET INSTALLATION (Market price)	Qty	1	597.719,20	597.719,20	
	Installation Components					
10.100.1062	Unskilled worker	h	11,2	165,00		1.848,00
10.100.1081	Master electrician	h	11,2	250,00		2.800,00
10.100.1083	Master electrician's helper	h	11,2	185,00		2.072,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	5,33	700,00		3.731,00
				Total Excluding Profit (TRY)	597.719,20	10.451,00
				Material and Installation w/o Profit (TRY)	608.170,20	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**13.063,75**	
				Unit Price (TRY)	**760.212,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.750.1100	**Metallic arrester tip / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1100	Metallic arrester tip / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	2.252,32	2.252,32	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	2.252,32	1.200,00
				Material and Installation w/o Profit (TRY)	3.452,32	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.500,00**	
				Unit Price (TRY)	**4.315,40**	

Item No	Analysis Name					UoM
35.750.1501	**Mean excitation way: DL = 15 - 25 m / Active arrester tip / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1501	Mean excitation way DL = 15 to 25 m. / Active arrester tip / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	10.673,60	10.673,60	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	10.673,60	1.635,00
				Material and Installation w/o Profit (TRY)	12.308,60	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**15.385,75**	

Item No	Analysis Name					UoM
35.750.1502	**Mean excitation way: DL = 30 - 40 m / Active arrester tip / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1502	Mean excitation way DL = 30 to 40 m. / Active arrester tip / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	11.704,00	11.704,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	11.704,00	1.635,00
				Material and Installation w/o Profit (TRY)	13.339,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**16.673,75**	

Item No	Analysis Name					UoM
35.750.1503	**Mean excitation way: DL = 40 - 50 m / Active arrester tip / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1503	Mean excitation way DL = 40 to 50 m. / Active arrester tip / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	12.140,80	12.140,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician’s helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	12.140,80	1.635,00
				Material and Installation w/o Profit (TRY)	13.775,80	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**17.219,75**	

Item No	Analysis Name					UoM
35.750.1504	**Mean excitation way: DL = 60 m / Active arrester tip / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1504	Mean excitation way DL = 60 m. / Active arrester tip / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	12.880,00	12.880,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	12.880,00	1.635,00
				Material and Installation w/o Profit (TRY)	14.515,00	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**18.143,75**	

Item No	Analysis Name					UoM
35.750.1600	**Roof-top post (for radioactive arrester tip) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1600	Roof-top post (for active arrester tip) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	3.852,80	3.852,80	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	3.852,80	1.635,00
				Material and Installation w/o Profit (TRY)	5.487,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**2.043,75**	
				Unit Price (TRY)	**6.859,75**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.750.1650	**Lightning counter / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1650	Lightning counter / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	2.565,16	2.565,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	2.565,16	125,25
				Material and Installation w/o Profit (TRY)	2.690,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**3.363,01**	

Item No	Analysis Name					UoM
35.750.1700	**Active lightning rod test device / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.1700	Active lightning rod test device / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	2.799,16	2.799,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	2.799,16	125,25
				Material and Installation w/o Profit (TRY)	2.924,41	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**3.655,51**	

Item No	Analysis Name					UoM
35.750.2001	**50-mm² electrolytic copper wire / Roof surrounding and drop wires / Lightning Protection System (TS EN 62305-1/2/3/4)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.2001	50-mm² electrolytic copper wire / Roof surrounding and drop wires / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	m	1	263,76	263,76	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician's helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	263,76	48,50
				Material and Installation w/o Profit (TRY)	312,26	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**390,32**	

Item No	Analysis Name					UoM
35.750.2002	**25-mm² electrolytic copper wire / Roof surrounding and drop wires / Lightning Protection System (TS EN 62305-1/2/3/4)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.2002	25-mm² electrolytic copper wire / Roof surrounding and drop wires / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	m	1	132,16	132,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,05	165,00		8,25
10.100.1081	Master electrician	h	0,1	250,00		25,00
10.100.1083	Master electrician's helper	h	0,05	185,00		9,25
				Total Excluding Profit (TRY)	132,16	42,50
				Material and Installation w/o Profit (TRY)	174,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**53,13**	
				Unit Price (TRY)	**218,32**	

Item No	Analysis Name					UoM
35.750.2003	**3 x 25 or 4 x 20 mm electrolytic copper strip for drop wires / Roof surrounding and drop wires / Lightning Protection System (TS EN 62305-1/2/3/4)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.2003	3 x 25 or 4 x 20 mm electrolytic copper strip for drop wires / Roof surrounding and drop wires / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	m	1	398,16	398,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician’s helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	398,16	59,50
				Material and Installation w/o Profit (TRY)	457,66	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**572,08**	

Item No	Analysis Name					UoM
35.750.3001	**50 mm² solid copper / Installation of surrounding wires around the building / Lightning Protection System (TS EN 62305-1/2/3/4)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.3001	50 mm² solid copper / Installation of surrounding wires around the building / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	m	1	264,32	264,32	
	Installation Components					
10.100.1062	Unskilled worker	h	0,06	165,00		9,90
10.100.1081	Master electrician	h	0,11	250,00		27,50
10.100.1083	Master electrician’s helper	h	0,06	185,00		11,10
				Total Excluding Profit (TRY)	264,32	48,50
				Material and Installation w/o Profit (TRY)	312,82	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**60,63**	
				Unit Price (TRY)	**391,02**	

Item No	Analysis Name					UoM
35.750.3002	**30 x 3.5 mm galvanized steel flat bar in compliance with the relevant specifications / Installation of surrounding wires around the building / Lightning Protection System (TS EN 62305-1/2/3/4)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.3002	30 x 3.5 mm galvanized steel flat bar in compliance with the relevant specifications / Installation of surrounding wires around the building / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	m	1	71,68	71,68	
	Installation Components					
10.100.1062	Unskilled worker	h	0,07	165,00		11,55
10.100.1081	Master electrician	h	0,14	250,00		35,00
10.100.1083	Master electrician's helper	h	0,07	185,00		12,95
				Total Excluding Profit (TRY)	71,68	59,50
				Material and Installation w/o Profit (TRY)	131,18	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**74,38**	
				Unit Price (TRY)	**163,98**	

Item No	Analysis Name					UoM
35.750.4001	**Earth electrode (Plate) electrolytic copper / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.4001	Earth electrode (Plate) electrolytic copper / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	4.693,92	4.693,92	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	4.693,92	600,00
				Material and Installation w/o Profit (TRY)	5.293,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**750,00**	
				Unit Price (TRY)	**6.617,40**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.750.4002	**Earth electrode (Bar) electrolytic copper / Lightning Protection System (TS EN 62305-1/2/3/4)**					**m**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.4002	Earth electrode (Bar) electrolytic copper / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	m	1	2.005,92	2.005,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	0,5	250,00		125,00
10.100.1083	Master electrician's helper	h	0,5	185,00		92,50
				Total Excluding Profit (TRY)	2.005,92	300,00
				Material and Installation w/o Profit (TRY)	2.305,92	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**375,00**	
				Unit Price (TRY)	**2.882,40**	

Item No	Analysis Name					UoM
35.750.4003	**Conductor protecting pipe / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.4003	Conductor protecting pipe / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	728,00	728,00	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,54	250,00		135,00
10.100.1083	Master electrician's helper	h	0,54	185,00		99,90
				Total Excluding Profit (TRY)	728,00	284,40
				Material and Installation w/o Profit (TRY)	1.012,40	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**355,50**	
				Unit Price (TRY)	**1.265,50**	

Item No	Analysis Name					UoM
35.750.5001	**Up to 32 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5001	Up to 32 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	440,16	440,16	
	Installation Components					
10.100.1062	Unskilled worker	h	0,3	165,00		49,50
10.100.1081	Master electrician	h	0,6	250,00		150,00
10.100.1083	Master electrician's helper	h	0,6	185,00		111,00
				Total Excluding Profit (TRY)	440,16	310,50
				Material and Installation w/o Profit (TRY)	750,66	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**388,13**	
				Unit Price (TRY)	**938,33**	

Item No	Analysis Name					UoM
35.750.5002	**Up to 65 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5002	Up to 65 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	502,88	502,88	
	Installation Components					
10.100.1062	Unskilled worker	h	0,5	165,00		82,50
10.100.1081	Master electrician	h	1	250,00		250,00
10.100.1083	Master electrician's helper	h	1	185,00		185,00
				Total Excluding Profit (TRY)	502,88	517,50
				Material and Installation w/o Profit (TRY)	1.020,38	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**646,88**	
				Unit Price (TRY)	**1.275,47**	

Item No	Analysis Name					UoM
35.750.5003	**Up to 90 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5003	Up to 90 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	581,28	581,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,7	165,00		115,50
10.100.1081	Master electrician	h	1,4	250,00		350,00
10.100.1083	Master electrician's helper	h	1,4	185,00		259,00
				Total Excluding Profit (TRY)	581,28	724,50
				Material and Installation w/o Profit (TRY)	1.305,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**905,63**	
				Unit Price (TRY)	**1.632,22**	

Item No	Analysis Name					UoM
35.750.5004	**Up to 115 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5004	Up to 115 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	637,28	637,28	
	Installation Components					
10.100.1062	Unskilled worker	h	0,8	165,00		132,00
10.100.1081	Master electrician	h	1,6	250,00		400,00
10.100.1083	Master electrician's helper	h	1,6	185,00		296,00
				Total Excluding Profit (TRY)	637,28	828,00
				Material and Installation w/o Profit (TRY)	1.465,28	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.035,00**	
				Unit Price (TRY)	**1.831,60**	

Item No	Analysis Name					UoM
35.750.5005	**Up to 150 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5005	Up to 150 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	715,68	715,68	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician's helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	715,68	1.035,00
				Material and Installation w/o Profit (TRY)	1.750,68	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**2.188,35**	

Item No	Analysis Name					UoM
35.750.5006	**Up to 200 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5006	Up to 200 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	850,08	850,08	
	Installation Components					
10.100.1062	Unskilled worker	h	1,2	165,00		198,00
10.100.1081	Master electrician	h	2,4	250,00		600,00
10.100.1083	Master electrician's helper	h	2,4	185,00		444,00
				Total Excluding Profit (TRY)	850,08	1.242,00
				Material and Installation w/o Profit (TRY)	2.092,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.552,50**	
				Unit Price (TRY)	**2.615,10**	

Item No	Analysis Name					UoM
35.750.5007	**Up to 250 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5007	Up to 250 g welding powder / Exothermic welding attachment (copper to copper), (copper to aluminum), (copper to iron) / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Qty	1	917,28	917,28	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	917,28	1.552,50
				Material and Installation w/o Profit (TRY)	2.469,78	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.940,63**	
				Unit Price (TRY)	**3.087,22**	

Item No	Analysis Name					UoM
35.750.5500	**Chemical to reduce earthing resistance / Lightning Protection System (TS EN 62305-1/2/3/4)**					**Kg**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.750.5500	Chemical to reduce earthing resistance / Lightning Protection Installation (TS EN 62305-1/2/3/4) (Market price)	Kg	1	339,92	339,92	
	Installation Components					
10.100.1062	Unskilled worker	h	0,1	165,00		16,50
10.100.1081	Master electrician	h	0,25	250,00		62,50
10.100.1083	Master electrician's helper	h	0,25	185,00		46,25
				Total Excluding Profit (TRY)	339,92	125,25
				Material and Installation w/o Profit (TRY)	465,17	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**156,56**	
				Unit Price (TRY)	**581,46**	

Item No	Analysis Name					UoM
35.800.1110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1110	Width : 300 cm / Block barrier, crash tested with a 6800-7500 kg vehicle at 80 km/h, with a height to road surface of 90 cm-100 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System Market price	Qty	1	387.304,31	387.304,31	
	Installation Components					
10.100.1062	Unskilled worker	h	16	165,00		2.640,00
10.100.1081	Master electrician	h	8	250,00		2.000,00
10.100.1083	Master electrician's helper	h	8	185,00		1.480,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	387.304,31	12.799,77
				Material and Installation w/o Profit (TRY)	400.104,08	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**15.999,71**	
				Unit Price (TRY)	**500.130,10**	

Item No	Analysis Name					UoM
35.800.1120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1120	Width: 400 cm / Block barrier, crash tested with a 6800-7500 kg vehicle at 80 km/h, with a height to road surface of 90 cm-100 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System (Market price)	Qty	1	441.264,18	441.264,18	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician's helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	441.264,18	14.329,77
				Material and Installation w/o Profit (TRY)	455.593,95	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.912,21**	
				Unit Price (TRY)	**569.492,44**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.800.1130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1130	Width: 500 cm / Block barrier, crash tested with a 6800-7500 kg vehicle at 80 km/h, with a height to road surface of 90 cm-100 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System (Market price)	Qty	1	492.766,03	492.766,03	
	Installation Components					
10.100.1062	Unskilled worker	h	24	165,00		3.960,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	492.766,03	15.859,77
				Material and Installation w/o Profit (TRY)	508.625,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**19.824,71**	
				Unit Price (TRY)	**635.782,25**	

Item No	Analysis Name					UoM
35.800.1210						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1210	Width: 300 cm / Block barrier, crash tested with a 6800-7500 kg vehicle at 80 km/h, with a height to road surface of 101 cm - 110 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System Market price	Qty	1	586.677,30	586.677,30	
	Installation Components					
10.100.1062	Unskilled worker	h	20	165,00		3.300,00
10.100.1081	Master electrician	h	10	250,00		2.500,00
10.100.1083	Master electrician's helper	h	10	185,00		1.850,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	586.677,30	14.329,77
				Material and Installation w/o Profit (TRY)	601.007,07	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**17.912,21**	
				Unit Price (TRY)	**751.258,84**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.800.1220						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1220	Width: 400 cm / Block barrier, crash tested with a 6800-7500 kg vehicle at 80 km/h, with a height to road surface of 101 cm - 110 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System (Market price)	Qty	1	683.900,77	683.900,77	
	Installation Components					
10.100.1062	Unskilled worker	h	24	165,00		3.960,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	683.900,77	15.859,77
				Material and Installation w/o Profit (TRY)	699.760,54	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**19.824,71**	
				Unit Price (TRY)	**874.700,68**	

Item No	Analysis Name					UoM
35.800.1230						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1230	Width: 500 cm / Block barrier, crash tested with a 6800-7500 kg vehicle at 80 km/h, with a height to road surface of 101 cm - 110 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System (Market price)	Qty	1	778.795,14	778.795,14	
	Installation Components					
10.100.1062	Unskilled worker	h	28	165,00		4.620,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	778.795,14	17.389,77
				Material and Installation w/o Profit (TRY)	796.184,91	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**21.737,21**	
				Unit Price (TRY)	**995.231,14**	

Item No	Analysis Name					UoM
35.800.1310						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1310	Width: 300 cm / Block barrier, crash tested with a 12000 kg vehicle at 80 km/h, with a height to road surface of 100 cm - 120 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System (Market price)	Qty	1	754.244,03	754.244,03	
	Installation Components					
10.100.1062	Unskilled worker	h	24	165,00		3.960,00
10.100.1081	Master electrician	h	12	250,00		3.000,00
10.100.1083	Master electrician's helper	h	12	185,00		2.220,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	754.244,03	15.859,77
				Material and Installation w/o Profit (TRY)	770.103,80	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**19.824,71**	
				Unit Price (TRY)	**962.629,75**	

Item No	Analysis Name					UoM
35.800.1320						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1320	Width: 400 cm / Block barrier, crash tested with a 12001 kg vehicle at 80 km/h, with a height to road surface of 100 cm - 120 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System (Market price)	Qty	1	850.524,95	850.524,95	
	Installation Components					
10.100.1062	Unskilled worker	h	28	165,00		4.620,00
10.100.1081	Master electrician	h	14	250,00		3.500,00
10.100.1083	Master electrician's helper	h	14	185,00		2.590,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	850.524,95	17.389,77
				Material and Installation w/o Profit (TRY)	867.914,72	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**21.737,21**	
				Unit Price (TRY)	**1.084.893,40**	

Item No	Analysis Name					UoM
35.800.1330						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.1330	Width: 500 cm / Block barrier, crash tested with a 12002 kg vehicle at 80 km/h, with a height to road surface of 100 cm - 120 cm (included) / Crash-Test-Certified Block Barrier (Anti-Terror Road Blocker) System (Market price)	Qty	1	937.854,02	937.854,02	
	Installation Components					
10.100.1062	Unskilled worker	h	32	165,00		5.280,00
10.100.1081	Master electrician	h	16	250,00		4.000,00
10.100.1083	Master electrician’s helper	h	16	185,00		2.960,00
10.100.1091	Testing, Adjustment and Commissioning Specialist	h	8	700,00		5.600,00
19.100.1113	Mobile crane	h	1	1.079,77		1.079,77
				Total Excluding Profit (TRY)	937.854,02	18.919,77
				Material and Installation w/o Profit (TRY)	956.773,79	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**23.649,71**	
				Unit Price (TRY)	**1.195.967,24**	

Item No	Analysis Name					UoM
35.800.6105						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6105	Up to 300 kg, 24V DC motor, max 200 W / Sliding Door Motor (Market price)	Qty	1	7.600,00	7.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	7.600,00	1.035,00
				Material and Installation w/o Profit (TRY)	8.635,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**10.793,75**	

Item No	Analysis Name					UoM
35.800.6110						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6110	Up to 300 kg, 230V AC motor, max 250 W / Sliding Door Motor (Market price)	Qty	1	8.800,00	8.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2	250,00		500,00
10.100.1083	Master electrician’s helper	h	2	185,00		370,00
				Total Excluding Profit (TRY)	8.800,00	1.035,00
				Material and Installation w/o Profit (TRY)	9.835,00	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.293,75**	
				Unit Price (TRY)	**12.293,75**	

Item No	Analysis Name					UoM
35.800.6120						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6120	Up to 600 kg, 24V DC motor, max 350 W / Sliding Door Motor (Market price)	Qty	1	10.600,00	10.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician’s helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	10.600,00	1.252,50
				Material and Installation w/o Profit (TRY)	11.852,50	
% 25 Contractor’s Profit and Overheads Included				**Instal. Cost (TRY)**	**1.565,63**	
				Unit Price (TRY)	**14.815,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.800.6125						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6125	Up to 600 kg, 230V AC motor, max 500 W / Sliding Door Motor (Market price)	Qty	1	11.800,00	11.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1	165,00		165,00
10.100.1081	Master electrician	h	2,5	250,00		625,00
10.100.1083	Master electrician's helper	h	2,5	185,00		462,50
				Total Excluding Profit (TRY)	11.800,00	1.252,50
				Material and Installation w/o Profit (TRY)	13.052,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.565,63**	
				Unit Price (TRY)	**16.315,63**	

Item No	Analysis Name					UoM
35.800.6130						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6130	Up to 1000 kg, 24V DC motor, max 400 W / Sliding Door Motor (Market price)	Qty	1	13.000,00	13.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	13.000,00	1.552,50
				Material and Installation w/o Profit (TRY)	14.552,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.940,63**	
				Unit Price (TRY)	**18.190,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.800.6135						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6135	Up to 1000 kg, 230V AC motor, max 750 W / Sliding Door Motor (Market price)	Qty	1	14.800,00	14.800,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	14.800,00	1.552,50
				Material and Installation w/o Profit (TRY)	16.352,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.940,63**	
				Unit Price (TRY)	**20.440,63**	

Item No	Analysis Name					UoM
35.800.6140						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6140	Up to 1000 kg, 380V AC motor, max 1000 W / Sliding Door Motor (Market price)	Qty	1	18.400,00	18.400,00	
	Installation Components					
10.100.1062	Unskilled worker	h	1,5	165,00		247,50
10.100.1081	Master electrician	h	3	250,00		750,00
10.100.1083	Master electrician's helper	h	3	185,00		555,00
				Total Excluding Profit (TRY)	18.400,00	1.552,50
				Material and Installation w/o Profit (TRY)	19.952,50	
% 25 Contractor's Profit and Overheads Included				**Instal. Cost (TRY)**	**1.940,63**	
				Unit Price (TRY)	**24.940,63**	

Item No	Analysis Name					UoM
35.800.6150						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6150	Up to 1500 kg, 24V DC motor, max 500 W / Sliding Door Motor (Market price)	Qty	1	14.200,00	14.200,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
		Total Excluding Profit (TRY)			14.200,00	1.852,50
		Material and Installation w/o Profit (TRY)			16.052,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.315,63**	
		Unit Price (TRY)			**20.065,63**	

Item No	Analysis Name					UoM
35.800.6155						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6155	Up to 1500 kg, 230V AC motor, max 1000 W / Sliding Door Motor (Market price)	Qty	1	18.400,00	18.400,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
		Total Excluding Profit (TRY)			18.400,00	1.852,50
		Material and Installation w/o Profit (TRY)			20.252,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.315,63**	
		Unit Price (TRY)			**25.315,63**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.800.6160						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6160	Up to 1500 kg, 380V AC motor, max 1250 W / Sliding Door Motor (Market price)	Qty	1	22.000,00	22.000,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	3,5	250,00		875,00
10.100.1083	Master electrician's helper	h	3,5	185,00		647,50
		Total Excluding Profit (TRY)			22.000,00	1.852,50
		Material and Installation w/o Profit (TRY)			23.852,50	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.315,63**	
		Unit Price (TRY)			**29.815,63**	

Item No	Analysis Name					UoM
35.800.6170						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6170	Up to 2000 kg, 230V AC motor, max 1250 W / Sliding Door Motor (Market price)	Qty	1	23.200,00	23.200,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician's helper	h	4	185,00		740,00
		Total Excluding Profit (TRY)			23.200,00	2.070,00
		Material and Installation w/o Profit (TRY)			25.270,00	
% 25 Contractor's Profit and Overheads Included		**Instal. Cost (TRY)**			**2.587,50**	
		Unit Price (TRY)			**31.587,50**	

Electrical Installation Unit Price Analyses

01.01.2025

Item No	Analysis Name					UoM
35.800.6175						**Qty**
Item No	Description	UoM	Quantity	Unit Price	Price of Materials (TRY)	Price of Installation (TRY)
	Material Components					
30.800.6175	Up to 2000 kg, 380V AC motor, max 1500 W / Sliding Door Motor (Market price)	Qty	1	25.600,00	25.600,00	
	Installation Components					
10.100.1062	Unskilled worker	h	2	165,00		330,00
10.100.1081	Master electrician	h	4	250,00		1.000,00
10.100.1083	Master electrician’s helper	h	4	185,00		740,00
		Total Excluding Profit (TRY)			25.600,00	2.070,00
		Material and Installation w/o Profit (TRY)			27.670,00	
% 25 Contractor’s Profit and Overheads Included		**Instal. Cost (TRY)**			**2.587,50**	
		Unit Price (TRY)			**34.587,50**	



YERLİ ÜRETİM

Support for Domestic Production

www.csb.gov.tr
http://yfk.csb.gov.tr